

REBUILD BY DESIGN MEADOWLANDS

CITIZEN ADVISORY GROUP (CAG) MEETING #11

ALTERNATIVES 1, 2, & 3

October 17, 2017



PREPARED BY **AECOM**

Español 中文:繁體版 Việt-ngữ 한국어 Tagalog
Português العربية Kreyòl ગુજરાતી Italiano Polski
www.renewjerseystronger.org

Table of Contents

1.0 List of Acronyms	3
2.0 Agenda	4
3.0 Power Point Presentation.....	5
4.0 Personal Notes	38

1.0 List of Acronyms

List of Acronyms

BCR	Benefit/Cost Ratio
CAG	Citizen Advisory Group
CDBG-DR	Community Development Block Grant – Disaster Recovery
EFH	Essential Fish Habitat
EIS	Environmental Impact Statement
HUD	Department of Housing and Urban Development
NEPA	National Environmental Policy Act
NJDEP	New Jersey Department of Environmental Protection
RBD	Rebuild by Design
RBDM	Rebuild by Design Meadowlands

2.0 Agenda

Alternatives 1, 2, & 3

6-8 PM

October 17, 2017

**Carlstadt Borough Council Chambers
500 Madison St
Carlstadt, NJ 07072**

Project Website

www.rbd-meadowlands.nj.gov

Project Email

rbd-meadowlands@dep.nj.gov

Welcome

Presentation

Opening Remarks (10 Minutes)

Welcoming (Linda Fisher, NJDEP)

Agenda (Chris Benosky, AECOM)

Meadowlands Challenge (Garrett Avery, AECOM)

Purpose & Need

Screening Process

Project Roadmap

Alternative 1 Storm Surge Flooding: (Lulu Loquidis, AECOM)

Alternative 2 Frequent Rain Flooding: (Garrett Avery, AECOM)

Alternative 3 Storm Surge & Frequent Rain Flooding: (Garrett Avery & Lulu Loquidis, AECOM)

Build Plan

Future Plan

Next Steps & Q&A/Closure (Chris Benosky, AECOM)

Next Steps

Question and Answers

REBUILDBYDESIGN

MEADOWLANDS

CITIZENS ADVISORY GROUP MEETING

ALTERNATIVES 1, 2, & 3
OCTOBER 17, 2017

AECOM

AGENDA


Christopher Benosky, AECOM 2

- Welcome
- The Meadowlands Challenge
- Alternative 1
- Alternative 2
- Alternative 3
 - Build Plan
 - Future Plan
- Next Steps
- Question & Answer

**REBUILD BY DESIGN MEADOWLANDS****CAG Meeting #11 // October 17, 2017****AECOM**

THE MEADOWLANDS - A COMMUNITY AT RISK

3



- Nearly all the project area is within the 100-year floodplain

100-Year Floodplain



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

TWO MAIN CHALLENGES

4

1

Challenges from **MAJOR STORM SURGE** flooding

2

Challenges from **FREQUENT RAIN** flooding



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

CHALLENGE 1: STORM SURGE FLOODING

5



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

CHALLENGE 2: FREQUENT RAIN FLOODING

6



REBUILD BY DESIGN MEADOWLANDS


CAG Meeting #11 // October 17, 2017

AECOM

7

THE MEADOWLANDS CHALLENGE

The Meadowlands sits at a low elevation in relation to sea level. Protection from complex tidal influence and storm surge is limited. Existing storm infrastructure is under-performing and needs to be updated and maintained




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

8

EXISTING CHALLENGES INCREASE FLOODING RISK



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

RESILIENT SOLUTIONS TO RECOVER MORE QUICKLY



- Provides protection against frequent storm events and improved infrastructure for quicker recovery
- Photo: existing condition of existing tide gate at East Riser Ditch



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

TWO MAIN CHALLENGES

1

Challenges from **MAJOR STORM SURGE** flooding

2

Challenges from **FREQUENT RAIN** flooding




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

11

THE MEADOWLANDS - THREE ALTERNATIVES



Alternative 1:
Storm Surge Flooding

Alternative 2:
Frequent Rain Flooding

Alternative 3:
Storm Surge & Frequent
Rain Flooding



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

12

THE PURPOSE

ADDRESS FLOOD RISK

INCREASE RESILIENCY of the communities and ecosystems

REDUCE IMPACTS to critical infrastructure, residences, businesses, and ecological resources

*Purpose & Need from NOI and Public Scoping Document



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

THE NEED

13

ADDRESS systemic **INLAND FLOODING AND COASTAL FLOODING** from storm surges

INCREASE COMMUNITY RESILIENCY

REDUCE FLOOD insurance **RATES** and claims from future event

ENHANCE WATER QUALITY and protect ecological resources

PROTECT life, public health, and property

Incorporate flood hazard risk reduction strategy with **CIVIC, CULTURAL, AND RECREATIONAL VALUES**

*Purpose & Need from NOI and Public Scoping Document



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

PROJECT GOALS

14

1. Create the **BEST POSSIBLE PROJECT** with the available funding

2. Meets the Project Mandate by providing **FLOOD REDUCTION & CO-BENEFITS** such as reducing sediment & improving water quality

3. Construct a project that provides **STORM PROTECTION** and allows for a **QUICKER RECOVERY**



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

PROJECT CONSTRAINTS

1. Construct a complete project that functions as a **INDEPENDENT UTILITY** to meet purpose & need without relying on future projects
2. Use only **AVAILABLE FUNDS** without relying on future funding
3. Construct a fully-functional project by **SEPTEMBER 2022**




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

PROJECT ROADMAP



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

OUR PROCESS THE SCREENING TOOL

Concepts are screened against each other to determine how they will meet the below metrics



**FLOOD REDUCTION
BENEFITS**



**BUILT HUMAN
ENVIRONMENT**



**NATURAL
ENVIRONMENT**



**CONSTRUCTION
& MAINTENANCE**



**COST
& BENEFIT**



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

FLOOD REDUCTION BENEFITS



Categories Evaluated:

- Reduces Flood Risk from Coastal Storm Surge (Alternatives 1 and 3)
- Reduces Flood Risk from Rainfall /Interior Drainage Challenges (Alternatives 2 and 3)
- Provides Protection to Vulnerable and Underserved Populations
- Provides Protection to Critical Infrastructure (emergency services, hospitals, transit facilities)



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

19

BUILT HUMAN ENVIRONMENT



Categories Evaluated:

- Effects to Existing Utilities & Utility Infrastructure
- Effects to Existing Transportation Network, Local Traffic, and Connectivity
- Effects on Land Acquisition / Housing Displacements
- Potential to Provide Increased Waterfront Access
- Effects to Recreational, Civic, and Cultural Amenities and Uses
- Effects to Viewshed and Local Visual Quality
- Effects to Air Traffic Safety at Teterboro Airport



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017 **AECOM**

20

NATURAL ENVIRONMENT



Categories Evaluated:

- Effects to Existing Hazardous Waste Sites
- Effects to Berry's Creek Remediation
- Effects on the Transport of Environmental Contaminants/ Sediments during Flood Events
- Effects to Water Resources, including Water Quality, "Waters of the US," Wetlands, and Mitigation Banks
- Effects to Fisheries and Essential Fish Habitat (EFH)
- Effects on Protected Species and their Habitats
- Effects on Other Sensitive Ecological Resources, including Biodiversity, Habitat, and Migration/Movement Corridors
- Effects to Historic and Prehistoric Cultural Resources



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017 **AECOM**

CONSTRUCTION & MAINTENANCE

21



Categories Evaluated:

- Constructability
- Minimizes Long-Term Maintenance & Operation Requirements for Overall System
- Potential to Complete by September 2022



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

BENEFIT & COST

22



Categories Evaluated:

- Provides Benefits to the Project Area and Community
- Can be Implemented within Available Funding Limits
- Has a Positive Benefit/Cost Ratio



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

STORM SURGE FLOODING

ALTERNATIVE 1 LULU LOQUIDIS, AECOM


AECOM

ALTERNATIVE 1 STORM SURGE - **PROTECT** APPROACH & GOALS

24

+ INFRASTRUCTURE

By connecting the existing topographical high points, the project can reduce construction costs and minimize additional regrading of the Hackensack River edge



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017


AECOM

ALTERNATIVE 1 STORM SURGE - CULTIVATE APPROACH & GOALS

+ INFRASTRUCTURE

+ ECOLOGY

The ecological systems are essential to the Meadowlands. The approach will minimize disturbance, consider habitat improvements to fragmented systems, and creation of new ecological zones



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM


ALTERNATIVE 1 STORM SURGE - ENERGIZE APPROACH & GOALS

+ INFRASTRUCTURE

+ ECOLOGY

+ PARKS

As a co-benefit to flood reduction, the project seeks to connect existing public parks as well as provide new park space on existing public land




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 1 STORM SURGE - ANALYSIS HIGH POINTS

27



- Existing topography was analyzed to determine water flow and identify areas of high ground




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 1 STORM SURGE - ANALYSIS SOILS & SUB-STRUCTURE

28



- All proposed flood protection strategies were informed by geo-technical analysis
- The soil type helped the team determine how deep the piles and sub-structure needed to extend

Data Source:
USDA WSS AOI Web Soil Survey
<http://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 1 STORM SURGE – SCREENING OF CONCEPTS PROVIDING PROTECTION TO A 7' ELEVATION

Initial Concepts	Description	Within Budget	No Increased Flood Risk	Benefit Cost Ratio >1
Option 1	100-year Storm Protection/ Expanded Project Area	X	●	●
Option 2	100-year Storm Protection/ Project Area	X	●	●
Option 3	50-year Level of Protection/ Project Area	●	●	●
Option 4	Ring Levees/ Reduced Project Area	●	●	X
Option 5	Storm Surge Barrier on Hackensack River	X	X	●

50-YEAR LEVEL OF PROTECTION ADVANCES

- Explored many options to a 100-year flood, but all resulted in a fatal flaw
- The 7' NAVD88 design elevation was further analyzed




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 1 STORM SURGE - PLAN



- Provides protection from a storm surge to elevation 7' NAVD88 (approximately a 50-yr storm)
- Provides community co-benefits through water access & multifunctional wall elements
- Positive Benefit Cost Ratio greater >1
- Revised Feasibility-level concept cost exceeds \$150M

- 1 Existing Riverwalk
- - - 2 Sheet Pile Cantilever
- ⊗ 3 Berms at Fluvial Park
- 4 Cantilever Walkway
- 5 Sheet pile or Floodwall
- 6 Surge Barrier



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

31

CANTILEVER WALKWAY

CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- The Cantilever Walkway combines flood protection and public access



- 1 Public walk
- 2 Modular planter
- 3 Cantilever access
- 4 Recreational space



REBUILD BY DESIGN MEADOWLANDS


CAG Meeting #11 // October 17, 2017

AECOM

32

FLOOD PROTECTION

CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- The entire structure is built up to a 7' NAVD88 elevation



- 1 Flood protection system
- 2 Newly-created tidal wetland



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017


AECOM

33

VIEWING PLATFORM & SHEET PILE CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- Sheet pile is a cost effective material used in the southeast
- Public viewing platforms were integrated into the system



- 1 Viewing deck
- 2 Wetland




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017


AECOM

34

FLOOD PROTECTION CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- Sheet pile wraps around viewing platform to form the flood protection system



- 1 Sheet pile



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

FREQUENT RAIN FLOODING

ALTERNATIVE 2 GARRETT AVERY, AECOM


AECOM

ALTERNATIVE 2 FREQUENT RAIN FLOODING - **PROTECT** APPROACH & GOALS

36

+ INFRASTRUCTURE

Through enhancement and restoration, the existing channels of the project area will have capacity to convey stormwater away from flood-prone areas




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 2 FREQUENT RAIN FLOODING - **CULTIVATE** 37

APPROACH & GOALS



+ INFRASTRUCTURE

+ ECOLOGY

Native plantings and naturalized channel edges provide habitat and improve water quality




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 2 FREQUENT RAIN FLOODING - **ENERGIZE** 38

APPROACH & GOALS



+ INFRASTRUCTURE

+ ECOLOGY

+ PARKS

New park spaces are integral to the water management system; both by slowing runoff and improving water quality



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017


AECOM

ALTERNATIVE 2 FREQUENT RAIN FLOODING -ANALYSIS

39

20 SUB-BASINS

- Analyzed 20 sub-basin areas in the hydrologic model



----- Sub-basin



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017


AECOM

ALTERNATIVE 2 FREQUENT RAIN FLOODING -ANALYSIS

40

FREQUENCY & FLOW

- Runoff flows to lower elevations, into creeks or ditches and is conveyed eventually into the Hackensack River or Berry's Creek
- We listened to the community members and used their input to map areas of frequent flooding



- Floods in regular event
- Floods in heavy event
- Floods in major event
- Primary conveyance direction
- Sub-basin



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

41

ALTERNATIVE 2 FREQUENT RAIN FLOODING SCREENING

Initial Concepts	Description	Within Budget	Distribution of Benefits	Benefit Cost Ratio > 1
Main Street	Increase storage capacity at Indian Lake, improves storm drainage pipes, includes upgrades to existing Willow Lake pump station discharge line, and new street and park green infrastructure	●	X	X
DePeyster Creek	Upgrade of existing pump station, upgrades of existing upstream culvert, channel dredging with habitat restoration, and new street and park green infrastructure	●	●	X
Losen Slote & Carol Place	Two new pump stations and force mains to divert stormwater from residential area to downstream of Losen Slote, upgrades to existing storm drainage ditches and culverts, and new street and park green infrastructure	●	●	X
West Riser	New pump station, channel conveyance improvements with habitat restoration, culvert upgrades, and new street green infrastructure.	●	X	●
East Riser	Pump station improvements, channel conveyance improvements with habitat restoration, culvert and bridge upgrades, and new street and park green infrastructure.	X	●	●
Revised Concept	New pump station and force mains to divert stormwater from residential area to downstream of Losen Slote, upgrades to culverts and bridge crossings, East Riser Ditch conveyance improvement and new pump station, and new street and park green infrastructure	●	●	●

- Top concepts were reviewed and evaluated using the screening criteria
- The Revised Concept was a result of reviewing and rearranging to create a concept carrying increased benefits

REVISED CONCEPT ADVANCES




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 2 – FREQUENT RAIN FLOODING PLAN

42



- Reduction in areal extent of flooding and depth of flooding for fluvial storms of a recurrence interval of 100-yr or less
- Provides community co-benefits through green infrastructure
- Positive Benefit Cost Ratio greater > 1
- Revised Feasibility-level concept cost exceeds \$150M

- ① East Riser Channel Improvements + New Park
- ② Green Infrastructure + New Park
- ③ Force Main + Public Facility Improvements
- ④ Green Infrastructure + New Park
- ⑤ Park Improvements + 3 New Parks + Green Infrastructure




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

LOSEN SLOTE DRAINAGE IMPROVEMENTS CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES

43



- New pump stations improve conveyance capacity by moving water from one location to another



- 1 Submersible pump
- 2 36" force main
- 3 Losen Srote
- 4 Control panel



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

GREEN INFRASTRUCTURE & PARK IMPROVEMENTS CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES

44



- Wetland enhancement, improves storage and treatment capacities, and improves public recreation opportunity



- 1 Elevated boardwalk
- 2 Channel improvements
- 3 Shallow emergent marsh
- 4 Atlantic White Cedar



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM


STORM SURGE & FREQUENT RAIN FLOODING

ALTERNATIVE 3 - HYBRID GARRETT AVERY & LULU LOQUIDIS, AECOM

AECOM

ALTERNATIVE 3 – A PLAN FOR BOTH CHALLENGES

46



- ① East Riser Channel Improvements + New Park
- ② Green Infrastructure + New Park
- ③ Force Main + Public Facility Improvements
- ④ Green Infrastructure + New Park
- ⑤ Park Improvements + 3 New Parks + Green Infrastructure

- ① Existing Riverwalk
- ② Sheet Pile Cantilever
- ③ Berms at Fluvial Park
- ④ Cantilever Walkway
- ⑤ Sheet pile or Floodwall
- ⑥ Surge Barrier




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017


AECOM

ALTERNATIVE 3 HYBRID - THE BUILD & FUTURE PLAN



Build Plan

The *Build Plan* represents a feasible project that can be **constructed by 2022**. Components include flood reduction strategies to address frequent rain flooding



Future Plan

Components that were not selected for the *Build Plan* became elements of a *Future Plan*. These elements could be **implemented** by others **over time** as new funding sources become available




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 3 - BUILD PLAN FREQUENT FLOOD REDUCTION



- ① Pump station + Channel Improvements + New Park
- ② Green Infrastructure + New Park
- ③ Pump Station + Force Main + Public Facility Improvements
- ④ Green Infrastructure
- ⑤ Park Improvements + 1 New Park + Green Infrastructure

- Channel Improvements
- Force Main Improvements
- New Pump Stations
- Street Green Infrastructure
- Created Wetlands
- GI & Open Space Improvements




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

FOR FUTURE IMPLEMENTATION ADDITIONAL RAIN FLOODING REDUCTION FROM ALTERNATIVE 2

49



- ① East Riser Channel Improvements Extension toward South Hackensack
- ② A second Losen Slote Pump Station & Force Main




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

FOR FUTURE IMPLEMENTATION 50-YEAR STORM SURGE PROTECTION FROM ALTERNATIVE 1

50



- ① Existing Riverwalk
- ② Sheet Pile Cantilever
- ③ Berms at Fluvial Park
- ④ Cantilever Walkway
- ⑤ Sheet pile or Floodwall
- ⑥ Surge Barrier




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

ALTERNATIVE 3 - BUILD PLAN

51



- The Build Plan can be constructed and functional by 2022
- The plan put forth will require less maintenance than that of an Alternative 1 system
- Positive Benefit Cost Ratio greater >1
- Plan can be constructed within Available Funds

- ① East Riser Channel Improvements + New Park
- ② Green Infrastructure + New Park
- ③ Force Main + Public Facility Improvements
- ④ Green Infrastructure
- ⑤ Park Improvements + 1 New Park + Green Infrastructure




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

EAST RISER CHANNEL IMPROVEMENTS PROTECT

52



- Channel conveyance improvements below Moonachie Ave with a new pump station
- New wetland eco-park with ~12,000 SF of integrated green infrastructure and ~129,000 SF of wooded and emergent wetland to improve storage and water quality



REBUILD BY DESIGN MEADOWLANDS


CAG Meeting #11 // October 17, 2017

AECOM

53

EAST RISER CHANNEL IMPROVEMENTS

CULTIVATE & ENERGIZE



- Channel conveyance improvements include **habitat restoration with native vegetation**
- New wetland eco-park is part of the flood reduction system, but also offers benefits in the form of **habitat, environmental education, and recreation space**




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

54

EAST RISER CHANNEL IMPROVEMENTS CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- Improves conveyance capacity
- Captures road runoff and filters suspended solids
- Native vegetation provides habitat and improves visual quality along the channel

- 1 Gravel trench
- 2 Channel improvement
- 3 Native vegetation
- 4 Curb cut



REBUILD BY DESIGN MEADOWLANDS


CAG Meeting #11 // October 17, 2017

AECOM

LOSEN SLOTE DRAINAGE IMPROVEMENTS

PROTECT

55



- **New pump station** within the residential area of the stream
- Stormwater discharges via a **36" force main** to the downstream Loosen Srote marsh
- **Energy dissipation structure** limits erosion at discharge points
- Street green infrastructure **collects water** and **filters** total suspended solids



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

LOSEN SLOTE DRAINAGE IMPROVEMENTS

CULTIVATE & ENERGIZE

56



- 36" force main is located in the subsurface of the **public right-of-way**
- Green infrastructure benefits include **improved water quality**, new habitat, and **visual improvements**




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

57

LOSEN SLOTE DRAINAGE IMPROVEMENTS CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- A new pump station improves conveyance capacity by moving water from one location to another

- 1 Submersible pump
- 2 36" force main
- 3 Lozen SLOTE
- 4 Control panel




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

58

AVANTI PARK PROTECT



- **Water is stored** in new open space and green infrastructure
- ~19,000 SF of **improved wetland** and ~11,000 SF of native planting and raingardens **capture total suspended solids**




REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

59

AVANTI PARK CULTIVATE & ENERGIZE



- Street green infrastructure **improves water quality**, creates new habitat, and **provides visual improvements**
- New park space also creates places for people to gather, **new habitat**, and space for **recreation**



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

60

AVANTI PARK CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- Bioretention systems capture and filters 1.25 inches of rainfall in two hours through planting media
- New retention areas create room for additional water storage
- Undeveloped land becomes public park and productive ecosystem

- 1 Boardwalk foundation
- 2 Headwall & inlet pipe
- 3 Energy dissipator
- 4 Native planting
- 5 Integrated seating



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

STREET GREEN INFRASTRUCTURE CONCEPTUAL RENDERING FOR ILLUSTRATIVE PURPOSES



- Green infrastructure provides a holding space for street runoff that is slowly released back into the stormwater system
- Subsurface green infrastructure features provide storage and ability to infiltrate runoff to reduce peak flow reaching the existing stormwater system

- 1 Connection to storm system
- 2 Filter media
- 3 Native vegetation
- 4 Street Trees



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM


NEXT STEPS

CHRISTOPHER BENOSKY, AECOM

AECOM

UPCOMING SCHEDULE

63



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

NEXT STEPS

64

NJDEP / AECOM: UPCOMING ACTIVITIES

- Recommended Alternative **Public Meeting December 2017**
 - Alternative 1 – Storm Surge Flooding
 - Alternative 2 – Frequent Flood Reduction
 - Alternative 3 – Hybrid Alternative
- Draft Environmental Public Hearing in **Winter/Spring 2018**



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

NEXT STEPS

65

CAG: CALL TO ACTION

- Submit comments from CAG #11 meeting by **October 24, 2017**
- Share information from this meeting with friends and neighbors
- Continue to build interest in the Project
- Ensure the public knows about upcoming information (to be posted on Project website)



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

NEXT STEPS

66

Critical Information

Project Website

www.rbd-meadowlands.nj.gov

Project Email

rbd-meadowlands@dep.nj.gov

Question & Answer



REBUILD BY DESIGN MEADOWLANDS

CAG Meeting #11 // October 17, 2017

AECOM

4.0 Personal Notes

This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.

CAG MEETING #11 // OCTOBER 17, 2017 | 39

This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.