


## NEW JERSEY GEOLOGICAL SURVEY GEOLOGICAL SURVEY REPORT 18

# Hydraulic Properties of the Middle and Upper Aquifers of the Potomac-Raritan-Magothy Aquifer System in the Northern Coastal Plain of New Jersey





#### STATE OF NEW JERSEY

Thomas H. Kean, Governor

Department of Environmental Protection

Christopher J. Daggett, Commissioner

Environmental Management and Control Donald A. Deieso, Assistant Commissioner

Division of Water Resources
Jorge H. Berkowitz, Acting Director

Geological Survey Haig F. Kasabach, State Geologist

# Hydraulic Properties of the Middle and Upper Aquifers of the Potomac-Raritan-Magothy Aquifer System in the Northern Coastal Plain of New Jersey

by
Amleto A. Pucci, Jr., Jo Ann Gronberg, and Darryl A. Pope
U.S. Geological Survey
West Trenton, New Jersey

Prepared by the
United States Geological Survey
in cooperation with the
New Jersey Department of Environmental Protection
Division of Water Resources

New Jersey Department of Environmental Protection
Division of Water Resources
Geological Survey
CN-029
Trenton, New Jersey 08625

Geological Survey Reports (ISSN: 0741-7357) are published by the New Jersey Geological Survey, CN-029, Trenton, NJ 08625. This report may be reproduced in whole or part provided that suitable reference to the source of the copied material is provided. Additional copies of this and other reports may be obtained from:

Maps and Publications Sales Office Bureau of Revenue CN-402 Trenton, NJ 08625

A price list is available on request.

Use of brand, commercial, or trade names is for identification purposes only and does not constitute endorsement by the New Jersey Geological Survey.

#### CONTENTS

	Page
Abstract	. 1
Introduction	. 1
Purpose and scope	. 2
Location of the study area	. 2
Previous investigations	. 2
Hydrogeology	. 5
Well-numbering system	. 9
Acknowledgments	. 9
Methods of investigation	. 9
Aquifer tests	. 10
Data	. 10
Methods of interpretation	. 15
Middle aquifer of the Potomac-Raritan-Magothy aquifer	
system	. 16
Upper aquifer of the Potomac-Raritan-Magothy aquifer	
system	. 16
Well-acceptance tests	. 17
Data	
Method of interpretation	. 17
Results of hydraulic properties from previous investigations	. 21
Results of aquifer and well-acceptance tests	. 22
Hydraulic properties of the middle aquifer of the Potomac-Raritan-	
Magothy aquifer system	. 22
Hydraulic properties of the upper aquifer of the Potomac-Raritan-	
Magothy aquifer system	. 25
Summary	. 27
Selected References	. 28
Glossary	. 32
Appendix 1. Graphs showing water-level data from aquifer tests	. 35
Appendix 2. Graphs showing water-level data from aquifer tests and	
finite- element simulations	. 65
ILLUSTRATIONS	
Plate 1. Aquifer-test and well-acceptance-test site locations	
for the middle aquifer, Potomac-Raritan-Magothy	
aquifer system	.In
Pe	ocket
<ol><li>Aquifer-test and well-acceptance-test site locations</li></ol>	
for the upper aquifer, Potomac-Raritan-Magothy	
aquifer system	.In
	ocket
Figure 1. Location map of study area, and wells and lines of	
hydrogeologic sections (A-A', B-B') of the Potomac-	
Raritan-Magothy aquifer system	. 3
2. Hydrogeologic sections of the northern Coastal Plain	-
of New Jersey: A-A' and B-B'	. 7

#### ILLUSTRATIONS - - Continued

			Page
	3.	Histograms of mean transmissivities for aquifer	
		tests in the middle and upper aquifers of the	
		Potomac-Raritan-Magothy aquifer system	23
	4.		. 25
		from well-acceptance tests for the middle and upper	
		aquifers of the Potomac-Raritan-Magothy aquifer system	24
Figures	5 - 32	2 in appendix 1. Graphs of:	
Ū		Drawdown in observation well 23-392 for aquifer	
		test 1	37
	6.	Drawdown in pumping well 23-42 for aquifer test 2	. 3, 3,8
	7.	Drawdown in observation well 23-43 for aquifer	. 50
		test 2	30
	8.	Drawdown in pumping well 23-40 for aquifer test 3	. 40
	9.	Recovery in observation well 23-41 for aquifer	. 40
		test 3	41
•	10.	Drawdown in pumping well 23-44 for aquifer test 4	. 41
	11.	Drawdown in observation well 23-789 for aquifer test 4	. 42
	12.	Drawdown in observation well 23-788 for aquifer test 5	. 43
	13.	Drawdown in observation well 23-384 for aquifer test 6	. 44
	14.	Drawdown in observation wells 21-86 and 21-144 for	. 43
		aquifer test 7	1.6
	15.	Drawdown in observation well 23-197 for aquifer test 9	. 40
	16.	Drawdown in observation wells 23-127 and 23-171 for	. 4/
		aquifer test 11	48
	17.	Drawdown in observation well 23-474 for aquifer test 12	. 40 //Q
	18.	Distance-drawdown relation when well 23-621 was	. 47
		pumped for 164 hours in aquifer test 14	50
:	19.	Distance-drawdown relation when well 23-626 was	. 50
		pumped for 70 hours in aquifer test 15	51
	20.	Drawdown in test well 25-551 for aquifer test 16	52
	21.	Drawdown in observation well 25-550 for aquifer test 16	. 52 53
	22.	Drawdown in observation wells 21-81 and 21-86 for	. ,,
		aquifer test 17	5/4
	23.	Drawdown in test well 23-690 for aquifer test 18	. 55
	24.	Drawdown in observation well 23-684 for aquifer test 18	. 56
	25.	Drawdown in observation wells 25-289, 25-290, and 25-291	. 30
		for aquifer test 19	. 57
:	26.	Drawdown in observation wells 25-68 and 25-69 for	. 3,
		aquifer test 21	. 58
	27.	Drawdown in observation wells 23-595 and 23-596 for	. 50
		aquifer test 22	. 59
:	28.	Drawdown in test well 23-602 for aquifer test 23	. 60
:	29.	Drawdown in observation well 23-121 for aquifer test 24	61
•	30.	Distance-drawdown relations when well 23-743 was pumped for	
		48 hours in aquifer test 25	. 62
	31.	Drawdown in observation well 23-448 for aquifer test 26	. 02 63
	32.	Drawdown in observation wells 25-206 and 25-207 for	. 05
		aquifer test 27	64

#### ILLUSTRATIONS - - Continued

rag	55
Figures 33-39 in appendix 2.	
33. Model grid representing aquifer section for aquifer test 8	
conductivity values used in final model	9
Figures 35-39 Drawdown from field measurements and simulations results for: 35. Observation well 25-269 for aquifer test 8	0 1 2 3
TABLES	
Table 1. Geologic and hydrogeologic units in the Coastal Plain of New Jersey	6
<ol> <li>Lithologic subdivisions of the Raritan and Magothy Formations         and hydrogeologic units in and near the outcrop</li></ol>	8
storage coefficient	0
aquifer system	1
aquifer system	3
Raritan-Magothy aquifer system	
Raritan-Magothy aquifer system	9

#### CONVERSION FACTORS AND ABBREVIATIONS

For use of readers who prefer to use metric units (International System) conversion factors for the inch-pound terms used in this report are listed below:

<del></del>		<del></del>
Multiply Inch-Pound Uni	t By	To obtain Metric Unit
	<u>Length</u>	
<pre>inch (in.) foot (ft)</pre>	25.4 0.3048	millimeter (mm) meter (m)
	<u>Area</u>	
square mile (mi²)	2.59	square kilometer (km²)
	<u>Volume</u>	
gallon (gal)	.003785	cubic meter (m³)
	<u>Flow</u>	
foot per day (ft/d) foot squared per day (ft²/d)	0.3048 0.09294	meter per day (m/d) meter squared per day (m²/ d)
gallon per minute (gal/min)	0.000063	cubic meter per second (m <sup>3</sup> /s)
<pre>gallon per minute    per foot   ((gal/min)/ft)</pre>	0.0000192	<pre>cubic meter per second    per meter   ((m³/s)/m)</pre>

<u>Sea Level</u>: In this report "sea level" refers to the National Geodetic Vertical Datum of 1929 (NGVD of 1929) -- a geodetic datum derived from a general adjustment of the first-order level nets of both the United States and Canada, formerly called "Sea Level Datum of 1929."

# HYDRAULIC PROPERTIES OF THE MIDDLE AND UPPER AQUIFERS OF THE POTOMAC-RARITAN-MAGOTHY AQUIFER SYSTEM IN THE NORTHERN COASTAL PLAIN OF NEW JERSEY

By Amleto A. Pucci, Jr., Jo Ann M. Gronberg, and Daryll A. Pope

#### ABSTRACT

Data from 27 aquifer tests were analyzed to determine the transmissivities, hydraulic conductivities, and storage coefficients of the middle and upper aquifers, and the leakances of the intervening confining units of the Potomac-Raritan-Magothy aquifer system in the northern Coastal Plain of New Jersey. Hydraulic conductivities also were estimated from 147 well-acceptance tests for these aquifers.

The transmissivity ranges, determined from the aquifer tests, are 2,140 to 13,800 feet squared per day in the middle aquifer, and 1,760 to 19,400 feet squared per day in the upper aquifer. Storage coefficients range from  $2.6 \times 10^{-5}$  to  $3.4 \times 10^{-3}$  for the confined middle aquifer, and from  $1.0 \times 10^{-5}$  to  $1.8 \times 10^{-3}$  in the confined upper aquifer. Storage coefficients for the unconfined parts of the upper aquifer range from  $3.7 \times 10^{-3}$  to  $5.7 \times 10^{-1}$ . The ranges of lateral hydraulic conductivities, from aquifer tests and well-acceptance tests, are from 17 to 385 feet per day in the middle aquifer, and from 4 to 483 feet per day in the upper aquifer. Variability in hydraulic conductivity was found to be higher in or near the outcrops. The largest hydraulic conductivity values were concentrated in or near the outcrop areas of both aquifers. Greater leakage between the middle and upper aquifers is likely to occur in the southwest of the study area where the confining unit between the middle and upper aquifers is thin or is sandy.

#### INTRODUCTION

The U.S. Geological Survey, in cooperation with the New Jersey Department of Environmental Protection (NJDEP), is investigating the water-bearing properties of the middle and upper aquifers of the Potomac-Raritan-Magothy aquifer system of the northern Coastal Plain of New Jersey (fig.1). This investigation is part of a 5-year evaluation of the ground-water resources of the region (Leahy and others, 1987).

The middle and upper aquifers of the Potomac-Raritan-Magothy aquifer system in central New Jersey are the main focus of the investigation for three reasons:

- 1. The Potomac-Raritan-Magothy aquifer system is the most productive ground-water resource in the region, accounting for 100 percent of ground-water withdrawals from Coastal Plain resources in Middlesex County and 72 percent in Monmouth County (Vowinkel, 1984).
- 2. Extensive ground-water withdrawals from the Potomac-Raritan-Magothy aquifer system have resulted in deep cones of depression in the potentiometric surface of both the middle and upper aquifers. In 1983, in the middle aquifer, ground-water levels in the center of

the cone of depression in northern Monmouth County were 91 feet below sea level (Eckel and Walker, 1986, table 3). In 1983, water levels in the upper aquifer were 59 feet below sea level in areas of Monmouth County (Eckel and Walker, 1986, table 4).

3. Saltwater intrusion has been induced in both aquifers due to these cones of depression (Schaefer, 1983).

#### Purpose and Scope

The purpose of this study is to determine the hydraulic properties-transmissivity, hydraulic conductivity and, where possible, storage coefficients--for the middle and upper aquifers of the Potomac-Raritan-Magothy aquifer system in the northern New Jersey Coastal Plain. These values will be used in a computer simulation of the regional ground-water flow system.

This report summarizes the hydraulic properties of the middle and upper aquifers determined from aquifer tests at 27 sites and from well-acceptance tests at 147 locations. The aquifer-test data were solicited from consultants and water-supply companies. Analytic and finite-element numerical methods (Reilly, 1984) were used to evaluate the aquifer tests. Well-acceptance-test data were derived from existing computer files in the U.S. Geological Survey Ground Water Site Inventory data base. The methods of interpretation and test data are summarized.

#### Location of the Study Area

The study area, which covers approximately 400 square miles in the northern New Jersey Coastal Plain, is located in Middlesex, Monmouth, and eastern Mercer Counties. The western boundary of the study area is the Fall Line--the physiographic boundary between the Triassic and Jurassic rocks of the Appalachian Highlands and the unconsolidated sediments of the Atlantic Coastal Plain. The study area is bounded to the north by the Raritan Bay and to the east by the Atlantic Ocean. The southern boundary is an arbitrary southeast trending line running from the vicinity of Hightstown to the Atlantic Ocean (fig.1).

#### Previous Investigations

Several studies have addressed the ground-water resources of the Potomac-Raritan-Magothy aquifer system in the northern part of the New Jersey Coastal Plain. Vermeule (1884) first described the water supplies of the area. Barksdale (1937) discussed the geology and hydrology of the Farrington Sand near Parlin in Middlesex County. Barksdale and others (1943) extended the investigation, within Middlesex County, to all the major aquifers of the county. Appel (1962) reported on saltwater intrusion into the Farrington (middle) and Old Bridge (upper) aquifers in the northwest part of the study area. Parker and others (1964) included a description of the ground-water resources of the study area in a report on the Delaware River Basin. Jablonski (1968) discussed the major aquifers in Monmouth County. Hasan and others (1969) discussed the Old Bridge aquifer in the Sayreville area of Middlesex County. The Potomac-Raritan-Magothy aquifer system in the New Jersey Coastal Plain was described by Gill and Farlekas



#### **EXPLANATION**

#### MIDDLE AQUIFER OUTCROP

Outcrop area of the Old Bridge Sand Member of the Magothy Formation--Dashed where approximately located. (Modified from Barksdale and others, 1943, p. 21.)

#### UPPER AQUIFER OUTCROP

Outcrop area of the Farrington Sand

Member of the Raritan Formation-Dashed where approximately located.

(Modified from Barksdale and others,
1943, p. 21.)

●25-547 Well location and USGS well number




Figure 1.--Location of study area, and wells and lines of hydrogeologic sections (A-A', B-B') of the Potomac-Raritan-Magothy aquifer system.

(1976). Farlekas (1979) presented the geohydrology and a simulation of the Farrington (middle) aquifer in Middlesex and Monmouth Counties. Zapecza (1984) included the area in his report on the hydrogeologic framework of the New Jersey Coastal Plain. Pucci (1986) presented a summary of published and unpublished reports and data on the hydrogeology of the northern part of this study area.

#### **Hydrogeology**

The sediments of the Potomac Group, and the Raritan and Magothy Formations make up the Potomac-Raritan-Magothy aquifer system (table 1). Generally, this aquifer system is divided into lower, middle, and upper aquifers separated from each other by confining units (Zapecza, 1984, p. 14). However, in the study area this aquifer system consists only of the middle and upper aquifers (fig. 2); the lower aquifer is not present. In the northern part of the study area, the sediments of the Raritan and Magothy Formations have been subdivided into nine distinct units on the basis of economic importance (Ries and others, 1904, p. 166; Barksdale and others, 1943, p. 18). The lithologic subdivision of the Raritan and Magothy Formations and hydrogeologic units in and near the outcrop area are shown in table 2. Locally, the middle aquifer is known as the Farrington aquifer, and the upper aquifer is known as the Old Bridge aquifer (Farlekas, 1979).

Locally in updip parts of the study area the confining unit underlying the middle aquifer can consist of the Raritan fire clay, pre-Cretaceous bedrock, and saprolitic clay. Where present, the fire clay is a massive, multicolored clay that grades transitionally into the saprolitic clay that rests on bedrock (Ries and others, 1904, p. 192). In downdip areas the confining unit underlying the middle aquifer is composed primarily of fine grained sediments of the Potomac Group.

The middle aquifer is composed of the Farrington Sand Member of the Raritan Formation. In most of the study area, this sand member is characterized by sand, gravel, and lenses of clay. Locally in Monmouth County, the middle aquifer also includes the uppermost sand deposits of the Potomac Group (Farlekas, 1979, p. 9). According to Zapecza (1984, p. 17), the aquifer ranges in thickness from less than 50 feet in the outcrop area to more than 150 feet near the junction of Mercer, Middlesex, and Monmouth Counties.


The confining unit between the middle and upper aquifers is formed chiefly by the Woodbridge Clay Member of the Raritan Formation. The Woodbridge Clay Member is made up of micaceous silt and clay (Owens and Sohl, 1969, p. 239). Locally, it also includes the clayey lithofacies of the Sayreville Sand Member and the South Amboy Clay Member of the Raritan Formation (Farlekas, 1979, p. 16). This unit thickens from less than 50 feet in the outcrop area to more than 150 feet downdip (Zapecza, 1984, p. 18).


Locally, the upper aquifer includes the Old Bridge Sand Member and the Sayreville Sand Member where the South Amboy Fire Clay Member is thin or missing (Farlekas, 1979, p. 22). It consists chiefly of coarse-grained sand and gravel. Further downdip the upper aquifer coincides closely with the entire Magothy Formation. The thickness of this unit ranges from

Table 1.-- Geologic and hydrogeologic units in the Coastal Plain of New Jersey

STSIEN	SERIES	GEDLOGIC UNIT	LITHOLOGY	HYDR	OGEOLOGIC UNIT	HYDROLOGIC CHARACTERISTICS			
1		Alluvial deposits	Sand, silt, and black mud.		_				
uaternary	Halocene	Beach sand and gravel	Sand, quartz, light-colored, medium-to coarse- grained, pebbly.	Undi tia	fferen- ted	Surficial material, commonly hydraulicall connected to underlying aquifers. tocally some units may act as confining units. Thicker sands are			
	Pleistocene	Cape May Formation				capable of yielding large quantities of water.			
		Pensauken Formation	Send, quarts, light-colored, heterogeneous clayey, pebbly.						
		Bridgeton Formation							
		Seacon Hill Gravel	Gravel, quartz, light colored, sandy.	Kirki Cohar aqu sys	isey ifer	A major aquifer system. Ground water occurs generally under water-table conditions. In Cape May County the			
	Miocene	Cohensey Sand	Sand, quartz, light-colored, medium to coarse- grained, pebbly; local clay beds.			Cohansey Sand is under artesian conditions.			
(ertiary		Kirkwood Formation	Sand, quartz, gray and tan, very fine-to, medium-grained, micaceous, and dark- colored distomaceous clay.	Confining unit Rio Grande water bearing yong Confining unit Atlantic City 800-foot sand		Thick distomaceous clay bad occurs along coest and for a short distance inland, A thin water- bearing sand is present in the middle of this unit.			
						A major aquifer along the coast.			
						Poorly permemble sediments.			
	Oligocene	Piney Point Formation	Sand, quartz and glauconite, fine-to coarse-grained.	unit b	iney Point aguifer	Yields moderate quantities of water.			
	Eocene	Shark River Formation Manasquan Formation	Clay, silty and sandy, glauconitic, green, gray and brown, fine-grained quartz sand.	L	·	Poorty persemble sediments.			
	Paleocene	Vincentown Formation	Sand, quartz, gray and green, fine-to coarse- grained, glauconitic, and brown clayer, very fossiliferous, glauconite and quartz calcarents		incentown aquifer .	Yields smalt to moderate quantities of water in and near its outcrop area.			
		Hornerstown Sand	Sand, clayey, qlaucomitic, dark green, fine to coerse-grained.						
		Tinton Send	Sand, quartz, and glauconite, brown and gray.			Poorty permasble sediments.			
		Red Bank Sand	fine-to coarse-grained, clayey, micaceous.	Red Bank sand		Yields small quantities of water in and near its outcrop area.			
		Navesink Formation	Sand, clayery, silty, glauconitic, green and black, medium-to coarse-grained.	-		Poorly permeable sediments.			
		Mount Lauret Sand	Sand, quartz, brown and gray, fine-to coarse-grained, slightly glauconitic.	Hount	onah- Laurel ifer	A major squifer.			
		Venonah Formation	Sand, very fine-to fine-grained, gray and brown, silty, slightly glauconitic.	Marsh	alltown-				
		Marshalltown Formation	Clay, silty, dark greenish gray, glauconitic quartz sand.	confi	ah ning unit	A leaky confining unit.			
	Upper Cretaceous	Englishtown Formation	Sand, quartz, tan and gray, fine-to mediua- grained; local clay beds.		shtown ifer ten	A major equifer. Two sand units in Monmouth and Ocean Counties.			
		Woodbury Clay	Cley, gray and black, micaceous silt.			A Major continion unit   locally			
retaceous		Merchantville Formation	Clay, glauconitic, micaceous, gray and black: locally very fine-grained quartz and glauconitic sand.	Woodb	entville ury ning unit	A major confining unit. Locally the Merchantville Formation may contain a thin water-bearing sand.			
		Magothy Formation	Sand, quartz, light-gray, fine-to coarse- grained. Local beds of dark-gray lignitic clay.		Upper equifer				
		Raritan Formation	Sand, quartz, Light-gray, fine-to coarse- grained, pebbly, arkosic, red, white, and variegated clay.	nac-Raritan- thy aquifer ystem	Con- fining unit	A major acquifer system. In the morthern Coastal Flain, the upper acquifer is equivalent to the Old Bridge acquifer and the middle acquifer is equivalent to the Farrington acquifer. In the Delaware River Valley three acquifers are			
	Lower Cretaceous	Potomec Group	Atternating clay, sitt, sand, and gravel.	Potomac-I Magothy i	Con- fining unit Lower aquifer	River Valley three equifers are recognized. In the deeper sub- surface, units below the upper squifer are undifferentiated.			
Pre-Cri	etaceous	Bedrock	Precambrian and lower Paleozic crystalline rocks, metamorphic schist and gneiss; locally Triessic sandstone, shale and Jurassic basalt.	Sedro confli	:k ningunit	No wells obtain water from these consolidated rocks, except along Fall Line.			

Modified from Zapecza, 1984, table 1





#### **EXPLANATION**

25-566 U.S. Geological Survey well number

Datum is sea level

Hydrogeologic data from **Gronberg** and others (in press)

Figure 2.--Hydrogeologic sections of the northern Coastal Plain of New Jersey, A-A' and B-B'.

Table 2.--<u>Lithologic subdivisions of the Raritan and Magothy Formations and hydrogeologic units in and near the outcrop</u>

System	Geologi	c unit	Lithology	Mydrogeologic unit		
Cretaceous	a o gr Moro m ta Amb	ffwood beds gan beds oy Stoneware lay Member  Bridge Sand ember	Sand, quartz, light-gray, fine- to coarse- grained; local beds of dark-gray lignitic clay.	Potomac Raritan-	Confining unit	
	a o Cl r r i m Say t a Me a t n i Woo o M	th Amboy Fire ay Member reville Sand mber dbridge Clay ember rington Sand Member itan fire clay	Sand, quartz, light-gray, fine to coarse-grained, pebbly, arkosic, red white and variegated clay, and saprolitic clay developed on bedrock.	Magothy aquifer system <sup>1</sup>	Confining unit	
Pre-Cretaceous	Bed	rock	Precambrian and lower Paleozoic crystalline rocks, metamorphic shist and gneiss; locally Triassic, sandstone, shale and Jurassic basalt.	Bedro confin unit	ing	

Modified from Christopher, 1979, figure 2 and Zapecza, 1984, table 2.

<sup>&</sup>lt;sup>1</sup>To maintain consistent terminology, the aquifer-system name commonly used throughout New Jersey is used in this report. The lower aquifer is not mappable within the study area.

 $<sup>^2</sup>$ Locally the upper aquifer can include the Sayreville Sand Member where the South Amboy Fire Clay Member is thin or missing

approximately 50 feet in the outcrop area to more than 200 feet in southeastern Monmouth County (Zapecza, 1984, p. 18, and plate 11).

The confining unit which overlies the upper aquifer of the Potomac-Raritan-Magothy aquifer system is the Merchantville-Woodbury confining unit. It is composed mainly of the Merchantville Formation and the Woodbury Clay. The Merchantville Formation is made up of glauconite beds, and beds of micaceous clays and clayey silts (Zapecza, 1984, p. 19), while the Woodbury Clay is made up of massive clayey silt (Owens and Sohl, 1969, p. 242). This confining unit also locally includes the discontinuous Amboy Stoneware Clay Member and the Cliffwood and Morgan beds of the Magothy Formation. The thickness of this confining unit ranges from less than 200 feet near its outcrop to more than 300 feet in the Sandy Hook area (Zapecza, 1984, plate 12).

#### Well-Numbering System

The well-numbering system used in this report was developed by the New Jersey District of the U.S. Geological Survey. The first part of the number is a two-digit county code: 21 for Mercer, 23 for Middlesex, and 25 for Monmouth. The second part is a sequence number assigned to the well within the county. A representative well number is 23-236 for the 236th well inventoried in Middlesex County.

#### Acknowledgments

The authors would like to thank the following people for providing and permitting the publication of the aquifer test information: Gregory C. Fehrenbach, Administrator, Township of East Brunswick; Robert O. Harris, Health Officer, South Brunswick; William Iafe, Project Engineer, O & Y Old Bridge Development Corp.; Frederick E. Jahn, Township Administrator, Township of Freehold; Paul Kamber, Senior Vice President, Nestles Food Corporation; Martin E. Langenohl, Director, City of Perth Amboy, Department of Municipal Utilities; Harvey E. Lohr, Superintendent of Public Works, Borough of Spotswood; Raymond Martinelli, Water Commissioner, Borough of Hightstown; Donald J. Murphy, P.E., Managing Principal, Dames and Moore; Charles E. Robinson, Sr., P.E., Adtek Engineering Inc.; Michael A. Rogers, Executive Director, Monroe Township Municipal Utility Authority; August C. Schultes, P.E., President, A.C. Schultes and Sons; Russel G. Slayback, President, Leggette, Brashears, and Graham; Fred Trois, Director, Water Information Center, Geraghty and Miller; Peter S. Wersinger III, Esq., Attorney, Marlboro Township Municipal Utilities Authority; Hyman Bzura, President, Madison Industries; and Joseph M. DeSalvo, P.E., Senior Vice President, Converse Consultants, Inc.

#### METHODS OF INVESTIGATION

Hydraulic properties of the middle and upper aquifers were determined by two methods: (1) analysis of data from aquifer tests, and (2) analysis of data from well-acceptance tests. The transmissivity, hydraulic conductivity, and storage coefficient are hydraulic properties of an aquifer that can be determined from aquifer tests. Well-acceptance tests are used to test the productivity of a well and usually include specific-capacity data. Specific-capacity data can be used to estimate hydraulic conductivity

(McClymonds and Franke, 1972, p. 10). In general, the hydraulic-conductivity values estimated from the aquifer and well-acceptance tests fell within the range of values for sand and gravel published in several references (table 3).

Table 3.--Summary of average hydraulic conductivity and storage coefficient values

[ft/d=feet per day; a double dash (--) indicates data not available]

Reference	Lithologic description	Hydraulic conductivity	Storage coefficient (confined aquifer)
Davis, S.N., and De Wiest, R.J.M. (1966, p. 164)	Clean sands (good aquifers)	1 - 1,337 ft/d	
Freeze, R.A. and Cherry, John A. (1979, p29, p60	Clean sands	1 - 1,337 ft/d	5x10 <sup>-5</sup> to 5x10 <sup>-3</sup>
Todd, D.K. (1976, p.71)	Gravel, fine to sand, fine	8 - 1,476 ft/d	5x10 <sup>-5</sup> to 5x10 <sup>-3</sup>
Lohman, S.W. (1972, p.53)	Gravel, coarse to sand, very fine	3 - 1,000 ft/d	

Lithologic descriptions also can be used to estimate values of hydraulic conductivity. Well logs from the aquifer and well-acceptance tests for the middle and upper aquifers showed that these aquifers are composed of fine-to-coarse sands. The lithologic descriptions at each aquifer-test site are included in the summary tables 4 and 5 of the following sections.

#### <u>Aquifer Tests</u>

#### Data

Data from each aquifer test were evaluated for reasonableness and correctness. Factors that were considered in this evaluation included: (1) local hydrogeologic conditions, (2) duration of the test, (3) length of the well screen, (4) distance of the observation wells from the pumping well, and (5) the influence of other pumping wells in the vicinity of the test. This evaluation was followed by a field inspection of each aquifertest site. Records of long-term water-level trends were not available for the aquifer tests, so static-water level measurements made just prior to the tests were assumed to represent prepumping conditions. Drawdown, recovery, or water-level data for the aquifer tests are included in figures 5-32, and figures 35-39 of this report. These figures are in two appendixes at the end of this report.

Identifying data, design characteristics, the method of analysis, and estimated hydraulic properties are presented for each aquifer test in tables 4 and 5. Each aquifer test is numbered and can be referenced to a location on a plate; numbers 1 through 12 are shown on plate 1 for aquifer tests in the middle aquifer, numbers 13 through 27 are shown on plate 2 for aquifer tests in the upper aquifer. Identifying data for each aquifer test include a test identifier or name, the test date, the municipality where the test

Table 4.--<u>Summary of aquifer tests and estimated hydraulic properties for the middle aquifer of the Potomac-Raritan-Magothy aquifer system</u>

Gombined leakance of the overlying and underlying confining units of the middle aquifer
Combined observation well data used in the analysis
Analysis contributed by source of data
Analysis published by Hardt and Jablonski (1959)
Leakance for the overlying confining unit.

	Test Identifier	Discharge Test Duration Lithology Mean unit thickness Drawdown of	USGS well						
Test	Test date Municipality	pumped well Type of con-	number (dis- tagce from	Screened interval	Method of analysis 3,4			draulic prope	
No.	Source of data	finement	PW <sup>2</sup> (ft))	(ft)		<u> </u>	K	\$	<u>L<sup>6</sup></u>
1.	Dupont 6/16/44	610 gal/min 2 hr	23-393(PW)	246-284		••	••		••
	Sayreville Boro USGS	sand 85 ft	23-392(1,050)	237-291	T	7 <b>,75</b> 0	91	4.8 x 10 <sup>-5</sup>	••
		confined							
2.	East Brunswick	500 gal/min 24 hr	23- 42(PW)	161-171 195-215	J**	9,800	140		
	7/8-10/75 E. Brunswick Twp A.C. Schultes	sand, clayey 70 ft 23.7 ft confined	23- 43(50)	161 - 166 195 - 200	Ť	10,400	148	1.4 x 10 <sup>-4</sup>	• •
3.	East Brunswick #5 7/7-9/75	310 gal/min 24 hr sand	23- 40(PW)	162-172 201-221	J**	13,180	143	••	
	E. Brunswick Twp A.C. Schultes	92 ft 20.5 ft confined	23- 41(50)	161 · 166 197 · 202	J(R)**	10,200	111	3.4 x 10 <sup>-3</sup>	
4.	East Brunswick	540 gal/min 24 hr	23- 44(PW)	217-237 271-281	J**	9,630	116		••
	9/29-30/75 E. Brunswick Twp A.C. Schultes	sand(f-c),clayey 83 ft 16.5 ft confined	23-789(50)	212-217 271-276	T	10,600	128	8.0 x 10 <sup>-5</sup>	
5.	East Brunswick	325 gal/min	23- 47(PW)	119-144					••
	#7 10/16-17/75 E. Brunswick Twp A.C. Schultes	24 hr sand(m-c),clayey 55 ft 12.25 ft confined	23-788(50)	127-133	Т	9,400	171	4.2 x 10 <sup>-5</sup>	••
6.	Hercules	590 gal/min	23-380(PW)	184 - 237	••				• •
	6/16/44 Sayreville Boro USGS	3 hr sand 65 ft	23-384(350)	170-225	T	7,420	114	1.6 x 10 <sup>-5</sup>	3 <u></u> .
		confined							
7.	Hightstown 3/10-23/77	800 gal/min 8 hr	21- 85(PW)	316-336	••	••	••		
	Hightstown Boro A.C. Schultes	sand(f·c),clayey	21- 86(75)*	294 - 304 324 - 334					
	vi condites	confined	21-144(250)*	294 · 304 319 · 340	Ť	11,500	100	5.0 x 10 <sup>-5</sup>	••
8.	Marlboro MUA 4/3/72	1,236 gal/min 24 hr	25-268(PW)	632-679 688-698		••		••	••
	Marlboro Twp A.C. Schultes	sand(f-m),clayey 98 ft 48 ft leaky confined	25-269(600)	647·687 696·716		9,800	100	1.0 x 10 <sup>-4</sup>	†7.0 x 10 <sup>-4</sup>

<sup>1</sup> Lithologic Descriptors: (f,m,c)=(fine,medium,coarse)
2 PW=pumped well
3 R=Recovery Data
4 Methods of Analysis: J=Jacob, T=Theis,
FEM=radial finite element method
5 T=Transmissivity in square feet per day
K=Lateral hydraulic conductivity in feet per day
S=Storage coefficient (dimensionless)
1 = Leakance in feet per day per foot L=Leakance in feet per day per foot

Table 4.--<u>Summary of aquifer tests and estimated hydraulic properties for the middle aquifer of the Potomac-Raritan-Magothy aquifer system</u> --Cont.

		Discharge Test Duration Lithology <sup>1</sup> Mean unit thickness								
Test	Test Identifier Test date Municipality	Drawdown of pumped well Type of con-	USGS well number (dis- tagce from	Screened interval	Method of		<u> </u>	ydraulic prope	erties <sup>5</sup>	
No. Source of data	finement	PW <sup>2</sup> (ft))	(ft)	analysis <sup>3</sup> , <sup>4</sup>	T	K	s	L 6		
9.	Runyon, Old Deep 8/41 Old Bridge Twp	1,500 gal/min 2 hr sand	23-194(PW)	201-231 251-281				<del></del>		
	USGS	82 ft confined	23-197(298)	205-260	T	6,250	76	3.0 x 10 <sup>-4</sup>	· . · · · ·	
10.	South Brunswick 5/21-29/56	1,000 gal/min 168 hr	23-288(PW)	190-200				'	, <del></del>	
-	S. Brunswick Twp Leggette, Brashears, and Graham	sand,clayey 59 ft 27.6 ft leaky confined	*23-287(500) *23-290(1,000)	218-228 218-228	FEM	11,800	200	3.5 x 10 <sup>-4</sup>	†1.1 x 10 <sup>-3</sup>	
11.	Spotswood 1976 4/21-27/76 Spotswood	703 gal/min 168 hr sand,clayey 90 ft	23-499(PW) *23-127(1,600)	198-282	<del></del> .		<del></del>	<del></del>		
	Leggette, Brashears, and Graham	25.6 ft confined	*23-171(7,000)		T	13,800	153	2.2 x 10 <sup>-4</sup>		
12.	Woodbridge 3/25-28/57	140 gal/min 72 hr	23-473(PW)	39-59	••			:: - +		
	Woodbridge Twp USGS	sand 60 ft	23-474(480)	41-61	Т	2,145		2.6 x 10 <sup>-5</sup>	2.3 x 10 <sup>-3</sup>	
		confined	23-482(2,030)	44-54 64-76	T***	2,140	36	2.3 x 10 <sup>-4</sup>	· ·	

### Table 5.--Summary of aquifer tests and estimated hydraulic properties for the upper aquifer of the Potomac-Raritan-Magothy aquifer system

Lithologic Descriptors: (f,m,c)=(fine,medium,coarse)

PW=pumped well
R=Recovery Data

Methods of Analysis: J=Jacob, DD=Distance Drawdown,
HJ=Hantush Jacob, HM=Hantush Modified,
T=Theis, Tm=Thiem, FEM=Radial Finite Element Mode
T=Transmissivity in square feet per day
K=Lateral hydraulic conductivity in feet per day
S=Storage coefficient (dimensionless)
L=Leakance in feet per day per foot

6 Specific yield is reported for unconfined aquifer tests
\* Combined observation well data used in the analysis
\*\* Analysis contributed by data source
\*\*\* Analysis published by Barksdale, and others (1943)
† leakance for confining bed above upper aquifer
†† leakance for confining bed below upper aquifer

Test	Test Identifier Test date Municipality	Discharge Test Duration Lithology Mean unit thickness Drawdown of pumped well Type of con-	USGS well number (dis- tagce from	Screened interval	Method of	ξ <sub>,4 τ</sub>	ĸ	Hydraulic prop S <sup>6</sup>	perties <sup>5</sup>
<u>No.</u>	Source of data  E. Brunswick WD	finement 101 gal/min	PW <sup>2</sup> (ft)) 23-614(PW)	(ft) 28-38					
15.	Phase I 9/12-15/78 E.Brunswick Twp Leggette, Brashears, and Graham	9.5 hr sand(f·c) 20 ft 10.4 ft unconfined	23-615(100)	30-35	FEM	5,000	250	1.0 x 10 <sup>-2</sup>	
14.	E. Brunswick WD	300 gal/min	23-621(PW)	88-118	••				
	Phase II Test Well 6 10/30-11/6/78 E.Brunswick Twp Leggette, Brashears, and Graham	164 hr sand(f·m) 52'ft 17.5 ft semi·confined	*23-620(245) *23-619(490)	114-119 112-117	DD**	5,600	108	1.4 x 10 <sup>-1</sup>	
15.	East Brunswick Phase II	239 gal/min 70 hr	23-626(PW)	35-55			• •	••	
	Test Well 8 1/24-2/1/79 E.Brunswick Twp Leggette, Brashears and Graham	sand(f·c) 49 ft 18.4 ft semi-confined	*23-624(250) *23-625(122)	47·52 50-55	DD**	4,010	82	1.8 x 10 <sup>-3</sup>	••
16.	Freehold Twp 5/14·17/84	1,218 gal/min 72 hr	25-551(PW)	621-680	J**	8,420	56		••
	Freehold Twp A.C. Schultes	sand 150 ft 21.45 ft confined	25-550(100)	636-651	T	7,500	50	3.3 x 10 <sup>-4</sup>	
17.	Hightstown WD 3/10-23/77	900 gal/min 8 hr	21- 84(PW)	169-183			••		• •
	Hightstown Boro A.C. Schultes	sand(f-m),claye	y 21- 81(70) *21- 86(245)	181 · 205 144 · 264	нм	6,900	77	1.2 x 10 <sup>-4</sup>	3.0 x 10 <sup>-4</sup>
		leaky confined							
18.	Madison Indus- tries	150 gal/min 24 hr	23-690(PW)	29-39	J(R)	5,130	86		••
	3/4/82 Old Bridge Twp Converse	sand 60 ft 21.45 ft unconfined	23-684(170)	17-37	J(R)	5,820	97	5.7 x 10 <sup>-2</sup>	
19.	Matawan/	1,100 gal/min	25-292(PW)	341-414			••		
	Levitt and Sons 1/23-20/62 Aberdeen Twp Legette, Brashears, and Graham	168 hr sand,clayey 84 ft 159.4 ft leaky confined	*25-289(590) *25-290(1,000 *25-291(2,020		нм	5,600	67	2.6 x 10 <sup>-4</sup>	1.5 x 10 <sup>-5</sup> 1.5 x 10 <sup>-5</sup> 1.6 x 10 <sup>-5</sup>

Table 5.--Summary of aquifer tests and estimated hydraulic properties for the upper aquifer of the Potomac-Raritan-Magothy aquifer system - Cont.

	Test Identifier	Discharge Test Duration Lithology! Mean unit thickness Drawdown of	USGS well			-	н	ydraulic prope	rties <sup>5</sup>	
Test No.	Test date Municipality Source of data	pumped well Type of con- finement	number (dis- tance from PW <sup>2</sup> (ft))	Screened interval (ft)	Method of analysis	3,4 T	K	s <sup>6</sup>	L	
20.	Monroe MUA 8/21-24/80	985 gal/min 72 hr	23-555(PW)	168-200		••		••		
	Monroe Twp Dames and Moore	sand 103 ft 24.2 ft leaky confined	23-228(1,100)	127-138	FEM	15,450	150	1.0 x 10 <sup>-5</sup>	†2.5 x 10 <sup>-2</sup> ††2.5 x 10 <sup>-2</sup>	
21.	Nestles 6/22-25/70	1,000 gal/min 72 hr	25-70(PW)	576-640						
	Freehold Boro Leggette, Brashears, and Graham	sand,clayey 93 ft 35.9 ft confined	*25-68(870) *25-69(1,300)	557-607 564-614	Ţ	8,060	87	3.1 x 10 <sup>-4</sup>		
22.	Olympia and York 7/8-10/81 Old Bridge Twp	844 gal/min 48 hr sand,clayey	23-594(PW)	275-315		••	- •			
	Geraghty and Miller	64 ft 69.9 ft confined	*23-595(725) *23-596(1100)	285-290 289-294	T	5,400	84	1.9 x 10 <sup>-4</sup>	••	
23.	Perth Amboy WD 3/73	200 gal/min 2 hr	23-602(PW)	45-53	j**	1,760	26		••	•
	Old Bridge Twp Adtek	sand 69 ft	23-600(80)	68-79	j**	2,850	41	4.0 x 10 <sup>-5</sup>		
		unconfined								
24.	Parlin 5/31-6/1/39	512 gal/min 24 hr	23-172(PW)	55-75	••	••		••		
	Old Bridge Twp USGS	sand 59 ft	23-119(25)	65-85	Tm**	11,500	195	1.4 x 10 <sup>-4</sup>	••	
		unconfined	23-121(85)	75-85	Tm**	19,400	329	$3.7 \times 10^{-3}$	••	
25.	Perth Amboy WD 6/20-22/85	570 gal/min 48 hr	23-743(PW)	50-65		••		••	••	
	Runyon	sand	*23.745(50)	57-67	DD					
	Hydro Group	65 ft	*23-746(91)	57·67	DD		••		••	
		28.6 ft unconfined	*23-744(207)	60-75	DD**	9,500	146	••	- •	
26.	Spotswood WD 03/18/58	560 gal/min 4 hr	23-447(PW)	64-85		••		••	••	
	Spotswood Boro USGS	semi-confined	23-448(245)	62-83	T	9,750	••	7.0 x 10 <sup>-4</sup>	••	
27.	Union Beach 04/21-28/86	1,375 gal/min 144 hr	25-419(PW) 25-420(PW)	250-300 235-285						
	Union Beach Boro USGS	sand 70 ft  <u>leaky confined</u>	*25-207(4340) *25-206(4320)	247-277 225-285	НЈ	8,400	120	4.2 x 10 <sup>-4</sup>	6.5 x 10 <sup>-5</sup>	

occurred, supplier of the test data, and the U.S. Geological Survey well number. The design characteristics include the rate of discharge, duration of the test, lithologic descriptions of the aquifer material, the mean thickness of the aquifer, final drawdown in the pumped well, type of confinement, the designation of pumped well or the distance of the observation wells from the pumped well (next to the well number), and the screen intervals. The method of analysis of water-level data for the aquifer tests is included in the row of data for each well. In some cases, data from more than one observation well were used to analyze an aquifer test. The estimated hydraulic properties include the transmissivity, lateral hydraulic conductivity, storage coefficient for the aquifer, and leakance of the confining unit(s).

#### Methods of Interpretation

Transmissivity, lateral hydraulic conductivity, storage coefficient, confining-unit leakance(s), and specific capacity were calculated from drawdown and recovery data from 12 multiple-well aquifer tests in the middle aquifer, and 15 multiple-well aquifer tests in the upper aquifer. These data were analyzed by one or more of the following methods: (1) Theis (Wenzel, 1942, p. 88-89), (2) Jacob (Cooper and Jacob, 1946), (3) Thiem or Distance Drawndown (Lohman, 1972, p. 11-13), (4) Hantush-Jacob (Hantush and Jacob, 1955), (5) Hantush (Modified) (Hantush, 1960), (6) Boulton (1954), and (7) finite-element method (FEM) (Reilly, 1984).

The Theis, Jacob, and Thiem methods were developed to analyze tests in confined aquifers assuming constant discharge of a well in a nonleaky aquifer. The Hantush-Jacob method was developed using the assumption that the confining units leak. The Hantush (modified) method assumes the aquifer is confined and that leakage to the aquifer is from storage within the confining units. The analytic assumptions, procedures, and numerical criteria for all interpretations except the finite-element method are found in Reed (1980), Kruseman and De Ridder (1970), and Lohman (1972). The graphical analysis for those aquifer tests, which were evaluated using methods 1-6, are included in figures 5-32 of appendix 1 to this report. Results of analysis using method 7 are presented in figures 33-39 of appendix 2 to this report.

Most of the tests were conducted in the confined parts of the middle and upper aquifers. The data from the tests were analyzed using one or more of the methods for confined aquifers: Theis, Jacob, or Thiem. However, six of these tests were found to have characteristics of a leaky confined aquifer, and were analyzed with the Hantush-Jacob, Hantush (Modified), or finite-element methods. Six tests in the upper aquifer were located over the unconfined part of the aquifer. Tests in the unconfined region did not appear to be greatly affected by delayed yield, or they did not satisfy the Boulton criteria. Therefore, these tests were analyzed using methods designated for confined aquifers (Kruseman and De Ridder, 1970, p.107; and Lohman, 1972, p.22) or the finite-element method.

The graphical methods of analysis (methods 1-6) result from analytic solutions to ground-water-flow equations. For method 2, the field values for drawdown in a well over time are plotted on semilogarithmic paper

(Lohman, 1972, p. 23). In method 3, a plot of the relation of drawdown to the distance from the pumped well is made (Lohman, 1972, p. 11).

Graphical analysis for methods 1 and 4-6 are based on type-curve matching. Lohman (1972) explains the procedures for using each of these methods. In graphical analysis, field values for drawdown versus time (or time divided by the squared distance of the observation well to pumping well) are plotted on log-log paper. Both aquifer transmissivity and storage coefficient can be calculated using these methods. Methods 4 and 5 also are used to determine the leakance of confining units.

Numerical simulation, using the finite-element model RADFLOW (Reilly, 1984), was used to analyze data from aquifer tests 8, 10, 13, and 20. This model is applicable to analysis of radial flow in confined and unconfined aquifer flow systems. All four aquifer tests were simulated using a variation of the same 273-node, 480-element grid (figure 33 in appendix 2). The simulated area was 30,000 feet in radius and extended from either the surface of the overlying confining unit for confined aquifers, or from the water table to the underlying confining unit for unconfined aquifers to the bottom confining unit. Aquifers and confining units are represented as horizontal, homogeneous layers of uniform thickness.

The thicknesses of the hydrogeologic units, the location of geologic contacts, and the hydraulic properties for final calibrated simulation of each site are presented in figure 34 in appendix 2. Initial estimates of the hydraulic properties were made from simple analytic solutions. A series of simulations was done for each site in which the hydraulic properties of the confining units and the aquifers were varied until a match with the field data was obtained. Although a formal sensitivity analysis was not made, several simulations were done in which one value was changed while others were held constant, and the effect on the system was noted. Comparing the simulated values to other known hydraulic-property values in the area suggest that the values of the aquifer properties obtained in this way are reasonable. The graphical representations of field data and the matched numerical simulations for those aquifer tests are included in appendix 2. A match was defined when the shape and magnitude of the simulated drawdown curve was similar to the field data. The assumptions of numerical modeling and restrictions for the numerical code are beyond the scope of this report and are presented by Reilly (1984).

#### Middle aquifer of the Potomac-Raritan-Magothy aquifer system

Hydraulic properties for the middle aquifer were calculated by the graphical methods of either Theis or Jacob for confined, radially isotropic aquifers for 10 of the aquifer tests; finite-element analysis was used for 2 aquifer tests. The method used for analysis of each test is indicated in table 4.

#### Upper aquifer of the Potomac-Raritan-Magothy aquifer system

Hydraulic properties from five aquifer tests in the confined and semiconfined areas of the upper aquifer were determined by the type-curve matching graphical methods of Theis; by the distance-drawdown analysis of Thiem; and by the straight-line method of Jacob. Four aquifer tests indicated the confinement of the upper aquifer was leaky. Data from these tests were analyzed using Hantush-Jacob, Hantush (Modified) or the finite-element method. Tests in the unconfined region did not appear to be greatly affected by delayed yield nor did they satisfy the criteria for the Boulton (1954) method of analysis for unconfined aquifers. Therefore, these tests were analyzed using methods designated for confined aquifers (Kruseman and De Ridder, 1970, p. 107; and Lohman, 1972, p.22). The six unconfined aquifer tests were analyzed using the type-curve methods of Theis, the straight-line methods of Jacob and Thiem, and the finite-element method. The method of analysis for each test is indicated in table 5.

#### Well-Acceptance Tests

#### Data

The four criteria used in selecting well-acceptance tests in both aquifers were: (1) outside diameter of screen at least 6 inches, (2) screen length at least 20 feet, (3) test duration at least equal to 8 hours, and (4) constant pumping rate. The first two criteria insured that only well-acceptance tests for major production wells would be selected. These high-volume wells affect larger areas of the aquifer, and thereby, minimize the effects of small-scale heterogeneities in the aquifer in the vicinity of the well. The third and fourth criteria, test duration and constant pumping, were imposed so that a maximum drawdown for a constant rate of withdrawal would be approached, and the conditions of steady flow would be approximated.

Summaries of well-acceptance-test data, which were selected using the above criteria, are presented in tables 6 and 7 for the middle and upper aquifers, respectively. The well number, latitude and longitude, screen diameter and length, and test date are included in each table. Test data include the duration of the test, the pump discharge rate, drawdown in the discharging well at the end of the test, the specific capacity, and the estimated lateral hydraulic conductivity computed from these data. The location of each test site is shown on plate 1 or 2.

#### Method of Interpretation

Various formulas for estimating hydraulic conductivity from well-acceptance-test data have been reported (Bedinger and Emmett, 1963; McClymonds and Franke, 1972). Bennett (1976) derived the following linear interpolating formula used in this report to estimate lateral hydraulic conductivity from data that include specific-capacity measurements:

$$K=1.1 Q/(s x 1)$$
 (1)

where K is the lateral hydraulic conductivity, in feet per day (ft/d);

Q is the discharge, in cubic feet per day (ft3/day);

s is the water-level drawdown, in feet (ft); and

l is the length of well screen, in feet (ft).

Table 6.--<u>Summary of well-acceptance tests and estimated hydraulic conductivity for the middle aquifer of the Potomac-Raritan-Magothy aquifer system.</u>

[in., inches; ft, feet; hr, hour; gal/min, gallons per minute; (gal/min)/ft, gallons per minute per foot; ft/d, feet per day]

					-	Well·a	data	Fational		
USGS well number	Locat Latitude	ion Longitude	Scro Diameter (in.)		Date	Dura- tion (hr)	Dis- charge (gal/min	down	Specific capacity (gal/min)/	Estimated hydraulic conductivity ft) (ft/d)
23- 7 23- 9 23- 11 23- 13 23- 16	401755 401800 401818 401841 401842	743118 743206 742932 743355 743055	10 12 10 10	30 30 30 30 30 30	05/19/1964 06/10/1950 12/10/1956 11/27/1954 02/12/1973	8 55 8 8 24	590 1,200 644 400 473	209 22 147 92 52	3 55 4 4 9	20 385 31 31 64
23- 17 23- 25 23- 45 23- 46 23- 48	401843 401902 402426 402427 402431	743055 742912 742515 742507 742214	10 12 10 10 10	30 30 30 30 37	03/26/1963 07/23/1964 03/26/1969 12/02/1968 04/01/1931	28 8 8 8	560 785 60 60 620	228 47 5 5 5	3 17 12 12 12	17 118 85 85 71
23 · 50	402432	742212	10	50	10/11/1963	8	1,012	27	37	159
23 · 57	402441	742448	10	25	05/06/1954	16	600	35	17	145
23 · 58	402448	742700	8	20	05/07/1975	24	302	13	23	245
23 · 59	402456	742442	12	40	04/07/1955	8	1,067	36	30	157
23 · 60	402459	742643	6	20	05/10/1952	24	70	20	4	37
23- 63 23- 66 23-146 23-147 23-176	402501 402516 402350 402350 402407	742440 742408 741834 741840 741924	12 10 10 10 6	40 25 45 50 42	08/16/1951 03/14/1954 05/07/1966 06/30/1966 05/23/1972	8 15 8 8	1,000 600 1,254 1,265 285	21 30 35 44 43	48 20 36 29 7	253 169 169 122 33
23 - 179	402436	742041	6	42	06/07/1972	8	363	6	61	305
23 - 196	402537	742020	12	60	02/12/1968	8	1,534	28	55	193
23 - 201	402614	741744	12	40	10/10/1956	24	1,227	22	56	295
23 - 202	402625	741611	8	21	02/01/1957	8	360	40	9	91
23 - 232	402023	742858	12	42	06/15/1961	8	708	30	24	119
23 - 236	402038	742345	8	30	05/13/1963	8	740	78	9	67
23 - 240	402051	742746	12	48	03/15/1961	8	708	46	15	68
23 - 289	402056	742937	20	30	05/21/1956	167	1,000	28	36	252
23 - 298	402129	742901	10	20	06/03/1965	8	614	43	14	151
23 - 300	402124	742824	12	40	09/24/1966	8	726	65	11	59
23 · 302	402138	742940	10	30	04/14/1955	9	465	79	6	42
23 · 303	402139	742820	10	30	06/12/1957	19	1,050	45	23	165
23 · 304	402143	742821	12	30	01/05/1962	8	785	60	13	92
23 · 305	402143	742821	8	20	03/14/1957	9	698	20	35	370
23 · 315	402204	743024	12	35	08/03/1971	12	1,200	64	19 .	113
23-320	402223	742824	10	20	11/25/1952	8	515	39	13	140
23-332	402319	742708	10	30	06/27/1958	9	650	52	13	88
23-352	402605	741958	18	55	07/12/1967	8	1,236	22	56	216
23-386	402701	741917	12	61	04/04/1930	8	1,071	23	47	162
23-401	402744	741628	18	34	06/09/1967	16	1,218	82	15	93
23 · 411 23 · 430 23 · 432 23 · 434 23 · 436	402822 402923 402557 402556 402557	741630 741651 742138 742141 742138	10 12 8 17 6	25 30 31 25 29	05/28/1947 10/13/1972 06/27/1975 10/01/1951 02/01/1968	8 38 8 8	800 305 542 960 250	40 50 20 41 18	20 6 27 23 14	169 43 185 198 101
23-437	402559	742142	17	36	05/02/1967	48	1,130	90	13	74
23-452	402401	742243	10	50	05/22/1947	24	1,400	32	44	185
23-453	402404	742235	12	20	01/21/1929	8	1,040	82	13	134
23-502	402432	742215	12	50	03/21/1978	10	1,001	50	20	85
23-551	402548	742155	12	53	03/01/1980	24	825	19	43	174
23-552	402018	743021	16	50	05/01/1979	8	1,536	18	85	361
23-554	402745	741645	12	73	04/21/1980	24	1,455	76	19	56
23-568	402410	742231	12	70	02/17/1983	8	1,413	36	39	119
25- 55	401744	742135	10	20	11/01/1963	24	400	70	6	61
25-153	402444	741010	12	55	04/20/1970	8	1,000	70	14	55
25-230 25-231 25-247 25-249 25-262	402004 402004 401902 401859 402102	741853 741855 741811 741809 741353	12 12 8 8 8	90 80 70 69 80	02/18/1972 06/01/1974 07/09/1964 06/17/1968 06/01/1966	8 8 8 8	1,200 1,001 805 700 450	30 22 56 38 34	40 46 14 18 13	94 120 43 57 35
25-283 25-299 25-320 25-452 25-466	402514 402604 402705 401857 402610	741450 741417 735959 741811 741351	12 10 10 12 12	46 35 40 60 50	12/29/1956 06/22/1965 09/01/1970 12/23/1980 07/29/1977	8 8 8 8	703 1,007 638 1,200 1,263	28 68 39 33 216	25 15 16 36 6	116 90 87 128 25
25 - 467	402436	741013	12	50	02/06/1979	8	1,002	66	15	64
25 - 503	401640	741722	12	108	06/12/1981	16	1,205	23	52	103

Table 7.--Summary of Well-acceptance tests and estimated hydraulic conductivity for the upper aquifer of the Potomac-Raritan-Magothy aquifer system.

[in., inches; ft, feet; hr, hour; gal/min, gallons per minute; (gal/min)/ft, gallons per minute per foot; ft/d, feet per day]

					u	Well-acceptance-test data				
USGS well number	Locat Latitude	ion Longitude	Screen Diameter Le (in.) (	ngti ft)	Date	Dura- tion (hr)	Dis- charge (gal/min	down	Specific capacity (gal/min)/	
23- 5 23- 6 23- 18 23- 20 23- 21	401706 401727 401841 401848 401850	743033 743042 742905 742902 742901	8 12 12	20 40 40 40 40	06/01/1965 12/01/1973 10/24/1957 02/20/1968 09/29/1958	8 60 9 8 8	550 403 1,002 950 930	78 23 73 31 20	7 18 14 31 47	75 93 73 162 246
23 - 27 23 - 34 23 - 35 23 - 108 23 - 110	401906 401924 402010 402253 402308	742855 743015 742838 742247 742252	10 10 18	30 24 30 20 20	09/01/1964 09/24/1963 04/27/1956 11/01/1947 07/01/1942	8 16 144 8 12	771 200 524 1,018 1,215	47 5 36 67 55	16 40 15 15 22	116 353 103 161 234
23 - 135 23 - 145 23 - 148 23 - 156 23 - 192	402345 402348 402350 402356 402535	741838 742050 742232 742056 742014	16 17 16	58 40 20 30 20	12/02/1966 10/03/1972 05/11/1939 09/25/1972 01/02/1951	8 8 25 8 8	754 602 570 907 700	24 58 22 59 43	31 10 26 15 16	115 55 274 109 172
23 · 195 23 · 227 23 · 231 23 · 237 23 · 245	402537 402013 402019 402038 402202	742002 742834 742708 742755 742305	12 10 10	30 30 20 44 30	09/14/1965 10/09/1967 07/24/1965 11/15/1954 07/01/1963	24 8 8 36 8	550 650 401 455 500	25 83 57 39 13	22 8 7 12 38	155 55 74 56 272
23-345 23-356 23-361 23-367 23-403	402604 402614 402619 402624 402745	742003 741955 741958 741944 741631	12 12 12	20 21 23 31 58	10/11/1965 02/21/1959 10/01/1957 03/23/1960 01/26/1973	16 48 48 48 16	200 662 400 402 400	36 44 30 31 19	6 15 13 13 21	59 152 123 89 77
23-413 23-443 23-447 23-451 23-454	402824 402318 402329 402401 402404	741631 742333 742319 742243 742235	6 16 18	22 20 21 20 25	07/01/1965 07/28/1970 11/26/1956 08/26/1941 03/21/1929	8 24 8 8 8	380 50 421 1,050 845	36 36 29 23 45	11 1 15 46 19	102 15 146 483 159
23-490 23-549 23-567 23-569 23-570	401925 402745 401950 402738 402538	742620 741645 742750 741700 741950	10 16 10	38 41 81 30 20	10/24/1974 05/00/1980 07/07/1983 03/25/1982 11/08/1982	8 24 24 24 8	1,002 430 1,177 503 704	41 44 56 27 21	24 10 21 19 34	136 50 55 132 355
25 - 37 25 - 56 25 - 82 25 - 91 25 - 97	401607 401744 401412 401516 401625	741209 742135 741606 741530 741501	10 8 8	20 21 51 53 60	09/10/1963 05/07/1965 08/26/1957 08/21/1969 07/15/1966	168 8 8 8 24	660 524 510 554 200	199 47 28 37 168	3 11 18 15 1	35 112 76 60 4
25 - 98 25 - 100 25 - 101 25 - 103 25 - 111	401633 401635 401635 401646 402532	741726 741721 741721 741737 740932	8 12 12	54 26 99 97 40	04/17/1969 10/10/1948 06/01/1970 06/01/1974 04/05/1958	48 48 48 48	1,007 625 1,000 1,001 1,000	44 35 26 30 52	23 18 38 33 19	90 145 82 73 102
25-112 25-113 25-116 25-121 25-146	402537 402542 402400 402023 402327	740933 740850 735912 741100 741114	6 10 10	40 32 60 30 30	04/27/1960 08/01/1970 10/06/1961 01/11/1960 02/20/1962	8 8 8 27 24	1,000 200 700 430 157	40 107 154 34 56	25 2 5 13 3	132 12 16 89 20
25 · 154 25 · 175 25 · 177 25 · 190 25 · 191	402445 401246 401255 402621 402620	741019 741516 741147 740739 740741	8 8 10	30 81 20 60 60	02/27/1964 10/06/1969 08/31/1969 06/01/1945 05/27/1968	8 8 8 8	1,007 564 190 1,023 1,034	95 70 65 56 66	11 8 3 18 16	75 21 31 64 55
25-199 25-202 25-207 25-210 25-212	402542 402624 402626 401639 401232	741220 741145 741144 735936 742107	10 12 12	30 63 30 50 31	04/08/1964 12/01/1955 04/01/1970 05/01/1956 04/21/1956	18 8 8 8	430 1,060 1,254 726 403	128 78 47 66 26	3 14 27 11 16	24 46 188 47 106

Table 7.--<u>Summary of well-acceptance tests and estimated hydraulic conductivity for the upper aquifer of the Potomac-Raritan-Magothy aquifer system.</u> (cont.)

[in., inches; ft, feet; hr, hour; gal/min, gallons per minute; (gal/min)/ft, gallons per minute per foot; ft/d, feet per day]

USGS Well number			Well-acceptance-test data							
	Location Latitude Longitude		Screen Diameter Length (in.) (ft)		Date	Dura- tion (hr)	Dis- charge (gal/min	Draw- down )(ft)(	Specific capacity (gal/min)/	Estimated hydraulic conductivity ft) (ft/d)
25 · 244 25 · 288 25 · 293 25 · 294 25 · 295	401850 402349 402403 402428 402427	741459 741232 741245 741345 741348	12 12 12 12 8 8	70 80 38 30 30	05/01/1969 06/15/1967 06/12/1962 08/29/1944 05/25/1943	8 10 8 10 28	1,500 1,300 1,158 580 510	39 . 89 . 76 . 35 . 30	39 15 15 17 17	116 39 85 117 120
25-322 25-332 25-333 25-345 25-349	401157 401930 401214 401233 401322	742418 735841 740355 740100 740202	8 8 8 8	30 33 72 40 112	06/11/1956 05/04/1971 06/19/1956 06/28/1958 03/15/1956	72 8 8 8	350 350 1,001 1,000 1,000	110 20 32 68 77	3 18 31 15 13	22 112 92 78 25
25-358 25-360 25-362 25-456 25-462	402047 402054 401312 402640 402717	740420 740320 742802 740904 740816	8 10 8 10 8	50 91 30 39 50	05/25/1950 09/11/1975 12/14/1956 07/01/1976 06/04/1969	8 24 8 8 8	1,012 1,100 524 608 230	29 77 30 62 14	35 14 17 10 16	148 33 123 53 70
25-499 25-501 25-502 25-513 25-514	402353 401212 401420 402442 402641	741239 740358 741619 740242 740911	16 12 12 10 10	50 75 55 42 46	03/04/1981 08/04/1981 06/01/1981 10/07/1981 05/28/1983	24 24 36 8 8	1,200 1,404 1,205 876 524	128 29 68 69 19	9 48 18 13 28	40 137 68 64 127

This equation may be rewritten using discharge, Q, in gallons per minute (gal/min) and all other variables the same, as:

$$K=211.8 Q/(s x 1).$$
 (2)

Estimates of lateral hydraulic conductivity from specific-capacity data are shown in tables 6 and 7.

#### RESULTS OF HYDRAULIC PROPERTIES FROM PREVIOUS INVESTIGATIONS

Barksdale and others (1943, p. 42, 68, 106) summarized hydraulic-conductivity values determined from permeability-test data from 7 cores from the upper aquifer collected in or near the outcrop of the Farrington Sand Member of the Raritan Formation, and from 12 cores from the upper aquifer taken in or near the outcrop of the Old Bridge Sand Member of the Magothy Formation. Laboratory analysis showed that the vertical hydraulic conductivities range from 28 to 468 ft/d (feet per day) for the middle aquifer, and 31 to 340 ft/d for the upper aquifer; specific yields for the middle and upper aquifer were about 0.32 and 0.40, respectively.

Barksdale and others (1943) reported that lateral hydraulic-conductivity values, calculated from aquifer tests in the middle aquifer at the Perth Amboy Water Department well field in Old Bridge Township, ranged from 161 to 201 ft/d. They also reported three aquifer tests in the upper aquifer that produced lateral hydraulic-conductivity values ranging from 134 to 201 ft/d. The methods of analysis for these tests are not described nor are the exact locations given in their report. Results of aquifer test 24, in this report, was originally published by Barksdale and others (1943).

Hardt and Jablonski (1959) reported a transmissivity value of 2,140 ft²/d (feet squared per day), and a storage coefficient value of 2.3 x 10 4 for the middle aquifer at Woodbridge. Results from their report are included in this report (aquifer test 12). Additional unpublished data from their aquifer test were analyzed and are included in this report. Geraghty and Miller, Inc. (1976) reported a mean specific capacity of the middle aquifer of 29 (gal/min)/ft (gallons per minute per foot), and 20 (gal/min)/ft for the upper aquifer.

Farlekas (1979, p.12) analyzed data from an aquifer test of the middle aquifer performed by Leggette, Brashears, and Graham (1961) near Jamesburg in Middlesex County. At this site, Farlekas (1979) determined the transmissivity for the middle aquifer to be  $13,400~\rm{ft^2/d}$ , the storage coefficient to be  $1.6 \times 10^{-4}$ , and the lateral hydraulic conductivity to be  $216~\rm{ft/d}$ . Farlekas (1979, p.30-32) also published a transmissivity map, calculated from specific-capacity data, for the middle aquifer. The resultant transmissivity values range from 42 ft²/d near the Raritan River to  $16,800~\rm{ft^2/d}$  in the vicinity of Marlboro Township.

#### RESULTS OF AQUIFER AND WELL-ACCEPTANCE TESTS

# Hydraulic Properties of the Middle Aquifer of the Potomac-Raritan-Magothy Aquifer System

All of the aquifer tests occurred in the confined part of the aquifer; most of the tests occurred in Middlesex County, where depth to the aquifer is shallower. Results of the analyses indicate that the middle aquifer is a highly transmissive unit throughout most of the study area.


The transmissivities, determined from the 12 aquifer tests in the middle aquifer, range from 2,140 to 13,800 ft $^2$ /d (table 4). Lower transmissivity values tend to prevail in the northern half of the study area, in Sayreville Borough (test 1 and 6), Old Bridge Township (test 9) and Woodbridge Township (test 12), probably because the aquifer is thinner in these areas. If these four northernmost aquifer tests are not considered, the range in transmissivity is from 9,400 to 13,800 ft $^2$ /d. Figure 3(a) includes a histogram of the mean transmissivity values from each aquifer test in the middle aquifer.

Lateral hydraulic conductivities of the middle aquifer determined from aquifer tests range from 36 to 200 ft/d (table 4); whereas the range of hydraulic conductivities from well-acceptance tests is slightly larger but of the same orders of magnitude--17 to 385 ft/d (table 6). These values of hydraulic conductivity are consistent with aquifers composed of clean sands, and are consistent with the lithologic description of the aquifer material at each aquifer-test site. Figure 4(a) is a histogram of lateral hydraulic conductivities determined from the well-acceptance-test data for the middle aquifer.


Some of the variation in the hydraulic conductivities is due to the randomness of this aquifer property in the region and to the accuracy of the well-acceptance-test method of calculating hydraulic conductivity. Hydraulic-conductivity values from both aquifer tests and well-acceptance tests were divided into two categories; low (less than or equal to 100 ft/d) and high (greater than 100 ft/d). Low hydraulic-conductivity values were scattered throughout the study area; however, high values of hydraulic conductivity were concentrated near the outcrop of the Farrington Sand Member of the Raritan Formation of the middle aquifer. The range of hydraulic-conductivity values for the middle aquifer, within approximately 4 miles of the outcrop of the Farrington Sand Member, is from 20 to 385 ft/d; the range downdip from this area is from 15 to 169 ft/d.

Storage coefficients were derived only from the aquifer-test analyses. The storage coefficients for the middle aquifer range from  $2.6 \times 10^{-5}$  to  $3.4 \times 10^{-3}$ . Errors in the estimated storage coefficient may be introduced if the screened intervals for the pumped well are small in comparison to the aquifer thickness and if the aquifer contains semipermeable units that retard the vertical movement of water. If data from wells that are screened across a large part of an aquifer are considered, the effects of semipermeable units on this determination are minimized (Bentley, 1977). For these reasons, the best estimates of storage coefficient were from results for six of seven aquifer tests (aquifer tests 1, 2, 5, 8, 9, 11) where the well screen in the pumping well spans more than 40 percent of the

#### (a) Middle aquifer



#### (b) Upper aquifer



#### DISTRIBUTION OF TRANSMISSIVITY, IN FEET SQUARED PER DAY

Figure 3.--Histograms of mean transmissivities for aquifer tests in the middle and upper aquifers of the Potomac-Raritan-Magothy aquifer system.

#### (a) Middle aquifer NUMBER OF VALUES DISTRIBUTION OF HYDRAULIC CONDUCTIVITY, IN FEET PER DAY




Figure 4.--Histograms of lateral hydraulic conductivities determined from well-acceptance tests for the middle and upper aquifers of the Potomac-Raritan-Magothy aquifer system.

aquifer thickness. The range of storage coefficients for these tests is from  $4.2 \times 10^{-5}$  to  $3.0 \times 10^{-4}$ .

The analyses of the aquifer tests in the middle aquifer indicate that the confining units are relatively impermeable; however, leakage from the confining units was observed to affect drawdowns at three test locations (tests 8, 10, and 12). It is assumed in this analysis that leakage from the basal fire clay member (table 1) and bedrock is negligible. If so, leakage into the middle aquifer is from the overlying confining unit. The results of tests 8, 10, and 12, indicate a range of leakance from 7.0 x  $10^{-4}$  1/d (leakance in feet per day per foot) to 2.3 x  $10^{-3}$  1/d for this confining unit.

#### <u>Hydraulic Properties of the Upper Aquifer</u> of the Potomac-Raritan-Magothy Aquifer System

Aquifer tests in the upper aquifer were located in both confined and unconfined areas, and they were more broadly distributed throughout Monmouth County than the aquifer tests for the middle aquifer. This reflects the greater use of the water resources of the upper aquifer in the downdip part of the aquifer system (Vowinkel, 1984).

The transmissivity values for the upper aquifer range from 1,760 to  $19,400 \, \mathrm{ft^2/d}$ . A histogram of the mean transmissivities for aquifer tests is presented in figure 3(b). Transmissivities for the confined, semiconfined, and leaky-confined areas of the aquifer range from 4,010 to  $15,450 \, \mathrm{ft^2/d}$ . Of these, the six aquifer tests of the deepest part of the system (aquifer tests 16, 17, 19, 21, 22, 27) range in transmissivity values from 5,400 to 8,420 ft²/d.

Transmissivities in the unconfined part of the upper aquifer range from 1,760 to 19,400 ft<sup>2</sup>/d. Transmissivities for the three northernmost tests in the unconfined aquifer (aquifer tests 13, 18, and 23) range from 1,760 to 5,820 ft<sup>2</sup>/d. The lower transmissivity values for these tests are likely due to the thinness of the aquifer in the northern part of the study area. The remaining transmissivities in the unconfined area range from 9,500 to 19,400 ft<sup>2</sup>/d. Based on the interpretation of well logs, the upper aquifer is believed to be semiconfined at the site of aquifer tests 14 and 15, although the test sites are in the outcrop area.

The hydraulic conductivity from aquifer tests of the upper aquifer ranges from 26 to 329 ft/d; for well-acceptance tests, the values range from 4 to 483 ft/d (table 7). A histogram of hydraulic-conductivities determined from well-acceptance tests is shown in figure 4(b). The same distribution pattern of hydraulic conductivities observed in the middle aquifer is indicated in the upper aquifer. Low values (less than or equal to 100 ft/d) were scattered throughout the study area, whereas high values (greater than 100 ft/d) were concentrated in or near the outcrop of the Old Bridge Sand Member of the Magothy Formation.

The estimated range of storage coefficients in the confined, semiconfined, and leaky-confined areas of the upper aquifer range from  $1.0~\rm x$   $10^{-5}$  to  $1.8~\rm x$   $10^{-3}$ . This result derives from eight of the nine aquifer tests (tests 15, 16, 17, 19, 20, 21, 22, and 27). Test 14 had a value above

this range  $(1.4 \times 10^{-1})$ , which is closer to properties of an unconfined system. Lithologic interpretation of logs at this site, and proximity to the general outcrop region for the aquifer, suggest that the system is semiconfined at the site of test 14.

Analysis of drawdown data from three of five aquifer tests in the unconfined part of the aquifer (tests 13, 18, and 24) gave storage coefficients representative of unconfined aquifers, ranging from  $3.7 \times 10^{-8}$  to  $5.7 \times 10^{-2}$ . A storage-coefficient value below this range was calculated for test 23 (4.0 x  $10^{-5}$ ) in which the well screen penetrated only 11 percent of the saturated aquifer thickness. As discussed in the section on the results of analysis for the middle aquifer, where the screen length is such a small fraction of the aquifer thickness, clay layers within the aquifer can limit the migration of water to the screen causing a low value for storage coefficient (Bentley, 1977). Test 26, which was located near the edge of the unconfined area of the upper aquifer in the outcrop of the Old Bridge Sand Member, had a low storage coefficient (7.0 x  $10^{-4}$ ), which may indicate some effects of confining units at the site.

Leakage across the confining units was observed from the stresses caused by the test pumping at four locations. Because of the position of the upper aquifer between two confining units, leakage can occur through both the overlying and underlying confining units. Of the five tests in the deepest part of the system (aquifer tests 16, 19, 21, 22, and 27) leakage was observed at two, tests 19 and 27. Leakage at test 20. in the shallower part of the aquifer, was interpreted to come from both the overlying confining unit and the underlying confining unit. Test 10, in proximity to test 20, also indicates that the confining unit between the middle and upper aquifers is leaky in this part of the study area. The areal lithology as interpreted from lithologic logs indicates that this confining unit is thin or sandy in part of the aquifer system in the vicinity of Jamesburg Borough, South Brunswick Township, and the northwestern part of the Hightstown Borough area. The leakage observed during test 17 was likely to be predominantly through the overlying confining unit. Lithologic and geophysical logs at the site of test 17 show that the underlying confining unit between the middle and upper aquifer is intact. Test 7, which was a test of the middle aquifer near test 17, showed that the confining unit between the middle and upper aquifers was relatively impermeable to the imposed stresses during the aquifer test. Leakage to the upper aquifer is represented in table 5, either as combined leakance for the intervening confining units, where analytic methods of analysis were used, or as separate leakances from the overlying or underlying confining units where numerical methods of analysis were used.

#### **SUMMARY**

Transmissivities, lateral hydraulic conductivities, storage coefficients, and leakances were determined from 27 aquifer tests, and lateral hydraulic conductivities were determined from 147 well-acceptance tests for the middle and upper aquifers of the Potomac-Raritan-Magothy aquifer system in the northern Coastal Plain of New Jersey. Both aquifers are more uniform in hydraulic properties in the deeper confined system to the south and southeast. More variation in hydraulic properties was found in and near the unconfined parts of both aquifers.

Both the middle and upper aquifers are unconfined in the outcrop areas in the northwest part of the study area. Southeast of the outcrop areas, the aquifers become semiconfined and then confined. The confining unit between the middle and upper aquifers is thin or sandy in the southwestern part of the study area, and vertical leakage may occur between the aquifers in that area. Both aquifers are highly transmissive on the regional scale, and have hydraulic conductivities representative of clean sands.

Based on 12 aquifer tests in the confined area of the middle aquifer, the transmissivity ranges from 2,140 to 13,800 ft $^2$ /d. The lowest transmissivities generally are in the thinner part of the aquifer to the north. Lateral hydraulic conductivities of the middle aquifer calculated from aquifer tests and well-acceptance tests, range from 17 to 385 ft/d. Greater variation in lateral hydraulic conductivity for the middle aquifer appears in or near the unconfined part of the aquifer. The range of storage coefficient values for the middle aquifer is 2.6 x  $10^{-5}$  to  $3.4 \times 10^{-3}$ . The confining units are relatively impermeable; however, leakance was observed to occur in three aquifer tests.

Fifteen aquifer tests are reported for the unconfined and confined parts of the upper aquifer. Transmissivities for the upper aquifer range from 1,760 to 19,400 ft2/d. Lateral hydraulic conductivities from aquifer and well-acceptance tests for the upper aquifer range from 4 to 483 ft/d. Storage coefficients from three aquifer tests in the unconfined region range from  $3.7 \times 10^{-3}$  to  $5.7 \times 10^{-2}$ , which approaches estimated storage coefficients of unconfined aquifers. The effects of partial confinement on two other tests in the unconfined region produced storage coefficients below this range. Transmissivities of the confined part of the aquifer range from 4,010 to 15,450 ft<sup>2</sup>/d. The range of storage coefficients is estimated to be from  $1.0 \times 10^{-5}$  to  $1.8 \times 10^{-3}$ . The confining units are relatively impermeable, although leakance values were determined at two of five sites in the deeper confined system. Greater leakage between the middle and upper aquifers is likely to occur in the southwestern part of the study area near its outcrop, where the confining unit between the middle and upper aquifers is thin or sandy.

#### SELECTED REFERENCES

- Appel, C. A., 1962, Salt-water encroachment into aquifers of the Raritan Formation in the Sayreville area, Middlesex County, New Jersey: New Jersey Department of Conservation and Economic Development, Division of Water Policy and Supply Special Report 17, 47 p.
- Barksdale, H. C., 1937, Water supplies from the No. 1 Sand in the vicinity of Parlin, New Jersey: New Jersey Water Policy Commission Special Report 7, 33 p.
- Barksdale, H. C., Johnson, M. E., Baker, R. C., Schaefer, E. J., and DeBuchananne, G. D., 1943, The ground-water supplies of Middlesex County, New Jersey: New Jersey Water Policy Commission Special Report 8, 160 p.
- Bedinger, M. S., and Emmett, L. F., 1963, Mapping transmissibility of alluvium in the Lower Arkansas River Valley, Arkansas: U.S. Geological Survey Professional Paper 475-C, p. C188-C190.
- Bennett, G. D., 1976, Electric analog simulation of the aquifers along the south coast of Puerto Rico: U.S. Geological Survey Open-File Report 76-4, 101 p.
- Bentley, C. B., 1977, Aquifer test analyses for the Floridan aquifer in Flagler, Putnam, and St. Johns Counties, Florida: U.S. Geological Survey Water-Resources Investigations 77-36, 50 p.
- Boulton, N. S., 1954, Analysis of data from non-equilibrium pumping tests allowing for delayed yield from storage: Inst. Civil Engineers Proc. [London], v.28, p. 603-610. [Discussions by R.W. Stallman, W.C. Walton, and J. Ineson and reply by author.]
- Cooper, H. H., Jr., and Jacob, C. E., 1946, A generalized graphical method for evaluating formation constants and summarizing well-field history: American Geophysical Union Transactions, v. 27, no. 4, p. 526-534.
- Davis, S. N., and DeWiest, R. J. M., 1966, Hydrogeology: New York, John Wiley & Sons, 463 p.
- Eckel, J. A., and Walker, R. L., 1986, Water levels in major artesian aquifers of the New Jersey Coastal Plain, 1983: U.S. Geological Survey Water-Resources Investigations Report 86-4028, 62 p.
- Farlekas, G. M., 1979, Geohydrology and digital-simulation model of the Farrington aquifer in the northern Coastal Plain of New Jersey: U.S. Geological Survey Water-Resources Investigations 79-106, 55 p.
- Freeze, R. A., and Cherry, J. A., 1979, Groundwater: New Jersey, Prentice-Hall, Inc., 604 p.
- Geraghty and Miller, Inc., 1976, Middlesex County 208 area-wide waste management planning task 8-Ground-water analyses: Port Washington, New York.

#### SELECTED REFERENCES -- Continued

- Gill, H. E., and Farlekas, G. M., 1976, Geohydrologic maps of the Potomac-Raritan-Magothy aquifer system in the New Jersey Coastal Plain: U.S. Geological Survey Hydrologic Investigations Atlas HA-557, 2 plates, scale 1:500,000.
- Gronberg, J. M., Birkelo, B. A., and Pucci, A. A. Jr., in press, Selected borehole geophysical logs and drillers' logs data, northern Coastal Plain of New Jersey: U.S. Geological Survey, Open-File Report.
- Hantush, M. S., 1960, Modification of the theory of leaky aquifers: Journal Geophysical Research, v. 65, p. 3713-3725.
- Hantush, M. S., and Jacob, C. E., 1955, Nonsteady radial flow in an infinite leaky aquifer: American Geophysical Union Transactions, v. 36, p. 95-100.
- Hardt, W. F., and Jablonski, L. A., 1959, Results of a pumping test in the vicinity of Woodbridge, Middlesex County, New Jersey: U.S. Geological Survey Open-File Report, 8 p.
- Hasan, Asghar, Kasabach, H. F., and Malone, J. E., 1969, Water resources of the Sayreville area Middlesex County, New Jersey: New Jersey Department of Conservation and Economic Development, Division of Water Policy and Supply Water Resources Circular 20, 32 p.
- Heath, R. C., 1983, Basic ground-water hydrology: U.S. Geological Survey Water-Supply Paper 2220, 84 p.
- Jablonski, L. A., 1968, Ground-water resources of Monmouth County, New Jersey: New Jersey Department of Conservation and Economic Development, Division of Water Policy and Supply Special Report 23, 117 p.
- Kruseman, G. P., and De Ridder, N. A., 1970, Analysis and evaluation of pumping test data: Bulletin 11, International Institute for Land Reclamation and Improvement, Wageningen, The Netherlands, 203 p.
- Leahy, P. P., Paulachok, G. N., Navoy, A. S., and Pucci, A. A. Jr., 1987, Plan of study for the New Jersey Bond Issue ground-water supply investigations: New Jersey Department of Environmental Protection, Division of Water Resources, New Jersey Geological Survey Open-File Report 87-1, 53 p.
- Leggette, Brashears, and Graham, Consulting Ground-Water Geologists, 1961, Ground-water conditions in South Brunswick Township, New Jersey: New York City, 26 p.
- Lohman, S. W., 1972, Ground-water hydraulics: U.S. Geological Survey Professional Paper 708, 70 p.

#### SELECTED REFERENCES -- Continued

- McClymonds, N. E., and Franke, O. L., 1972, Water transmitting properties of aquifers on Long Island, New York: U.S. Geological Survey Professional Paper 627-E, 24 p.
- Owens J. P., and Sohl, N. F., 1969, Shelf and deltaic paleoenvironments in the Cretaceous-Tertiary formations of the New Jersey Coastal Plain, in Subitzky, Seymour, ed., Geology of selected areas in New Jersey and eastern Pennsylvania and guidebook of excursions: Geological Society of America and associated societies, November 1969, Annual Meeting, Atlantic City, New Jersey, New Brunswick, New Jersey, Rutgers University Press, p. 235-278.
- Parker, G. G., Hely, A. G., Keighton, W. B., Olmsted, F. H., and others, 1964, Water resources of the Delaware River Basin: U.S. Geological Survey Professional Paper 381, 200 p.
- Pucci, A. A., Jr., 1986, Summary of studies on the hydrogeology of saltwater intrusion in the Potomac-Raritan-Magothy aquifer system, central New Jersey--1926-85: in Proceedings of the Geological Association of New Jersey, v. 2, 18 p.
- Reed, J. E., 1980, Type curves for selected problems of flow to wells in confined aquifers: U.S. Geological Survey, Techniques of Water-Resources Investigations, book 3, chap. B3, 106 p.
- Reilly, T. E., 1984, A Galerkin finite-element flow model to predict the transient response of a radially symmetric aquifer: U.S. Geological Survey Water-Supply Paper 2198, 33 p.
- Ries, H., Kummel, H. B., and Knapp, G. N., 1904, The clays and clay industry of New Jersey: Geological Survey of New Jersey, Final Report, Trenton, N.J., vol. 6, 548 p.
- Schaefer, F. L., 1983, Distribution of chloride concentrations in the principal aquifers of the New Jersey Coastal Plain, 1977-81: U.S. Geological Survey Water-Resources Investigations Report 83-4061, 56 p.
- Todd, D. K., 1976, Groundwater hydrology: 2nd Edition, New York, John Wiley & Sons, 535 p.
- Vermeule, C. C., 1884, Report on water supply: Geological Survey of New Jersey, v. 3, Trenton, N.J., 352 p.
- Vowinkel, E. F., 1984, Ground-water withdrawals from the Coastal Plain of New Jersey, 1956-80: U.S. Geological Survey Open-File Report 84-226, 32 p.
- Wenzel, L. K., 1942, Methods for determining permeability of water-bearing materials, with special reference to discharging well methods: U.S. Geological Survey Water-Supply Paper 887, 192 p.

## SELECTED REFERENCES -- Continued

Zapecza, O. S., 1984, Hydrogeologic framework of the New Jersey Coastal Plain: U.S. Geological Survey Open-File Report 84-730, 61 p.

#### **GLOSSARY**

- ANISOTROPY: That condition in which significant properties vary with direction.
- AQUIFER: A geologic formation, group of formations, or part of a formation that contains sufficient saturated permeable material to yield significant quantities of water to wells or springs.
- AQUIFER TEST: A controlled field experiment wherein the effect of pumping a well is measured in the pumped well and in observation wells for the purpose of determining hydraulic properties of an aquifer.
- BEDROCK: The solid rock, commonly called "ledge", that underlies gravel, soil, or other superficial material.
- CONFINED AQUIFER: An aquifer in which ground water is under greater than atmospheric pressure. The static-water level in a well in a confined aquifer will rise above the top of the aquifer.
- DRAWDOWN: The decline of the water level in a well after pumping starts.

  It is the difference between the water level in a well after pumping starts and the static water level.
- HETEROGENEITY: Synonomous with nonuniformity. A material is heterogeneous if its hydrologic properties vary with position within it.
- HYDRAULIC CONDUCTIVITY: The volume of water at the existing kinematic viscosity that will move in unit time under unit hydraulic gradient through a unit area measured at right angles to the direction of flow, expressed herein in units of feet per day.
- ISOTROPY: That condition in which significant properties are independent of direction.
- LEAKANCE: The ratio of the vertical conductivity and thickness of a confining unit. Units of 1 over day.
- LITHOLOGIC LOG: Description of the geologic material collected during the sampling of test wells.
- RECOVERY: The rise of the water level in a well after pumping has stopped.

  It is the difference between the water level in a well after pumping stops and the water level as it would have been if pumping had continued at the same rate.
- SATURATED THICKNESS: The thickness of an aquifer below the water table.

  As measured for the sedimentary aquifers in this report, it is the vertical distance between the water table and the lower confining unit in the unconfined areas of the aquifers; in the confined areas, it is the vertical distance between the confining units of an aquifer.


#### GLOSSARY--Continued

- SPECIFIC CAPACITY: The rate of discharge of water from the well divided by the drawdown of water level in the pumped well, expressed herein in units of gallons per minute per foot per unit of time.
- SPECIFIC DISCHARGE (FOR GROUND WATER): The rate of discharge of ground water per unit area measured at right angles to the direction of flow, expressed in units of feet per day.
- SPECIFIC YIELD: Ratio of the volume of water a fully saturated rock or unconsolidated material will yield by gravity drainage, given sufficient time, to the total volume of rock or unconsolidated material. Expressed as a dimensionless unit.
- STEADY FLOW: The flow that occurs if at every point of a flow system the specific discharge has the same magnitude and direction over time.
- STORAGE COEFFICIENT: Volume of water an aquifer releases from or takes into storage per unit surface area of the aquifer per unit change in head. In an unconfined aquifer the storage coefficient is approximately equal to the specific yield. Expressed as a dimensionless unit.
- TRANSMISSIVITY: Rate at which water of the prevailing kinematic viscosity is transmitted through a unit width of aquifer under unit hydraulic gradient. It is equal to the product of hydraulic conductivity and saturated thickness of the aquifer, expressed herein in units of square feet per day.
- UNCONFINED AQUIFER (WATER-TABLE): One in which the upper surface of the saturated zone, the water table, is at atmospheric pressure and is free to rise and fall.
- WATER TABLE: The upper surface of the saturated zone.
- WELL-ACCEPTANCE TEST: A controlled test by an installed pump to determine the productivity of a well expressed as its specific capacity.

## APPENDIX I

## GRAPHS SHOWING WATER-LEVEL DATA FROM AQUIFER TESTS

Data are included in figures 5-32 for documentation purposes and for reference by the reader. The methods for interpreting these data are summarized in the text. Descriptors and type curves, which are used in the graphical analyses, also are included in each figure. Descriptors and interpretation procedures are as documented in the cited references, and are compiled in Lohman (1972).



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 5.--Drawdown in observation well 23-392 for aquifer test 1.





Figure 6.--Drawdown in pumping well 23-42 for aquifer test 2.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 7.--Drawdown in observation well 23-43 for aquifer test 2.




Figure 8.--Drawdown in pumping well 23-40 for aquifer test 3.




Figure 9.--Recovery in observation well 23-41 for aquifer test 3.






Figure 10.--Drawdown in pumping well 23-44 for aquifer test 4.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 11.--Drawdown in observation well 23-789 for aquifer test 4.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 12.--Drawdown in observation well 23-788 for aquifer test 5.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 13.--Drawdown in observation well 23-384 for aquifer test 6.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 14.--Drawdown in observation wells 21-86 and 21-144 for aquifer test 7.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 15.--Drawdown in observation well 23-197 for aquifer test 9.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 16.--Drawdown in observation wells 23-127 and 23-171 for aquifer test 11.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 17.--Drawdown in observation well 23-474 for aquifer test 12.




Figure 18.--Distance-drawdown relation when well 23-621 was pumped for 164 hours in aquifer test 14.




Figure 19.--Distance-drawdown relation when well 23-626 was pumped for 70 hours in aquifer test 15.






Figure 20.--Drawdown in test well 25-551 for aquifer test 16.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 21.--Drawdown in observation well 25-550 for aquifer test 16.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 22.--Drawdown in observation wells 21-81 and 21-86 for aquifer test 17.




Figure 23.--Drawdown in test well 23-690 for aquifer test 18.






Figure 24.--Drawdown in observation well 23-684 for aquifer test 18.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 25.--Drawdown in observation wells 25-289, 25-290, and 25-291 for aquifer test 19.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 26.--Drawdown in observation wells 25-68 and 25-69 for aquifer test 21.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 27.--Drawdown in observation wells 23-595 and 23-596 for aquifer test 22.






Figure 28.--Drawdown in test well 23-602 for aquifer test 23.




Figure 29.--Drawdown in observation well 23-121 for aquifer test 24.






Figure 30.--Distance-drawdown relations when well 23-743 was pumped for 48 hours in aquifer test 25.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 31.--Drawdown in observation well 23-448 for aquifer test 26.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 32.--Drawdown in observation wells 25-206 and 25-207 for aquifer test 27.

## APPENDIX 2

GRAPHS SHOWING WATER-LEVEL DATA FROM AQUIFER TESTS AND FINITE-ELEMENT SIMULATIONS

Data included in figures 33-39 are for documentation purposes and for reference by the reader. The method of finite-element analysis, which is used to interpret the data, is summarized in the text, and in Reilly (1984).



# **EXPLANATION**


- 51 Node number
- 72 Element number
- △ Constant head node
  - Location of simulated test well screen
  - Location of simulated observation well screen

```
117
DEPTH BELOW LAND SURFACE, IN FEET
                     Clay
                     Kr = 1.0; Kz = .1; Ss = 2 \times 10^{-6}
        302
                     Sand (Upper aquifer)
                                                                                Marlboro MUA
                    Kr = 150; Kz = 30; Ss = 5 \times 10^{-7}
                                                                                   (Aquifer test 8)
        454
                     Kr = 1.0; Kz = .1; Ss = 2 \times 10^{-6}
        597
                     Sand (Middle aquifer)
                     Kr - 100; Kz - 10; Ss - 1 \times 10^{-6}
        709
         66
DEPTH BELOW LAND SURFACE, IN FEET
                     Clay
                     Kr = 1.0; Kz = 1.0; Ss = 1.7 \times 10^{-6}
         75
                                                                                   South Brunswick
                     Sand (Upper aquifer)
                     Kr = 200; Kz = 30; Ss = 1.7 \times 10^{-6}
                                                                                (Aquifer test 10)
         98
                     Clay
                     Kr = 1.0; Kz = .1; Ss = 5 \times 10^{-6}
        186
                     Sand (Middle aquifer)
                     Kr - 120; Kz - 30; Ss - 1 \times 10^{-6}
        260
         17
                     Sand (Upper aquifer)
  DEPTH, FEET
                     Kr = 250; Kz = 10; Sy = .01
                                                                                   East Brunswick WD
                                                                                    Phase I
         38
                                                                                   (Aquifer test 13)
                     Kr = 1.0; Kz = 1.0; Sy = .01
         60
         76
DEPTH BELOW LAND
  SURFACE, IN FEET
                     Clay
                     Kr = 1.0; Kz = 1.0; Ss = 2.4 \times 10^{-7}
        117
                     Sand (Upper aquifer)
                     Kr = 200; Kz = 15; Ss = 1 \times 10^{-7}
                                                                                Monroe MUA
                                                                                   (Aquifer test 20)
        220
                     Kr = 1.0; Kz = 0.5; Ss = 1.8 \times 10^{-5}
        240
                     Sand (Middle aquifer)
                     Kr = 240; Kz = 19; Ss = 2 \times 10^{-7}
        290
    Kr = lateral hydraulic conductivity, in feet per day;
```

Kz = vertical hydraulic conductivity, in feet per day;
Ss = specific storage (dimensionless)

Sy - specific yield (dimensionless)

Figure 34.--Simplified hydrogeologic sections of aquifer-test sites 8, 10, 13, and 20 showing lateral and vertical hydraulic-conductivity values used in final model.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 35.--Drawdown from field measurements and simulations results for observation well 25-269 for aquifer test 8.





Figure 36.--Drawdown from field measurements and simulations results for observation well 23-287 for aquifer test 10.



LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED,
IN MINUTES PER FOOT SQUARED

Figure 37.--Drawdown from field measurements and simulations results for observation well 23-290 for aquifer test 10.






Figure 38.--Drawdown from field measurements and simulations results for observation well 23-615 for aquifer test 13.




LOGARITHM OF TIME DIVIDED BY OBSERVATION-WELL DISTANCE SQUARED, IN MINUTES PER FOOT SQUARED

Figure 39.--Drawdown from field measurements and simulations results for observation well 23-228 for aquifer test 20.

Hydraulic Properties of the Middle and Upper Aquifers of the Potomac-Raritan-Magothy Aquifer System in the Northern Coastal Plain of New Jersey (Geological Survey Report 18, New Jersey Geological Survey)



Aquifer-test and well-acceptance-test site locations for the middle aquifer, Potomac-Raritan-Magothy aquifer system



Aquifer-test and well-acceptance-test site locations for the upper aquifer, Potomac-Raritan-Magothy aquifer system

