PROPOSED TRAIL NETWORK

Primary Trails
Material: Asphalt and Concrete
Width: 12'
Total Length: 4.62 Miles

Secondary Trail
Material: Compacted Stone Aggregate
Width: 8'
Total Length: 0.98 Miles

Boardwalk
Material: Various Wood and Composite Components
Width: Location Dependent (12' or 8')
Total Length: 634'

SECONDARY TRAILS

BOARDWALK

PRIMARY TRAILS

PLAZA SPACE

TRAIL NETWORK

LIBERTY STATE PARK
ECOSYSTEM RESTORATION PROJECT

US Army Corps of Engineers. NOAA U.S. FISH & WILDLIFE SERVICE pH PRINCETON HDR