Clean Water Financing

Priority System, Intended Use Plan, Project Priority List and Response Document for Federal Fiscal Year 2008

New Jersey Department of Environmental Protection
Environmental Regulation
Division of Water Quality
Municipal Finance and Construction Element

January 2008

CLEAN WATER FINANCING

FEDERAL FISCAL YEAR 2008 (FFY2008) PRIORITY SYSTEM, INTENDED USE PLAN, PROJECT PRIORTY LIST AND RESPONSE DOCUMENT

TABLE OF CONTENTS

PROGRAM OVERVIEW Page 1

FFY2008 PRIORITY SYSTEM
I - Priority List - General Page 6
II - Ranking Methodology Page 6
III - Construction Grants Program Policies Page 13

FFY2008 INTENDED USE PLAN Page 13
A. Financial Relationships between the CWSRF and the DWSRF Page 16
B. Document Submittal Schedules Page 16
C. Loan Awards Page 18
D. Smart Growth Initiatives and the Financing Program Page 19
E. Preaward Approvals/Emergency Projects Page 24
F. Socially and Economically Disadvantaged (SED) Business Participation Page 24
G. Stormwater/Nonpoint Source (NPS) Management Projects Page 25
H. Brownfields Set-Aside and Conduit Projects Page 27
I. Combined Sewer Overflows Page 28
J. Short-Term and Long-Term Goals; DEP Fee; Miscellaneous Items Page 28

APPENDIX A. RESPONSE DOCUMENT
APPENDIX B. STATE FISCAL YEAR 2008 LOAN AWARDS LIST
APPENDIX C. PROJECT PRIORITY LIST
APPENDIX D. PROJECT NARRATIVES

Priority System, Intended Use Plan, Project Priority List, and Response Document for Federal Fiscal Year 2008 (FFY2008)

- Clean Water Financing -

PROGRAM OVERVIEW

The Water Quality Act of 1987, which amended the Clean Water Act (CWA), required states to establish a Clean Water State Revolving Fund (CWSRF) program to qualify for federal capitalization grants. The CWSRF provides financial assistance for the construction and implementation of projects that help to protect, maintain and improve water quality. It is a self-perpetuating program, in that loan repayments are used to finance future projects.

Established in 1988, New Jersey's CWSRF program is included in the Environmental Infrastructure Financing Program (EIFP). The EIFP is a partnership between the New Jersey Department of Environmental Protection (Department) and the New Jersey Environmental Infrastructure Trust (Trust) providing low-interest loans for infrastructure projects. The Department and the Trust also administer New Jersey's Drinking Water SRF (DWSRF) under the Safe Drinking Water Act, the priorities and policies for which are established in a separate Priority System document. Together, since 1988 the clean water and drinking water components of the EIFP have awarded approximately $4 billion in loans throughout the State. As of January 30, 2008, 394 of the 646 funded projects totaling approximately $1.8 billion in construction costs have been completed, have initiated operations, and have been administratively closed out; 252 projects totaling almost $2.2 billion in project costs are actively contracting or under construction.

Every year, the Department develops a "Proposed Priority System, Intended Use Plan, and Project Priority List" as required by federal and State law. After the public has had an opportunity to comment on the Department's proposal, the Department submits a final "Priority System, Intended Use Plan, Project Priority List, and Response Document" to USEPA for its approval. The Priority System (PS) describes the ranking methodology for the municipal water pollution control projects that are eligible for financial assistance through the EIFP. The ranking system gives highest priority to projects that address discharges of raw, diluted, or inadequately treated sewage to the State's waters during wet weather, including projects to abate combined sewer overflows (CSOs) and projects to address sanitary sewer systems that overflow. CSO abatement projects are expensive and are usually located in financially distressed urban areas, making cost a serious concern. Discharges from combined sewer systems impair water uses, and

can lead to the closing of beaches and shellfish beds. Projects to remediate overflows of sanitary sewage are essential to safeguard water quality and result in improvements to the health, safety, aesthetic value, and recreational attributes of the State's waters.

It should be noted that the pace of the loan program has significantly increased in recent years. The loan awards have exceeded an average of $400 million per year; an amount four times the average of the loan awards made from 1992-1999. Concurrently, the federal contribution to the Clean Water SRF Programs has been significantly curtailed resulting in reduced amount of loan monies being available to provide new loans. Therefore, it is possible that adequate funds may not be available to finance all projects that submit applications for the Clean Water Financing Program in 2008 and beyond. Projects are certified for funding based on the project's rank, the amount of available funds, and compliance with the Program's requirements and deadlines for planning, design and application submittal.

In view of the reduced amount of available funding, portions of the FFY2008 Priority System ranking methodology have been revised and some of the funding policies have been amended from those adopted under the FFY2007 Priority System document. The most significant changes included in the FFY2008 Priority System are identified below:

1. The project ranking methodology was adjusted to assign higher priority for traditional wastewater management projects that are more directly linked to water quality (such as combined sewer overflow (CSO) abatement activities, sewage treatment plant (STP) upgrades and sanitary sewer rehabilitation) as compared to projects in the non-traditional project categories (such as landfill closures, land acquisition, landfill construction and site remediation). The Department has assigned higher priority to traditional projects with direct water quality implications over the non-traditional project categories because (1) these projects are directly related to ambient water quality and public health and have greater potential to adversely impact designated water uses (such as potable water supplies and recreational activities); (2) the latest Clean Watershed Needs Survey shows that more than 80% of New Jersey's needs are in the wastewater treatment categories (and these needs are on the rise with new requirements for combined sewer systems and phosphorous control on the horizon); and (3) there is no other significant source of financing available to owners/operators of wastewater treatment facilities to maintain and improve their systems.

However, the Program continues to maintain eligibility for all of the project categories that have been eligible in the past. Specific details regarding the ranking methodology can be found in Section II under "Priority System".

2. In part, to offset the impact of the priority ranking changes on financing of brownfield redevelopment projects, the FFY2008 Priority System document establishes a reserve dedicated solely for landfill closure and site remediation projects. The Department has allocated $30 million in Fund loans as the "Brownfield Set-Aside" for the 2008 Financing Program. Project priority will be determined in accordance with the ranking methodology included in this document and the set-aside funds will be allocated based on the project's rank, the sponsor's ability to meet program requirements and the amount of funds available for these purposes. In

cases where the available Fund loan does not cover 50 or 75 percent of the allowable project costs, the Trust may finance the remaining allowable costs, which may exceed their standard 50 or 25 percent contribution. Financing above and beyond the amount set-aside for such projects will be considered if monies are available after the need for funding of higher ranking projects during the funding cycle has been satisfied. Conversely, if funds in the set-aside category remain unused because of insufficient demand for brownfield redevelopment loans in the 2008 Program, those funds may be used to finance projects listed on the Priority List that may otherwise not receive financing in the 2008 Program.

In addition, a new project category (Conduit Financing) has been included in the FFY2008 Priority System to establish a separate classification for projects where a developer, LLC, partnership or other private entity is involved and a local government unit serves as the applicant on the private entity's behalf to statutorily qualify for loans from the Department and the Trust. This category generally includes landfill closure and site remediation projects where the project site is privately owned and/or private use is anticipated. However, if a local government unit that sponsors a project on behalf of a private entity commits to providing a general obligation pledge (including its unlimited taxing power) as security for the DEP and Trust loans, the project is considered exempt from the conduit financing classification and the corresponding limitations. Projects that are secured with a local government's general obligation pledge will be assigned points under the ranking methodology as if the site were in public ownership.

The Department will continue the $25 million per project limit on the amount of Fund monies that a conduit borrower can receive. The changes to the 2008 Priority System ranking methodology give one of the lowest point assignments to conduit projects and previously-financed conduit borrowers will not be eligible for supplemental loans from the Department to cover unanticipated cost increases due to bid receipt, differing site conditions, change orders or other circumstances.

3. The FFY2008 Priority System document does not include provisions for a second chance program. The Department considered eliminating the second chance program in the 2007 Financing Program, but rather than eliminating it, the FFY2007 Priority System indicated that the second chance provisions would be eliminated in the 2008 funding cycle. No comments regarding the elimination of second chance provisions were received. The elimination of the second chance provisions was made to better manage the program workload that has been steadily increasing along with its scope in recent years. There is often not enough time for the Department to adequately evaluate the project and provide certification to the Trust. Second chance projects generally do not have complete planning documents, have difficulty completing public participation activities in the short time available, and generally do not apply for permits and approvals needed to implement the project in a timely manner. Also, the need for a second chance process is not as pressing, as it once was, because of the Department's ability to issue pre-award approval and provide interim financing for projects that miss the initial October deadline.

4. The FFY2008 Priority System continues the enhanced financing for smart growth projects with the exception of open space land acquisition projects, and those landfill closure and site remediation projects not located in special Brownfield Designated Areas (BDA). New projects

in these two categories will continue to be eligible in 2008, but at the traditional (50% DEP/50% Trust) financing rate. Landfill closure and site remediation projects located in BDAs remain eligible for the Smart Growth funding rate of 75% DEP/25% Trust.

5. The Priority System establishes a new requirement for projects involving publicly-owned brownfield projects. Project sponsors must pledge that the site on which the improvements occur will remain in public ownership for the term of the loan (typically 20-23 years). While the Financing Program will allow the public sponsor to sell the improved land to a private entity and use it for private purposes, the loans provided by the Department and the Trust to finance the remediation must be repaid in full upon the transfer of ownership. This requirement does not apply to conduit borrowers' projects, which by their nature, involve private developer(s) and private ownership interests.

6. The Priority System modifies and expands the "Approved Watershed Management Plan" ranking subcategory to include the following subcomponents:

Environmental Enhancement Activity	Points
Watershed-Based Implementation Plans	50
Implementation of Regional Stormwater Management Plans	50
Sustainable Community Planning	100

The changes to this category encourage and facilitate the implementation of environmentally sustainable practices at the local government level that go beyond compliance with existing regulatory requirements and incorporate one or more of the aforementioned environmental enhancement activities. Additional points are assigned for projects located in or benefiting municipalities where sustainable community strategies have been developed and master plans and/or ordinances adopted that include provisions to reduce water consumption, encourage water reuse and incorporate "green" building techniques that increase water efficiency such as green roofs, green streets, tree filters, rain gardens, rain barrels, and porous pavement.

7. The FFY2008 Priority System provides financing to projects in the following order: (1) Supplemental Loans, (2) Emergency Projects, (3) Projects with pre-award approval, (4) Wastewater Management Projects: (a) Combined Sewer Overflow and Sanitary Sewer Overflow Abatement, (b) Sewage Treatment Plant Improvements, (c) Rehabilitation/Replacement of Sanitary Collection and Conveyance Systems, (d) Sludge Management, (e) Wastewater Reuse, (f) Septic System Repair or Replacement, (g) New wastewater treatment, conveyance or collection systems, (5) Stormwater Management Activities, (6) Nonpoint Source Pollution Controls: (a) Landfill Closures, (b) Open Space Land Acquisition, (c) Landfill Construction, (d) Site Remediation, and (7) Conduit Borrowers.

Since the priority ranking methodology has been significantly changed and the subsidy for certain categories of projects is being reduced, the Department is assigning a higher priority to those projects that obtained pre-award approval in prior years, but were unable to close on the Department and Trust loans in 2007. This one-year exception is necessary to be fair to project sponsors that have diligently pursued loan awards in the 2007 funding cycle but were unable to

execute loan agreements in accordance with the program's schedule for legitimate reasons beyond their control. In addition, projects that received pre-award approval at a time when the project scope qualified for the enhanced financing program will continue to be eligible for reimbursement of up to 75 percent of the allowable project costs at zero percent interest. This provision will only be effective for the 2008 Financing Program. Currently, five land acquisition projects that have pre-award approval for specific sites may fall in this category, with an estimated aggregate loan amount of $25 million.

The Department no longer routinely distributes hard copies of the Priority System document for public review but will make individual exceptions upon request, if necessary. The format for distribution of the Priority System documents is via compact discs (CDs) and posting on the Department's web site at http://www.nj.gov/dep/dwq/cwpl.htm. In addition to the complete Priority System, Intended Use Plan, Project Priority List and Response Document, the CDs and the web posting include a project description and project ranking worksheet for each listed project.

It should be noted that, although Congress provided funds to the CWSRF in FFY2007, reductions to the federal funding levels were made in FFY2008 and further reductions may be experienced in the future. The State's receipt of additional federal funding in the future is uncertain since the CWA has not yet been reauthorized. Loan repayments and State bond proceeds are available to address some clean water needs but additional federal funding will be necessary to fully address the overall water quality improvement needs of the State. Several legislative initiatives to reauthorize the CWA and provide increased funding for wastewater treatment projects and other water quality improvements have been proposed.

PRIORITY SYSTEM

I. Project Priority List — General Information

Clean water projects must be listed on the Project Priority List in order to be considered eligible for financial assistance under the EIFP. The applicant must also submit all the required application material in a timely manner.

The Priority List identifies the estimated total eligible building costs under the appropriate project category. Except for open space land acquisition projects, the figure under the "Total Eligible Project Cost" includes the estimated total eligible building costs, the related costs for construction services (i.e., administrative, legal, engineering, inspection, one year start-up services, etc.), the allowance for planning and/or design, three percent for the recipient's administrative costs, and a five percent contingency cost. The figure under the "Total State Amount" column represents 100 percent of the estimated total eligible project costs. Project scope changes and related cost updates submitted by project sponsors in response to the public participation process are included on the final FFY2008 List.

Any significant revisions to the Priority List during the fiscal year will be subject to a public participation process, including a 30-day comment period. The Department does not, however, consider the following revisions to the Priority List to be significant:

1. Bypassing (i.e., deferring the funding of) a project to a future fiscal year if all requirements (including commitment to and compliance with the project document submittal schedule) of the CWSRF are not satisfied on schedule.
2. Increases or decreases in allowable project costs that may change the fundable range of the Priority List.
3. The addition of a project or projects to the fundable range as a result of their qualifying under the Public Health Hazard (PHH) bypass or emergency project criteria.
4. The revision of the fundable range of the Priority List as a result of a change in (1) the allocation that New Jersey receives, (2) the State's contribution to the CWSRF, and/or (3) the total amount of monies made available for clean water projects from the EIFP.
5. The revision of the fundable range of the Priority List as a result of ensuring the proper dollar amount is obligated to eligible project categories (if limitations are included under the CWA's reauthorization).
6. The replacement of a project sponsor identified on the Project Priority List with another eligible project sponsor that willingly assumes the role of loan applicant for the project.

II. Ranking Methodology

The Department ranks all projects on the basis of the total number of ranking points each project receives and places the projects on the Priority List according to their ranking. Projects receive points under five categories. These are (1) Local Environmental Enhancement Planning Activities, (2) Project Discharge Category, (3) Water Use/Water Quality, (4) Smart Growth Approvals, and (5) Population.

A. Local Environmental Enhancement Planning Activities

The purpose of this section is to encourage and facilitate implementation of environmentally sustainable practices at the local government level. Prudent environmental planning that incorporates sustainability measures is necessary to achieve cost-effective and environmentally sound water quality improvement within the watershed. Priority will be given to projects located in or benefiting municipalities that have implemented programs and actions that go beyond compliance with existing regulatory requirements and incorporate the following environmental enhancement planning strategies.

Watershed-Based Implementation Plans: Watershed-Based Implementation Plans address impairment(s) found on Sublists 4 or 5 of the New Jersey Integrated Water Quality Monitoring and Assessment Report. Prudent watershed planning is necessary to achieve cost-effective and environmentally sound water quality improvement within the watershed. To provide an incentive for project sponsors to complete watershed-based plans that promote the implementation of point and nonpoint source pollution control projects that are consistent with Department goals, projects located in or benefiting municipalities that demonstrate implementation of watershed-based plans will be given an additional 50 priority points.

Implementation of Regional Stormwater Management Plans: Regional stormwater management plans are voluntary local analyses that provide targeted protection to a specific area based on local issues and conditions. Regional stormwater management plans are adopted into Water Quality Management Plans and may include specific implementation projects that address existing impacts of stormwater runoff. Projects located in or benefiting municipalities with adopted regional stormwater management plans will be provided an additional 50 priority points.

Sustainable Community Planning: Sustainability communities develop and adopt master plans and ordinances that improve the overall quality of life for citizens of today as well as generations of tomorrow by planning within natural resource capacity constraints and providing for a healthy economy, environment and society. Projects located in or benefiting municipalities where sustainable community strategies have been developed and master plans and/or ordinances adopted will be awarded an additional 100 priority points. These strategies must include but are not limited to the following:

- A plan to reduce water consumption and increase water efficiency and re-use.
- Policies that require consideration of green design in municipal construction projects or redevelopment projects, such as green roofs, green streets, tree filters, rain gardens, rain barrels, porous pavements, etc.

The FFY2008 Priority System reflects the Department's priorities to encourage sustainable growth in communities by incorporating consistent criteria for the protection of natural resources and implementation of smart growth and green design principles.

Green design principles include green building practices that increase energy and water efficiency; use renewable energy; use environmentally friendly building materials that are made with recycled materials, are durable, sustainability harvested or produced locally; improve indoor air quality; and makes appropriate site selection and minimizes site disturbance to reduce environmental impacts.

B. Project Discharge Category Points

All projects receive ranking points based on the project discharge category. In case of multiple purpose proposals, projects qualify for the discharge category that represents the major scope of the project. If a project has aspects that can be described by more than one category, the project may be broken into separate projects. Tables IA and IB show the project discharge categories and their corresponding ranking points.

Table IA. Ranking Points Related to Project Discharge Category For Wastewater Treatment Facilities

Project Discharge Category	Description	Points
Combined Sewer Overflow (CSO) & Sanitary Sewer Overflow (SSO)	This category includes projects that involve combined sewer system (CSS) rehabilitation/repair, the construction of treatment and/or storage facilities within CSS, at discharge locations or at domestic treatment works that reduce or eliminate CSOs, or the separation of combined sewer systems by the consolidation and elimination or permanent sealing of CSO discharge points. Also included are projects that implement corrective measures to rectify overloaded conveyance systems that experience chronic overflows which result in discharges of raw or inadequately treated sewage, including projects for rehabilitation, repair, and/or replacement of the conveyance system.	600
Sewage Treatment Plant (STP) Improvements	STP improvements include upgrades, expansion or other improvements to a treatment facility or the elimination of an existing STP and the connection to an alternative treatment facility to meet applicable treatment levels. This category also includes the purchase and installation of security and energy efficiency measures at the STP.	500
Sanitary Sewer System	This category includes a wide variety of corrective measures to sanitary sewer collection and conveyance systems that do not experience chronic overflows, such	

Rehabilitation	as the rehabilitation, repair, or replacement of sanitary sewers, pump stations, interceptors, or the purchase of equipment to properly maintain the sanitary sewer system.	450
Sludge Treatment/Disposal Facilities	Included in this category are projects involving the construction of facilities to manage sludge from STPs or from potable water treatment activities, such as the installation of dewatering equipment, or the implementation of land application or composting activities. Also included in this category of projects are improvements or repairs to sludge incinerators.	350
Wastewater Reuse	Wastewater reuse includes the construction of facilities that promote the reclamation of water for beneficial reuse such as the use of treated effluent for agricultural or other purposes. This category includes the construction of conveyance and distribution systems to allow for reuse activities.	300
Septic System Repair/Replacement	Under this category are projects that involve repairs, improvements, and/or replacement of individual or small community, on-site septic systems.	275
New Systems	This category includes projects that involve the construction of new facilities to provide collection, conveyance or treatment of sanitary sewage.	250

Table IB. Ranking Points Related to Project Categories for Stormwater and Nonpoint Source Pollution Management Facilities

Project Category	Description	Points
Stormwater Management and Other NPS activities	This category includes the construction or rehab-ilitation of stormwater basins, sewer systems or storm drains, the extension of outfall pipes, green roofs, green streets, tree filters, rain gardens, rain barrels, porous pavement or the purchase of maintenance equipment (such as street sweepers, aquatic weed harvesters and skimmer boats). Also included in this category are projects that stabilize streambanks, restore lakes or address runoff from salt storage facilities and the implementation of measures to address pollution concerns from agricultural cropland activities and manure runoff management and feedlot operations.	225
Landfill Closure, Open Space Land Acquisition and Conservation and Well Sealing	Included in this category is the implementation of measures to prevent and control pollutants from entering groundwater at non-operating landfill sites that are publicly owned and at abandoned well	150

	locations. The category also includes open space land acquisition and conservation projects that help to protect or maintain water quality.	
Landfill Construction and Remedial Action Activities	This category includes the construction of facilities to collect, convey and/or treat leachate and runoff from new publicly-owned landfill cells or from publicly-owned contaminated sites.	75
Projects sponsored by Conduit Borrowers/ Private Activity	This category generally includes environmental infrastructure projects where a developer, LLC, partnership or other private party is involved in the project. Also included in this category are landfill closure measures and remedial action activities where the project site is privately owned. If a local government unit that sponsors a project on behalf of a private entity commits to providing a general obligation pledge (including its unlimited taxing power) as security for the DEP and Trust loans, the project is considered exempt from the conduit financing classification and corresponding funding limitations. Projects that are secured with a local unit's general obligation pledge are assigned higher points under the project discharge category as if the site were in public ownership.	50

C. Water Use/Water Quality Points

Points for water uses (present and potential) and for existing water quality conditions are given to projects that will improve discharges that adversely impact surface waters. The assignment of points for "public nuisance" is given to on-site system projects where failures have been identified. Table II below shows the breakdown of the ranking points for water use; in general, the highest values are given for projects that discharge to water bodies with potable, recreational, and fishing uses.

Table II. Ranking Points Related to Water Use (Existing and Potential)

Water Use		**Basis/Description**	**Points**
Public Potable Water Supply		Public and nonpublic community surface supply for water companies or municipalities based on NJ Statewide Water Supply Master Plan.	200
Recreation ("Primary Contact")		Waters with bathing areas monitored routinely as public beaches as well as the Delaware River upstream of Trenton (north of East Bridge Street at the Lower Trenton Bridge).	125
Fishing	Shellfish	State water bodies that are designated as shellfish growing waters by *N.J.A.C.* 7:12.	125

	Trout	State freshwater bodies designated for trout production or maintenance by the NJ Water Quality Standards (*N.J.A.C.* 7:9B).	75
	Non-trout	State freshwater classifications not designated trout production or maintenance by *N.J.A.C.* 7:9B (see Trout description above), including all Delaware River freshwater zones above mile-point 85 as defined by the Delaware River Basin Commission.	25
Public Nuisance		Indirect water use impacts; applies to areas with identified on-site wastewater treatment system failures.	50
Agriculture		Surface water for agricultural use, such as irrigation and farm ponds, based on Department diversion permit (permits required for >70 gal/min diversion).	25
Industry		Surface water known to be used for industrial use such as cooling.	25

Table III shows the points for not meeting or marginally meeting certain water quality parameters. The points reflect the impact the parameters have on meeting the State's goal to protect and enhance surface water resources, quality criteria, and designated water uses. The magnitude of the contribution that municipal sewerage facilities have on each of the conditions is reflected in the points awarded under these categories. Dissolved oxygen and fecal coliform have the highest points because of their immediate and direct impact on the fishable/swimmable water use, coupled with the fact that inadequate municipal treatment facilities can be a major cause of contravening water quality standards.

Nutrients reflect the presence of phosphorus/phosphates and nitrates/nitrites in a water body. Excessive nutrient levels in freshwater streams and lakes may result in impacts on water uses, including algal blooms; depleted oxygen levels; odor, taste and increased treatment costs for purveyors; impacts on aquatic populations, and esthetic concerns. Points are given for nutrients only if the surface waters involved significantly impact existing potable water reservoirs, surface water impoundments or lakes, public bathing areas, or shellfish growing waters. Since there are no nutrient standards for coastal and estuarine waters, no points were assigned for discharges to those water bodies.

Points for toxics address the relative magnitude of ammonia, metals, pesticides, and organic chemicals in the water body. Toxics were also given lower points since in most cases the significant contributions of toxic substances come from industrial sources that are better controlled through pretreatment and are only incidentally abated by municipal treatment facilities. In the case of the toxicity of ammonia, municipal facilities are usually the main source, but the most significant impact is associated with streams designated for trout production/maintenance, which already receive a high number of points under the water use category.

Table III. Ranking Points Related to Water Quality				
		Points for Water Quality that		
Water Quality		Meet	Marginally Meet	Do Not Meet
		The Water Quality Standard*		
Parameter	Dissolved Oxygen	0	50	100
	Fecal Coliform	0	50	100
Parameter	Nutrients	0	25	50
Category	Toxics	0	25	50

*The Water Quality Standard for the applicable parameter or category.

D. Smart Growth Approvals

The Department seeks to coordinate and enhance the State Planning Commission's (SPC) efforts to encourage smart growth through the implementation of the State Development and Redevelopment Plan. The Department assigns ranking points to projects that serve municipalities that the SPC has approved under the Center Designation or Plan Endorsement Process.

For a project serving more than one municipality, the SPC points were included for ranking purposes if the designated center or the endorsed plan is a significant component of the overall project. For further information regarding the State Development and Redevelopment Plan, contact the NJ Office of Smart Growth, Department of Community Affairs, 101 South Broad Street, 7th floor, PO Box 204, Trenton NJ 08625-0204 or call (609) 292-7156.

Table IV. Ranking Points Related to State Planning Commission Approvals	
Community Type	Points
Urban Centers and Complexes	50
Regional Centers	25
Existing Designated Towns	15
Existing Villages	10
Hamlets	5

In addition, projects located in or benefiting areas designated as BDAs, TDR receiving areas or Transit Villages also receive 10 points, so that these projects will rank higher than similar projects that are not located in, or provide benefit to, these smart growth areas.

E. Population Points

Projects are also assigned points based on the population of the project area. One point is given for every million people living in the project area on a year-round basis. Thus, if projects have the same number of ranking points after having received all eligible points,

population points become the tiebreaker, with higher priority given to the project serving the higher population.

F. Public Health Hazard (PHH) and Emergency Repair Projects

In instances where project conditions are determined to constitute a PHH by the Commissioner of the Department of Environmental Protection in consultation with the Commissioner of the Department of Health, the project will receive funding priority over other projects on the Priority List. The review procedure involves a survey of the extent of wastewater problems such as: incidences of sewage-borne disease, contaminated wells, and homes or buildings with sewage back up. Details of the PHH procedure are available in the FFY96 PS document and are incorporated in the FFY2008 PS document by reference. Copies of the FFY96 PS document may be requested by calling the Bureau of Program Development and Technical Services at (609) 292-3859.

The Department recognizes that environmental infrastructure emergencies may occur that endanger public health and welfare and can result in substantial environmental damage. Such circumstances require an immediate response for which a complete technical and environmental review in advance of construction to address the emergency situation is not necessary or feasible. The Department has developed a process to respond expeditiously when emergencies occur, obtain basic project information, make an eligibility determination and issue a preaward approval so that owners/operators can expeditiously undertake the needed repairs and maintain eligibility for those expenditures through the EIFP.

For ranking purposes, projects eligible for financing in the 2008 Program will be offered loan awards in the following order: (1) Supplemental Loans, (2) Emergency Projects, (3) Projects with pre-award approval, (4) Wastewater Management Projects: (a) Combined Sewer Overflow and Sanitary Sewer Overflow Abatement, (b) Sewage Treatment Plant Improvements, (c) Rehabilitation/Replacement of Sanitary Collection and Conveyance Systems, (d) Sludge Management, (e) Wastewater Reuse, (f) Septic System Repair or Replacement, (g) New wastewater treatment, conveyance or collection systems, (5) Stormwater Management Activities, (6) Nonpoint Source Pollution Controls: (a) Landfill Closures, (b) Open Space Land Acquisition, (c) Landfill Construction, (d) Site Remediation, and (7) Conduit Borrowers.

III. Construction Grants Program Policies

The delegation of authority for the Federal Construction Grants Program from the U.S. Environmental Protection Agency to the New Jersey Department of Environmental Protection expired on June 30, 2000. As of July 1, 2000, USEPA Region II has assumed full responsibility for the program. Any questions on outstanding Federal Construction Grants projects or issues should be directed to Mr. Michael Hajducek, P.E., USEPA Region II, Water Programs Branch, 290 Broadway, New York, New York 10007. Mr. Hadjucek can be contacted by calling at (212) 637-3858.

INTENDED USE PLAN

USEPA requires the Department to develop an Intended Use Plan (IUP) annually to qualify for CWSRF capitalization grants to support the program and the project loans. This IUP provides information on funds available through the EIFP to provide financial assistance for clean water projects in SFY2009 and identifies State policies governing loan awards. It includes information on the following:

1. the list of projects used for funding purposes;
2. the long and short-term goals of the state's program;
3. the programmatic activities to be supported with the anticipated funds;
4. the timing and use of such funds;
5. the criteria and method of distribution of the funds; and
6. provisions for interim reporting (as required by the Regional Administrator at the time of a capitalization grant award).

Programmatic requirements imposed by the Water Quality Act of 1987 include 1 through 5 below. It is anticipated that these provisions will be maintained in a subsequent federal reauthorization act or federal policy. If substantial changes in the Act necessitate the Department's revision of the FFY2008 PS document, additional public participation efforts will be conducted.

1. The schedule of state capitalization grant payments, jointly agreed upon by the Administrator of the EPA and each state, is based upon the state's IUP.
2. States are required to deposit in the CWSRF, from state monies, an amount equal to at least 20 percent of the total amount of all capitalization grants made to the state.
3. The fund created with federal capitalization grants can only be used to provide assistance for (a) the construction of publicly owned treatment works, (b) the implementation of a NPS (nonpoint source) management program, which includes construction of stormwater/NPS management facilities, and (c) the development and implementation of an estuary conservation and management plan. Although CWSRF loans may only be provided for publicly-owned wastewater treatment and stormwater sewer systems, if a government unit assumes ownership of a privately-owned system, a loan may be provided under the authority of section 603(c) of the federal CWA. A state may also deem the public ownership requirement as being met for small/on-site systems if adequate inspections and operations are ensured through the establishment of a septic management district or use of service easements. In New Jersey, since the CWSRF enabling legislation requires that the loan be awarded only to a local government unit, privately-owned NPS management projects (including landfill closure, landfill construction and site remediation) must secure the sponsorship of a local government unit to act on behalf of the private entity.
4. Monies in the CWSRF may be used to provide loans at or below market interest rate, for terms not greater than 20 years (after completion of construction). Repayments must begin no later than one year after completion of the project and must be credited to the CWSRF (principal and interest) for Title VI purposes. The recipient of a loan must establish a

dedicated source of repayments. The CWA also authorized the use of federal CWSRF monies to refinance local debt obligations, provide guarantees, or purchase insurance.

5. Prior to and including FFY94, states were required to reserve the greater of $100,000 or one percent of their annual allotment for the development and implementation of NPS management programs. This reserve may be re-enacted or otherwise modified for FFY2008 as a result of reauthorization of the CWA or subsequent federal guidance.

The Table below represents estimated amounts of the available sources and anticipated uses for the Clean Water component of the Environmental Infrastructure Financing Program:

SFY2008 Financing Program

Sources:

Funds Available from prior years	$167.9M
Interim Financing Program Funds	$114.0M
Repayments from prior years' loans	$ 54.0M
FY2007 CWSRF Grant (Project Fund)	$ 48.7M
Transfer to DWSRF	($6.0M)
Total	$378.6M

Uses:

Projects Financed in the SFY2008 Program	$246.2M
Trust Debt Service Reserve	$ 0.0M
Total	$246.2M
Projected Balance Available for SFY2009 Program:	$132.4M

SFY2009 Financing Program

Anticipated Sources:

Funds Available from prior years	$132.4M
Repayments from prior years' loans	$ 63.0M
Other (Projected interest, DSR release, …)	$ 64.9M
FY2008 CWSRF Grant (Project Fund)	$ 26.7M
Total	$287.0M

Anticipated Uses:

Projects to be Financed in the SFY2009 Program	$250.0M
Trust Debt Service Reserve	$ 0.0M
Total	$250.0M

Projected Carry-Forward Balance for CWSRF Program: $37.0M

A. Financial Relationships between the CWSRF and the DWSRF

The Safe Drinking Water Act Amendments of 1996 offer states the flexibility to meet the funding needs for drinking water and wastewater facilities by transferring funds from one SRF program to the other. Annually, an amount up to 33% of the Drinking Water SRF Capitalization Grant may be transferred from the CWSRF program to the DWSRF program, or vice versa. The USEPA has issued guidance that would allow utilization of transfer credits and transfer of funds on a net basis (i.e., funds could be moved in both directions), provided that the final transferred amount does not exceed the authorized ceiling.

The CWSRF program evaluates funds available to determine if adequate monies are available to be utilized for clean water projects in the current fiscal year. In addition, the type and number of DWSRF projects are reviewed and a determination is made on the need of the funds to be transferred from the CWSRF loan repayments to the DWSRF accounts or vice-versa. In accordance with established procedures, a total of eight transfers of funds from CWSRF repayments to DWSRF have thus far been approved by USEPA for a sum of $64,256,610.

The Department fully supports efforts to enact legislation to continue to allow the transfer of funds and the transfer provision has been extended by the USEPA for FFY2008. If approved, the Department reserves the right to transfer funds from the CWSRF to the DWSRF (or vice-versa) each fiscal year to the extent allowed by law. The Department will annually evaluate the monies available in each SRF program and whether there is a need to transfer funds. While all projects that meet the program requirements and are ready to proceed have been able to receive a CWSRF or DWSRF loan in the past, the ability of the programs to finance all qualifying projects in the future is uncertain because of reduced funding.

In addition to the potential transfer of funds between the CWSRF and DWSRF, the Department is continuing its policy to cross-collateralize the DWSRF with the CWSRF. This feature results in significant savings to project sponsors and, in particular, the drinking water project sponsors since there is a large source of revenue available to cover possible loan defaults. Under the EPA-approved procedures associated with cross-collateralization, a temporary transfer of funds between the two SRFs may occur as may be necessary to cover the default of a loan repayment or other financial obligation. The Department and the Trust would take steps to collect any obligations resulting from a loan default and reimburse the appropriate drinking water or clean water account.

B. Document Submittal Schedules

All local government units that have a project or projects listed or eligible for listing on the FFY2008 Priority List were required to commit to the following schedule by October 15, 2007 to be considered for FFY2008 funding. The commitment had to be made in writing to the Assistant Director, Municipal Finance and Construction Element (MF&CE) with a copy to the Executive Director, New Jersey Environmental Infrastructure Trust. Prior to the submission of a commitment letter, all applicants were encouraged to attend a pre-planning meeting with appropriate staff within the Municipal Finance and Construction Element.

2008 Loan Program -Traditional Schedule	
Activity	**Deadline**
Commitment Letter and Planning Documents	October 15, 2007
Design Documents and Loan Application	March 3, 2008
Loan Award	November 2008

The planning and design documents for clean water projects must consist of:

1. A complete project report.
2. The environmental assessment report (level 1, level 2 or level 3, as determined by the Department). For those projects that have the potential to facilitate growth or cause significant adverse environmental impacts, the Department will thoroughly evaluate the planning submitted by the project sponsor which may include but not be limited to the water quality/quantity impacts, location in the State, impacts to riparian corridors, the existing pollution control needs, assessment of the resulting environment, detailed assessment of proposed alternatives and cost-effectiveness of the proposal. The Department's funding decisions will take into account the project's growth potential, the project's location and the project's aggregate impacts as determined through such evaluations.
3. Complete cultural resources survey documentation.
4. Long-term sludge management plan for projects involving a treatment plant upgrade or expansion.
5. Documentation of completed public participation activities.
6. The results of preliminary coordination activities with lead agencies regarding environmental and permit concerns.
7. Plans and specifications for the project, including appropriate environmental mitigation/restoration components.
8. For open space land acquisition projects, an evaluation of the land to be acquired, including the water quality benefits to be derived from the proposed land purchase.
9. For any stormmater/NPS management project, the water quality benefits to be achieved by the proposed work.
10. Documentation that all applicable permits and approvals to implement the project have been received from all applicable federal, State and County agencies.

Projects with unacceptable planning documentation and those lacking the required construction permits and approvals will be bypassed (removed from funding consideration in the current funding cycle). If the local government unit does not commit to the document submittal schedule, the Department interprets this as a decision to not pursue funding in FFY2008/SFY2009 and will result in a "BEYOND 08" designation under the estimated State certification date column on the Priority List.

C. Loan Awards

Loan awards for new projects will be made in FFY2008/SFY2009 for up to 100 percent of the allowable project costs to cover the low bid building costs and other allowable project costs that are identified in the program rules at N.J.A.C. 7:22-3, 4, and 5. The loan term will generally be 20 years but can not exceed the useful life of the facility. The initial loan amount will be limited to the certified project cost, which may reflect (1) the estimated allowable project cost based on the project sponsor's loan application or (2) the low bid building cost. The adjustment to provide funding based on the low bid building cost will be made only after all project-related contracts have been awarded.

Adjustments to provide warranted loan increases for differing site conditions will be made only after all allowable project costs have been incurred. Consideration will be given to providing warranted loan increases, subject to the Department's and the Trust's approval, legislative approval in the form of an appropriations bill(s) providing such monies, and the availability of funds. Any dollar changes in cost estimates for projects on the Priority List may result in the Department requesting the municipality to provide a third-party concurrence on the cost change. Should cost underruns occur after a low bid building cost adjustment and the completion of construction, budget line item changes may be approved for allowable cost overruns. In these cases, administrative/legal/fiscal costs will not be subject to the three percent limit as specified in the rules. A greater amount could be approved should sufficient funds remain and if sufficient justification and documentation for the higher costs are submitted and approved. If a recipient receives Department approval to reduce the project scope through the elimination of a contract (or portion thereof), the eligible project cost (and therefore the financial assistance amount) will be reduced through the Department's and the Trust's "deobligation". The amount to be deobligated will be equal to the estimated cost of the scope of work included in the original loan award.

Local government units are required to meet the technical, administrative, and environmental provisions of the rules of the Department and the Trust (*N.J.A.C.* 7:22-3, 4, 5, 8, 9, and 10). Disbursement and loan repayment provisions must also be consistent with the rules.

Planning and design costs may be fully reimbursable and eligible for financial assistance from the EIFP at the time of loan award. Alternatively, a project sponsor can opt for an allowance to assist in defraying planning and design expenses. If State funding for planning and design costs has otherwise been awarded for the same project scope (such as through the Sewage Infrastructure Improvement Act Grants Program), the planning and design costs eligible for EIFP financing would be reduced accordingly.

Financial assistance will only be awarded to a distinct project segment that will result, in itself, in an operable treatment works (i.e., not relying on award of funds for additional portions of the project). Financial assistance awards will not be made to projects that are under an enforcement action unless a federal or State court-sanctioned order or State administrative order (only accepted in certain cases) specifying a compliance schedule has been established. A copy of the

judicial or administrative order will be required at the time of submittal of the project application.

All wastewater treatment projects must be sized in accordance with a cost-effective analysis to accommodate existing needs as well as 20-year reserve capacity. Historically, the recipient's financial assistance from the Department was limited to the cost of the project with a capacity based upon flow records and flows anticipated prior to the date of initiation of operation as established in the Fund loan agreement. In order to advance the State's smart growth initiatives, the Department and the Trust have adopted amendments to the Financing Program rule that allows the Department to fully fund its share of project costs related to reserve capacity for projects that serve areas designated as Urban Centers and Complexes as approved by the State Planning Commission.

Amendments to the Trust's enabling legislation authorized the establishment of a short-term financing program. CWSRF loan repayments have been channeled to the Trust for this purpose in the past. The interim loans provide funds to project sponsors that are eligible for financing in the current fiscal year to cover project costs anticipated to be incurred prior to the award of the long-term loans from the Department and the Trust, which are typically awarded in November. The Trust, in consultation with the Department, adopted amendments to the Trust's rule to make the short-term financing option available to prospective borrowers that receive preaward approval and project certification from the Department and the Trust.

D. Smart Growth Initiatives and the Financing Program

The Smart Growth Initiative focuses the Department and all other agencies of New Jersey State government on three central objectives:

- Make developed areas healthier, more appealing places – with cleaner air, cleaner water, and more parks and open space;
- Reduce the rate at which forests, open space, farmland and other undeveloped areas are being lost to development; and,
- Promote and accelerate development in urban and suburban areas or other growth areas identified through sound planning.

To advance efforts to incorporate smart growth objectives into State policies and financing programs, the Department initially made several changes to the Financing Program in FFY2003 which are being continued in the current Priority System proposal. The most significant change involves modifying the percentage of project costs the Department and the Trust provides to project sponsors. Historically, all project sponsors received a loan for half of the project costs from the Department at 0% interest and a loan for the remaining project costs from the Trust at market rate. Under the Smart Growth Financing Package, the Department provides up to 75% of the project costs at 0% interest, while the Trust provides the remainder of the project costs at market rate to certain types of projects described below:

Urban Centers and Urban Complexes – Wastewater treatment and stormwater management projects that serve Urban Centers and Urban Complexes designated by the State Planning Commission are considered Smart Growth. To date, the State Planning Commission has designated Asbury Park, Atlantic City, Camden, Elizabeth, Jersey City, New Brunswick, Newark, Paterson and Trenton as Urban Centers and one Urban Complex, the Hudson County Urban Complex, which includes the following municipalities: Bayonne, East Newark, Guttenberg, Harrison, Hoboken, Jersey City, Kearny, North Bergen, Secaucus, Union, Weehawken, and West New York.

To address instances where a project does not exclusively serve an urban center/complex, the Department has determined that the 75/25 funding package will be provided only to that portion of the project that serves an Urban Center/Complex. In addition, the Department will include projects located in an Urban Center/Complex in the 75/25 funding package provided the project has direct quality of life implications for the Urban Center/Complex. An example of such a project would be odor controls for sludge management facilities (that serve areas beyond the Urban Center/Complex) located in an Urban Center that would reduce odors generated from the sludge management facilities and improve the air quality in the urban area.

In addition, the Department and the Trust adopted amendments to the Financing Program rules that allow the Department to fully fund its share of reserve capacity costs at 0% interest for projects serving designated Urban Centers and Complexes.

Combined Sewer Overflow Abatement – Combined sewer systems (CSSs) are wastewater collection systems designed to carry sanitary sewage, industrial and commercial wastewater, and storm water runoff in a single system of pipes to a publicly owned treatment works (POTW). During dry weather, all flow (composed primarily of sanitary sewage and industrial/commercial wastewater) is conveyed to the POTW. During periods of rainfall or snow melt, the total wastewater flows entering the collection system can exceed the capacity of the system or the treatment facility. Under such conditions, CSSs are designed to overflow at predetermined CSO points and result in discharges excess wastewater flows directly to surface water bodies such as rivers, estuaries, and coastal waters.

Because CSOs discharges include raw sewage, they contain a combination of untreated human waste and pollutants discharged by commercial and industrial establishments. CSOs also have a significant storm water component that includes pollutants from urban and rural runoff. These pathogens, solids, and toxic pollutants may be discharged directly to the waters of the state during wet weather events. Combined sewer overflows are a human health concern because they can create the potential for exposure to disease-causing pathogens, including protozoa, bacteria, and viruses. Exposure to CSO contaminants through swimming or other contact can lead to infectious diseases such as hepatitis, gastrointestinal disorders, dysentery, and swimmer's ear infection. Other forms of bacteria can cause typhoid, cholera, and dysentery. Human health also can be impacted from ingesting fish or shellfish contaminated by CSO discharges.

All projects that contribute to the correction of combined sewer systems and discharge points including elimination, relocation or consolidation of discharge points and construction of

facilities or purchase of equipment to remove solids and floatables are eligible for the enhanced financing package.

On-Site Rehabilitation of Septic Systems - Under the Financing Program, a local government unit may apply for funding to upgrade or replace failing on-site systems. The nature and extent of failures would be documented during planning and a Septic Management District (SMD) would have to be established in order to assure on-going operation and maintenance (typically, this involves implementing a system to assure regular, usually once every three years, pump out and/or inspection of the on-site systems). While some SMDs have formed in New Jersey (so there is institutional precedent on which to advance this option), none have tackled the costly job of system rehabilitation as yet.

By providing the Smart Growth Financing Package to such projects, the Program:

- corrects existing wastewater problems in a way that is appropriate to a rural environment;
- the correction does not result in inappropriate growth-inducement that could potentially occur with construction of a centralized collection and conveyance system;
- the on-going operation of the SMD results in pollution control benefits and reduced water supply impacts; and
- the funding enhancement may entice additional municipalities to establish their own SMD and address long-standing failing septic system problems.

Designated Brownfields Development Areas - These are areas that have applied for and have received formal designation by the Department under the BDA Initiative. Wastewater treatment and stromwater management projects that are located in DEP designated BDAs are eligible for the Smart Growth Financing Package. The sites within the BDA will be handled by a single project manager, who will coordinate with partnering state agencies to direct targeted technical and financial assistance to sites within the BDA neighborhoods.

Currently, there are twenty-three BDAs (www.state.nj.us/dep/srp/brownsfields/bda/bdalist.htm) in New Jersey and they are as follows: Cramer Hill BDA in Camden, Camden County; North Camden BDA in Camden, Camden County; Monument/Magic Marker BDA in Trenton, Mercer County; Elizabethport BDA in Elizabeth, Union County; Milltown Ford Avenue BDA in Milltown Borough, Middlesex County; Route 73 South BDA in Palmyra Borough, Burlington County; Coit Street BDA in Irvington, Essex County; Lister Avenue BDA in Newark, Essex County; and Pennsauken Waterfront in Pennsauken Township, Camden; Waterfront South in Camden, Camden County; Bayonne Route 440 BDA in Bayonne, Hudson County; Harrison Waterfront BDA in Harrison, Hudson County; Assunpink Greenway BDA in Trenton, Mercer County; Keyport Waterfront BDA in Keyport Borough, Monmouth County; Great Falls Historic Distric BDA in Paterson, Passaic County; West Lake Avenue in Neptune Township; Central Valley in Orange/West Orange; Salem Industrial Green way in Salem City; Bellmawr Landfills in Bellmawr; Chrome Waterfront in Carteret; Grand Jersey in Jersey City; and North Outerbridge Crossing in Perth Amboy. It is anticipated that the municipality will most often serve as the loan recipient under this option to effect remediation at multiple sites in the designated BDA, although county improvement authorities or similar entities could also participate and provide assistance in this environmental improvement effort.

By providing the Smart Growth Financing Package to such projects, the Program:

- provides a financial incentive that could encourage other municipalities to seek BDA designation to qualify for the EIFP's "75/25" enhanced funding;
- provides an alternative source of financing, and at a lower cost than that which is currently available; and
- enables more efficient use of available State funding.

Designated Transit Villages - The New Jersey Department of Transportation (NJDOT) and NJ TRANSIT spearhead a multi-agency Smart Growth partnership known as the Transit Village Initiative. The Transit Village Initiative helps to redevelop and revitalize communities around transit facilities to make them an appealing choice for people to live, work and play, thereby reducing reliance on the automobile. The Transit Village Initiative is an excellent model for Smart Growth because it encourages growth in New Jersey where infrastructure and public transit already exist. Wastewater treatment and stormwater infrastructure needed to address improvements in Transit Village areas are eligible for the Smart Growth Financing Package.

Studies have shown that an increase in residential housing options within walking distance of a transit facility, typically a one quarter to one half mile radius, does more to increase transit ridership than any other type of development. Therefore, it is a goal of the Transit Village Initiative to bring more housing, more businesses and more people into communities with transit facilities.

Municipalities that have been designated a Transit Village by the inter-agency Transit Village Task Force must have an adopted land-use strategy for achieving compact, transit-supportive, mixed-use development within walking distance of transit facilities. This can be in the form of a redevelopment plan, zoning ordinance, master plan or overlay zone. There are currently 17 designated Transit Villages. They are Pleasantville (1999), Morristown (1999), Rutherford (1999), South Amboy (1999), South Orange (1999), Riverside (2001), Rahway (2002), Metuchen (2003), Belmar (2003), Bloomfield (2003), Bound Brook (2003), Collingswood (2003), Cranford (2003). Matawan (2003), New Brunswick (2005), Journal Square/Jersey City (2005), and Netcong (2005).

By providing the Smart Growth Financing Package to such projects, the Program:

- provides enhanced financing to enable municipalities to address the increased need for wastewater and/or stormwater infrastructure to serve population increases in the designated Transit Village;
- provides a financial incentive that could encourage other municipalities to seek approval for the Transit Village designation to qualify for the EIFP's "75/25" enhanced funding; and
- advances the smart growth goals inherent in the Transit Village Area Initiative, including not only the community revitalization, but two other goals of the Transit Village Initiative, to reduce traffic congestion and improve air quality by increasing transit riders.

Transfer of Development Rights (TDR) Receiving Areas - The transfer of development rights is a realty transfer system where development potential in a specified preservation area can be

purchased by private investors for use in a targeted growth area. In exchange for a cash payment, landowners in the preservation area place a restrictive easement on the property that will maintain the resource in perpetuity. The land in the designated receiving area can then be developed at a higher density than allowed under the baseline zoning. This process reduces the consumption of our critical resources, while still accommodating growth, and eliminates "windfalls and wipeouts" in property values normally associated with zoning changes. The transfer of development rights is only allowed where a municipality has implemented a TDR program. Sponsors of projects that serve areas designated as TDR Receiving Areas under the State TDR Act (P.L. 2004, c.2), by the Highlands Council, by the Pinelands Commission or by Burlington County pursuant to the Burlington County Transfer of Development Rights Demonstration Act (P.L. 1989, c. 86) are considered Smart Growth. The participating municipality (or municipalities in a regional program) designates sending and receiving areas based on their preservation and growth goals, respectively. Planning and implementation documents are created by the municipality that governs where and how development rights can be transferred. Implementing a transfer of development rights program requires a major planning initiative on the part of the participating municipality. Before any credits can transfer from landowner to developer, certain planning and implementation documents must be adopted. The State TDR Act requires several items including a Development Transfer Plan Element, a Capital Improvement Plan, a Utility Service Plan, Transfer Ordinance, Plan Endorsement and other approvals.

By adding this category of projects into the Smart Growth Financing Package, the Program:

- provides a financial incentive that could encourage municipalities to be designated as a TDR Receiving Area to qualify for the EIFP's "75/25" enhanced funding;
- provides an alternative source of financing, and at a lower cost than is currently available to address the increased need for wastewater treatment and/or stormwater infrastructure to serve population increases in areas identified through prudent planning and designated as TDR Receiving Areas; and
- advances the smart growth goals inherent in the TDR process that provides for the designation of preservation areas that will maintain and protect critical resources in perpetuity.

To address instances where a wastewater treatment or stormwater management project does not exclusively serve a designated TDR Receiving Area, the Department has determined that the 75/25 funding package will be provided only to that portion of the project that serves a designated TDR Receiving Area.

In addition to these initiatives, for those projects that have the potential to facilitate growth or cause significant adverse environmental impacts, the Department will continue to thoroughly evaluate the planning submitted by the project sponsor. Such evaluation will include, but will not be limited to the water quality/quantity impacts, location in the State, impacts to riparian corridors, the existing pollution control needs, assessment of the resulting environment, detailed assessment of proposed alternatives and cost-effectiveness of the proposal. The Department's funding decisions will take into account the project's growth potential, its location and the project's aggregate impacts as determined through such evaluations.

Collectively, these initiatives will enhance the Department's and the Trust's ability to promote smart growth and will also allow the Environmental Infrastructure Financing Program to provide the funds needed to make it a reality.

E. Preaward Approvals and Emergency Projects

Eligible projects can qualify to receive preaward approvals if the requirements of the rules (N.J.A.C. 7:22-3.32 and 4.32) are met. This is a significant difference from the federal Construction Grants Program, since project sponsors may maintain the eligibility of project costs incurred prior to the execution of formal State loan agreements. However, to maintain the eligibility of such costs, project planning (including the issuance and expiration of an Environmental Assessment prepared by the Department) and design and contract documents (including issuance of authorization to advertise and award contracts for which reimbursement is sought) must be reviewed and approved by the Municipal Finance and Construction Element. Further, all permits and approvals for the construction of the project must be secured. It should be noted that federal policy limits the amount of funds the States may withdraw from capitalization grants for "refinancings." Since federal policy defines any costs incurred prior to loan award to be "refinanced," there is a possibility that reimbursement for all preaward costs may not be feasible at the time of loan award.

The Department recognizes that environmental infrastructure emergencies may occur that endanger public health and welfare and can result in substantial environmental damage. Such circumstances require an immediate response for which a complete technical and environmental review in advance of construction is not possible. The Department has developed a process to respond expeditiously when emergencies occur, obtain basic project information, make an eligibility determination and issue a preaward approval so that owners/operators can undertake the needed repairs and maintain eligibility for those expenditures through the EIFP.

Qualifying emergency conditions would be limited to those where failure has occurred or where failure is imminent and unless corrected, will result in substantial pollution of the environment (such as collapse of a wastewater line) and/or substantial curtailment of the functions of the infrastructure.

As indicated in the Priority System section of this document, emergency projects will receive funding priority over all other new projects on the Project Priority List, both for interim as well as long-term financing.

F. Socially and Economically Disadvantaged (SED) Business Participation

Project sponsors are required to set a goal of awarding at least 10 percent of a project's costs for construction, materials, or services to small business concerns owned and controlled by SED individuals as defined in the Small Business Act (15 *U.S.C.* 637(a) and (d)) and any rules promulgated pursuant thereto. The Department and the Trust have adopted the SED rules (at N.J.A.C. 7:22-9), that identify the SED utilization requirements that project sponsors will have to meet.

G. Stormwater/Nonpoint Source (NPS) Management Projects

Because of the need to address water quality concerns related to stormwater runoff, the Department and the Trust have expanded the scope of the Financing Program to include construction costs for a wide variety of stormwater/NPS management projects. The Department's general view, after consultation with local and regional planners and stormwater managers, is that expensive structural retrofits should not be implemented before completion of regional analysis and planning. Thus, if the project will impact the capacity, hydrology, or hydraulics of existing stormwater management facilities, systems, or downstream waterbodies, a watershed-based implementation plan appropriate to the project's location should be prepared. Watershed-based planning assesses the overall needs of an area to ensure that proposed projects will improve/maintain water quality, water quantity and ecosystem health in a cost-effective manner. Watershed-based planning differs from the individual project planning which is site-specific and which is a routine requirement of funding under the EIFP. Although the EIFP does not fund watershed-based planning, the EIFP does provide an allowance for a project's site-specific planning and design. The allowance is based on a percentage of the building costs. Stormwater/NPS management projects must support efforts to achieve and/or maintain water quality, compatible with designated uses of the water body.

Implementation of USEPA's Phase II Municipal Stormwater Program requires municipalities, counties and other public entities to control stormwater discharges from new and existing developments. In New Jersey, the program is being implemented through the issuance of NJPDES general permits. Program implementation requires capital expenditures for equipment acquisition, additional personnel to implement best management practices, and expenses for public education (an innovative component, to change the behavior of people to reduce environmental impacts). Low-cost funding for the equipment procurement and construction of needed facilities is available through the EIFP, and is described in more detail below. In 2004 and 2005, the Department awarded $6 million each year in grants to municipalities and counties to implement the NJPDES permit requirements. The Department has also provided additional funding for some capital improvement projects that can be combined with CWSRF loans (up to 20% grants and 80% SRF loans).

The stormwater/NPS management projects that are eligible for EIFP loans include both new or modifications of stormwater management systems, facilities, basins, or other stormwater/NPS management facilities (including land acquisition to site the eligible facilities). Stormwater/NPS management projects also include, but are not limited to: green roofs, green streets, tree filters, rain gardens, rain barrels, porous pavement, installation of packed media filters, replacement of existing storm drains with newer designs that incorporate features to remove solids, floatables, oil and grease, and/or other pollutants; purchase or replacement of equipment to reduce solids and/or floatables, such as netting on outfalls and skimmer boats; purchase of maintenance equipment, such as street sweepers, leaf collection equipment, beach cleaning equipment, and aquatic weed harvesters; rehabilitation of tide gates and existing basins or other stormwater systems, including pump stations; extension and/or stabilization of outfall points; implementation/construction of systems that will result in water quality benefits, such as salt

storage structures/runoff control systems, feedlot manure/runoff control systems, and streambank/lake stabilization/restoration projects which are consistent with habitat protection.

In FFY2000, the Financing Program added the water quality aspects of landfill closure and new cell construction to the list of eligible NPS projects as described below. In FFY2001, open space land acquisition and conservation, remedial action activities and well sealing were added to the list of eligible NPS projects under the EIFP as described further below:

Landfill Closure and Construction - The Financing Program also includes landfill closure and landfill construction projects (including new landfill cells) under eligible NPS projects. The Department recognizes that landfills are a major pollution concern and are identified as a nonpoint source of pollution in the State's Stormwater and NPS Program Plan developed under Section 319 of the Clean Water Act. Eligible landfill closure activities include such items as landfill capping systems, leachate collection, storage and treatment systems, side slope seepage prevention and controls, gas condensate systems and other activities. Financing for landfill construction projects is generally limited to those project elements that prevent, reduce, or control the generation of leachate or are required for the collection, storage and treatment of leachate. Elements of a landfill construction project that may be financed include landfill liner systems, leachate removal or collection systems, and related maintenance equipment, toe-drains and cut-off walls, leachate sampling facilities and equipment, leachate storage facilities (lagoons, tanks, tank covers and aeration systems), leachate evaporation systems, and others. In addition to leachate controls, other eligible elements include barge shelters, containment booms, litter fences, and other means to prevent municipal solid waste from blowing off the landfill site and polluting surface waters. Before any landfill closure or construction project is approved under the Financing Program, the project sponsor must submit and receive all applicable permits and approvals from the Department's Division of Solid and Hazardous Waste.

Open Space Land Acquisition and Conservation - The EIFP provides loans to municipal and county applicants for the preservation of open space land as a means to provide an overall water quality benefit to the project area. A conservation restriction (easement) is applied, which ensures that the water quality is protected in perpetuity. Passive recreational uses such as hiking, cross-country skiing, horseback riding and birding are allowed on the portion of the parcels that are purchased with loans from the EIFP. Development is not allowed on the properties that are acquired through the EIFP, since this encourages the use of impervious surfaces and causes land alterations which can adversely affect the hydrology of an area as well as other nonpoint source impacts. Surface runoff can increase and groundwater filtration can decrease. Since most of New Jersey consists of sole source aquifers, which "are those aquifers that contribute more than 50% of the drinking water to a specific area and the water would be impossible to replace if the aquifer were contaminated" (NJ Geological Survey), the protection of these resources is an environmental priority. When the land remains as open space with no development pressures, the water recharge to these vital aquifer systems is maintained. In addition, other environmental resources (i.e., endangered species, wetlands, stream corridors, floodplains, etc.) that may be present will also benefit from the preservation of the open space.

Remedial Action Activities - The clean-up of hazardous waste sites and other contaminated sites is critical to preventing further contamination of groundwaters in the State. The water-quality related components of projects for spill cleanups, brownfields restoration and hazardous waste site cleanups are some examples of the activities that are eligible through the Financing Program. Treatment of contaminated groundwater also qualifies for financing if the treated water is returned to the environment. While treatment solely to provide a safe, potable drinking water supply is ineligible for CWSRF financing, it is eligible for DWSRF financing.

Well Sealing - The proper sealing of unused monitoring and water supply wells is also important to protect groundwaters in the State. Municipalities and other public entities can sponsor projects through the Financing Program to properly fill and seal abandoned wells in accordance with N.J.A.C. 7:9-9.

H. Brownfields Set-Aside and Conduit Borrowers

In part, to offset the impact of the ranking changes that places brownfields redevelopment projects at or near the bottom of the Priority List, the FFY2008 Priority System document establishes a reserve dedicated solely for landfill closure and site remediation projects. The Department will allocate $30 million in Fund loans to the "Brownfields Set-Aside" for the 2008 Financing Program. Project priority will be determined in accordance with the ranking methodology included in this document and funds in the set-aside will be allocated based on the project's rank, the sponsor's ability to meet program requirements and the amount of available funds for these purposes. In cases where the available Fund loan does not cover 50 or 75 percent of the allowable project costs, the Trust may finance the remaining allowable costs, which may exceed their standard 50 or 25 percent contribution. Financing above and beyond the amount set-aside for such projects will be provided if monies are available after the need for funds for projects other than brownfields in the funding cycle have been satisfied. Conversely, if there are funds remaining in the set-aside because of insufficient demand for brownfield redevelopment loans in the 2008 Program, those funds can be used to finance projects listed on the Priority List that may otherwise not receive financing in the 2008 Program.

The FFY2008 Priority System establishes a new requirement for projects involving publicly-owned brownfields projects. Project sponsors must pledge that the site on which the improvements occur will remain in public ownership for the term of the loan (typically 20-23 years). While the Financing Program will allow the public sponsor to sell the improved land to a private entity and use it for private purposes, the loans provided by the Department and the Trust to finance the improvements must be repaid in full upon the transfer of ownership. This requirement does not apply to conduit borrowers' projects, which by their nature, involve private developer(s) and private ownership interests.

The Department is also continuing the practice of setting a limit of $25 million on the amount of Fund monies that any conduit borrower project can receive. In addition, previously-financed conduit borrowers will not be eligible for supplemental loans from the Department to cover unanticipated cost increases due to bid receipt, differing site conditions, change orders or other circumstances.

I. Combined Sewer Overflows (CSOs)

The New Jersey Pollutant Discharge Elimination System Permits (Both Individual Discharge to Surface Water Permits issued to Domestic Treatment Works that receive and treat sewage generated in Combined Sewer Systems or Individual Authorizations under the General Permit for Combined Sewer Systems) include provisions for the implementation of all of the nine minimum control measures deemed appropriate and applicable to the portions of the combined sewer systems (CSSs) collection and conveyance systems regulated by the permit. The permits issued to owners and operators of CSSs required the performance of land-side monitoring and modeling activities for use in the development of Storm Water Management Models (SWMMs) of the CSSs. Permits issued to CSSs and CSO Points required permittees to develop and evaluate the feasibility of pathogen control technologies and to prepare cost and performance curves for various scenarios and to quantify expected removal of other pollutants that may occur incidental to the control of pathogens. Permits issued to Domestic Treatment Works (DTWs) require permittees to determine the feasibility and cost of receiving and treating additional sewage flows at the DTW as a means of reducing CSO discharges.

Low-cost funding for the implementation of CSO abatement facilities is available through the EIFP. Such projects are, in fact, eligible for the enhanced Smart Growth Financing Package as identified on page 20 of this document. In addition, the Department has provided grants for certain activities to help defray the costs to achieve compliance with the requirements of the general permit as well as implementation of CSO Long-term Control Plans.

J. Short-Term and Long-Term Goals; DEP Fee; Miscellaneous Items

The short-term goal of New Jersey's financing program is to provide funding to needed, high-ranked water quality improvement projects. The long-term goal of the program is to establish and maintain a sound, self-sufficient, self-perpetuating financing program with adequate funds to assist communities with the financial burden of providing costly wastewater treatment and stormwater/nonpoint source management facilities to meet on-going water quality enhancement/preservation needs of the State.

As provided for in the January 1988 Initial Guidance for State Revolving Funds, a state that has deposited monies in a dedicated revolving fund after March 7, 1985 and prior to receiving a capitalization grant, may credit these monies toward the match, binding commitments, and equivalency requirements. Since some of the projects certified by the Department receive state-only sources of funding, these state-only projects may qualify under the federal criteria to bank monies to satisfy the CWSRF's match, binding commitment, and equivalency requirements.

In recognition that modifications to the IUP may occur, the Department may provide updates of the IUP to the USEPA. Department will submit an Annual Report representing the actual use of the CWSRF funds to the USEPA in accordance with the requirements of the Water Quality Act of 1987 and Agency guidance.

In accordance with the USEPA Policy on Fees Charged on Assistance Provided Under the SRF Programs, states must disclose information regarding the assessment and use of any fees

associated with SRF activities that are passed on to the program participants. In New Jersey, each SRF project is financed with two loans, one from the Department which utilizes federal SRF capitalization grants and one from the NJ Environmental Infrastructure Trust, which utilizes bond proceeds from the Trust bond sale.

Prior to FFY2002, adequate resources were available to cover the Department's costs for administration of the program without levying a fee. The Department began charging a fee associated with the EIFP in 2002. While the initial amount to be collected through the fee was $1M, subsequent Appropriations Acts required the Department to collect $5 million from the November 2003 and 2004 borrowers. Rather than require cash payment from the project sponsors at closing, the Trust included the Department loan origination fee in the borrowers' Trust loan (and secured that portion of the bond issue with non-SRF funds) to cover $5 million of Department's costs in administering the Financing Program. The legislation for the SFY2006 Program established a "Department Loan Origination Fund" that is administered by the Trust. The program now has a stable fixed fee of 2 percent of the participant's loan amount. There is no SRF funding involved in the Department loan origination fee. The Department's loan origination fee is not included in the principal amount of the CWSRF loan and is separately accounted for.

The Trust's loan is issued at the same market interest rate as the Trust obtains from the sale of its bonds. Rather than bonding for all of the eligible closing costs associated with each financing, the Trust charges the borrowers a one-time surcharge of up to 0.4% of the principal Trust loan amount to partially cover the costs associated with that particular year's bond sale. These issuance costs include such activities as: bond counsel, financial advisor, rating agencies, printing and publishing of the Notice of Sale, the Preliminary Official Statement, the Official Statement, and other costs related to the Trust's bond sale. In addition, the Trust charges an annual administrative fee of up to 0.3% of the Trust's bond principal loan amount to cover the balance of the closing cost and the annual operating expenses associated with the operations of the Trust and the on-going costs associated with the Loan Servicer and Trustees. The Trust Annual Fee is not included in the principal amount of the loan. The annual fees collected by the trust are held in an account outside of the SRF. In SFY2009, the Trust anticipates collecting administrative fees associated with the CWSRF and DWSRF programs of approximately $4.0 million.

The FFY2008 Priority System continues the reporting process introduced in the Proposed Addenda to the FFY2005 Priority System document that describes a new initiative being undertaken by USEPA in an effort to demonstrate and track the CWSRF program's positive contribution to environmental quality. USEPA has developed a small set of core measures to show how the CWSRF impacts compliance, water quality and designated uses and a one-page form that captures the reach of the CWSRF in terms of subsidy, population affected and volume of wastewater treated. The Department and the project sponsors will complete the "CWSRF Benefits Reporting Form" and the Department will submit this information to USEPA.

FFY2008 Financing Program Schedule for Clean Water Projects	
Date	**Action**
As soon as possible	Prospective applicants attend a preplanning meeting with Department – MF&CE representatives.
September 26, 2007	Public hearing on Proposed FFY2008 PS document.
October 15, 2007	1. Close of Comment Period. 2. Public Health Hazard (PHH) bypass requests due. 3. FFY2008 applicants submit commitment letter, all planning documents (i.e., project reports) to Department, including final NJPDES permit.
(on or before) January 15, 2008	Department/Trust submits list of projects (based on Priority System ranking methodology) to Legislature for forthcoming State Fiscal Year.
February 2008	Trust conducts Financial Seminars for FFY2008 applicants.
March 5, 2008	FFY2008 applicants submit design and complete loan application.
May 2008	Financial Plan for State Fiscal Year 2008 submitted by Department/Trust to Legislature.
July/August 2008	1. Legislature acts on Financial Plan. 2. Department/Trust transmit draft loan agreements to qualifying applicants.
September 2008	1. Trust financial transactions completed. 2. Execute Department/Trust loan agreements in escrow.
November 2008	Department/Trust loan closing with FFY2008 sponsors.

New Jersey State

DEPARTMENT OF ENVIRONMENTAL PROTECTION

ENVIRONMENTAL REGULATION

DIVISION OF WATER QUALITY

MUNICIPAL FINANCE AND CONSTRUCTION ELEMENT

APPENDIX - A

RESPONSE DOCUMENT

for the

FFY2008 PRIORITY SYSTEM DOCUMENT

(CLEAN WATER FINANCING)

RESPONSE DOCUMENT FOR THE FFY2008 PRIORITY SYSTEM DOCUMENT (CLEAN WATER FINANCING)

The Clean Water Act and its amendments require the United States Environmental Protection Agency (USEPA) and the states to provide for and encourage public participation in the development and implementation of the federally supported Clean Water State Revolving Fund (CWSRF) Program. In New Jersey, the CWSRF is a component of the Environmental Infrastructure Financing Program (EIFP) that provides financing for a wide variety of wastewater, stormwater and nonpoint source pollution control projects. The requirements for public participation activities also apply to the development and/or major revision(s) of the State's Priority System, Intended Use Plan and Project Priority List.

The response document addresses the comments received during the public participation process for the FFY2008 Proposal document issued in August 2007.

Public Participation Process

On August 24, 2007, the New Jersey Department of Environmental Protection (Department) issued a notice regarding the availability of the FFY2008 Proposal document to the standard mailing list of approximately 1,200 potential applicants and other interested parties to seek public input. The mailing list is periodically updated and includes municipalities, consulting engineers, environmental commissions, various interest groups, state legislators, county health departments, environmental groups, county planning boards and commissions and other interested parties. The notice identified various means to obtain a complete copy of the proposal and advised that a hearing to receive public input on the proposal will be held on September 26, 2007 and that the public comment period will close on October 1, 2007. The August 24, 2007 public notice satisfies the 30-day requirement for availability of relevant documents for the public's review in accordance with applicable federal rules.

On September 26, 2007 at 10:00 a.m., the Department held the public hearing at the offices of the New Jersey Environmental Infrastructure Trust located in Lawrence Township, New Jersey. The public hearing was chaired by Scott Shymon from the Bureau of Program Development and Technical Services, Municipal Finance and Construction Element (MF&CE), who presented information relevant to the Clean Water Priority System, Intended Use Plan and Project Priority List proposal. Adequate time was allocated for public comment and questions. Several individuals and entities attended the hearing and provided testimony. A transcript of the hearing is available from the transcription services (Class Act Reporting Agency, LLC of Mount Laurel, NJ) to any interested person or organization upon request. In addition, a copy of the transcript may be reviewed at the MF&CE's offices in Trenton.

At the public hearing, several individuals requested that the Department extend the public comment period to allow more time for prospective borrowers to review the impacts of the

changes being proposed. On September 28, 2007, the Department sent a notice to the standard mailing list and posted information on the Department's web site stating that the public comment period has been extended to October 15, 2007 to allow more time for review and comment on the FFY2008 Priority System document. All comments submitted in accordance with the deadline have been considered in the preparation of the final FFY2008 Priority System documents. The following section identifies the comments received on the proposal document and addresses the agency's responses to the issues brought forth. The numbers in parentheses at the end of each comment correspond to the number assigned to each commenter in the listing at the end of the document on page 6.

SUMMARY OF PUBLIC ISSUES AND RESPONSES

COMMENT

The ranking methodology adjustments assign the lowest priority to brownfield remediation and landfill closure projects, especially those that are being conducted with the public sponsor as a conduit borrower. Several of these sites are in portfield cities, and the intended end uses include land side distribution and flex space warehousing, which is a stated priority of the State's smart growth initiatives and consistent with Governor Corzine's Economic Growth Strategy. Commenters expressed concern that the significant proposed reduction in priority ranking for brownfield and landfill projects sends the wrong message to the regulated community that these are not smart growth projects. The FFY2008 Priority System proposal should be revised to restore the priority for brownfield and landfill projects. (1, 4-19)

RESPONSE

The Department recognizes that, in many cases, brownfield remediation and landfill closure projects are integrally related to the State's Economic Growth Strategy and smart growth initiatives. Ideally, the Financing Program should have sufficient funds available to fully finance all of the eligible water-quality related projects (including brownfield remediation and landfill closure projects) throughout the State. However, the federal contribution to the CWSRF Programs has been decreasing, resulting in reduced amount of funds available to provide new loans under the Program. Concurrently, the pace of the program has increased and loan awards have exceeded an average of $400 million per year; an amount four times the average of the loan awards made from 1992-1999. It is unfortunate that an unlimited supply of funds is not available to the Department to fund all infrastructure improvement projects. Adjustments to the point system for assignment of relative priority to various categories of projects, therefore, has become necessary.

The CWSRF program was initially established to address water-quality concerns related to publicly-owned treatment works and the collection, conveyance and treatment of sanitary sewage. Due to reductions in available funding, the Department has adjusted the project ranking methodology for the FFY2008 Priority System to assign higher priority for traditional wastewater management projects that are more directly linked to water quality (such as combined sewer overflow (CSO) abatement activities, sewage treatment plant (STP) upgrades and sanitary sewer rehabilitation) as compared to projects in the non-traditional project categories (such as landfill closures, land acquisition, landfill construction and site remediation).

Rather than opting to eliminate certain categories of projects, the Program continues to maintain eligibility for all of the project categories that have been eligible in the past since several of these projects are consistent with the State's smart growth initiatives and Governor Corzine's Economic Growth Strategy. The priority ranking related adjustments do not imply that projects in Portfield cities described by the commenters are not smart growth projects.

To offset the adverse impact of the priority ranking changes on financing of brownfields redevelopment projects, the FFY2008 Priority System document establishes a reserve dedicated solely for landfill closure and site remediation projects. In addition, the Department has reinstated the enhanced Smart Growth Financing Package for site remediation and landfill closure projects that have been designated a Brownfield Development Area (BDA). By doing so, the Department provides a financial incentive that could encourage other municipalities to seek BDA designation to qualify for the EIFP's "75/25" enhanced funding.

COMMENT

The FFY2008 Priority System proposal establishes a "Brownfields Set-Aside" of $25 million from the Department that can be matched with NJ Environmental Infrastructure Trust funds for a total of $50 million. Although it is recognized that additional money may be moved over from the traditional program if there are excess funds, $50 million is grossly insufficient. The Department should increase the set aside so that at least $50 million is allocated for these projects, bringing the program total to $100 million. (1, 4-19)

RESPONSE

The Department proposed to allocate $25 million in Fund loans as the "Brownfields Set-Aside" for the 2008 Financing Program and has increased that reserve to $30 million in the final FFY2008 Priority System document. As noted by the commenters, financing above and beyond the amount set-aside for such projects will be considered if monies are available after the need for funding of higher ranking projects during the funding cycle has been satisfied. Conversely, if there are funds in the set-aside leftover because of insufficient demand for brownfield redevelopment loans in the 2008 Program, those funds may be used to finance projects listed on the Priority List that may otherwise not receive financing in the 2008 Program. Historically, brownfield projects generally do not represent a significant portion of the total number of projects financed in a given year and, with the exception of one project, the Program has provided less than $50 million for brownfields projects of the $4.1 billion in total financing. The Department will continue to periodically evaluate the amount of available funds in the Program, the need for the set aside and the appropriate amount to allocate for its purposes. Appropriate adjustments will be made, as and if deemed necessary.

COMMENT

The proposed changes significantly reduce the ranking of brownfield and landfill projects and a set aside is for all practical intents and purposes capped at $25 million from the Department and $25 million from the NJ Environmental Infrastructure Trust, yet the Department is also proposing that projects that received preaward approval in prior years but were not able to close on their loan will be offered funding in 2008, thus increasing the competition for what is already a significantly reduced funding amount.

The Department states that this one-year exception is fair to project sponsors that diligently pursued loans in the 2007 Program, but it is clearly unfair to those sponsors and applicants that have expended funds for due diligence, project engineering, and permitting before they knew that the ranking system would be drastically changed and their chances of funding dramatically reduced. If the proposed changes are adopted, they will likely lead to numerous projects being abandoned. (1, 4-19)

RESPONSE

The Priority System changes that provide a higher priority to those land acquisition projects that obtained a pre-award approval in prior years, but were unable to close on the Department and Trust loans in 2007 for factors beyond their control, does not impact the ability of the Financing Program to provide loans to landfill closure and site remediation projects. The monies that the Department would use to make the land acquisition loans would not come from the Brownfields Set Aside. In addition, since the Priority Systems for prior funding years have consistently ranked land acquisition projects higher than site remediation and landfill projects, it provides no more of an advantage for a land acquisition with preaward approval than a new land acquisition project in relation to brownfield remediation and landfill closure projects.

In addition to brownfield clean-up and landfill projects, the changes to the priority ranking also significantly reduce the ranking for land acquisition projects. Much like the setaside was established in the FFY2008 Priority System to dampen the adverse impacts on brownfield projects, provisions were included to allow projects with preaward approval to receive priority over other new projects seeking loans in 2008. This one-year exception is necessary to be fair to the seven land acquisition projects that had preaward approval for specific sites prior to the finalization of the 2008 Project Priority List. Currently, only three land acquisition projects have applied for financing in the 2008 cycle.

The Program is set up in such a way that prospective sponsors and applicants need to expend funds for preliminary activities, including due diligence, project engineering, and permitting applications before they qualify for preaward approval, project certification and loan awards. It is unfortunate that an adequate supply of funds is not available to the Department for these infrastructure improvement projects. As stated earlier, the pace of the loan program has significantly increased in recent years. The loan awards have exceeded an average of $400 million per year; an amount four times the average of the loan awards made from 1992-1999. Concurrently, the federal contribution to the CWSRF Programs has been significantly curtailed, resulting in reduced amount of funds available to provide new loans under the Program. The federal contribution to the CWSRF in 2008 is projected to be less than $28 million, a record low amount.

The sponsors of the land acquisition projects that have preaward approval have not only expended funds for environmental studies and independent appraisals, they have produced those documents, submitted them for review and received the necessary approvals to secure preaward approval. A preaward approval indicates that the Program will allow the applicant to proceed with implementation of the project.

COMMENT
One commenter expressed concerns that projects located in BDAs would no longer be eligible for the blended 75/25 smart growth rate. The commenter noted that the lower cost loans are needed in order to afford the extensive infrastructure work needed to complete the project and that these projects create permanent job opportunities, housing opportunities and increase both ratables and generate State tax revenue. Another commenter added that the use of the Financing Program for environmental remediation is important to create economic development and create jobs. (2, 20)

RESPONSE
The Department agrees with the economic benefits of financing projects located in designated BDAs and has reinstated the 75/25 financing package for site remediation and landfill closure projects in areas that have a Brownfield Development Area (BDA) designation.

COMMENT
The proposed policy also makes brownfield and landfill projects ineligible for the smart growth blended rate of 75% for a no cost loan and 25% for a bond rate loan but retains this rate for other projects. This again sends the wrong message that these projects are not consistent with the State's Smart Growth Initiative and the Governor's Economic Growth Strategy, which is clearly not the case. The Department should reinstate eligibility for the lower smart growth blended rate for all brownfield and landfill projects, especially those in Portfield cities, designated urban centers and distressed cities. (1-19)

RESPONSE
The Department recognizes that, in many cases, brownfield remediation and landfill closure projects are integrally related to the State's Economic Growth Strategy and smart growth initiatives. Ideally, the Department would like to maintain the smart growth blended rate for the projects that have been designated as smart growth in the past, including designated urban centers and other appropriate areas. If the broad categories for smart growth were maintained, the Department would not be able to finance as many projects that submit applications for financing and the pace at which environmental infrastructure improvements are implemented would be hampered. As repeatedly stated elsewhere, interest in the loan program has significantly increased in recent years and the federal contribution to the CWSRF Program has been significantly curtailed, resulting in reduced amount of funds available to provide new loans. The federal contribution to New Jersey's CWSRF in 2008 is projected to be less than $28 million, a record low amount. With the reduced amount of funds available, cut backs in the smart growth 75/25 financing package are necessary.

The changes to the blended rate of 75% for a no cost loan and 25% for a bond rate loan were not exclusive to brownfield remediation and landfill closure projects. New land acquisition projects and some other categories of nonpoint source pollution control projects are also no longer eligible for the 75/25 blended rate financing package as well, regardless of their location.

In finalizing the FFY2008 Priority System, the Department agrees that all of the site remediation and landfill closure projects should not be excluded from eligibility for the smart growth 75/25

financing package and has reinstated the 75/25 financing package for site remediation and landfill closure projects that have a Brownfield Development Area (BDA) designation. Wastewater treatment, stormwater management, site remdiation and landfill closure projects that are located in DEP-designated BDAs are eligible for the Smart Growth Financing Package.

COMMENT

The Department should convene a stakeholders' process to discuss these and other comments from the regulated community before any modifications to the availability and/or eligibility of low-cost financing for brownfield or landfill closure projects are made. (1, 4-19)

RESPONSE

The Financing Program offers adequate opportunities for interested parties to participate and comment on the program's policies as they are developed. These include monthly open public meetings of the NJ Environmental Infrastructure Trust, annual public hearings and opportunities for written comments on the Clean Water and Drinking Water Priority System documents.

Please take note that the Department does not have direct control over the amount of funding available for low-cost financing of the wide variety of environmental infrastructure projects eligible for clean water financing. The amount of funds that the Department anticipates to have available annually is published in the Priority System documents and is subject to change based on interest earnings, loan repayments, the federal grants for the CWSRF and other factors.

In addition, while the project ranking methodology for the FFY2008 Priority System has been adjusted, the Department continues to maintain eligibility for all of the project categories that have been eligible in the past.

COMMENTERS TO THE FFY2008 PROPOSED PRIORITY SYSTEM DOCUMENT FOR CLEAN WATER FINANCING

Local Government Units:

1. Carteret Borough
2. Elizabeth City
3. Hudson County
4. Kearny Town
5. Keyport Borough
6. Paterson Environmental Revitalization Committee
7. Paterson City
8. Perth Amboy City
9. PA-PDC Perth Amboy Urban Renewal & Pannattoni Development Co

Organizations:

10. Dornoch Management
11. EXCEL Environmental Resources, Inc
12. Florio Perducci
13. Lennar (Sterns and Weinroth)
14. National Brownfield Association
15. National Association of Industrial Office Properties

16. NJ Chamber of Commerce
17. Monroe Center Development
18. PlanSmart NJ
19. Scarinci & Hollenbeck, LLC
20. The Morris Companies

New Jersey State

DEPARTMENT OF ENVIRONMENTAL PROTECTION

ENVIRONMENTAL REGULATION

DIVISION OF WATER QUALITY

MUNICIPAL FINANCE AND CONSTRUCTION ELEMENT

APPENDIX - B

STATE FISCAL YEAR 2008 LOAN AWARDS LIST

for the

FFY2008 PRIORITY SYSTEM

(CLEAN WATER FINANCING)

State Fiscal Year 2008 Clean Water Loan Awards

Local Unit	Project No.		Amount	Date of Award
Asbury Park City (Asbury Partners, LLC)	S340883-03	$	8,185,700	11/07/07
Atlantic County Utility Authority	S340809-15/16	$	2,977,535	11/07/07
Bayonne LRA	S340051-02	$	17,059,000	11/07/07
Bergen County	S340110-02	$	7,416,298	11/07/07
Bergen County UA	S340386-05	$	1,489,600	11/07/07
Berkeley Heights Township	S340385-04	$	4,060,000	11/07/07
Berkeley Township SA	S340969-05	$	3,289,000	11/07/07
Caldwell Borough	S340523-04	$	15,157,000	11/07/07
Camden County MUA	S340640-09	$	10,150,000	11/07/07
Dumont Borough	S340922-02/3	$	3,144,000	11/07/07
Edgewater Borough	S340446-08	$	2,315,308	11/07/07
Elmwood Park Borough	S340863-02	$	4,096,776	11/07/07
Franklin Township SA	S340839-01	$	12,500,000	11/07/07
Jefferson Township	S340747-06	$	1,374,700	11/07/07
Jersey City MUA	S340928-05	$	12,151,154	11/07/07
Kearny Town	S340259-03	$	4,831,000	11/07/07
Kearny MUA	S340259-05	$	5,410,000	11/07/07
Leonia Borough	S340073-01	$	446,214	11/07/07
Linden City	S342005-01-2	$	1,842,722	11/07/07
Linwood City	S340095-01	$	475,000	
Magnolia Borough	S340285-01/2	$	1,826,574	11/07/07
Medford Township	S340346-03	$	2,212,400	11/07/07
Middlesex County UA	S342012-01	$	65,324,490	11/07/07
Mount Holly MUA	S340817-03	$	24,354,050	11/07/07
Musconetcong SA	S340384-06	$	1,813,580	11/07/07
Newark City	S340815-08/09/10	$	32,050,707	11/07/07
North Bergen MUA	S340399-21	$	37,703,440	11/07/07
North Hudson SA	S340952-09	$	6,059,553	11/07/07
Ocean County UA	S340372-26-1/28/29/30/31	$	27,502,780	11/07/07
Ocean SA, Township of (Monmouth County)	S340750-06	$	5,921,000	11/07/07
Passaic Valley Sewerage Commissioners	S340689-11/14	$	24,189,156	11/07/07
Pine Hill Borough MUA	S340274-03	$	1,040,766	11/07/07
Point Pleasant Beach Borough	S340479-02	$	588,784	11/07/07
Princeton Sew. Oper. Committ.C/O /Princetc	S340656-04A	$	1,696,443	11/07/07
Princeton Sew. Oper. Committ.C/O /Princetc	S340656-04B	$	1,696,443	11/07/07
Rockaway Valley RSA	S340821-03	$	12,988,630	11/07/07
Saddle Brook Township	S340148-02	$	1,966,308	11/07/07
Seaside Park Borough	S340083-01	$	3,906,212	11/07/07
Somerset Raritan Valley SA	S340801-06	$	12,714,500	11/07/07
Stone Harbor Borough	S340722-01	$	1,467,934	11/07/07
Stony Brook RSA	S340400-04	$	5,300,000	11/07/07
West Deptford Township	S340947-03	$	6,047,000	11/07/07
Westville Borough	S340289-01	$	614,048	11/07/07
Total Clean Water Projects = 43		**Subtotal**	**$ 397,355,805**	

State Fiscal Year 2005 Clean Water (Land Acquisition) Loan Awards

Local Unit	Project No.		Amount	Date of Award
Berkeley Township	S343071-01	$	1,300,000	11/07/07
Cherry Hill Township	S343066-02	$	4,043,130	11/07/07
High Bridge Borough	S343072-01	$	909,255	11/07/07
NJ Water SA (Raritan Basin)	N03 3054-04	$	2,320,750	11/07/07
Total C.W. Land Acq. Projects = 4		**Subtotal**	**$ 8,573,135**	
		TOTAL	**$ 405,928,940**	

New Jersey State

DEPARTMENT OF ENVIRONMENTAL PROTECTION

ENVIRONMENTAL REGULATION

DIVISION OF WATER QUALITY

MUNICIPAL FINANCE AND CONSTRUCTION ELEMENT

APPENDIX - C

FINAL FEDERAL FISCAL YEAR 2008 (FFY 2008)

PROJECT PRIORITY LIST

STATE OF NEW JERSEY

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
1	340430-02 PASSAIC VALLEY SC					79,793			100,557		BEYOND08
2	340638-04 BRIDGEWATER TOWNSHIP			1,054					1,465		BEYOND08
3	340781-04 RARITAN BOROUGH			250					360		BEYOND08
4	340418-03 OAKLAND BOROUGH		7,000		21,760				36,522		BEYOND08
5	340495-03 SPARTA TOWNSHIP	1,470	637						2,853		BEYOND08
6	340366-06 CAMDEN CITY					46,353			58,648		BEYOND08
7	340810-03 LOWER TOWNSHIP MUA		2,333						3,135		BEYOND08
8	340964-01 WARREN TOWNSHIP SA	3,000							3,997		BEYOND08
9	340699-05 MIDDLESEX COUNTY UA	179,409							224,459		BEYOND08
10	340699-03 MIDDLESEX COUNTY UA	285,613							363,247		BEYOND08
11	340835-01 ORADELL BOROUGH			204					295		BEYOND08
12	340488-05 HOPATCONG BOROUGH				13,400				17,222		T 080830
13	340349-03 PENNSAUKEN TOWNSHIP					1,400	2,600		5,308		BEYOND08
14	340636-04 POMPTON LAKES BOROUGH MUA		770	110					1,232		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

STATE OF NEW JERSEY
FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
15	340942-11 ELIZABETH CITY					4,000			5,308		T 080830
16	340815-13 NEWARK CITY					6,400			8,363		T 080830
17	340928-03 JERSEY CITY MUA					37,122			47,046		BEYOND08
17	340928-04 JERSEY CITY MUA					1,790			2,437		BEYOND08
19	340399-26 BAYONNE MUA					58,300			73,637		BEYOND08
20	340688-04 RIDGEFIELD PARK VILLAGE					13,000			16,713		BEYOND08
21	340854-02 GUTTENBERG TOWN					280			376		BEYOND08
22	340463-06 MEDFORD LAKES BOROUGH		3,105						4,135		BEYOND08
23	340850-03 PATERSON CITY					15,030			19,295		T 080830
24	340747-05 JEFFERSON TOWNSHIP				14,922				19,158		BEYOND08
25	340453-03 WARREN CO-PAULINSKILL/BLAIRSTOWN	595	411		911				2,607		BEYOND08
26	340399-09 HUDSON COUNTY UA (HOBOKEN)					10,846			14,038		BEYOND08
27	340299-04 LINDEN-ROSELLE SA				4,199	5,044			12,027		BEYOND08
28	340117-02 TWO RIVERS WRA	5,928							7,760		T 080830

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
29	340097-02 MIDDLETOWN TOWNSHIP SA		13,600						17,477		T 080830
30	340399-20 NORTH BERGEN MUA		30,000						38,083		BEYOND08
31	340639-05 RIDGEWOOD VILLAGE				1,520				2,075		BEYOND08
32	340275-01 RIVERTON BOROUGH	649							914		BEYOND08
33	340747-02 JEFFERSON TOWNSHIP	1,428							1,952		BEYOND08
34	340925-01 WRIGHTSTOWN (WRIGHTSTOWN MUA)	2,000	900						3,866		BEYOND08
35	340386-07 BERGEN COUNTY UA	5,437							7,157		T 080830
36	340952-11 NORTH HUDSON SA					29,850			37,894		T 080830
37	340652-01 NORTH BERGEN TOWNSHIP/HUDSON CO UA				2,800	200			3,997		BEYOND08
38	340454-05 WARREN COUNTY (PEQUEST RIVER) MUA		3,000						3,997		BEYOND08
39	340372-32 OCEAN COUNTY UA		2,000						2,718		T 080830
39	340372-33 OCEAN COUNTY UA		700						985		T 080830
41	340898-01 HAMILTON TOWNSHIP		8,830						10,686		BEYOND08
42	340809-08 ATLANTIC COUNTY UA	1,196							1,640		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
43	340821-04 ROCKAWAY VALLEY RSA	7,500							9,782		BEYOND08
44	340410-05 NEPTUNE TOWNSHIP SA		8,200						10,684		BEYOND08
45	340463-05 EVESHAM MUA (WOODSTREAM)	2,550	52	102	2,713				7,132		BEYOND08
46	340446-09 EDGEWATER MUA	1,500	300						2,451		BEYOND08
47	340809-09 ATLANTIC COUNTY UA	2,000							2,718		BEYOND08
48	340870-02 PENNSVILLE SA		1,200		4,281				7,211		BEYOND08
49	340526-06 GLOUCESTER CO UA (GIBBSTOWN)	1,122	561						2,294		BEYOND08
50	340917-01 DELAWARE TOWNSHIP MUA		800	300					1,522		BEYOND08
51	340952-10 NORTH HUDSON SA		7,422						9,683		T 080830
52	340536-06 EAST WINDSOR MUA	1,207	7,992						11,971		T 080830
53	340130-01 MONTGOMERY TOWNSHIP		8,500						11,070		T 080830
54	340362-05 HARRISON TOWNSHIP	794							1,114		T 080830
55	340958-05 GLOUCESTER CITY					166			243		BEYOND08
56	340454-04 WARREN COUNTY (PEQUEST RIVER) MUA		5,000						6,614		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
57	340935-01 MANSFIELD TOWNSHIP	700	300						1,396		BEYOND08
58	340780-03 WANAQUE VALLEY RSA	2,000							2,718		BEYOND08
59	340518-04 BUENA BOROUGH MUA	1,500							2,049		BEYOND08
60	340416-11 TRENTON CITY	3,000							3,997		BEYOND08
61	340346-04 MEDFORD TOWNSHIP		5,185						6,844		T 080830
62	340747-04 JEFFERSON TOWNSHIP (ROCKAWAY)				4,932				6,526		BEYOND08
63	340832-01 HOWELL TWP MUA				4,435				5,877		BEYOND08
64	340686-04 ESSEX UNION JOINT MEETING	8,600							11,199		BEYOND08
65	340902-03 GLOUCESTER COUNTY UA	6,239							8,156		T 080830
66	340336-03 LONG BRANCH SA	644			481				1,553		BEYOND08
67	340461-05 LANDIS SA	2,700							3,603		BEYOND08
68	340128-01 WESTERN MONMOUTH UA		6,105						7,982		T 080830
69	340850-01 PATERSON CITY			22,136					28,256		BEYOND08
70	340366-03 CAMDEN CITY			15					22		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
71	340416-12 TRENTON CITY			2,000					2,718		BEYOND08
72	340366-07 CAMDEN CITY			2,409					3,229		BEYOND08
72	340366-08 CAMDEN CITY			2,000					2,718		T 080830
74	340652-07 NORTH BERGEN TOWNSHIP			450					639		BEYOND08
75	340806-04 PARSIPPANY-TROY HILLS TOWNSHIP		8,316						10,833		T 080830
76	340259-06 KEARNY MUA				4,000				5,308		T 080830
77	340804-04 SALEM COUNTY BOARD OF FREEHOLDERS		14,218						18,263		BEYOND08
78	340884-01 ASBURY PARK CITY				1,581				1,897		BEYOND08
79	340803-04 HACKETTSTOWN MUA				1,011				1,411		BEYOND08
80	340123-01 LOGAN TOWNSHIP MUA	7,500	6,000						17,350		T 080830
81	340376-04 MORRISTOWN TOWN			6,600					8,621		BEYOND08
82	340656-05 PRINCETON SOC			3,485					4,633		T 080830
83	340336-05 LONG BRANCH SA			1,000					1,396		BEYOND08
84	340889-01 DOVER TOWN			664					935		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
85	340360-01 METUCHEN BOROUGH			2,800					3,734		BEYOND08
86	340295-01 BOUND BROOK BOROUGH			150					218		BEYOND08
87	340664-03 WILDWOOD CITY			2,250					3,032		BEYOND08
88	340719-02 WILDWOOD CREST BOROUGH			3,500					4,653		BEYOND08
89	340626-03 WEST WILDWOOD BOROUGH			396					564		BEYOND08
90	340921-04 MILLVILLE CITY			5,350	1,200				8,557		BEYOND08
91	340170-03 CINNAMINSON SA			1,650					2,250		T 080830
92	340778-01 TOTOWA BOROUGH			700					985		BEYOND08
93	340304-02 FREEHOLD BOROUGH			300					430		BEYOND08
94	340712-07 BURLINGTON CITY			4,420	900				7,012		T 080830
95	340816-03 BERNARDSVILLE BOROUGH			809					1,135		BEYOND08
96	340911-01 MANASQUAN BOROUGH			4,600					6,093		BEYOND08
97	340347-01 SOUTH BOUND BROOK BOROUGH				850				1,239		BEYOND08
98	340864-01 AVALON BOROUGH		310	796					1,530		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
99	340858-01 CRANFORD TOWNSHIP			443					629		BEYOND08
100	340752-01 PLEASANTVILLE CITY			151					220		BEYOND08
101	340967-01 MATAWAN BOROUGH			500					708		BEYOND08
102	340326-06 SOUTH AMBOY CITY			168					244		BEYOND08
103	340372-34 OCEAN COUNTY UA			6,300					8,234		T 080830
103	340372-35 OCEAN COUNTY UA			400					570		T 080830
105	340709-02 CAMDEN COUNTY MUA			12,184					15,673		BEYOND08
106	340637-04 MIDDLESEX COUNTY UA			15,618					20,043		BEYOND08
107	340768-02 BERGEN COUNTY UA			12,184					15,673		BEYOND08
108	340547-03 RAHWAY VALLEY SA			4,482					5,938		BEYOND08
108	340547-08 RAHWAY VALLEY SA			1,250					1,713		BEYOND08
110	340902-04 GLOUCESTER COUNTY UA			11,342					14,642		T 080830
111	340809-10 ATLANTIC COUNTY UA			3,175					4,227		BEYOND08
112	340952-02 NORTH HUDSON SA			4,950					6,549		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
113	340299-05 LINDEN ROSELLE SA			271					389		BEYOND08
114	340756-02 ROCKAWAY VALLEY REG SA			4,482					5,938		BEYOND08
115	340700-06 NORTHWEST BERGEN CO UA			6,076					7,944		BEYOND08
116	340117-03 TWO RIVERS WRA			2,900					3,866		T 080830
117	340843-01 EAST ORANGE CITY			1,903					2,588		BEYOND08
118	340844-01 CLIFTON CITY			1,025					1,428		BEYOND08
119	340433-04 WOODBRIDGE TOWNSHIP			807					1,132		BEYOND08
120	340391-06 EWING LAWRENCE SA			2,000					2,718		BEYOND08
120	340391-08 EWING LAWRENCE SA			7,500					9,782		BEYOND08
122	340364-04 GLOUCESTER TOWNSHIP MUA			2,000					2,718		T 080830
123	340945-05 OLD BRIDGE MUA			1,600					2,183		BEYOND08
124	340845-01 PASSAIC CITY			4,018					5,331		BEYOND08
125	340364-01 GLOUCESTER TOWNSHIP MUA			1,100					1,540		BEYOND08
126	340393-07 WAYNE TOWNSHIP			1,500					2,049		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
127	340930-03 WASHINGTON TOWNSHIP MUA			683					962		BEYOND08
128	340969-01 BERKELEY TOWNSHIP			2,000					2,718		BEYOND08
129	340410-04 NEPTUNE TWP SA			3,369					4,481		BEYOND08
130	340895-01 WINSLOW TWP (SICKLERSVILLE)				1,473				2,013		BEYOND08
131	340853-01 FORT LEE BOROUGH			481					682		BEYOND08
132	340859-01 ORANGE CITY			685					964		BEYOND08
133	340353-02 EGG HARBOR TOWNSHIP MUA			650					916		BEYOND08
133	340753-03 EGG HARBOR TOWNSHIP MUA			650					916		BEYOND08
135	340423-03 MONROE MUA			1,649					2,249		BEYOND08
136	340459-05 PEQUANNOCK RIVER BASIN RSA			425					604		BEYOND08
137	340769-02 BERGEN COUNTY UA (TRIBORO)			1,150					1,584		BEYOND08
138	340639-07 RIDGEWOOD VILLAGE	2,189		2,375					6,046		BEYOND08
139	340715-03 MADISON-CHATHAM JOINT MEETING			553					782		BEYOND08
140	340866-01 SOUTH BRUNSWICK TOWNSHIP			260					374		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
141	340404-06 LONG HILL TOWNSHIP			1,700					2,317		BEYOND08
142	340968-01 HAZLET TOWNSHIP			650					916		BEYOND08
142	340443-05 EDGEWATER BOROUGH			2,301					3,091		BEYOND08
144	340906-03 HILLSIDE TOWNSHIP			791					1,110		BEYOND08
145	340314-01 ROSELLE BOROUGH			1,156					1,592		BEYOND08
146	340817-04 MOUNT HOLLY MUA			1,400					1,915		T 080830
147	340939-01 CARTERET BOROUGH			5,500					7,234		BEYOND08
148	340912-02 MOORESTOWN TOWNSHIP			611					862		BEYOND08
149	340863-01 ELMWOOD PARK BOROUGH			777					1,091		BEYOND08
150	340829-01 BRIDGETON CITY			975					1,362		BEYOND08
151	340922-01 DUMONT BOROUGH			2,717					3,625		BEYOND08
152	340400-03 STONY BROOK REGIONAL SA			393					560		BEYOND08
153	340313-01 PALISADES PARK BOROUGH			300					430		BEYOND08
154	340577-07 READINGTON TOWNSHIP			155					226		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
155	340730-01 OCEAN CITY			39					57		BEYOND08
156	340580-04 WARREN CO LOPAT SA			1,809					2,463		BEYOND08
157	340382-03 BERNARDS TOWNSHIP SA			337					482		BEYOND08
158	340115-01 HADDON TOWNSHIP			5,000					6,614		T 080830
159	340533-04 VERONA BOROUGH			1,054					1,465		BEYOND08
160	340855-01 SPRINGFIELD TOWNSHIP			1,054					1,465		BEYOND08
161	340938-01 HIGHLAND PARK BOROUGH			3,242					4,315		BEYOND08
162	340873-03 CLINTON TOWNSHIP SA			1,000					1,396		T 080830
163	340717-05 CEDAR GROVE TOWNSHIP			260					374		BEYOND08
164	340766-02 PARSIPPANY-TROY HILLS TWP			35					51		BEYOND08
165	340381-05 ROXBURY TWP			962					1,344		BEYOND08
166	340329-01 HASBROUCK HEIGHTS BOROUGH			11,000					14,226		BEYOND08
167	340618-01 SOMERS POINT CITY			77					113		BEYOND08
168	340703-05 FLORHAM PARK SA			1,000					1,396		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
169	340862-01 WESTWOOD BOROUGH			690					971		BEYOND08
170	340716-04 LITTLE FALLS MUA			1,600					2,183		BEYOND08
171	340841-01 RIVER EDGE BOROUGH			320					458		BEYOND08
172	340780-02 WANAQUE VALLEY RSA/WANAQUE			1,136					1,567		BEYOND08
173	340326-04 SAYREVILLE BOROUGH			168					244		BEYOND08
174	340517-01 FAIRVIEW BOROUGH			1,027					1,431		BEYOND08
175	340425-01 LITTLE FERRY BOROUGH			3,700					4,915		BEYOND08
176	340309-01 AUDUBON BOROUGH			779					1,094		BEYOND08
177	340362-04 HARRISON TOWNSHIP			790	714				2,054		T 080830
178	340363-04 RUNNEMEDE BOROUGH				1,200				1,645		T 080830
179	340877-01 HADDON HEIGHTS BOROUGH			976					1,364		BEYOND08
180	340914-01 BOGOTA BOROUGH			103	30				194		BEYOND08
181	340861-01 GLEN RIDGE BOROUGH			234					337		BEYOND08
182	340846-01 MONTVALE BOROUGH			71					104		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
183	340346-01 MEDFORD TOWNSHIP			3,000					3,997		BEYOND08
184	340916-01 DUNELLEN BOROUGH			1,000					1,396		BEYOND08
185	340278-01 UNION BEACH BOROUGH			1,700					2,317		BEYOND08
186	340264-02 LOPATCONG TOWNSHIP			2,000					2,718		BEYOND08
187	340426-06 N ARLINGTON - LYNDHURST JT MTG (NARL)			150					218		BEYOND08
187	340426-05 N ARLINGTON-LYNDHURST JT MTG (LYND)			3,527					4,688		BEYOND08
187	340310-01 ROCHELLE PARK TOWNSHIP			1,653					2,255		BEYOND08
190	340840-01 SPRING LAKES HEIGHTS, BOROUGH OF			111					163		BEYOND08
191	340330-01 MORRIS PLAINS BOROUGH			335					479		BEYOND08
192	340106-02 NEPTUNE CITY BOROUGH			300					430		BEYOND08
193	340901-01 HIGHLANDS BOROUGH			622					877		BEYOND08
194	340129-01 FRANKLIN BOROUGH			2,000					2,718		T 080830
195	340502-05 PENNS GROVE SA			390					556		BEYOND08
196	340901-02 HIGHLANDS BOROUGH			100					147		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
196	340361-01 ROSELAND BOROUGH			83					123		BEYOND08
198	340362-01 HARRISON TOWNSHIP	450		1,875					3,125		BEYOND08
199	340326-07 SAYREVILLE BOROUGH				3,527				4,688		BEYOND08
200	340440-04 FLEMINGTON BOROUGH			1,200					1,645		BEYOND08
201	340319-01 MEDFORD LAKES BOROUGH			200					289		BEYOND08
202	340917-02 DELAWARE TOWNSHIP MUA			300					430		BEYOND08
203	340842-01 HIGH BRIDGE BOROUGH			160					243		BEYOND08
204	340504-02 STANHOPE BOROUGH			289					415		BEYOND08
205	340109-01 POHATCONG TOWNSHIP			498					706		BEYOND08
206	340956-02 DELANCO TOWNSHIP SA			1,355					1,854		BEYOND08
207	340257-02 WOODBURY HEIGHTS BOROUGH			1,345					1,841		BEYOND08
208	340659-01 SEA ISLE CITY			470					667		BEYOND08
209	340970-02 MOONACHIE BOROUGH		160	70					332		BEYOND08
210	340849-01 WOODLYNNE BOROUGH			3,203					4,264		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
211	340324-01 ALPHA BOROUGH			450					639		BEYOND08
212	340871-03 GIBBSBORO BOROUGH			1,079			17		1,518		T 080830
213	340335-01 AVON-BY-THE-SEA BOROUGH			2,782			200		3,973		BEYOND08
214	340966-03 LAVALETTE BOROUGH			1,856					2,526		BEYOND08
215	340966-02 LAVALETTE BOROUGH			300					430		BEYOND08
216	340713-02 WEYMOUTH TOWNSHIP MUA			400					570		BEYOND08
217	340822-01 PEAPACK & GLADSTONE BOROUGH			85					125		BEYOND08
218	340738-03 WYCKOFF TOWNSHIP				11,220				14,494		BEYOND08
219	340567-04 ALLENTOWN BOROUGH	175		225					570		BEYOND08
220	340412-08 DEAL BOROUGH			900					1,259		BEYOND08
221	340311-02 SHIP BOTTOM BOROUGH			570					805		T 080830
222	340590-02 BAY HEAD BOROUGH			1,635					2,230		BEYOND08
223	340935-02 MANSFIELD TOWNSHIP			100					147		BEYOND08
224	340761-02 ROOSEVELT BOROUGH			1,100					1,522		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
225	340683-05 PASSAIC VALLEY SC	105,400							132,505		BEYOND08
225	340689-06 PASSAIC VALLEY SEWERAGE	50,000							63,223		BEYOND08
227	340366-02 CAMDEN CITY	470							667		BEYOND08
228	340883-01 ASBURY PARK CITY	527							746		BEYOND08
229	340820-03 LONG BRANCH SA	2,824							3,766		BEYOND08
230	340915-02 HIGHTSTOWN BOROUGH	569							804		BEYOND08
231	340640-06 CAMDEN COUNTY MUA	13,000							16,713		T 080830
232	340687-05 BERGEN COUNTY UA	29,802							37,834		BEYOND08
233	340686-03 ESSEX-UNION JOINT MEETING	15,000							19,257		BEYOND08
234	340818-04 BURLINGTON COUNTY BOARD OF	7,781							10,144		BEYOND08
235	340399-15 HUDSON COUNTY UA	15,603							20,024		BEYOND08
236	340900-01 HUDSON COUNTY UA (AREA I)				21,091				26,962		BEYOND08
237	340405-04 ATLANTIC COUNTY UA	15,275							19,607		BEYOND08
238	340886-01 PARSIPPANY-TROY HILLS TWP	1,001							1,398		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
239	340661-06 CAPE MAY COUNTY MUA	9,457							12,302		BEYOND08
240	340390-05 WANAQUE VALLEY REG SA	10,000	6,000	1,000	3,000				25,607		BEYOND08
241	340819-02 MOUNT HOLLY SA	3,920							5,203		BEYOND08
242	340805-02 MILFORD BOROUGH	2,604		456					4,076		BEYOND08
243	340965-01 ALLOWAY TOWNSHIP/QUINTON TOWNSHIP				7,640				9,963		BEYOND08
244	340946-02 STAFFORD TOWNSHIP				6,100				7,975		BEYOND08
245	340638-03 BRIDGEWATER TOWNSHIP			52	1,615				2,273		BEYOND08
246	340626-04 WEST WILDWOOD BOROUGH				37				55		BEYOND08
247	340781-03 RARITAN BOROUGH				387				551		BEYOND08
248	340434-02 WANAQUE BOROUGH				212				306		BEYOND08
249	340927-03 HAMMONTON TOWN				3,752				4,983		BEYOND08
250	340872-01 HOPE TOWNSHIP	356							508		BEYOND08
251	340809-14 ATLANTIC COUNTY UA		3,520						4,679		T 080830
252	340809-11 ATLANTIC COUNTY UA		5,800						7,602		T 080830

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
253	340945-04 OLD BRIDGE MUA				25,990				33,032		BEYOND08
254	340929-01 WAYNE TOWNSHIP				1,360				1,861		BEYOND08
255	340437-03 NEW BRUNSWICK CITY			675					950		BEYOND08
256	340895-02 WINSLOW TWP				2,003				2,722		BEYOND08
257	340875-01 VOORHEES TOWNSHIP				4,246				5,630		BEYOND08
258	340304-01 FREEHOLD TOWNSHIP				3,678				4,886		BEYOND08
259	340526-03 GLOUCESTER CO UA (MONROE)	1,310	562		281				2,911		BEYOND08
260	340897-01 SOUTH BRUNSWICK TOWNSHIP				896				1,254		BEYOND08
261	340478-05 ROCKAWAY TOWNSHIP	5,549			8,077				17,510		BEYOND08
262	340931-02 MONTVILLE TOWNSHIP MUA				12,820				16,484		BEYOND08
263	340650-03 MANCHESTER TWP				6,872				8,972		BEYOND08
264	340382-02 BERNARDS TOWNSHIP SA				380				542		BEYOND08
265	340461-04 GLOUCESTER COUNTY UA (FRANKLIN TWP)				5,481				7,211		BEYOND08
266	340418-05 OAKLAND BOROUGH				32,200				40,854		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
267	340745-02 VERNON TWP				5,050				6,677		BEYOND08
268	340592-03 MAHWAH TOWNSHIP			182	6,862				9,194		BEYOND08
269	340760-03 WANTAGE TWP				402				572		BEYOND08
270	340403-05 CHATHAM TOWNSHIP	500							708		BEYOND08
271	340634-03 BLOOMINGDALE BOROUGH				2,842				3,790		BEYOND08
272	340909-01 UPPER SADDLE RIVER, BOROUGH OF				991				1,384		BEYOND08
273	340404-05 LONG HILL TWP				11,221				14,495		BEYOND08
274	340650-05 MANCHESTER TOWNSHIP				10,644				13,791		BEYOND08
275	340957-01 FAIRFIELD TOWNSHIP				5,582				7,336		BEYOND08
276	340705-03 CARLSTADT SA				4,026				5,342		BEYOND08
277	340607-03 PLUMSTED TWP	14,132			27,974				53,312		T 080830
278	340737-01 MAHWAH TOWNSHIP	158							230		BEYOND08
279	340759-02 SUSSEX CO.	4,500	0		1,000				7,234		BEYOND08
280	340489-03 WHARTON BOROUGH				421				599		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
281	340790-02 BERLIN TOWNSHIP				600				847		BEYOND08
282	340742-02 FRANKFORD TWP				2,007				2,727		BEYOND08
283	340568-02 BLAIRSTOWN TWP				1,092				1,512		BEYOND08
284	340729-01 RIVERDALE BOROUGH				1,273				1,744		BEYOND08
285	340473-01 RIVERDALE BOROUGH				3,265				4,345		BEYOND08
286	340592-06 MAHWAH TOWNSHIP			275	3,896				5,532		BEYOND08
287	340652-06 NORTH BERGEN MUA				3,000				3,997		BEYOND08
288	340445-02 OXFORD TOWNSHIP				125				183		BEYOND08
289	340838-01 EVESHAM MUA	2,747							3,665		BEYOND08
290	340487-02 KINNELON BOROUGH				7,641				9,964		BEYOND08
291	340480-06 PEQUANNOCK TOWNSHIP				7,152				9,333		BEYOND08
292	340930-01 WASHINGTON TOWNSHIP				2,496				3,335		BEYOND08
293	340650-06 MANCHESTER TOWNSHIP				2,500				3,340		BEYOND08
294	340485-04 RARITAN TOWNSHIP MUA	6,570							8,583		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
295	340619-03 UPPER TWP (STRATHMERE)				1,707				2,326		BEYOND08
296	340480-05 PEQUANNOCK TOWNSHIP				4,838				6,403		BEYOND08
297	340740-02 BRANCHVILLE BOROUGH				1,900				2,584		BEYOND08
298	340961-01 SOUTHAMPTON TOWNSHIP				1,806				2,459		BEYOND08
299	340892-02 GALLOWAY TOWNSHIP				4,300				5,700		BEYOND08
300	340959-02 NORTH ARLINGTON BOROUGH				500				708		BEYOND08
301	340831-01 SHAMONG TWP	1,988							2,702		BEYOND08
302	340271-01 MILLSTONE BOROUGH				2,500				3,340		BEYOND08
303	340836-01 PLAINSBORO TOWNSHIP				1,530				2,089		BEYOND08
304	340918-01 CLAYTON BOROUGH(SILVER LAKE)				829				1,162		BEYOND08
305	340870-01 PENNSVILLE SA				1,581				2,157		BEYOND08
306	340833-01 BUENA BOROUGH MUA	509							721		BEYOND08
307	340480-03 PEQUANNOCK TOWNSHIP				1,200				1,645		BEYOND08
308	340594-02 LINCOLN PARK BOROUGH				3,189				4,245		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
309	340433-08 WOODBRIDGE TOWNSHIP				25				36		BEYOND08
310	340051-04 BAYONNE LRA						3,650		4,850		T 080830
311	340119-01 JERSEY CITY RA						2,224		3,000		T 080830
312	340942-09 ELIZABETH CITY						3,500		4,653		T 080830
313	340635-03 HOBOKEN CITY						50		73		BEYOND08
314	340029-03 SECAUCUS TOWN					1,650			2,250		T 080830
315	340778-04 TOTOWA BOROUGH			350					420		BEYOND08
316	340816-04 BERNARDSVILLE BOROUGH			455					646		BEYOND08
317	340258-01 CAPE MAY CITY				250				360		BEYOND08
318	340830-01 BEDMINSTER TOWNSHIP		35,000						44,376		BEYOND08
319	340506-02 CRANBURY TOWNSHIP				2,700				3,603		BEYOND08
320	340680-05 MIDDLESEX COUNTY UA	1,018							1,419		BEYOND08
321	340386-06 BERGEN COUNTY UA	25,000							31,783		BEYOND08
322	340817-02 MOUNT HOLLY SA	1,102							1,525		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
323	340902-01 GLOUCESTER COUNTY UA	3,723							4,945		BEYOND08
324	340801-03 SOMERSET-RARITAN VALLEY SA	1,054							1,465		BEYOND08
325	340804-03 SALEM COUNTY BD OF CHOSEN	5,162							6,816		BEYOND08
326	340806-03 PARSIPPANY-TROY HILLS TWP	246							354		BEYOND08
327	340700-05 NORTHWEST BERGEN CO UA	1,683							2,294		BEYOND08
328	340638-05 BRIDGEWATER TOWNSHIP						557		788		T 080830
329	340865-01 WEST ORANGE TOWNSHIP			8,466	847				12,117		BEYOND08
330	340832-02 MANASQUAN RIVER REG SA				3,467				4,610		BEYOND08
331	340282-01 HOPEWELL TOWNSHIP				18,685				23,940		BEYOND08
332	340099-01 HILLSBOROUGH TOWNSHIP				4,200				5,570		T 080830
333	340954-01 CHERRY HILL TOWNSHIP			456	456				1,276		BEYOND08
334	340649-02 PEMBERTON TOWNSHIP MUA	5,000		3,500	1,500				13,800		BEYOND08
335	340895-04 WINSLOW TOWNSHIP (CEDAR BROOK)				3,000				3,997		BEYOND08
335	340895-05 WINSLOW TOWNSHIP (W. ATCO)				3,600				4,852		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
337	340066-01 DEPTFORD TOWNSHIP MUA				1,223				1,677		BEYOND08
338	340632-07 RANDOLPH TOWNSHIP			3,221	3,550				8,842		BEYOND08
339	340446-06 EDGEWATER BOROUGH				1,617				2,207		BEYOND08
340	340869-02 ABERDEEN TOWNSHIP				2,121				2,871		BEYOND08
341	340491-02 WEST WINDSOR TOWNSHIP				400				570		BEYOND08
342	340545-04 GLASSBORO BOROUGH				2,977				3,968		BEYOND08
343	340839-03 FRANKLIN TOWNSHIP (GLOUCESTER CO.)		1,200						1,645		BEYOND08
344	340495-04 SPARTA TOWNSHIP				2,081				2,821		BEYOND08
345	340803-03 HACKETTSTOWN MUA	451							641		BEYOND08
346	340919-02 HOLMDEL TOWNSHIP				32,050				40,665		BEYOND08
347	340778-05 WEST PATERSON BOROUGH				517				733		BEYOND08
348	340163-01 WATERFORD TOWNSHIP MUA				2,474				3,309		BEYOND08
349	340903-02 HAMILTON TOWNSHIP MUA				2,044				2,774		BEYOND08
350	340282-02 HOPEWELL TOWNSHIP				2,603				3,475		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
351	340368-01 EAST GREENWICH TOWNSHIP				464				660		BEYOND08
352	340664-02 WILDWOOD CITY						1,831		2,492		BEYOND08
353	340956-03 DELANCO TOWNSHIP SA				1,400				1,915		BEYOND08
354	340370-01 WOODBINE MUA		6,212		3,500				12,630		BEYOND08
355	340078-01 WEYMOUTH TOWNSHIP MUA			162					236		BEYOND08
356	340359-01 GREENWICH TOWNSHIP		7,600		1,000				11,199		BEYOND08
357	340876-02 CHESTER BOROUGH	718	132						1,191		BEYOND08
358	340955-01 COMMERCIAL TOWNSHIP	4,200			2,854				9,207		BEYOND08
359	340649-04 PEMBERTON TOWNSHIP MUA							880	1,232		BEYOND08
360	340030-02 PALMYRA BOROUGH							238	343		BEYOND08
361	340967-02 MATAWAN BOROUGH						3,310		4,404		BEYOND08
361	340967-03 MATAWAN BOROUGH							200	289		BEYOND08
363	340569-03 BYRAM TOWNSHIP							150	218		BEYOND08
364	340159-01 MENDHAM BOROUGH							220	318		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
364	340159-02 MENDHAM BOROUGH						132		193		BEYOND08
366	340788-05 MONMOUTH COUNTY BOARD OF							655	923		BEYOND08
367	340525-01 CAMDEN COUNTY BOARD OF FREEHOLDERS							560	792		BEYOND08
367	340525-02 CAMDEN COUNTY DEPARTMENT OF PARKS							1,235	1,693		BEYOND08
367	340525-03 CAMDEN COUNTY DEPARTMENT OF PARKS							552	781		BEYOND08
370	340280-01 UNION COUNTY						3,776		5,015		BEYOND08
371	340097-01 MIDDLETOWN TOWNSHIP						250	2,750	3,997		T 080830
372	340364-05 GLOUCESTER TOWNSHIP MUA						950		1,328		T 080830
373	340969-06 BERKELEY TOWNSHIP						8,230		10,723		T 080830
374	340397-01 EWING TOWNSHIP							325	465		BEYOND08
374	340397-03 EWING TOWNSHIP							126	185		BEYOND08
376	340423-04 MONROE TOWNSHIP						220		318		BEYOND08
377	340268-01 MARLBORO TOWNSHIP							115	169		BEYOND08
378	340750-04 OCEAN TOWNSHIP						855		1,198		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
379	340283-02 MAPLEWOOD TOWNSHIP						4,130		5,479		BEYOND08
380	340892-03 GALLOWAY TOWNSHIP				400		6,500		9,008		BEYOND08
381	340113-01 SCOTCH PLAINS TOWNSHIP						1,350		1,847		T 080830
382	340346-02 MEDFORD TOWNSHIP						3,600		4,784		BEYOND08
383	340968-02 HAZLET TOWNSHIP						290		416		BEYOND08
383	340968-03 HAZLET TOWNSHIP							95	140		BEYOND08
385	340537-05 MOUNT OLIVE TOWNSHIP						904		1,266		BEYOND08
386	340919-03 HOLMDEL TOWNSHIP							218	316		BEYOND08
387	340385-03 BERKELEY HEIGHTS TOWNSHIP						350		500		BEYOND08
388	340938-02 HIGHLAND PARK BOROUGH						335		479		BEYOND08
389	340927-04 HAMMONTON TOWN						170		247		BEYOND08
390	340474-01 NEW PROVIDENCE BOROUGH						150		180		BEYOND08
391	340329-02 HASBROUCK HEIGHTS BOROUGH						5,000		6,614		BEYOND08
392	340827-03 BRIGANTINE CITY						184		267		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
393	340126-01 MILLSTONE TOWNSHIP							250	360		T 080830
394	340073-02 LEONIA BOROUGH						315		451		T 080830
395	340363-05 RUNNEMEDE BOROUGH						1,050		1,460		T 080830
396	340166-01 EDGEWATER PARK TOWNSHIP						1,500		2,049		BEYOND08
397	340265-01 BOONTON TOWN						250		360		BEYOND08
398	340446-10 EDGEWATER MUA						1,940		2,639		T 080830
399	340267-01 KEYPORT BOROUGH						150	100	360		BEYOND08
400	340374-01 CRESSKILL BOROUGH						310		444		BEYOND08
401	340105-01 WESTAMPTON TOWNSHIP						200		289		BEYOND08
402	340164-01 PAULSBORO BOROUGH						687		967		BEYOND08
403	340112-01 OCEAN TOWNSHIP						500		708		T 080830
404	340308-01 BERLIN BOROUGH						500		708		BEYOND08
405	340790-03 BERLIN TOWNSHIP						853	88	1,317		BEYOND08
406	340338-03 SOMERDALE BOROUGH						952		1,331		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
407	340446-07 EDGEWATER BOROUGH						2,000		2,718		BEYOND08
408	340901-04 HIGHLANDS BOROUGH						552		781		BEYOND08
409	340361-02 ROSELAND BOROUGH						1,000		1,396		BEYOND08
409	340901-03 HIGHLANDS BOROUGH						593	267	1,205		BEYOND08
411	340541-04 MOUNT ARLINGTON BOROUGH						91		134		BEYOND08
412	340856-01 EGG HARBOR TOWNSHIP						1,944		2,643		BEYOND08
413	340285-03 MAGNOLIA BOROUGH				48		270		455		BEYOND08
414	340285-04 MAGNOLIA BOROUGH						108		159		BEYOND08
415	340319-02 MEDFORD LAKES BOROUGH						250		360		BEYOND08
416	340842-02 HIGH BRIDGE BOROUGH							110	162		BEYOND08
416	340842-03 HIGH BRIDGE BOROUGH						5,200		6,863		T 080830
418	340263-01 LAWNSIDE BOROUGH						132		193		BEYOND08
419	340966-04 LAVALETTE BOROUGH						282		405		BEYOND08
420	340729-02 RIVERDALE BOROUGH						200		289		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
421	340165-01 LIBERTY TOWNSHIP							101	148		BEYOND08
422	340335-02 AVON BY THE SEA BOROUGH						250		360		BEYOND08
423	340077-01 SEA BRIGHT BOROUGH						2,560		3,419		BEYOND08
424	340339-01 TETERBORO BOROUGH						870		1,219		BEYOND08
425	343069-01 JERSEY CITY							10,000	13,000		BEYOND08
426	340366-05 CAMDEN CITY							5,000	6,614		BEYOND08
427	342009-01 BAYONNE LOCAL REDEVELOPMENT							2,957	3,941		BEYOND08
428	343008-01 PRINCETON TOWNSHIP							3,500	4,653		BEYOND08
429	343041-01 WILDWOOD CREST BOROUGH							3,000	3,997		BEYOND08
430	343045-01 CAPE MAY CITY							4,000	5,308		BEYOND08
431	343031-01 MENDHAM TOWNSHIP							4,000	5,308		BEYOND08
432	343004-03 MERCER COUNTY							800	1,122		BEYOND08
433	342008-01 SUSSEX COUNTY MUA							1,800	2,451		BEYOND08
434	343035-01 WARREN COUNTY							2,374	3,185		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
435	343027-02 EDISON TOWNSHIP							43,826	55,475		BEYOND08
436	343051-02 HAMILTON TOWNSHIP							1,247	1,709		T 080830
437	343010-02 BRICK TOWNSHIP							3,264	4,345		T 080830
438	343021-02 MIDDLETOWN TOWNSHIP							2,380	3,193		BEYOND08
439	343014-01 GLOUCESTER TOWNSHIP							949	1,328		BEYOND08
440	343055-01 NJ WATER SA (MANASQUAN BASIN)							10,000	13,000		BEYOND08
441	343044-01 WASHINGTON TOWNSHIP (GLOUCESTER							725	1,019		BEYOND08
442	343017-01 FRANKLIN TOWNSHIP							16,863	21,625		BEYOND08
443	343023-02 EVESHAM TOWNSHIP							433	616		BEYOND08
444	343011-01 HOWELL TOWNSHIP							1,500	2,049		BEYOND08
445	343024-01 HACKENSACK CITY							519	735		BEYOND08
446	342005-02 LINDEN CITY							690	971		T 080830
447	343059-01 MARLBORO TOWNSHIP							3,000	3,997		BEYOND08
448	342003-01 EVESHAM TOWNSHIP							2,200	3,055		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
449	343039-01 MANALAPAN TOWNSHIP							2,600	3,471		BEYOND08
450	343015-01 MOUNT LAUREL TOWNSHIP							3,135	4,174		BEYOND08
451	343018-01 FREEHOLD TOWNSHIP							2,000	2,718		BEYOND08
452	343005-02 WEST WINDSOR TOWNSHIP							6,669	8,712		BEYOND08
453	343060-01 BURLINGTON TOWNSHIP							429	610		BEYOND08
454	343007-01 RANDOLPH TOWNSHIP							8,370	10,903		BEYOND08
455	343022-01 MORRIS TOWNSHIP							2,000	2,718		BEYOND08
456	343025-01 POINT PLEASANT BOROUGH							460	654		BEYOND08
457	343034-04 READINGTON TOWNSHIP							10,815	14,000		T 080830
458	343054-05 NJ WATER SA							2,120	2,869		T 080830
459	343012-01 CLINTON TOWNSHIP							9,605	12,493		BEYOND08
460	343003-01 HANOVER TOWNSHIP							9,000	11,714		BEYOND08
461	343042-01 BRIGANTINE CITY							5,000	6,614		BEYOND08
462	343070-01 OAKLAND BOROUGH							12,060	15,516		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
463	342013-01 SOMERVILLE BOROUGH						4,100	4,100	10,684		T 080830
464	343068-01 MARLTON/BURLINGTON COUNTY BCF							52	76		BEYOND08
465	343029-01 MONTGOMERY TOWNSHIP							3,454	4,594		BEYOND08
466	343064-01 RIVER VALE TOWNSHIP							5,000	6,614		BEYOND08
467	343016-01 CHATHAM TOWNSHIP							2,000	2,718		BEYOND08
468	343001-01 FLORHAM PARK BOROUGH							7,500	9,782		BEYOND08
469	343036-01 BORDENTOWN TOWNSHIP							10,447	13,550		BEYOND08
470	343047-01 BYRAM TOWNSHIP							1,400	1,915		BEYOND08
471	343038-01 EDGEWATER PARK TOWNSHIP							100	147		BEYOND08
472	343052-01 MILLTOWN BOROUGH							3,500	4,653		BEYOND08
473	343067-01 ALLENDALE BOROUGH							5,200	6,863		T 080830
474	343040-01 MANSFIELD TOWNSHIP							1,196	1,641		BEYOND08
475	343019-01 PLUMSTED TOWNSHIP							6,800	8,879		BEYOND08
476	342004-01 FAIRFIELD TOWNSHIP							1,200	1,645		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
477	343073-01 POINT PLEASANT BEACH BOROUGH							15,000	19,257		T 080830
478	343009-01 MILLSTONE TOWNSHIP							9,000	11,714		BEYOND08
479	343026-01 EASTAMPTON TOWNSHIP							3,000	3,997		BEYOND08
480	343062-01 EAST AMWELL TOWNSHIP							350	500		BEYOND08
481	343072-02 HIGH BRIDGE BOROUGH							4,200	5,570		T 080830
482	343053-01 MINE HILL TOWNSHIP							1,000	1,396		BEYOND08
483	343049-01 PEAPACK & GLADSTONE BOROUGH							750	1,054		BEYOND08
484	342002-01 ESTELL MANOR CITY							1,140	1,572		BEYOND08
485	340416-13 TRENTON CITY							7,740	10,091		BEYOND08
486	340044-01 CAMDEN REDEVELOPMENT AGENCY							137,500	172,309		BEYOND08
487	340051-03 BAYONNE LRA						3,000	18,000	26,849		T 080830
488	340111-02 NJ CITY UNIVERSITY/JERSEY CITY MUA			110			1,171	16,012	22,174		T 080830
489	340815-12 NEWARK CITY						1,000	9,000	13,000		T 080830
490	340098-01 HARRISON TOWN/RA				3,728		4,589	28,050	46,098		T 080830

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
491	340815-11 NEWARK CITY						2,000	18,000	25,607		T 080830
492	340942-06 ELIZABETH CITY							2,500	3,340		BEYOND08
492	340942-10 ELIZABETH CITY						275	7,325	9,911		T 080830
494	340087-01 TRENTON CITY/MCIA						1,300	800	2,844		BEYOND08
495	340044-02 CAMDEN REDEVELOPMENT AGENCY			16,300	19,500				45,383		BEYOND08
495	340044-03 CAMDEN REDEVELOPMENT AGENCY							10,000	13,000		BEYOND08
497	340437-12 NEW BRUNSWICK							2,500	3,340		BEYOND08
498	340094-01 HUDSON COUNTY IA							5,000	6,614		T 080830
499	340341-05 HARRISON TOWN/HUDSON COUNTY IA							25,000	31,783		BEYOND08
499	340098-02 HARRISON TOWN/RA				1,918		2,755		6,189		T 080830
501	340124-01 UNION COUNTY IA						2,000	16,000	23,069		T 080830
502	340107-01 MORRIS COUNTY							10,000	13,000		BEYOND08
503	340435-07 PERTH AMBOY RA							29,000	36,825		T 080830
504	340037-01 EAST AMWELL							450	639		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

FINAL FEDERAL FISCAL YEAR 2008 PROJECT PRIORITY LIST

Rank	Loan/Seq No Recipient	Eligible Category Cost Breakdown (Total Building Costs)							Total Eligible Project Costs	Total State Amount	Est St Cert Date
		Cat 1	Cat 2	Cat 3	Cat 4	Cat 5	Cat 6	Cat 7			
505	340349-04 PENNSAUKEN TOWNSHIP				3,247			40,543	55,431		T 080830
506	340103-01 SOUTH ORANGE VILLAGE TOWNSHIP							1,500	2,049		BEYOND08
507	340435-08 PERTH AMBOY RA							15,000	19,257		T 080830
508	340923-09 HACKENSACK CITY						1,000	6,350	9,589		T 080830
509	342011-01 BELLMAWR BOROUGH			750	3,998		1,000	22,700	36,129		T 080830
510	340102-01 MILLTOWN BOROUGH							5,000	6,614		BEYOND08
511	340063-01 ATLANTIC CITY MUA						22,125		28,243		BEYOND08

All costs shown are in thousands ($1000's)

Cat 1 - Secondary/Sludge/Septage Treatment
Cat 2 - Advanced Treatment
Cat 3 - Sewer System Rehabilitation
Cat 4 - New Collectors, Interceptors & Appurtenances
Cat 5 - Correction of Combined Sewer Overflows
Cat 6 - Stormwater Management
Cat 7 - Nonpoint Source Management

New Jersey State

DEPARTMENT OF ENVIRONMENTAL PROTECTION

ENVIRONMENTAL REGULATION

DIVISION OF WATER QUALITY

MUNICIPAL FINANCE AND CONSTRUCTION ELEMENT

APPENDIX - D

Project Narratives

for the

FFY2008 PRIORITY SYSTEM

(CLEAN WATER FINANCING)

Anticipated Recipient :	PASSAIC VALLEY SC		
Project No. :	340430-02	Eligible Project Cost:	$ 100,557,651
FY08 Rank :	1		
County :	ESSEX	Total State Amount :	$ 100,557,651

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	150

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	250
			State Planning Commission	50.00000
			Population	1.35000
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	1051.35000

Project Name, Number

PASSAIC VALLEY SC
340430-02
CSO ABATEMENT

Priority List Rank

1

County

ESSEX

Existing Population

1,350,000

Service Area

East Newark, Harrison, Kearny, Newark, Paterson

Need for Project

Wastewater generated in the PVSC service area is treated at its secondary treatment facility located in the City of Newark. During significant rain events, the PVSC interceptor sewers, adjacent to the Passaic River, overflow into this watercourse resulting in the violation of Water Quality Standards for dissolved oxygen, fecal coliform. High levels of toxics are also experienced. The Passaic River in the project area is classified as SE-2 and SE-3. Currently, the river is used for non-trout fishing and industrial water use. This study will determine the extent of the impacts on the Passaic River resulting from combined sewer overflows and develop solutions to those detrimental impacts documented during the study.

Project Description

The first phase of the combined sewer overflow facility plan for the PVSC District has been completed. Phase II of the facility plan will include detailed analysis and design of alternative control measures. Control alternatives analyzed in Phase I included best management practices, minor regulator modifications, inline storage, offline storage, swiss and helical bond regulators, and instream aeration. Alternative evaluation during the second phase of the facility plan will include the computer analysis and final plan selection. The first phase of the facility plan showed that the major loadings to the Lower Passaic River originated from the Upper Passaic and Saddle Rivers and stormwater runoff in non-CSO areas. The selected plan will provide a solution of the impaired water use (industrial water use and non-trout fishing) which result from CSO's.

Anticipated Recipient	:	BRIDGEWATER TOWNSHIP		
Project No.	:	340638-04	Eligible Project Cost:	$ 1,465,130
FY08 Rank	:	2		
County	:	SOMERSET	Total State Amount :	$ 1,465,130

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	175

State Planning Commission	25.00000
Population	0.01220
BDA Points	0
Transit Villages	0
TOTAL POINTS	1050.01220

Project Name, Number

BRIDGEWATER TOWNSHIP
340638-04
I/I CORRECTION - OVERFLOW

Priority List Rank

2

County

SOMERSET

Existing Population

12,200

Service Area

Township of Bridgewater

Need for Project

Excessive infiltration in the North Branch trunk sewer results in raw sewage overflows into the North Branch Raritan River, which is classified as FW-2, nontrout and supplies industrial process water. These overflows have contributed to high levels of fecal coliform, bacteria, and nutrients which exceed water quality standards. Toxic levels marginally meet standards. The Bridgewater Township sewerage system overflows occur upstream of an intake to the Elizabethtown Water Company.

Project Description

The rehabilitation of the trunk sewers will require grouting and slip-lining the existing pipe. The exact nature and scope of work to be performed will be further defined when a sewer system evaluation survey is completed.

Anticipated Recipient	: RARITAN BOROUGH			
Project No.	: 340781-04	Eligible Project Cost:	$	360,245
FY08 Rank	: 3			
County	: SOMERSET	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	175
			State Planning Commission	25.00000
			Population	0.00599
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	1050.00599

Project Name, Number

RARITAN BOROUGH
340781-04
I/I CORRECTION - OVERFLOW

Priority List Rank

3

County

SOMERSET

Existing Population

5,990

Service Area

Raritan Borough

Need for Project

Many of the sewers in the Borough of Raritan are at least 75 years old and have never been rehabilitated. The infiltration/inflow (I/I) resulting from sewer pipe decay is estimated at 40-50 percent of the total flow from the Borough. This condition results in raw sewage overflows which adversely impact the Raritan River by contributing to the elevated nutrient and bacteriological levels in the River, which is classified as FW2-NT. Toxic levels marginally meet existing standards. The River is used as an industrial water supply and as a potable water supply for the Elizabethtown Water Company.

Project Description

The project will include rehabilitating a portion of the existing 20 miles of sewers or replacing that which is beyond repair. It may also be necessary to replace some of the undersized sewers with larger ones. This rehabilitation work will eliminate the sewage overflows from this system and reduce excessive flow into the Somerset-Raritan Valley Sewerage Authority (SRVSA) plant.

Anticipated Recipient	: OAKLAND BOROUGH		
Project No.	: 340418-03	Eligible Project Cost:	$ 36,522,885
FY08 Rank	: 4		
County	: BERGEN	Total State Amount :	$ 36,522,885

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	350

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	175
			State Planning Commission	0.00000
			Population	0.01300
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	1025.01300

Project Name, Number

OAKLAND BOROUGH
340418-03
STP, INTERCEPTOR, & COLLECTION SYSTEM

Priority List Rank

4

County

BERGEN

Existing Population

13,000

Service Area

Borough of Oakland

Need for Project

The area is currently served by septic systems and some small package treatment plants. As treatment requirements increase from Level 4 to Level 5, the plants will be unable to meet their effluent requirements. Ground and surface waters (Ramapo River, FW2-NT), are used for recreation as well as a potable water source, and are being degraded by the failure of existing disposal facilities.

Project Description

The proposed project includes the construction of a wastewater treatment plant, interceptor sewer and collection system. The proposed interceptor sewer and collection system will convey all flows from the six (6) wastewater treatment plants (that will be abandoned) to the proposed wastewater treatment plant.

Anticipated Recipient	:	SPARTA TOWNSHIP		
Project No.	:	340495-03	Eligible Project Cost:	$ 2,853,484
FY08 Rank	:	5		
County	:	SUSSEX	Total State Amount :	$ 2,853,484

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	400

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	25
Toxics	0	25	50	25
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.01432
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	1000.01432

Project Name, Number

SPARTA TOWNSHIP
340495-03
STP UPGRADES, ON-SITE REHABILITATION

Priority List Rank

5

County

SUSSEX

Existing Population

14,320

Service Area

The study area consists of that portion of Sparta Township (48%) which is situated within the Upper Wallkill River Basin. On-site rehabilitation in conjunction with a Septic System Management District would consider the entire Township as a service area during implementation.

Need for Project

All existing point source discharges must be addressed. Should these discharges remain in existence, they must be upgraded to meet the effluent limitations needed to protect existing water quality. In cases of discharge to the Wallkill River (FW2-TM) (Plaza and H.S. #1 and #2 plants), advanced wastewater treatment will be required to diminish any impacts to Franklin Pond, a downstream potable water source for Franklin Borough. Primary contact recreation is also adversely impacted by these discharges. The Wallkill river marginally meets standards for fecal coliform, nutrients and toxics. In addition, the failure rate for individual septic systems is averaging about 3% per year. Many of the existing systems (e.g., cesspool) cannot meet the minimum requirements for subsurface disposal and must be replaced.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Plaza STP (NJ0027057) AST-90%	.030	.040	91.3	12.6	86.0	23.3
Board of Ed.- Alpine School (NJ0027065) AST-95%	.027	.008	97	7.4	93	16
Board of Ed.- H.S. Plant #1 (NJ0027073)	.022	.005	98.6	4.14	97	1.44
Board of Ed.- H.S.Plant #2 (NJ0027081)	.027	.008	87.6	4.2	98	2.56

Project Description

A likely alternative for wastewater disposal in Sparta Township is on-site rehabilitation in conjunction with initiation of septic management district planning. Therefore, the major scope of work for this project would include the upgrading of all existing point source discharges to acceptable treatment levels. This would preclude development of any future point source discharges in Sparta Township for the 20 year planning period.

Anticipated Recipient :	CAMDEN CITY		
Project No. :	340366-06	Eligible Project Cost:	$ 58,648,610
FY08 Rank :	6		
County :	CAMDEN	Total State Amount :	$ 58,648,610

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	225

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	25
Toxics	0	25	50	25
			Subtotal	100
			State Planning Commission	50.00000
			Population	0.07990
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	975.07990

Project Name, Number

CAMDEN CITY
340366-06
CSO ABATEMENT

Priority List Rank

6

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

The proposed project is needed for compliance with the requirements of the CSO General Permit. The General Permit requires removal of solids/floatables greater than ½″ in size.

Project Description

The proposed project includes elimination of CSO points through rerouting and installation of solids and floatables controls at CSO points.

Anticipated Recipient	: LOWER TOWNSHIP MUA			
Project No.	: 340810-03	Eligible Project Cost:	$	3,135,057
FY08 Rank	: 7			
County	: CAPE MAY	Total State Amount :	$	3,135,057

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	225

State Planning Commission	0.00000
Population	0.01953
BDA Points	0
Transit Villages	0
TOTAL POINTS	975.01953

Project Name, Number

LOWER TOWNSHIP MUA
340810-03
STP IMPROVEMENTS

Priority List Rank

7

County

CAPE MAY

Existing Population

19,530

Service Area

Lower Township

Need for Project

Studies performed by NJDEP and the Cape May Board of Health have shown a need to find an alternate water source. The U.S. Geological Survey also indicated the need for an alternative water source. The existing discharge adversely impacts primary contact recreation and shellfish harvesting uses. Water quality does not meet standards for fecal coliform and nutrients and marginally meets standards for dissolved oxygen and toxics.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Lower Township STP (NJ0023809)	4.0	1.44	91.4	18.52	93.4	12.62

Project Description

The proposed solution is to construct a sand filter with an ultravoilet system and distribution system so the water can be used to recharge the local aquifers and halt salt water intrusion. Land application of the effluent to local golf courses and farms will be considered.

Anticipated Recipient	: WARREN TOWNSHIP SA			
Project No.	: 340964-01	Eligible Project Cost:	$	3,997,392
FY08 Rank	: 8			
County	: SOMERSET	Total State Amount :	$	3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	25
Toxics	0	25	50	50
			Subtotal	225
			State Planning Commission	0.00000
			Population	0.00187
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	975.00187

Project Name, Number

WARREN TOWNSHIP SA
340964-01
STP UPGRADES

Priority List Rank

8

County

SOMERSET

Existing Population

1,870

Service Area

Warren Township

Need for Project

Existing STPs are causing pollution and impacting the Passaic River. The river has potable water, fishing and industrial water uses. The water quality does not meet standards for fecal coliform and toxics and marginally meets standards for dissolved oxygen and nutrients.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Warren Twp SA (Stage I/II) (NJ0022489)	0.47	0.327	96.3	2.9	97.1	1.9
Warren Twp SA (Stage IV) (NJ0022497)	0.80	0.402	96.6	2.8	95.0	5.3
Warren Twp SA (Stage V) (NJ0050369)	0.38	0.094	97.1	2.8	97.8	1.3

Project Description

The Warren Township Sewerage Authority proposes to construct phosphorous reduction facilities at its three STPs.

Anticipated Recipient :	MIDDLESEX COUNTY UA		
Project No. :	340699-05	Eligible Project Cost:	$ 224,459,094
FY08 Rank :	9		
County :	MIDDLESEX	Total State Amount :	$ 224,459,094

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.69438
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	950.69438

Project Name, Number

MIDDLESEX COUNTY UA
340699-05
STP UPGRADE

Priority List Rank

9

County

MIDDLESEX

Existing Population

694,380

Service Area

Most of Middlesex County and parts of Somerset and Union Counties

Need for Project

MCUA's existing wastewater treatment plant requires future expansion particularly for treating maximum daily and peak hourly flows. The Authority has initiated work on plant expansion in order to be able to treat current and future projected flows to assure compliance with its NJPDES permit limitations.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Edward J. Patten	120	115	91.9	16.1	92.0	18.5

Project Description

In order to treat the projected increase in service area flows, capacity expansion is necessary to increase the rated capacity of the plant to 180 mgd. Additional facilities include new final settling tanks, new aerated grit chambers, modification of the existing grit chambers, new primary settling tanks and associated pipe galleries. These improvements will improve the efficiency and maintainability of the plant. Other improvements include modifications to the existing UNOX tanks, conversion of the existing aerobic digesters into UNOX tanks, and upgrading and replacement of existing obsolete instrumentation and control systems.

The plant currently uses chlorine for disinfection. In order to eliminate the chlorine residuals, an ozone disinfection system was piloted and was demonstrated to be viable and suitable for implementation.

Anticipated Recipient :	MIDDLESEX COUNTY UA		
Project No. :	340699-03	Eligible Project Cost:	$ 363,247,172
FY08 Rank :	10		
County :	MIDDLESEX	Total State Amount :	$ 363,247,172

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.49657
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	950.49657

Project Name, Number

MIDDLESEX COUNTY UA
340699-03
OUTFALL CONSTRUCTION

Priority List Rank

10

County

MIDDLESEX

Existing Population

496,570

Service Area

Borough of Bound Brook, East Brunswick Sewerage Authority, Township of Edison, Franklin Township Sewerage Authority, Township of Greenbrook, Borough of Highland Park, Borough of Metuchen, Borough of Middlesex, Monroe Township, City of New Brunswick, Borough of Milltown, Township of North Brunswick, Old Bridge Township Sewerage Authority, Township of Piscataway, Borough of North Plainfield, Borough of Watchung, Township of Scotch Plains, City of Plainfield, Borough of Sayreville, Borough of South Bound Brook, Township of South Brunswick, Borough of South Plainfield, Borough of South River, Borough of Spotswood, Borough of Dunellen, Borough of Fanwood

Need for Project

The MCUA treatment plant currently discharges its treated effluent into the Raritan Bay (SE-1) through a submerged outfall constructed in 1958. Despite the initiation of secondary treatment in 1978, this discharge, acting in conjunction with various other discharges, serves to degrade the water quality of the Bay. Fecal coliform and toxics standards are in violation while DO levels are marginally acceptable. This water quality degradation ultimately limits the use of the Bay for its intended uses of shellfish harvesting and primary contact recreation.

Project Description

This project entails the construction of an extended outfall to discharge to the Raritan Bay. The point of discharge will be determined to maximum diffusion and dilution. When this project is constructed, the Bay should be able to be utilized for its intended uses.

Anticipated Recipient	: ORADELL BOROUGH			
Project No.	: 340835-01	Eligible Project Cost:	$	295,455
FY08 Rank	: 11			
County	: BERGEN	Total State Amount :	$	295,455

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	200

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	25
Toxics	0	25	50	25
			Subtotal	150
			State Planning Commission	0.00000
			Population	0.00847
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	950.00847

Project Name, Number

ORADELL BOROUGH
340835-01
I/I CORRECTION - OVERFLOW

Priority List Rank

11

County

BERGEN

Existing Population

8,470

Service Area

Oradell Borough

Need for Project

The Borough of Oradell sewer collection system is subject to excessive infiltration/inflow. Peak flows surcharge several manhole covers, with the raw sewage overflow impacting upon the main intake canal of the Hackensack Water Company. Water quality standards are marginally acceptable for DO, fecal coliform, nutrients, and toxics.

Project Description

Minor rehabilitation techniques are proposed to correct the infiltration/inflow problem and eliminate the raw sewage overflows.

Anticipated Recipient :	HOPATCONG BOROUGH		
Project No. :	340488-05	Eligible Project Cost:	$ 17,222,998
FY08 Rank :	12		
County :	SUSSEX	Total State Amount :	$ 17,222,998

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	400

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	275
			State Planning Commission	15.00000
			Population	0.01589
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	940.01589

Project Name, Number

HOPATCONG BOROUGH
340488-05
COLLECTION SYSTEM

Priority List Rank

12

County

SUSSEX

Existing Population

15,888

Service Area

Borough of Hopatcong

Need for Project

This project is necessary to protect the waters of Lake Hopatcong (FW2-TM), a potable water supply source. Wastewater treatment methods in Hopatcong Borough consist of individual on-site systems. There are reported septic system failures which have been determined to adversely affect fishable (trout) and primary contact recreation uses of the lake. Water quality does not meet standards for dissolved oxygen and nutrients and marginally meet standards for fecal coliform and toxics. Nutrient inputs from existing septic systems would continue to be a major source of excessive aquatic plant and algae growth even if all systems were operating properly. The project is needed to eliminate septic systems in the densely developed portion of the watershed.

Project Description

The proposed project includes the installation of a collection and conveyance system to connect approximately 609 homes to the Musconetcong Sewerage Authority’s STP which will treat the new flows from the Borough of Hopatcong.

Anticipated Recipient	:	PENNSAUKEN TOWNSHIP		
Project No.	:	340349-03	Eligible Project Cost:	$ 5,308,104
FY08 Rank	:	13		
County	:	CAMDEN	Total State Amount :	$ 5,308,104

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	225

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	25
Toxics	0	25	50	25
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.03474
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	925.03474

Project Name, Number

PENNSAUKEN TOWNSHIP
340349-03
CSO ABATEMENT

Priority List Rank

13

County

CAMDEN

Existing Population

34,740

Service Area

Township of Pennsauken

Need for Project

A portion of Pennsauken Township is served by combined storm and sanitary sewers. During high intensity rainfalls, the capacity of the system is exceeded resulting in sanitary sewer overflows into homes, streets and waterways. The existing situation results in sewage discharges to the Back Channel of the Delaware River near the Cooper River. Public water supply, shellfish, agricultural and industrial water uses are adversely impacted. Water quality in the area of the discharge marginally meets standards for dissolved oxygen, nutrients and toxics.

Project Description

The project involves the construction of a large diameter storm sewer along Browning Avenue from Route 130/Madison Avenue to the Delaware River to prevent flow from entering the combined sewer system and the Camden City system, stormwater detention facilities to detain stormwater prior to its entering the combined system, the separation of the sanitary and storm sewer systems in portions of the Township and the enlargement of the existing storm sewer system to handle a greater capacity.

Anticipated Recipient	:	POMPTON LAKES BOROUGH MUA		
Project No.	:	340636-04	Eligible Project Cost:	$ 1,232,571
FY08 Rank	:	14		
County	:	PASSAIC	Total State Amount :	$ 1,232,571

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	175
			State Planning Commission	0.00000
			Population	0.01054
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	925.01054

Project Name, Number

POMPTON LAKES BOROUGH MUA
340636-04
STP IMPROVEMENTS, I/I CORRECTION

Priority List Rank

14

County

PASSAIC

Existing Population

10,539

Service Area

Pompton Lakes Borough

Need for Project

The existing facilities are approximately 30 years old and are deteriorating rapidly. Improvements are needed to ensure compliance with the NJPDES permit.

Project Description

The project includes the rehabilitation of existing STP structures and equipment, I/I correction work, rehabilitation of existing pumping stations, and an addition to the administration building.

Anticipated Recipient	:	ELIZABETH CITY		
Project No.	:	340942-11	Eligible Project Cost:	$ 5,308,104
FY08 Rank	:	15		
County	:	UNION	Total State Amount :	$ 5,308,104

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	50.00000
			Population	0.12057
			BDA Points	0
			Transit Villages	10
			TOTAL POINTS	910.12057

Project Name, Number

ELIZABETH CITY
340942-11
CSO ABATEMENT

Priority List Rank

15

County

UNION

Existing Population

120,568

Service Area

City of Elizabeth

Need for Project

The City of Elizabeth owns and operates several combined sewer overflows. The overflows discharge to the Elizabeth River, Arthur Kill, Newark Bay, Great Ditch and Peripheral Ditch. The discharges adversely impact non-trout fishing and industrial water uses. Water quality does not meet standards for fecal coliform, nutrients and toxics. The proposed project will relieve overflows and reduce flow to the treatment plant.

Project Description

The proposed project includes installing a separated storm sewer system throughout the entire midtown, rehabilitation of the 125 year old sanitary sewer, and reconstruction of an existing sanitary sewer pumping station.

Anticipated Recipient	:	NEWARK CITY		
Project No.	:	340815-13	Eligible Project Cost:	$ 8,363,576
FY08 Rank	:	16		
County	:	ESSEX	Total State Amount :	$ 8,363,576

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	50.00000
			Population	0.27355
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	900.27355

Project Name, Number

NEWARK CITY
340815-13
CSO ABATEMENT

Priority List Rank

16

County

ESSEX

Existing Population

273,550

Service Area

City of Newark

Need for Project

The City of Newark must construct improvements to its combined sewer system to comply with General Permit conditions regarding elimination of dry weather overflows and discharge of solids/floatables equal to, or greater than, one-half inch (1/2") diameter.

Project Description

This project consists of the construction of solids/floatables controls at six outfall sites including Jackson/Polk Street, and Roanoke Avenue.

Anticipated Recipient :	JERSEY CITY MUA		
Project No. :	340928-03	Eligible Project Cost:	$ 47,046,859
FY08 Rank :	17		
County :	HUDSON	Total State Amount :	$ 47,046,859

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	200

State Planning Commission	50.00000
Population	0.24006
BDA Points	0
Transit Villages	0
TOTAL POINTS	900.24006

Project Name, Number

JERSEY CITY MUA
340928-03
CSO ABATEMENT

Priority List Rank

17

County

HUDSON

Existing Population

240,055

Service Area

Jersey City, Kearny, Secaucus

Need for Project

The combined sewer overflows in the planning area discharge to the Hackensack and Hudson Rivers, and Upper New York Bay. The designated uses for these waters include secondary contact recreation, propagation and maintenance of fish and wildlife populations, the migration of anadromous fish, industrial water supply and other reasonable uses. The water quality is defined as poor due to the presence of high concentrations of indicator organisms such as fecal coliforms and toxic substances, and the observation of depressed levels of dissolved oxygen. The unsatisfactory water quality has been attributed to high pollutant loadings from inadequately treated municipal and industrial effluents, combined sewer overflows and non-point sources.

Project Description

The proposed project includes construction of a grit chamber on the interceptor just downstream of the CSO regulator to collect and remove inorganic material that could potentially clog the interceptor and cause DWOs. The MUA also proposes to construct a new pump station, sewer line, and force main to handle sanitary flows while separating out the stormwater flow.

Anticipated Recipient	: JERSEY CITY MUA			
Project No.	: 340928-04	Eligible Project Cost:	$	2,437,780
FY08 Rank	: 17			
County	: HUDSON	Total State Amount :	$	2,437,780

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	200
			State Planning Commission	50.00000
			Population	0.24006
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	900.24006

Project Name, Number

JERSEY CITY MUA
340928-04
CSO ABATEMENT

Priority List Rank

17

County

HUDSON

Existing Population

240,055

Service Area

Jersey City

Need for Project

The combined sewer overflows in the planning area discharge to the Hackensack and Hudson Rivers, and Upper New York Bay. The designated uses for these waters include secondary contact recreation, propagation and maintenance of fish and wildlife populations, the migration of anadromous fish, industrial water supply and other reasonable uses. The water quality is defined as poor due to the presence of high concentrations of indicator organisms such as fecal coliforms and toxic substances, and the observation of depressed levels of dissolved oxygen. The unsatisfactory water quality has been attributed to high pollutant loadings from inadequately treated municipal and industrial effluents, combined sewer overflows and non-point sources.

Project Description

The proposed project includes cleaning of box culverts from their Hudson River discharges to CSO chambers and installation of manholes to facilitate future cleaning.

Anticipated Recipient :	BAYONNE MUA		
Project No. :	340399-26	Eligible Project Cost:	$ 73,637,105
FY08 Rank :	19		
County :	HUDSON	Total State Amount :	$ 73,637,105

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	50.00000
			Population	0.06184
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	900.06184

Project Name, Number

BAYONNE MUA
340399-26
CSO ABATEMENT

Priority List Rank

19

County

HUDSON

Existing Population

61,842

Service Area

City of Bayonne

Need for Project

The City of Bayonne has a combined sewer system that is more than 75 years old. The MUA is investigating disinfection as a long-term-control measure for CSO discharges.

Project Description

The proposed project includes construction of facilities to capture and treat discharges from 33 combined sewer overflow discharge points.

Anticipated Recipient	: RIDGEFIELD PARK VILLAGE		
Project No.	: 340688-04	Eligible Project Cost:	$ 16,713,680
FY08 Rank	: 20		
County	: BERGEN	Total State Amount :	$ 16,713,680

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	250
			State Planning Commission	0.00000
			Population	0.01287
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	900.01287

Project Name, Number

RIDGEFIELD PARK VILLAGE
340688-04
CSO ABATEMENT

Priority List Rank

20

County

BERGEN

Existing Population

12,873

Service Area

Village of Ridgefield Park

Need for Project

Ridgefield Park has a combined sewer system and is investigating disinfection as a long-term-control measure for CSO discharges.

Project Description

The proposed project includes construction of facilities to capture and treat discharges from 6 combined sewer overflow discharge points.

Anticipated Recipient	: GUTTENBERG TOWN			
Project No.	: 340854-02	Eligible Project Cost:	$	376,252
FY08 Rank	: 21			
County	: HUDSON	Total State Amount :	$	376,252

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	50.00000
			Population	0.00827
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	900.00827

Project Name, Number

GUTTENBERG TOWN
340854-02
CSO ABATEMENT

Priority List Rank

21

County

HUDSON

Existing Population

8,268

Service Area

Guttenberg

Need for Project

The combined sewer overflow in the planning area discharges to the Hudson River. The designated water uses for the Hudson River include secondary contact recreation, propagation and maintenance of fish and wildlife populations, the migration of anadromous fish, industrial water supply and other reasonable uses. The water quality has been defined as poor due to the presence of high concentrations of indicator organisms such as fecal coliforms and toxic substances, and the observation of depressed levels of dissolved oxygen.

Project Description

The proposed project involves the construction of solids/floatables control measures at the combined sewer overflow point located off River Road, which discharges to the Hudson River.

Anticipated Recipient	:	MEDFORD LAKES BOROUGH		
Project No.	:	340463-06	Eligible Project Cost:	$ 4,135,382
FY08 Rank	:	22		
County	:	BURLINGTON	Total State Amount :	$ 4,135,382

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	150

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	50
			Subtotal	250
			State Planning Commission	0.00000
			Population	0.00500
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	900.00500

Project Name, Number

MEDFORD LAKES BOROUGH
340463-06
STP UPGRADE

Priority List Rank

22

County

BURLINGTON

Existing Population

5,000

Service Area

Medford Lakes Borough, portions of Medford Township

Need for Project

The Rancocas Creek and the lakes in the headwaters of the Haynes Creek are classified as FW2-NT nontrout waters with primary contact recreational uses. The existing water quality does not meet standards for fecal coliform, nutrients and toxics and marginally meets standards for dissolved oxygen. The effluent from the existing wastewater treatment facilities have exceeded the assimilative capacity of the stream and the facilities do not afford the degree of treatment to safely accommodate the current and future population within the service area. The project is needed to provide advanced wastewater treatment in order to comply with the Borough's NJPDES permit and ACO requirements. The following is the existing inventory of the wastewater facilities:

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Medford Lakes Borough (NJ0021326)	0.55	0.41	89.7	19.3	95.6	5.1

Project Description

The proposed project consists of the construction of a new "Bardenpho" treatment process (biological treatment for BOD, SS and nutrient removal) combined with rapid sand filters for effluent polishing and the demolition of existing Imhoff tanks, trickling filter and slow sand filter.

The ultimate sludge disposal will be incorporated into the county-wide sludge management facility.

Anticipated Recipient	: PATERSON CITY		
Project No.	: 340850-03	Eligible Project Cost:	$ 19,295,494
FY08 Rank	: 23		
County	: PASSAIC	Total State Amount :	$ 19,295,494

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	175
			State Planning Commission	50.00000
			Population	0.14922
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	875.14922

Project Name, Number

PATERSON CITY
340850-03
CSO ABATEMENT

Priority List Rank

23

County

PASSAIC

Existing Population

149,222

Service Area

City of Paterson

Need for Project

As part of their NJPDES permit, the City of Paterson must undertake design and construction of solids/floatable control facilities at its combined sewer overflow discharge locations. Overflows from the city discharge into the Passaic River and, in one area, to the Molly Ann Brook. They are a public nuisance due to floatables and unacceptable fecal coliform levels. Water quality does not meet standards for nutrients, and the level of toxics is only marginally acceptable. The discharges adversely impact the non-trout fishing and industrial uses of the Passaic River.

Project Description

The proposed project includes work at four discharge points to install solids/floatables control facilities. Three sites will have a combination of mechanical screening and netting facilities, one site will have a static bar screen.

Anticipated Recipient :	JEFFERSON TOWNSHIP		
Project No. :	340747-05	Eligible Project Cost:	$ 19,158,252
FY08 Rank :	24		
County :	MORRIS	Total State Amount :	$ 19,158,252

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	400

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	225

State Planning Commission	0.00000
Population	0.00869
BDA Points	0
Transit Villages	0
TOTAL POINTS	875.00869

Project Name, Number

JEFFERSON TOWNSHIP
340747-05
COLLECTION SYSTEM/INDIVIDUAL SYSTEMS

Priority List Rank

24

County

MORRIS

Existing Population

8,690

Service Area

Jefferson Township (Musconetcong River Basin)

Need for Project

Existing on-site systems are failing and may eventually lead to serious health hazards throughout this part of the Township. The failures are occurring because of certain soils limitations: shallow depth to bedrock, high water tables and steep slopes. Repairs have been attempted but with few successful results. A large number of on-site systems border Lake Hopatcong (FW2-TM), a potable water supply, and Lake Shawnee (FW2-TM). These waters are fishable (trout) and primary recreation quality. This portion of Jefferson Township contains a package sewage treatment plant servicing the Consolidated School. This system provides secondary treatment and discharge into tributaries of Lake Hopatcong. Water quality marginally meets standards for fecal coliform and toxics. Nutrient and D.O. levels violate existing standards.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Consolidated School Secondary (NJ0021091)	0.0075	0.01156	97.8	4.35	96.2	4.85

If the plan to connect into the Musconetcong Sewer Authority (MSA) is implemented, this sewage treatment plant will also connect into the MSA.

Project Description

This project includes the construction of a collection system for the Musconetcong River Basin portion of Jefferson which may also include an interceptor, pump station, and force main. Also, a septic system management plan will be recommended for the remaining portion of the Township.

Anticipated Recipient	:	WARREN CO-PAULINSKILL/BLAIRSTOWN		
Project No.	:	340453-03	Eligible Project Cost:	$ 2,607,692
FY08 Rank	:	25		
County	:	WARREN	Total State Amount :	$ 2,607,692

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	225

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	25
Toxics	0	25	50	25
			Subtotal	150
			State Planning Commission	0.00000
			Population	0.00489
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	875.00489

Project Name, Number

WARREN CO-PAULINSKILL/BLAIRSTOWN
340453-03
STP, INTERCEPTOR, PUMPING STATION

Priority List Rank

25

County

WARREN

Existing Population

4,890

Service Area

Blairstown Township

Need for Project

Portions of Blairstown have documented septic failure which may eventually lead to health problems. It was determined that the fecal coliform count violates the water quality standards and marginally meets standards for nutrients and toxics. At present, there are two privately owned and operated STP's in the study area. At the time the regional facilities become available the existing plants will tie into it. North Warren Regional High School is occasionally in noncompliance with their NJPDES permit requirements, which indicates inadequate secondary treatment. Primary contact recreation and agricultural water use are adversely impacted. This project is proposed in order to meet the stringent requirements established for the receiving waters.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Blair Academy (Secondary) (NJ0022101)	0.050	0.008	96.1	5.2	90.7	7.4
North Warren Regional High School (Secondary) (NJ0031046)	0.005	0.007	92.8	15.8	94.0	9.7

Project Description

The selected plan for this project will include a sewage treatment plant, interceptor, pump station, force main and possible sludge/septage management.

Anticipated Recipient :	HUDSON COUNTY UA (HOBOKEN)		
Project No. :	340399-09	Eligible Project Cost:	$ 14,038,507
FY08 Rank :	26		
County :	HUDSON	Total State Amount :	$ 14,038,507

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.19444
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	850.19444

Project Name, Number

HUDSON COUNTY UA (HOBOKEN)
340399-09
CSO ABATEMENT

Priority List Rank

26

County

HUDSON

Existing Population

194,440

Service Area

Guttenberg, Hoboken, Union City, Weehawken, West New York (HCUA Planning Area III)

Need for Project

The combined sewer overflows in the planning area discharge to the Hudson River. The designated water uses for the Hudson River include secondary contact recreation, propagation and maintenance of fish and wildlife populations, the migration of anadromous fish, industrial water supply and other reasonable uses. The water quality has been defined as poor due to the presence of high concentrations of indicator organisms such as fecal coliforms and toxic substances, and the observation of depressed levels of dissolved oxygen. The unsatisfactory water quality has been attributed to the continuous diversion of dry and wet weather sanitary sewer flows to the river. The combined sewer system, which is 100+ years old, contains collapsing sewer lines, and regulators and tide gates that are deteriorated and stuck. This condition has resulted in diversions of sewage flows to the river and intrusion of tidal flows into the system and treatment works.

Project Description

The construction of in-line storage facilities utilizing existing sewers is planned for Hoboken. In West New York, the construction of swirl concentrators is proposed. Studies indicate that facilities to abate pollution in Union City and Weehawken would not be cost effective.

Although this project has not been formally adopted by HCUA, studies indicate that this work is the most cost effective solution to pollution abatement.

The rehabilitation of tide gates and regulation in Hoboken, Weehawken and Union City has been funded under Marine CSO funds. However, the major portion of the project in this planning area has not been funded.

Anticipated Recipient :	LINDEN-ROSELLE SA		
Project No. :	340299-04	Eligible Project Cost:	$ 12,027,071
FY08 Rank :	27		
County :	UNION	Total State Amount :	$ 12,027,071

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.10070
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	850.10070

Project Name, Number

LINDEN-ROSELLE SA
340299-04
I/I CORRECTION - OVERFLOW

Priority List Rank

27

County

UNION

Existing Population

100,700

Service Area

The planning area includes the City of Linden and the Borough of Roselle

Need for Project

The Authority is required to complete a rehabilitation program to eliminate discharge points 003 and 004, and a sewer separation program to eliminate discharge points 001 and 002 as per the Part IIIb Special Conditions of the existing grant No. C340299-01. These discharges affect the quality of the Rahway River (SE-3). Fishable non-trout and industrial water uses are presently impacted due to fecal coliform, toxics, and DO (marginal) levels being unacceptable.

Project Description

The project is for the construction of relief sewers to enable the LRSA to eliminate discharge points 003 and 004 in the City of Linden. Elimination of these discharge points will improve water quality in the receiving stream. The alignment of relief sewers falls within the Wheeler Park Easement. This project requires the approval from Green Acres.

Anticipated Recipient	:	TWO RIVERS WRA		
Project No.	:	340117-02	Eligible Project Cost:	$ 7,760,140
FY08 Rank	:	28		
County	:	MONMOUTH	Total State Amount :	$ 7,760,140

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.07871
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	850.07871

Project Name, Number

TWO RIVERS WRA
340117-02
STP UPGRADE

Priority List Rank

28

County

MONMOUTH

Existing Population

78,706

Service Area

Eatontown, Fair Haven, Fort Monmouth, Little Silver, Monmouth Beach, Oceanport, Red Bank, Rumson, Sea Bright, Shrewsbury, Shrewsbury Township, a portion of Tinton Falls, West Long Branch

Need for Project

Upgrades at the Two Rivers Water Reclamation Authority Treatment Plant will improve reliability and productivity.

Project Description

The proposed project includes retrofitting the existing Sludge Processing System, installation of a new Supervisory Control and Data Acquisition System throughout the Authority’s collection system, installation of buoyancy prevention devices for plant clarifiers, and installation of electrical devices to eliminate single point failures.

Anticipated Recipient	: MIDDLETOWN TOWNSHIP SA		
Project No.	: 340097-02	Eligible Project Cost:	$ 17,477,546
FY08 Rank	: 29		
County	: MONMOUTH	Total State Amount :	$ 17,477,546

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.06633
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	850.06633

Project Name, Number

MIDDLETOWN TOWNSHIP SA
340097-02
STP IMPROVEMENTS

Priority List Rank

29

County

MONMOUTH

Existing Population

66,327

Service Area

Middletown Township, Highlands, Atlantic Highlands

Need for Project

Wastewater treatment plant improvements will improve the operations and reduce long-term operations and maintenance costs.

Project Description

The proposed project includes addition of an aeration tank, clarifier blower building and return activated sludge building. The existing aeration system will be replaced with fine bubble diffuser technology. Miscellaneous plant improvements required to accommodate the proposed improvements will be made.

Anticipated Recipient	: NORTH BERGEN MUA		
Project No.	: 340399-20	Eligible Project Cost:	$ 38,083,680
FY08 Rank	: 30		
County	: HUDSON	Total State Amount :	$ 38,083,680

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	250
			State Planning Commission	50.00000
			Population	0.04600
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	850.04600

Project Name, Number

NORTH BERGEN MUA
340399-20
STP UPGRADE

Priority List Rank

30

County

HUDSON

Existing Population

46,000

Service Area

North Bergen

Need for Project

The Township of North Bergen-Central WWTF will be required to meet "Level 3" treatment. The plant discharges to the Cromakill Creek Tributary-Hackensack River (SE-2). DO and fecal coliform levels are unacceptable and toxics marginally acceptable. The existing STP is also in need of extensive rehabilitation. The receiving waterway has industrial water uses as well as freshwater fishery (non-trout) uses.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Township of North Bergen; Central-WWTF (NJ0034339)	10	5.72	85.8	29.5	85.2	26.2

Project Description

The proposed project includes the replacement of the rotating biological contractors with activated sludge in combination with grit removal. The project also includes the upgrade of the influent pump station, construction of chlorine contact tanks, a screening building, four primary clarifiers, a new operations building, sludge thickening/storage facilities, a new electrical system, and a plant-wide SCADA control system.

Anticipated Recipient	:	RIDGEWOOD VILLAGE		
Project No.	:	340639-05	Eligible Project Cost:	$ 2,075,987
FY08 Rank	:	31		
County	:	BERGEN	Total State Amount :	$ 2,075,987

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.02486
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	850.02486

Project Name, Number

RIDGEWOOD VILLAGE
340639-05
I/I CORRECTION - OVERFLOW

Priority List Rank

31

County

BERGEN

Existing Population

24,860

Service Area

Village of Ridgewood

Need for Project

An Infiltration/Inflow (I/I) analysis has been completed which documents the existence of excessive I/I within the service area. An additional study will be undertaken to further define the quantity of excessive I/I that can be cost-effectively removed from this system. This project is needed to eliminate periodic overflow, causing discharge of untreated sewage into the HoHoKus and Diamond Brooks (FW2-NT, previously FW-2) which is adversely affecting the quality of these waterways, and posing a potential public health problem. The brooks have fishing and industrial uses. The affected waterways do not meet standards for fecal coliform and toxics, and marginally meets the dissolved oxygen standard.

Project Description

The proposed project will consist of 820 feet of gravity sewers and 8,400 feet of force main. Three pumping stations will be modified - Ridgewood Lawns P.S.; Bellair Road P.S. and Andover P.S. These mechanical improvements will enable the pump stations to handle additional sewage flows previously bypassed. These improvements are currently being designed.

Anticipated Recipient	: RIVERTON BOROUGH			
Project No.	: 340275-01	Eligible Project Cost:	$	914,970
FY08 Rank	: 32			
County	: BURLINGTON	Total State Amount :	$	914,970

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	100

State Planning Commission	0.00000
Population	0.00278
BDA Points	0
Transit Villages	0
TOTAL POINTS	850.00278

Project Name, Number

RIVERTON BOROUGH
340275-01
STP IMPROVEMENTS

Priority List Rank

32

County

BURLINGTON

Existing Population

2,775

Service Area

Riverton Borough

Need for Project

The existing STP was constructed in the early 1950’s and is becoming obsolete. The Borough’s STP discharges to the Delaware River and impacts potable water, fishable-nontrout and agricultural water uses. Water quality marginally meets standards for dissolved oxygen and fecal coliform.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Riverton Borough STP (NJ0021610)	0.22	0.204	97.4	14.3	93.4	17.6

Project Description

The proposed project involves the construction of a new wastewater treatment plant utilizing a sequencing batch reactor process.

Anticipated Recipient	: JEFFERSON TOWNSHIP			
Project No.	: 340747-02	Eligible Project Cost:	$	1,952,637
FY08 Rank	: 33			
County	: MORRIS	Total State Amount :	$	1,952,637

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	200

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	125

State Planning Commission	0.00000
Population	0.01671
BDA Points	0
Transit Villages	0
TOTAL POINTS	825.01671

Project Name, Number

JEFFERSON TOWNSHIP
340747-02
PUMP STATION, FORCE MAIN, COLLECTION SYSTEM

Priority List Rank

33

County

MORRIS

Existing Population

16,710

Service Area

Jefferson Township

Need for Project

The need for the development of a wastewater management plan for the Township of Jefferson has resulted from problems being experienced with existing on-site disposal systems. These systems are adversely affecting fishable trout and primary contact recreation waters, and the limited ability of four small treatment plants to provide adequate treatment. Fecal coliform and toxics levels are marginally acceptable and nutrients levels are totally unacceptable. Also, the sludge generated is being stored in an old tank on-site at the White Rock Lake STP, which is an unsatisfactory sludge disposal method. The receiving stream is a tributary of Mitt Pond which ultimately flows in the Boonton reservoir. High and Middle School discharges to Russia Brook (FW2-TM).

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
High and Middle School (secondary)	0.28	Not Available	99.6	5.96	99.9	7.15
White Rock Lake (AWT) (NJ0026867)	0.155	0.0621	98.7	6.375	95.7	5.0

Project Description

Jefferson Township performed a 201 Study for portions of Jefferson which lie both in the Rockaway Basin and Upper Musconetcong Basin (See C340747-05 for description of the Musconetcong plan). The proposed plan for Rockaway consists of expansion and upgrading of the existing White Rock Lake STP to 250,000 gpd and using the oxidation ditch process. Wastewater from the Cozy Lake, Lake Swannomoa and the White Rock Lake areas would be treated there. The proposed facility would include a pumping station, force main, interceptor and collection system.

Anticipated Recipient	:	WRIGHTSTOWN (WRIGHTSTOWN MUA)		
Project No.	:	340925-01	Eligible Project Cost:	$ 3,866,213
FY08 Rank	:	34		
County	:	BURLINGTON	Total State Amount :	$ 3,866,213

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	275

State Planning Commission	0.00000
Population	0.00315
BDA Points	0
Transit Villages	0
TOTAL POINTS	825.00315

Project Name, Number

WRIGHTSTOWN (WRIGHTSTOWN MUA)
340925-01
STP UPGRADE

Priority List Rank

34

County

BURLINGTON

Existing Population

3,150

Service Area

Wrightstown

Need for Project

The 0.2 mgd treatment plant in Wrightstown must be upgraded to meet required water quality standards; the plant will also be expanded. The treatment plant discharges to North Run, thence to Crosswicks Creek. The waters do not meet water quality standards for dissolved oxygen, fecal coliform, or nutrients, and levels of toxics are only marginally acceptable. Thus, use of these waters for non-trout fishing and agriculture are adversely impacted.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Wrightstown STP (NJ0022985)	0.2	0.155	98.4	2.4	99.1	5.0

Project Description

The proposed project will upgrade the plant's secondary treatment processes. A pump station and emergency generator will be installed. The following process units will also be added to the existing facilities: nitrification/denitrification, sludge dewatering and handling, ultraviolet disinfection, and 24-hour composite sample controls.

Anticipated Recipient	:	BERGEN COUNTY UA		
Project No.	:	340386-07	Eligible Project Cost:	$ 7,157,336
FY08 Rank	:	35		
County	:	BERGEN	Total State Amount :	$ 7,157,336

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	250
			State Planning Commission	0.00000
			Population	0.49114
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	800.49114

Project Name, Number

BERGEN COUNTY UA
340386-07
STP IMPROVEMENTS

Priority List Rank

35

County

BERGEN

Existing Population

491,140

Service Area

The BCUA currently serves 51 municipalities.

Need for Project

The effluent from the BCUA treatment plant is discharged into the Hackensack River classified as SE waters, which is a tidal estuary below the Oradell Reservoir dam. Water quality in the Hackensack River violates standards for dissolved oxygen, fecal coliform and toxics. Improvements at the treatment plant will increase efficiency.

Project Description

The proposed project includes replacement of the return activated sludge pumps, upgrade of the motor control center, relocation of the controls to a new electrical building and modification of the piping system to meet the minimum clearances required by the current building code.
In an effort to enhance the secondary clarifiers and achieve the additional carbonaceous biochemical oxygen demand and total suspended solids pollutant loading required for influent flows greater than 75 MGD during summer months, BCUA plans upgrades that include replacement of the influent baffles, secondary setting polymer addition and the addition of mid-tank baffles and replacement of effluent weirs.

Anticipated Recipient :	NORTH HUDSON SA		
Project No. :	340952-11	Eligible Project Cost:	$ 37,894,935
FY08 Rank :	36		
County :	HUDSON	Total State Amount :	$ 37,894,935

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	150
			State Planning Commission	50.00000
			Population	0.20000
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	800.20000

Project Name, Number

NORTH HUDSON SA
340952-11
CSO IMPROVEMENTS

Priority List Rank

36

County

HUDSON

Existing Population

200,000

Service Area

City of Hoboken and portions of the Township of Weehawken, Union City, and West New York

Need for Project

The proposed improvements will decrease the number of overflows from the Authority’s combined sewer system lessen the amount of raw sewage discharged to the Hudson River.

Project Description

The proposed project includes construction of three combined sewage pump stations for separately conveying solids/floatables facility overflows, increasing the wet weather capacity of a sewer line, construction of a new conveyance, replacement of the Liberty Place pump station, and construction of a new force main to divert sewage from the River road WWTP to the Adams Street WWTP.

Anticipated Recipient	:	NORTH BERGEN TOWNSHIP/HUDSON CO UA		
Project No.	:	340652-01	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	37		
County	:	HUDSON	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	100
			State Planning Commission	50.00000
			Population	0.01166
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	800.01166

Project Name, Number

NORTH BERGEN TOWNSHIP/HUDSON CO UA
340652-01
COLLECTION SYSTEM

Priority List Rank

37

County

HUDSON

Existing Population

11,660

Service Area

Portions of North Bergen (Area III)

Need for Project

North Bergen Area III is serviced by the Woodcliff STP. A portion of this district is currently unsewered and contains malfunctioning septic systems. Sanitary connections have been made to an existing storm water system resulting in discharge of untreated sewage to the Hudson River. This discharge impacts industrial water use and freshwater-nontrout uses, as well as contributing to fecal coliform violations. The Hillcrest pumping station contains an overflow and requires rehabilitation.

Project Description

A new sanitary sewer collection system will be constructed to convey flows from the unsewered areas. The illegal connections will be corrected and the flow collected for treatment. Sewage will be transported to the Woodcliff STP or to a neighboring facility for treatment. The Hillcrest Pumping Station will also be rehabilitated.

Anticipated Recipient	:	WARREN COUNTY (PEQUEST RIVER) MUA		
Project No.	:	340454-05	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	38		
County	:	WARREN	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	200

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.00320
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	800.00320

Project Name, Number

WARREN COUNTY (PEQUEST RIVER) MUA
340454-05
PHOTOVOLTAIC

Priority List Rank

38

County

WARREN

Existing Population

3,200

Service Area

Towns of Oxford and Belvidere and protions of White, Washington and Mansfield Townships

Need for Project

Electrical power generated by photovoltaic units will be used by the WCMUA at its Belvidere and Oxford WWTPs to reduce the facility load during daily peak electrical demand.

Project Description

The proposed project includes installation of 300kw photovoltaic plants to generate additional electricity.

Anticipated Recipient	:	OCEAN COUNTY UA		
Project No.	:	340372-32	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	39		
County	:	OCEAN	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	25
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	25
			State Planning Commission	0.00000
			Population	0.59999
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	775.59999

Project Name, Number

OCEAN COUNTY UA
340372-32
FINAL CLARIFIER

Priority List Rank

39

County

OCEAN

Existing Population

599,994

Service Area

17 municipalities in central Ocean County

Need for Project

The STP improvements are needed to ensure operational reliability and to enable normal maintenance of the process units. The Central and Northern Water Pollution Control Facilities discharge to the Atlantic Ocean and adversely effects the shellfishing and recreational attributes along the Ocean County beachfront.

Project Description

The proposed project includes rehabilitation and/or replacement of the steel rake mechanisms, baffles, weirs, motors, controls, lighting, and re-coating of concrete surfaces.

Anticipated Recipient	: OCEAN COUNTY UA			
Project No.	: 340372-33	Eligible Project Cost:	$	985,189
FY08 Rank	: 39			
County	: OCEAN	Total State Amount :	$	985,189

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	25
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	25

State Planning Commission	0.00000
Population	0.59999
BDA Points	0
Transit Villages	0
TOTAL POINTS	775.59999

Project Name, Number

OCEAN COUNTY UA
340372-33
CHLORINE BUILDING CONVERSION

Priority List Rank

39

County

OCEAN

Existing Population

599,994

Service Area

17 municipalities in central Ocean County

Need for Project

The STP improvements are needed to ensure operational reliability and to enable normal maintenance of the process units. The Central Pollution Control Facilities discharge to the Atlantic Ocean and adversely effects the shellfishing and recreational attributes along the Ocean County beachfront.

Project Description

The proposed project includes conversion of OCUA’s Central Pollution Control Facilities chlorine building to a vehicle maintenance facility.

Anticipated Recipient :	HAMILTON TOWNSHIP		
Project No. :	340898-01	Eligible Project Cost:	$ 10,686,034
FY08 Rank :	41		
County :	MERCER	Total State Amount :	$ 10,686,034

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	25
	Subtotal	75

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	50
Toxics	0	25	50	0
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.09542
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	775.09542

Project Name, Number

HAMILTON TOWNSHIP
340898-01
STP IMPROVEMENTS

Priority List Rank

41

County

MERCER

Existing Population

95,420

Service Area

Hamilton Township, Washington Township, 31% of West Windsor Township

Need for Project

The effluent from the existing treatment plant is not meeting water quality standards for ammonia, required under the NJPDES permit conditions. The Hamilton Township facility discharges into Crosswicks Creek (FW2-NT) classified as fishable, non-trout which also has agricultural and industrial uses; this water body does not meet standards for fecal coliform and nutrients and is marginally acceptable for dissolved oxygen.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Hamilton Twp.(NJ0026301)	16.0	10.2	91.4	16	94.1	12.3

Project Description

The proposed project involves the construction of an addition to the existing wastewater treatment plant for treatment of ammonia to comply with water quality standards.

Anticipated Recipient	: ATLANTIC COUNTY UA			
Project No.	: 340809-08	Eligible Project Cost:	$	1,640,997
FY08 Rank	: 42			
County	: ATLANTIC	Total State Amount :	$	1,640,997

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.16367
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	750.16367

Project Name, Number

ATLANTIC COUNTY UA
340809-08
STP IMPROVEMENTS

Priority List Rank

42

County

ATLANTIC

Existing Population

163,667

Service Area

The municipalities of Absecon, Atlantic City, Brigantine, Egg Harbor City, Egg Harbor Township, Galloway, Hamilton, Linwood, Longport, Margate, Northfield, Pleasantville, Somers Point and Ventnor.

Need for Project

Improvements to the STP are needed to ensure operational reliability and component integrity. Certain process equipment must be replaced or improved. The existing discharge to the Atlantic Ocean has the potential to adversely impact shellfish and recreational uses.

Project Description

The project involves (1) upgrade of the existing sludge incinerator air pollution control system, (2) replacement of the three return activated sludge (RAS) screw pumps, (3) replacement of wastewater treatment plant scum concentrator, (4) installation of five primary clarifier covers with odor control system, (5) replacement and relocation of the plant washdown pumps, (6) installation of two drywells and four pumps to accommodate the scrubber supply and drainage system and (7) ultraviolet effluent treatment.

Anticipated Recipient	: ROCKAWAY VALLEY RSA			
Project No.	: 340821-04	Eligible Project Cost:	$	9,782,685
FY08 Rank	: 43			
County	: MORRIS	Total State Amount :	$	9,782,685

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	200
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.12063
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	750.12063

Project Name, Number

ROCKAWAY VALLEY RSA
340821-04
STP

Priority List Rank

43

County

MORRIS

Existing Population

120,630

Service Area

Boonton Town, Boonton Township, Denville, Dover, Jefferson (48%), Kinnelon (32%), Mine Hill (65%), Randolph (78%), Rockaway Borough, Rockaway Township, Roxbury, Victory Gardens, Wharton

Need for Project

Rockaway Valley Regional Sewerage Authority is proposing improvements to its treatment facility to ensure continued compliance with the current NJPDES effluent parameter for CBOD as flows increase to the current design flow. The project will also provide advanced phosphorous reduction capability as well as significantly lowering nitrate levels in Rockaway River.

Project Description

The proposed project inludes the construction of advanced wastewater treatment facilities at the existing RVRSA treatment plant. The new facilities will consist of chemical addition equipment, process reactors, and advanced solids/liquid separation treatment facilities.

Anticipated Recipient	: NEPTUNE TOWNSHIP SA		
Project No.	: 340410-05	Eligible Project Cost:	$ 10,684,529
FY08 Rank	: 44		
County	: MONMOUTH	Total State Amount :	$ 10,684,529

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03473
BDA Points	0
Transit Villages	0
TOTAL POINTS	750.03473

Project Name, Number

NEPTUNE TOWNSHIP SA
340410-05
STP UPGRADE

Priority List Rank

44

County

MONMOUTH

Existing Population

34,727

Service Area

Neptune Township, Avon-By-The-Sea Borough, Bradley Beach Borough, Ocean Grove Camp Meeting Association

Need for Project

The Authority’s treatment plant has struggled to meet the permit limitatoins for the toxicity of its discharge.

Project Description

The proposed project includes installation of a BIOFOR-N biological aeration system to provide tertiary for the Authority’s effluent.

Anticipated Recipient	:	EVESHAM MUA (WOODSTREAM)		
Project No.	:	340463-05	Eligible Project Cost:	$ 7,132,162
FY08 Rank	:	45		
County	:	BURLINGTON	Total State Amount :	$ 7,132,162

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.02867
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	750.02867

Project Name, Number

EVESHAM MUA (WOODSTREAM)
340463-05
STP, INTERCEPTOR

Priority List Rank

45

County

BURLINGTON

Existing Population

28,670

Service Area

Evesham Township (Woodstream)

Need for Project

The South Branch of the Pennsauken Creek is classified as FW2-NT nontrout waters with industrial water use. The existing water quality is voilated for fecal coliform and toxics with marginal violation of dissolved oxygen. The effluent from the existing wastewater treatment facilities have exceeded the assimilative capacity of the stream and the facilities do not afford the degree of treatment to safely accommodate the current and future population within the Project Area. The following is the existing inventory of the wastewater facilities:

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Woodstream (NJ0024040)	1.25	0.91	96.8	10.9	99.1	3.3

Project Description

This project is to provide a cost effective regional sewerage system for the Southwest Branch Rancocas Creek drainage basin. Implementation of the project will accomplish the attainment of water quality in area streams, the prevention of health hazards and the protection of the environment. Presently, the facility planning effort is evaluating the various alternatives which will accommodate the required levels of treatment necessary to alleviate the pollution problem. The alternatives which can be implemented are land disposal, discharge to the confluence of the Southwest Branch or discharge at the present location. The ultimate sludge disposal will be incorporated into the on-going countywide sludge and septage management plan recommendations.

Anticipated Recipient	:	EDGEWATER MUA		
Project No.	:	340446-09	Eligible Project Cost:	$ 2,451,173
FY08 Rank	:	46		
County	:	BERGEN	Total State Amount :	$ 2,451,173

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	200
			State Planning Commission	0.00000
			Population	0.01000
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	750.01000

Project Name, Number

EDGEWATER MUA
340446-09
STP OUTFALL/IMPROVEMENTS

Priority List Rank

46

County

BERGEN

Existing Population

10,000

Service Area

Edgewater Borough, the majority of Cliffside Park, and portions of Fort Lee

Need for Project

The proposed project will serve a dual purpose. The project will improve the overall quality of the Authority’s effluent and also improve the method by which the effluent is discharged into the Hudson River.

Project Description

The proposed project includes installation of an automated filtering system to remove particles 20 microns or larger, and an extension of the treatment facility’s outfall pipe further into the Hudson River to provide an adequate mixing zone.

Anticipated Recipient	: ATLANTIC COUNTY UA			
Project No.	: 340809-09	Eligible Project Cost:	$	2,718,518
FY08 Rank	: 47			
County	: ATLANTIC	Total State Amount :	$	2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	125

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.16367
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	725.16367

Project Name, Number

ATLANTIC COUNTY UA
340809-09
STP IMPROVEMENTS

Priority List Rank

47

County

ATLANTIC

Existing Population

163,667

Service Area

The municipalities of Absecon, Atlantic City, Brigantine, Egg Harbor City, Egg Harbor Township, Galloway, Hamilton, Linwood, Longport, Margate, Northfield, Pleasantville, Somers Point and Ventnor.

Need for Project

Improvements to the STP are needed to ensure operational reliability and component integrity. Certain process equipment must be replaced or improved. The existing discharge to the Atlantic Ocean has the potential to adversely impact shellfish and recreational uses.

Project Description

The project involves (1) installation of new variable speed drive units to replace existing single speed drive units controlling 500hp effluent pumps allowing the equalization basin to be taken off line for maintenance and cleaning (2) installation of a new bar screen and conveyor system to reduce rags and solids from passing through the process system (3) installation of a CEM/DAS system to monitor the sludge furnace emission levels of oxygen and carbon-dioxide (4) replacement of the centrifuge back drive units with new units and a control panel for automatic torque control for higher efficiency (5) replacement of Dezurik valves to prevent leaking and the cross contamination of processes (6) installation of a supervisor computer and data acquisition system (SCATA) to electronically optimize unit processes (7) replacement and relocation of the plant washdown pumps and (8) sludge hopper enlargement. This project also includes minor necessary improvements to ensure operational reliability.

Anticipated Recipient	: PENNSVILLE SA			
Project No.	: 340870-02	Eligible Project Cost:	$	7,211,095
FY08 Rank	: 48			
County	: SALEM	Total State Amount :	$	7,211,095

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	25
			Subtotal	175
			State Planning Commission	0.00000
			Population	0.01500
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	725.01500

Project Name, Number

PENNSVILLE SA
340870-02
STP UPGRADE, COLLECTION SYSTEM

Priority List Rank

48

County

SALEM

Existing Population

15,000

Service Area

Pennsville Township

Need for Project

Areas in Pennsville have malfunctioning septic systems which have been creating a public nuisance and are a potential health hazard. Modifications to Pennsville's treatment plant are needed to ensure operational reliability.

Project Description

The proposed project includes construction of improvements to its wastewater treatment plant. Also included in the project is the construction of pump stations, a sewer force main and gravity sewer, and modifications to existing pumping facilities to accommodate additional flow from new areas.

Anticipated Recipient	:	GLOUCESTER CO UA (GIBBSTOWN)		
Project No.	:	340526-06	Eligible Project Cost:	$ 2,294,564
FY08 Rank	:	49		
County	:	GLOUCESTER	Total State Amount :	$ 2,294,564

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	50
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	25
			Subtotal	175
			State Planning Commission	0.00000
			Population	0.00531
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	725.00531

Project Name, Number

GLOUCESTER CO UA (GIBBSTOWN)
340526-06
STP UPGRADE, SLUDGE MANAGEMENT

Priority List Rank

49

County

GLOUCESTER

Existing Population

5,310

Service Area

Gibbstown - Greenwich Township

Need for Project

The Gibbstown plant is discharging to Wiggins Pond, a tributary of the Delaware River. The effluent is not in compliance with the permit requirements. Due to the stringent effluent limitations as established by the Department, discontinuation of the discharge to Wiggins Pond has become necessary. Wiggins Pond (SE-2) is a non-trout stream with severe violations of fecal coliform and marginal violations of D.O. and toxics. Wiggins Pond supports industrial water use. Also, there exists a major problem due to the presence of high-strength chemical wastes. The plant also receives intermittent discharges of slaughtering wastes from a local butchery. The combined effect of these wastes tend to upset the biological processes.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Gibbstown(Secondary)(NJ0030333)	1.0	0.77	92.2	19.8	89	25.7

Project Description

The project consists of upgrading the existing Gibbstown plant by using the oxidation ditch process and construction of an outfall for direct effluent discharge to the Delaware River. It also includes the construction of influent and effluent pump stations and force mains.

Anticipated Recipient	: DELAWARE TOWNSHIP MUA			
Project No.	: 340917-01	Eligible Project Cost:	$	1,522,661
FY08 Rank	: 50			
County	: HUNTERDON	Total State Amount :	$	1,522,661

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	100

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	25
			Subtotal	125
			State Planning Commission	0.00000
			Population	0.00100
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	725.00100

Project Name, Number

DELAWARE TOWNSHIP MUA
340917-01
STP IMPROVEMENTS

Priority List Rank

50

County

HUNTERDON

Existing Population

1,000

Service Area

Seargentsville (including light business district)

Need for Project

The Delaware Township MUA is facing an Administrative Consent Order for compliance with the July 1, 1988 deadlines for meeting effluent limits stipulated under the Clean Water Act. An existing treatment facility must be upgraded to meet NJPDES permit limitations; an increase in treatment capacity is also being considered. The Delaware Township MUA also plans to rehabilitate portions of the existing sewer system.

The treatment plant discharges into the Wickecheoke Creek in the Delaware River Basin. This water body is a trout fishery with agricultural water uses; water quality standards for fecal coliform are not being met, while those for toxics are only marginally acceptable.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Delaware Township MUA (Secondary) (NJ0020290)	.027	Not Avail-able	93	13	87.3	16.9

Project Description

One alternative under consideration to upgrade the STP is to convert the existing secondary treatment facility into a larger Sequential Batch Reactor System.

Anticipated Recipient	: NORTH HUDSON SA			
Project No.	: 340952-10	Eligible Project Cost:	$	9,683,168
FY08 Rank	: 51			
County	: HUDSON	Total State Amount :	$	9,683,168

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	100
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	150
			State Planning Commission	50.00000
			Population	0.20000
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	700.20000

Project Name, Number

NORTH HUDSON SA
340952-10
STP IMPROVEMENTS

Priority List Rank

51

County

HUDSON

Existing Population

200,000

Service Area

City of Hoboken and portions of the Township of Weehawken Union City,and West New York

Need for Project

Upgrades at the River Road and Adams Street Wastewater Treatment Plants will improve reliability and productivity allowing more flow to be treated thus minimzing CSO overflows.

Project Description

The proposed project includes in-kind replacement of the Adams Street sludge storage tank recirculation pump and ancillary equipment, repair of concrete spalling and rebar corrosion on the River road WWTP secondary clarifiers, in-kind replacement of the River Road WWTP trickling filter recirculation pumps and ancillary equipment, replacement of tie-down straps on the River Road WWTP outfall on the Hudson River, and construction of a new biological process for treating trickling filter effluent. The project also includes emergency in-kind replacement of failed PURAC backwash feed pumps, trickling filter feed pumps, PURAC feed pumps and plant effluent pumps.

Anticipated Recipient	: EAST WINDSOR MUA		
Project No.	: 340536-06	Eligible Project Cost:	$ 11,971,732
FY08 Rank	: 52		
County	: MERCER	Total State Amount :	$ 11,971,732

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	25

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	150

State Planning Commission	0.00000
Population	0.02340
BDA Points	0
Transit Villages	0
TOTAL POINTS	675.02340

Project Name, Number

EAST WINDSOR MUA
340536-06
STP IMPROVEMENTS

Priority List Rank

52

County

MERCER

Existing Population

23,401

Service Area

East Windsor

Need for Project

The original Wastewater Management Plan for EWMUA concluded that a total treatment capacity of 4.5 mgd was required to serve the future sewer service area. In 1999, the Authority submitted a Wastewater Management Plan Amendment with an expanded capacity of 4.5 mgd. In March 2007 the plan amendment was approved. As a result of anti-degredation requirements the effluent permit limits for the 4.5 mgd permit are to be based on the total pollutant loads for the current permitted flow of 3.35 mgd.

Project Description

The proposed upgrades includes a new influent bar screen and compactor, new influent pumps with variable frequency drives, modifications to existing activated sludge aeration system, addition of a third final clarifier and gravity filter, addition of a new ultraviolet disinfection system, new SCADA system and modification to the existing sludge handling system including a new sludge thickening system and sludge pump replacement.

Anticipated Recipient :	MONTGOMERY TOWNSHIP		
Project No. :	340130-01	Eligible Project Cost:	$ 11,070,944
FY08 Rank :	53		
County :	SOMERSET	Total State Amount :	$ 11,070,944

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	25

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	150

State Planning Commission	0.00000
Population	0.01748
BDA Points	0
Transit Villages	0
TOTAL POINTS	675.01748

Project Name, Number

MONTGOMERY TOWNSHIP
340130-01
STP IMPROVEMENTS

Priority List Rank

53

County

SOMERSET

Existing Population

17,481

Service Area

Montgomery Township

Need for Project

Due to the age and condition of existing equipment, coupled with the issuance of stringent discharge limits, the Township will upgrade the plant using bioreactor technology. MBR technology provides a higher level of treatment than is possible with conventional activated sludge and sand filtration.

Project Description

The proposed upgrade includes construction membrane bioreactor at the North Princeton Development Center/Skillman Village Wastewater Treatment Plant.

Anticipated Recipient	: HARRISON TOWNSHIP			
Project No.	: 340362-05	Eligible Project Cost:	$	1,114,504
FY08 Rank	: 54			
County	: GLOUCESTER	Total State Amount :	$	1,114,504

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	25

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	150
			State Planning Commission	0.00000
			Population	0.00879
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	675.00879

Project Name, Number

HARRISON TOWNSHIP
340362-05
SOLAR PANELS & STORAGE FACILITY

Priority List Rank

54

County

GLOUCESTER

Existing Population

8,788

Service Area

Harrison Township

Need for Project

Installation of solar panels will make Harrison’s treatment facility more energy efficient. A new storage facility will protect equipment and vehicles from the elements and extend their useful life.

Project Description

The proposed project includes installation of solar panels and a new storage facility at the treatment plant.

Anticipated Recipient	: GLOUCESTER CITY			
Project No.	: 340958-05	Eligible Project Cost:	$	243,047
FY08 Rank	: 55			
County	: CAMDEN	Total State Amount :	$	243,047

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	600
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	600

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	15.00000
			Population	0.01148
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	665.01148

Project Name, Number

GLOUCESTER CITY
340958-05
CSO ABATEMENT

Priority List Rank

55

County

CAMDEN

Existing Population

11,484

Service Area

Gloucester City

Need for Project

The proposed project is needed for compliance with the requirements of the CSO General Permit. The General Permit requires removal of solids/floatables greater than ½" in size.

Project Description

The proposed project includes elimination of two CSO points through rerouting and installation of solids and floatables controls at five CSO points.

Anticipated Recipient	:	WARREN COUNTY (PEQUEST RIVER) MUA		
Project No.	:	340454-04	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	56		
County	:	WARREN	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	150

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00320
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	650.00320

Project Name, Number

Priority List Rank

WARREN COUNTY (PEQUEST RIVER) MUA
340454-04
STP IMPROVEMENTS

56

County

WARREN

Existing Population

3,200

Service Area

Town of Oxford and portions of White, Washington, and Mansfield Townships

Need for Project

The proposed project consists of upgrading the treatment plant from secondary treatment to advanced secondary treatment in order to meet current and anticipated future NJPDES permit limits, replacing chlorination with ulta-violet disinfection, and improving sludge handling.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
NJ0035483	0.50	0.285	90.0	25.0	85.0	30.0

Project Description

The proposed project involves the upgrade of the existing secondary treatment facility to Upflow Sludge Blanket Filtration (activated sludge) with sand filtration and UV disinfection. The existing solids handling system will be upgraded to gravity thickeners and improved sludge holding facilities.

Anticipated Recipient	:	MANSFIELD TOWNSHIP		
Project No.	:	340935-01	Eligible Project Cost:	$ 1,396,910
FY08 Rank	:	57		
County	:	WARREN	Total State Amount :	$ 1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	100

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	50

State Planning Commission	0.00000
Population	0.00100
BDA Points	0
Transit Villages	0
TOTAL POINTS	650.00100

Project Name, Number

MANSFIELD TOWNSHIP
340935-01
STP IMPROVEMENTS

Priority List Rank

57

County

WARREN

Existing Population

1,000

Service Area

Diamond Hill Development

Need for Project

The existing facilities at the Diamond Hill Sewer Company (NJ0028592), which serves the Diamond Hill Development, is inadequately treating sewage and has been doing so for a few decades. The discharge is to Hances Brook, which is classified as FW2-Trout Production Category One waters. The private owner of the sewer company would not make the necessary repairs to the facilities, so Mansfield Township is evaluating whether or not to takeover the Diamond Hill Sewer Company.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Diamond Hill Sewer Co. (NJ0028592)	NA	0.08	69.5	41.3	86.4	20.5

Project Description

The proposed project involves the construction of a completely new treatment plant, including secondary and advanced treatment facilities. All existing facilities are inadequate for reuse.

Anticipated Recipient	:	WANAQUE VALLEY RSA		
Project No.	:	340780-03	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	58		
County	:	PASSAIC	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	25
Toxics	0	25	50	0
			Subtotal	75
			State Planning Commission	0.00000
			Population	0.00971
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	625.00971

Project Name, Number

WANAQUE VALLEY RSA
340780-03
STP IMPROVEMENTS

Priority List Rank

58

County

PASSAIC

Existing Population

9,710

Service Area

Wanaque Borough

Need for Project

Wanaque Valley Regional Sewerage Authority has proposed improvements and process modifications to their existing wastewater treatment plant in order to increase the efficiency of the wastewater treatment facility. The proposed project is expected to result in improved effluent quality. The existing discharge adversely impacts fishable (non-trout) and industrial water uses. Water quality marginally meets standards for fecal colifrom and nutrients.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Wanaque Valley RSA (NJ0053759)	1.25	.782	97.2	4.5	97.7	4.1

Project Description

The proposed project involves minor modifications to improve the effluent quality of the wastewater treatment facility.

Anticipated Recipient	:	BUENA BOROUGH MUA		
Project No.	:	340518-04	Eligible Project Cost:	$ 2,049,114
FY08 Rank	:	59		
County	:	ATLANTIC	Total State Amount :	$ 2,049,114

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	50
Toxics	0	25	50	0
			Subtotal	50

State Planning Commission	0.00000
Population	0.00370
BDA Points	0
Transit Villages	0
TOTAL POINTS	600.00370

Project Name, Number

BUENA BOROUGH MUA
340518-04
PUMP STATION, FORCE MAIN

Priority List Rank

59

County

ATLANTIC

Existing Population

3,700

Service Area

Buena Borough

Need for Project

An Administrative Consent requires that the outfall must be relocated from Deep Run (Pineland waterway) to the Blackwater Branch Stream (a non-Pineland waterway).

Project Description

The proposed project involves the construction of a new effluent pump station and 3 miles of force main which will discharge the effluent to the Blackwater Branch Stream.

Anticipated Recipient	: TRENTON CITY			
Project No.	: 340416-11	Eligible Project Cost:	$	3,997,392
FY08 Rank	: 60			
County	: MERCER	Total State Amount :	$	3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	25

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.08540
BDA Points	0
Transit Villages	0
TOTAL POINTS	575.08540

Project Name, Number

TRENTON CITY
340416-11
STP

Priority List Rank

60

County

MERCER

Existing Population

85,403

Service Area

City of Trenton

Need for Project

The primary treatment system at the Trenton Sewage Treatment Plant was built in 1957. Rehabilitation of this system will modernize the process and provide a more reliable system that will improve solids removal in the plant improving the quality of the discharge to the Delaware River.

Project Description

The proposed project includes rehabilitation of eight primary settling tanks, including all biosolids collection equipment; replacement of eight original pumps and piping; and installation of a new motor control system.

Anticipated Recipient	:	MEDFORD TOWNSHIP		
Project No.	:	340346-04	Eligible Project Cost:	$ 6,844,986
FY08 Rank	:	61		
County	:	BURLINGTON	Total State Amount :	$ 6,844,986

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	25

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	50

State Planning Commission	0.00000
Population	0.02225
BDA Points	0
Transit Villages	0
TOTAL POINTS	575.02225

Project Name, Number

MEDFORD TOWNSHIP
340346-04
STP IMPROVEMENTS

Priority List Rank

61

County

BURLINGTON

Existing Population

22,253

Service Area

Medford Township

Need for Project

The existing package aeration plants are incapable of producing effluent with significantly reduced phosphorous levels to achieve permit limitations.

Project Description

The proposed upgrade includes construction of two additional RBC treatment trains to replace the existing package aeration plants.

Anticipated Recipient	: JEFFERSON TOWNSHIP (ROCKAWAY)			
Project No.	: 340747-04	Eligible Project Cost:	$	6,526,216
FY08 Rank	: 62			
County	: MORRIS	Total State Amount :	$	6,526,216

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	200

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	50
Toxics	0	25	50	25
			Subtotal	125

State Planning Commission	0.00000
Population	0.00787
BDA Points	0
Transit Villages	0
TOTAL POINTS	575.00787

Project Name, Number

JEFFERSON TOWNSHIP (ROCKAWAY)
340747-04
COLLECTION SYSTEM

Priority List Rank

62

County

MORRIS

Existing Population

7,870

Service Area

Jefferson Township (Rockaway River Basin)

Need for Project

Some of the on-site systems that exist in the Rockaway River Basin of Jefferson Township have documented repeated failures. Most of the systems are failing due to shallow depth to bedrock, high water tables and steep slopes. Rehabilitation has been attempted on some systems but the results have been generally unsuccessful. Trout fishing and primary contact recreation uses of Russia Brook (FW2-TM) are adversely impacted due to the unacceptable levels of nutrients and marginally acceptable levels of toxics and fecal coliform. These facilities may pose serious health hazards in the future for the township if not corrected.

Project Description

This project includes the design and construction of a local wastewater system for the Rockaway River Basin portion of Jefferson Township. The recommended wastewater management plan for this portion of Jefferson Township consists of two major parts: 1) centralized sewer service for Cozy Lake, Lake Swannanoa and White Pine Lake area in the Rockaway Basin and 2) Septic Management for the remaining portions.

Anticipated Recipient	: HOWELL TWP MUA			
Project No.	: 340832-01	Eligible Project Cost:	$	5,877,522
FY08 Rank	: 63			
County	: MONMOUTH	Total State Amount :	$	5,877,522

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	75
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	0
	Subtotal	225

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	50
Nutrients	0	25	50	25
Toxics	0	25	50	25
			Subtotal	100
			State Planning Commission	0.00000
			Population	0.00192
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	575.00192

Project Name, Number

HOWELL TWP MUA
340832-01
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

63

County

MONMOUTH

Existing Population

1,920

Service Area

Howell Township

Need for Project

The Freewood Acres section of Howell Township is currently relying on on-site septic disposal systems for the treatment of wastewater. Many of these existing systems provide inadequate treatment, which has resulted in the degradation of Aldrich Lake. Aldrich Lake experiences high fecal coliform, toxics, and nutrients concentrations. Consequently, trout fishing, primary contact recreation, and farming are impacted.

Project Description

Preliminary investigations indicate that a collection system will need to be constructed in the planning area. The collection system will be connected via an interceptor into the Manasquan River Regional Sewerage Authority conveyance system for treatment and disposal.

Anticipated Recipient	: ESSEX UNION JOINT MEETING		
Project No.	: 340686-04	Eligible Project Cost:	$ 11,199,679
FY08 Rank	: 64		
County	: UNION	Total State Amount :	$ 11,199,679

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.47800
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	550.47800

Project Name, Number

ESSEX UNION JOINT MEETING
340686-04
STP IMPROVEMENTS

Priority List Rank

64

County

UNION

Existing Population

478,000

Service Area

16 communities in Essex and Union Counties

Need for Project

JMEUC operates a 75 mgd secondary sewage treatment plant. Due to recent experience with unreliable electric service, which resulted in violations, JMEUC proposes to install an on-site co-generation facility to ensure plant reliabilty.

Project Description

The proposed project includes installation of a co-generation power plant, which will serve as the primary power source at the JMEUC facilities.

Anticipated Recipient	:	GLOUCESTER COUNTY UA		
Project No.	:	340902-03	Eligible Project Cost:	$ 8,156,430
FY08 Rank	:	65		
County	:	GLOUCESTER	Total State Amount :	$ 8,156,430

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.20000
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	550.20000

Project Name, Number

GLOUCESTER COUNTY UA
340902-03
STP IMPROVEMENTS

Priority List Rank

65

County

GLOUCESTER

Existing Population

200,000

Service Area

Clayton Borough, Deptford Twp., Glassboro Borough, Mantua Twp., Monroe Twp., National Park Borough, Paulsboro Borough, Washington Twp., Wenonah Borough, W. Deptford Twp., Westville Borough, Woodbury City, and Woodbury Hts Borough

Need for Project

This project will replace aging clarifier equipment and mechanisms to increase aeration capacity, replace the primary switchgear, and install a new transformer for the electric blowers. The improvements will allow GCUA to adequately handle current flow and will increase the efficency and longevity of the treatment facilities.

Project Description

The proposed improvements to the treatment facility include the replacement of aging clarifier equipment, installation of additional electrical blowers for the aeration basin diffusers, and replacement of the existing primary switchgear with a new lineup consisting of double-ended switchgear with tie breaker.

Anticipated Recipient	: LONG BRANCH SA			
Project No.	: 340336-03	Eligible Project Cost:	$	1,553,702
FY08 Rank	: 66			
County	: MONMOUTH	Total State Amount :	$	1,553,702

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	125
Recreation(Primary Contact)	125	125
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	250

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	25
Toxics	0	25	50	0
			Subtotal	25

State Planning Commission	25.00000
Population	0.03000
BDA Points	0
Transit Villages	0
TOTAL POINTS	550.03000

Project Name, Number

LONG BRANCH SA
340336-03
CONVEYANCE FACILITIES, GRIT HANDLING

Priority List Rank

66

County

MONMOUTH

Existing Population

30,000

Service Area

City of Long Branch, Borough of West Long Branch (small portion)

Need for Project

The Long Branch Sewerage Authority is confronted with two wastewater treatment problems. The first problem is the insufficient useable capacity of the existing Joline Avenue Ocean Outfall (capacity 13 mgd). Under normal operation, the existing gravity sewer and outfall pumping station (capacity 8.5 mgd) provide adequate discharge capacity for the treated effluent. However, under emergency and peak flow conditions, an added capacity was formerly provided by a 14 inch force main connected to the North Broadway Ocean Outfall. In June of 1978, a coastal storm completely destroyed the North Broadway Outfall. Without replacement of the lost effluent capacity and with flows in excess of 8.5 mgd, the treatment units are at times overtopped, discharging partially treated wastewater. The second problem stems from the increased amount of grit and sand reaching the plant since the plant was designed. The grit and sand have caused extensive downtime to the primary settling tanks and, in addition, have caused excessive wear on the equipment. The overflow condition coupled with the inadequate secondary treatment caused by the extensive downtime of the primary settling tanks has a negative impact upon the intended uses (i.e, shellfish harvesting and recreation) of the coastal waters (SC) in this area.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Long Branch SA (NJ0024783)	5.4	4.6	94.3	12.7	94.2	12

Project Description

The project proposes to solve the effluent capacity problem by the construction of 3,500 feet of 20 inch force main between the existing treatment plant and the Joline Avenue Ocean Outfall. The force main will be used for emergency or peak flows in excess of the capacity of the Joline Ave. effluent facilities. Some modifications of the existing pumping facilities at the treatment plant will also be required. This scheme will allow the full 13 mgd capacity of the Joline Ave. Ocean Outfall to be utilized. The excessive grit and sand problem will be corrected by the construction of an appropriate grit removal facility. The completion of these projects will insure adequate secondary wastewater treatment within the Long Branch SA service area.

Anticipated Recipient	: LANDIS SA			
Project No.	: 340461-05	Eligible Project Cost:	$	3,603,428
FY08 Rank	: 67			
County	: CUMBERLAND	Total State Amount :	$	3,603,428

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.05478
BDA Points	0
Transit Villages	0
TOTAL POINTS	525.05478

Project Name, Number

LANDIS SA
340461-05
STP INFLUENT PS, GRIT CHAMBER

Priority List Rank

67

County

CUMBERLAND

Existing Population

54,780

Service Area

City of Vineland, part of Franklin Township and part of Pittsgrove Township

Need for Project

Facility was previously upgraded under a federal Construction Grant as Project No. C340461-02-2 and TWA SO-8-86-6073 without grit and scum removal. Under existing conditions, the influent flow is pumped twice and this is inefficient. The project will result in one central pumping facility with grit/scum removal which will improve the operational reliability of downstream treatment units.

Project Description

Construction of four (4) 60-inch diameter open flight screw pumps (archimedes screw) for a design flow of 12.2 MGD and peak of 24.3 MGD. Each screw capacity will be 8.1 MGD, with one unit as standby. Due to the efficiency of the screw pump, estimated power savings would be $10,000/yr. Metering will be by two Parshall flumes, chart recorded and mechanical barscreens. The grit/grease removal system will consist of a 3.2 x 36 meter grease removal channel and a 3.4 x 36 meter grit removal channel with the associated mechanical and aeration systems. A biofilter will be constructed to control odors from the proposed enclosed screw pumps as well as the headworks facility.

Anticipated Recipient	:	WESTERN MONMOUTH UA		
Project No.	:	340128-01	Eligible Project Cost:	$ 7,982,377
FY08 Rank	:	68		
County	:	MONMOUTH	Total State Amount :	$ 7,982,377

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	25

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.02500
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	525.02500

Project Name, Number

WESTERN MONMOUTH UA
340128-01
STP IMPROVEMENTS

Priority List Rank

68

County

MONMOUTH

Existing Population

25,000

Service Area

Townships of Manalapan and Marlboro, the Borough of Englishtown and a portion of the Township of Freehold

Need for Project

The capital improvement projects are necessitated to maintain continued operation of the existing treatment process and to minimize potential failure of treatment plant components. Failures could result in violations of WMUA’s NJPDES permit and may potentially cause a sewer discharge or surcharge of the system, which would impact the quality of the discharge stream and utimately affect the public.

Project Description

The proposed project includes removal of the existing bar screens and headworks equipment and replacement with a new concrete structure, screens, metering equipment and bypass system. Other projects include excavation and disposal of existing reed beds; replacement of existing pressure filter media and valve sytem; replacement of aeration system blowers and associated appurtenances with new blowers, variable frequency drives and additional dissolved oxygen sensors; repair of existing digester #1’s cover; and replacement of transfer switches and main control panel.

Anticipated Recipient	: PATERSON CITY		
Project No.	: 340850-01	Eligible Project Cost:	$ 28,256,876
FY08 Rank	: 69		
County	: PASSAIC	Total State Amount :	$ 28,256,876

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.14922
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.14922

Project Name, Number

PATERSON CITY
340850-01
I/I CORRECTION

Priority List Rank

69

County

PASSAIC

Existing Population

149,222

Service Area

City of Paterson

Need for Project

A sewer system evaluation survey recently performed by Elson T. Killam Associates for the Passaic Valley Sewerage Commissioners' service area found excessive infiltration/inflow (I/I) in this municipality's sewer system.

Project Description

An Infiltration/Inflow correction program, which will consist of grouting slip lining, and repairing/replacing structurally damaged pipes and manholes will be undertaken to remove the identified excessive I/I.

Anticipated Recipient	: CAMDEN CITY			
Project No.	: 340366-03	Eligible Project Cost:	$	22,131
FY08 Rank	: 70			
County	: CAMDEN	Total State Amount :	$	22,131

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.08700
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.08700

Project Name, Number

CAMDEN CITY
340366-03
PS REHABILITATION

Priority List Rank

70

County

CAMDEN

Existing Population

87,000

Service Area

City of Camden

Need for Project

The City has identified a need to replace the existing inoperative pneumatic air ejector pump station with a new station utilizing submersible pumps.

Project Description

The proposed project consists of the purchase and installation of the necessary equipment to replace the existing lift station.

Anticipated Recipient	: TRENTON CITY			
Project No.	: 340416-12	Eligible Project Cost:	$	2,718,518
FY08 Rank	: 71			
County	: MERCER	Total State Amount :	$	2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.08540
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.08540

Project Name, Number

TRENTON CITY
340416-12
SEWER REHABILITATION

Priority List Rank

71

County

MERCER

Existing Population

85,403

Service Area

City of Trenton

Need for Project

The City of Trenton's brick sewers date back to the 1800's. They are in dire need of repair and are subject to exfiltration, which threatens the quality of the surrounding groundwater.

Project Description

The City proposes to line and stabilize deteriorated brick using various trenchless rehabilitation processes.

Anticipated Recipient	:	CAMDEN CITY		
Project No.	:	340366-07	Eligible Project Cost:	$ 3,229,626
FY08 Rank	:	72		
County	:	CAMDEN	Total State Amount :	$ 3,229,626

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.07990
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.07990

Project Name, Number

CAMDEN CITY
340366-07
SEWER REHABILITATION

Priority List Rank

72

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

The City has determined through inspection and assessment that most of the City’s sanitary sewers need to be reconstructed.

Project Description

The proposed project consists of the reconstruction or replacement of sewer lines throughout the City.

Anticipated Recipient	:	CAMDEN CITY		
Project No.	:	340366-08	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	72		
County	:	CAMDEN	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.07990
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.07990

Project Name, Number

CAMDEN CITY
340366-08
SEWER REPLACEMENT

Priority List Rank

72

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

An existing sewer located under a building is improperly situated and is failing structurally.

Project Description

The proposed project includes the filling and abandonment of the existing 36-inch sanitary sewer. A new 36-inch sewer of 1490 LF will be constructed within existing easements acquired by the City of Camden and designed to circumvent the building so as not to interfere with maintenance activities.

Anticipated Recipient	: NORTH BERGEN TOWNSHIP			
Project No.	: 340652-07	Eligible Project Cost:	$	639,645
FY08 Rank	: 74			
County	: HUDSON	Total State Amount :	$	639,645

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.05809
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.05809

Project Name, Number

NORTH BERGEN TOWNSHIP
340652-07
SEWER REHABILITATION

Priority List Rank

74

County

HUDSON

Existing Population

58,092

Service Area

Township of North Bergen

Need for Project

The Township's combined sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the combined system. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the combined system.

Anticipated Recipient :	PARSIPPANY-TROY HILLS TOWNSHIP		
Project No. :	340806-04	Eligible Project Cost:	$ 10,833,981
FY08 Rank :	75		
County :	MORRIS	Total State Amount :	$ 10,833,981

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.05065
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.05065

Project Name, Number

PARSIPPANY-TROY HILLS TOWNSHIP
340806-04
PHOTOVOLTAIC SYSTEM

Priority List Rank

75

County

MORRIS

Existing Population

50,649

Service Area

Denville Township, East Hanover Township, Montville Township, Mountain Lakes Borough, Parsippany-Troy Hills Township

Need for Project

The Parsippany-Troy Hills wastewater treatment plant treats sanitary sewer discharges prior to surface water discharge. This proposed project is intended to reduce the Township’s reliance on conventional electric power generation methods by substituting a sustainable alternative source of power for the treatment plant, which will result in environmental benefits not only in improved water quality but also improving air quality and less reliance on natural resources.

Project Description

The proposed projct includes design and construction of a photovoltaic power system to provide energy to the wastewater treatment plant.

Anticipated Recipient	: KEARNY MUA			
Project No.	: 340259-06	Eligible Project Cost:	$	5,308,104
FY08 Rank	: 76			
County	: HUDSON	Total State Amount :	$	5,308,104

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.04051
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.04051

Project Name, Number

KEARNY MUA
340259-06
PUMP STATION, FORCE MAIN

Priority List Rank

76

County

HUDSON

Existing Population

40,513

Service Area

Town of Kearny

Need for Project

The Bergen Avenue Pumping Station will serve the western portion of the KMUA Meadowlands Sewer District. The pumping station will collect leachate from the Keegan Landfill and serve existing development. The Harrison Avenue Force Main will serve the Bergen Avenue Pumping Station and the proposed MSLA 1-D Landfill Pumping Station, which will allow for the closure of the landfill.

Project Description

The construction of the Bergen Avenue Pumping Station includes construction of a control and generator building, a triplex wet well, manholes, sewage grinder manhole, two metering vaults, a valve chamber, installation of a flow meter, a sewage grinder, site piping, an instrumentation shelter and three submersible pumps. The Harrison Avenue Force Main project includes placing approximately 7,600 linear feet of 8″ diameter HDPE pipe from the future Bergen Avenue Pumping Station to the existing Harrison Avenue Pumping Station. The other portion of the project includes installing approximately 200 linear feet of 6″ HDPE pipe from the new MSLA 1-D Pumping Station to a tie-in point with the Harrison Avenue Force Main.

Anticipated Recipient	: SALEM COUNTY BOARD OF FREEHOLDERS		
Project No.	: 340804-04	Eligible Project Cost:	$ 18,263,633
FY08 Rank	: 77		
County	: SALEM	Total State Amount :	$ 18,263,633

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01829
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.01829

Project Name, Number

SALEM COUNTY BOARD OF FREEHOLDERS
340804-04
STP

Priority List Rank

77

County

SALEM

Existing Population

18,291

Service Area

Carney's Point Township, Oldmans Township, Penns Grove Borough, Pilesgrove Township

Need for Project

Salem County is proposing to modify two existing treatment plants and convey the flows from four communities to the DuPont treatment plant.

Project Description

The proposed project includes the modification of existing treatment facilities, construction of new pump stations, and installation of wastewater conveyance systems to transport wastewater from all four muncipalities to the DuPont wastewater treatment facility.

Anticipated Recipient	:	ASBURY PARK CITY		
Project No.	:	340884-01	Eligible Project Cost:	$ 1,897,200
FY08 Rank	:	78		
County	:	MONMOUTH	Total State Amount :	$ 1,897,200

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01701
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.01701

Project Name, Number

ASBURY PARK CITY
340884-01
I/I CORRECTION

Priority List Rank

78

County

MONMOUTH

Existing Population

17,010

Service Area

Asbury Park City

Need for Project

The existing collection system consists of vitrified clay pipes with leaky joints. A large portion of the piping may be cracked, leading to infiltration.

Project Description

The project consists of replacement of a major portion of the collection system.

Anticipated Recipient	:	HACKETTSTOWN MUA		
Project No.	:	340803-04	Eligible Project Cost:	$ 1,411,500
FY08 Rank	:	79		
County	:	WARREN	Total State Amount :	$ 1,411,500

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01040
BDA Points	0
Transit Villages	0
TOTAL POINTS	500.01040

Project Name, Number

HACKETTSTOWN MUA
340803-04
TREATMENT PLANT ABANDONMENT

Priority List Rank

79

County

WARREN

Existing Population

10,403

Service Area

Hackettstown Town, Independence Township

Need for Project

HMUA has been ordered to takeover the Diamond Hill Sewer Company and close its treatment plant.

Project Description

The proposed project includes construction of gravity sewers and a force main along with a pump station upgrade to allow all wastewater in the Diamond Hill service area to be conveyed to the HMUA wastewater collection system.

Anticipated Recipient :	LOGAN TOWNSHIP MUA		
Project No. :	340123-01	Eligible Project Cost:	$ 17,350,281
FY08 Rank :	80		
County :	GLOUCESTER	Total State Amount :	$ 17,350,281

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	500
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	500

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00603
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	500.00603

Project Name, Number

LOGAN TOWNSHIP MUA
340123-01
STP EXPANSION

Priority List Rank

80

County

GLOUCESTER

Existing Population

6,032

Service Area

Logan Township and a portion of Woolwich Township

Need for Project

The expansion of the LTMUA Water Reclamation Facility is intended to provide additional capacity for planned residentual development in the service area, consistent with the Wastewater Management Plan and to insure that the facility continues to meet established NJPDES permit limits.

Project Description

The proposed improvements to the treatment facility include construction of a membrane bioreactor, a new headworks facility, a new UV disinfection system, and an additional rotary drum thickener. The effluent pumping station will be upgraded and instrumentation and electrical upgrades including a new emergency generator will be installed.

Anticipated Recipient	: MORRISTOWN TOWN			
Project No.	: 340376-04	Eligible Project Cost:	$	8,621,779
FY08 Rank	: 81			
County	: MORRIS	Total State Amount :	$	8,621,779

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.01679
BDA Points	0
Transit Villages	10
TOTAL POINTS	485.01679

Project Name, Number

MORRISTOWN TOWN
340376-04
I/I CORRECTION

Priority List Rank

81

County

MORRIS

Existing Population

16,790

Service Area

Town of Morristown

Need for Project

An Infiltration/Inflow (I/I) analysis has concluded that excessive I/I exists within the town's sewer system. Additional studies are underway to further define the quantity of excessive I/I and to propose an I/I correction program to eliminate a portion of the excessive I/I.

Project Description

This proposed project will be for the minor rehabilitation of sections of sanitary sewer pipe, grouting of sewer lines, grouting and sealing leaking manholes and repair or adjustments of defective manholes.

Anticipated Recipient	:	PRINCETON SOC		
Project No.	:	340656-05	Eligible Project Cost:	$ 4,633,901
FY08 Rank	:	82		
County	:	MERCER	Total State Amount :	$ 4,633,901

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.03023
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.03023

Project Name, Number

PRINCETON SOC
340656-05
SEWER REHABILITATION

Priority List Rank

82

County

MERCER

Existing Population

30,230

Service Area

Princeton Township, Princeton Borough

Need for Project

Rehabilitation of the collection system will reduce the amount of extraneous flow that must be conveyed to the Stony Brook STP.

Project Description

The proposed project includes the rehabilitation and/or replacement of sanitary sewer mains and laterals in addition to the replacement of two major pieces of equipment used to operate and maintain the sewer system.

Anticipated Recipient	: LONG BRANCH SA			
Project No.	: 340336-05	Eligible Project Cost:	$	1,396,910
FY08 Rank	: 83			
County	: MONMOUTH	Total State Amount :	$	1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.02866
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.02866

Project Name, Number

LONG BRANCH SA
340336-05
I/C ABATEMENT

Priority List Rank

83

County

MONMOUTH

Existing Population

28,660

Service Area

City of Long Branch

Need for Project

To reduce elevated levels of bacteria in stormwater discharges to coastal waters.

Project Description

To eliminate cross-connections between sanitary and storm sewers by replacing portions of sewers, sealing manholes, and sealing leaks. To eliminate interconnections due to leaks, flows, or overflows from the sanitary sewer system.

Anticipated Recipient	: DOVER TOWN			
Project No.	: 340889-01	Eligible Project Cost:	$	935,648
FY08 Rank	: 84			
County	: MORRIS	Total State Amount :	$	935,648

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.01441
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.01441

Project Name, Number

DOVER TOWN
340889-01
I/I CORRECTION

Priority List Rank

84

County

MORRIS

Existing Population

14,410

Service Area

Town of Dover

Need for Project

The Rockaway Valley Regional Sewerage Authority Infiltration/Inflow (I/I) Analysis and Sewer System Evaluation Survey identified excessive I/I in this municipality's sewer system.

Project Description

The excessive I/I will be removed by grouting, slip lining, and other minor rehabilitation procedures.

Anticipated Recipient	: METUCHEN BOROUGH			
Project No.	: 340360-01	Eligible Project Cost:	$	3,734,892
FY08 Rank	: 85			
County	: MIDDLESEX	Total State Amount :	$	3,734,892

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01280
BDA Points	0
Transit Villages	10
TOTAL POINTS	475.01280

Project Name, Number

METUCHEN BOROUGH
340360-01
I/I CORRECTION

Priority List Rank

85

County

MIDDLESEX

Existing Population

12,800

Service Area

Borough of Metuchen

Need for Project

A report prepared by Middlesex County Utilities Authority in 1981 indicates that the Borough experiences excessive quantities of infiltration and inflow in its sanitary sewer system resulting in capacity problems and high sewer bills and that cost-effective rehabilitation is warranted.

Project Description

Sanitary sewer system rehabilitation measures include, but are not limited to, testing and sealing, repairing laterals, spot repairs, manhole repairs and pipe lining or replacement.

Anticipated Recipient	: BOUND BROOK BOROUGH			
Project No.	: 340295-01	Eligible Project Cost:	$	218,940
FY08 Rank	: 86			
County	: SOMERSET	Total State Amount :	$	218,940

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01016
BDA Points	0
Transit Villages	10
TOTAL POINTS	475.01016

Project Name, Number

BOUND BROOK BOROUGH
340295-01
SEWER REHABILITATION

Priority List Rank

86

County

SOMERSET

Existing Population

10,155

Service Area

Borough of Bound Brook

Need for Project

The clay tile mains on Vosseller Ave., Union Ave., Church St., Wahnetah Dr., and Watchung Rd. leak at the joints causing infiltration during wet weather and exfiltration during dry weather, which seaps into the Raritan River.

Project Description

The proposed project includes replacing the existing mains, manholes, and laterals to the right-of-way.

Anticipated Recipient	:	WILDWOOD CITY		
Project No.	:	340664-03	Eligible Project Cost:	$ 3,032,199
FY08 Rank	:	87		
County	:	CAPE MAY	Total State Amount :	$ 3,032,199

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00544
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.00544

Project Name, Number

WILDWOOD CITY
340664-03
SEWER REHABILITATION

Priority List Rank

87

County

CAPE MAY

Existing Population

5,436

Service Area

City of Wildwood

Need for Project

The existing collection system serving the City is very old, and is subject to an extreme amount of I/I. Rehabilitation of the entire sanitary sewer system is necessary to prevent groundwater from seeping in and sewage from seeping into the groundwater.

Project Description

This proposed project will be for an I/I correction program to eliminate the portion of I/I that is excessive and detrimental to the existing collection system. In some cases minor replacement may be necessary.

Anticipated Recipient	:	WILDWOOD CREST BOROUGH		
Project No.	:	340719-02	Eligible Project Cost:	$ 4,653,327
FY08 Rank	:	88		
County	:	CAPE MAY	Total State Amount :	$ 4,653,327

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00398
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.00398

Project Name, Number

WILDWOOD CREST BOROUGH
340719-02
SEWER REHABILITATION

Priority List Rank

88

County

CAPE MAY

Existing Population

3,980

Service Area

Borough of Wildwood Crest

Need for Project

The Borough has been experiencing pipe collapses plus other problems due to undersized, tuberculated pipes. Groundwater is infiltrating into the lines and untreated sewage is leaching into groundwater.

Project Description

The proposed project includes the replacement of vitrified clay pipes.

Anticipated Recipient	: WEST WILDWOOD BOROUGH			
Project No.	: 340626-03	Eligible Project Cost:	$	564,453
FY08 Rank	: 89			
County	: CAPE MAY	Total State Amount :	$	564,453

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00037
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.00037

Project Name, Number

WEST WILDWOOD BOROUGH
340626-03
I/I CORRECTION

Priority List Rank

89

County

CAPE MAY

Existing Population

370

Service Area

West Wildwood Borough

Need for Project

The West Wildwood sewer collection system is possibly subjected to excessive amounts of infiltration/inflow. Extensive use of six inch diameter pipes, very flat slopes, high groundwater, grease and detergent buildups as well as sand infiltration all contribute to the excessive I/I.

Project Description

The rehabilitation measures proposed in alleviating the excessive I/I and unclogging the system include: cleaning, internal inspection, repair and/or replacement of damaged or deteriorated sewer pipe, manholes and house laterals.

Anticipated Recipient	:	MILLVILLE CITY		
Project No.	:	340921-04	Eligible Project Cost:	$ 8,557,247
FY08 Rank	:	90		
County	:	CUMBERLAND	Total State Amount :	$ 8,557,247

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00000
BDA Points	0
Transit Villages	0
TOTAL POINTS	475.00000

Project Name, Number

MILLVILLE CITY
340921-04
I/I CORRECTION, COLLECTION SYSTEM

Priority List Rank

90

County

CUMBERLAND

Existing Population

0

Service Area

City of Millville

Need for Project

A sewer system evaluation survey performed by the Millville Wastewater Utility (MWU) found that their 100 year old collection sytem has various structural, maintenance and excessive I/I problems. Repair and/or replacement is urgently needed.

Project Description

The project involves the rehabilitation of the Columbia Avenue force main, the Marlyn, Westwood Terrace, Rt. 49, Rieck Avenue main extension, the Rt. 47, Orange Street, Gorton Road main upgrade, the Ireland Avenue Pump Station Replacement and the hydraulic main upgrade from Ireland Avenue to the West Side Pump station.

Anticipated Recipient	:	CINNAMINSON SA		
Project No.	:	340170-03	Eligible Project Cost:	$ 2,250,375
FY08 Rank	:	91		
County	:	BURLINGTON	Total State Amount :	$ 2,250,375

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01460
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.01460

Project Name, Number

CINNAMINSON SA
340170-03
PUMP STATION & FORCE MAIN UPGRADE

Priority List Rank

91

County

BURLINGTON

Existing Population

14,595

Service Area

Township of Cinnaminson

Need for Project

The existing forty-year old asbestos cement force main has failed in places creating a discharge of untreated sewage to grounwater and to Pompeston Creek. Rehabilitating the force main will restore the structural integrity and prevent raw sewage discharges. Installation of a six-inch force main will allow for the distribution of reclaimed water from the Authority’s treatment plant to the Riverton Country Club. Rehabilitation of the pumping station will increase the reliabilty of the 50 year old facility.

Project Description

The project includes lining or replacement of 3,500 feet of eigteen inch asbestos cement sanitary sewer force main and installation of a six-inch force main in the same trench to complete the pipeline from the Authority’s treatment plant to the Riverton Country Club. Improvements to the Highland Avenue Pump Station include replacement of pumps, screening equipment, electrical controls and safety equipment.

Anticipated Recipient	: TOTOWA BOROUGH			
Project No.	: 340778-01	Eligible Project Cost:	$	985,189
FY08 Rank	: 92			
County	: PASSAIC	Total State Amount :	$	985,189

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01119
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.01119

Project Name, Number

TOTOWA BOROUGH
340778-01
I/I CORRECTION

Priority List Rank

92

County

PASSAIC

Existing Population

11,190

Service Area

Totowa Borough

Need for Project

The Township's sewer system contains excessive infiltration/inflow (I/I) as documented by the I/I analysis. Additional studies will estimate the quantity of I/I in the system to eliminate a portion of excessive I/I.

Project Description

This project is for the I/I correction of Totowa Borough's existing sewer system to eliminate a portion of infiltration/inflow that is excessive. The project will be for the minor rehabilitation of sections of sanitary sewer pipe including grouting, sealing, and repair of defective manholes.

Anticipated Recipient	: FREEHOLD BOROUGH			
Project No.	: 340304-02	Eligible Project Cost:	$	430,399
FY08 Rank	: 93			
County	: MONMOUTH	Total State Amount :	$	430,399

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01098
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.01098

Project Name, Number

FREEHOLD BOROUGH
340304-02
SEWER REHABILITATION

Priority List Rank

93

County

MONMOUTH

Existing Population

10,976

Service Area

Borough of Freehold

Need for Project

The Borough’s gravity sewer system is over 50 years old and experiences I/I within the system.

Project Description

This proposed project may include the grouting and sealing of leaking manholes and sewer lines, repair or adjustments of defective manhole covers, and other minor rehabilitation measures.

Anticipated Recipient	: BURLINGTON CITY			
Project No.	: 340712-07	Eligible Project Cost:	$	7,012,292
FY08 Rank	: 94			
County	: BURLINGTON	Total State Amount :	$	7,012,292

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00974
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.00974

Project Name, Number

BURLINGTON CITY
340712-07
SEWER REHABILITATION, PUMP STATION

Priority List Rank

94

County

BURLINGTON

Existing Population

9,736

Service Area

City of Burlington

Need for Project

The sanitary sewer collection system of thr City of Burlington is substantially deteriorated allowing large amounts of infiltration and ex-filtration. The Mitchell Avenue Pump Station has numerous deficiencies. Foremost, is an insufficient wetwell that causes surcharging and raw sewage releases. Also, the inverted siphon has recently ruptured causing a raw sewage release to the Assicunk Creek and though it has been repaired it needs to be replaced due to its age and condition.

Project Description

The proposed project includes heavy cleaning, grouting, spot lining, and television inspection of untelevised lines in the City, this will be followed by lining and small excavated repairs to facilitate lining. The Mitchell Avenue Pump Station project will include decommissioning of the existing pump station and construction of a new pump station and force main replacing the existing pump station and eliminating an inverted siphon crossing the creek.

Anticipated Recipient	:	BERNARDSVILLE BOROUGH		
Project No.	:	340816-03	Eligible Project Cost:	$ 1,135,113
FY08 Rank	:	95		
County	:	SOMERSET	Total State Amount :	$ 1,135,113

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00668
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.00668

Project Name, Number

BERNARDSVILLE BOROUGH
340816-03
I/I CORRECTION

Priority List Rank

95

County

SOMERSET

Existing Population

6,680

Service Area

Borough of Bernardsville

Need for Project

Based on an infiltration/inflow analysis sponsored by the Somerset County Planning Board, the Upper Raritan Watershed Wastewater Facilities Plan recommends a Sewer System Evaluation Survey (SSES) be performed on the Bernardsville sewer system.

Project Description

The SSES will include a physical survey of the Bernardsville sewer system, including manhole inspections and flow inspection (measurement of sewage flows in isolated reaches of pipe), rainfall simulation and smoke testing, building inspection of units suspected of contributing inflow to the sanitary sewers, and television inspection. I/I correction in accordance with the recommendations of the SSES will follow.

Anticipated Recipient	:	MANASQUAN BOROUGH		
Project No.	:	340911-01	Eligible Project Cost:	$ 6,093,106
FY08 Rank	:	96		
County	:	MONMOUTH	Total State Amount :	$ 6,093,106

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00534
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.00534

Project Name, Number

MANASQUAN BOROUGH
340911-01
SEWER REHABILITATION

Priority List Rank

96

County

MONMOUTH

Existing Population

5,340

Service Area

Borough of Manasquan

Need for Project

The existing sanitary sewer system consists of 80-year old terra cotta pipes, many of which are 6-inches in diameter. Many of the pipes are cracked, have broken joints, and deteriorated manholes. The Borough is located in a coastal area and often experiences high groundwater conditions.

Project Description

The project consists of the repair/replacement of several sections of the Borough's sewer system.

Anticipated Recipient	:	SOUTH BOUND BROOK BOROUGH		
Project No.	:	340347-01	Eligible Project Cost:	$ 1,239,434
FY08 Rank	:	97		
County	:	SOMERSET	Total State Amount :	$ 1,239,434

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00350
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.00350

Project Name, Number

SOUTH BOUND BROOK BOROUGH
340347-01
INTERCEPTOR

Priority List Rank

97

County

SOMERSET

Existing Population

3,500

Service Area

South Bound Brook Borough (West of Cedar Street to border of Borough).

Need for Project

The project is needed to reduce or eliminate sanitary sewer overflows in the Borough. The overflow into the Raritan Delaware Canal occurs periodically.

Project Description

The proposed project includes the construction of a relief sewer line to handle sewage from the overflow problem areas and direct the additional sewage to the regional Sewage Treatment Plant for treatment.

Anticipated Recipient	: AVALON BOROUGH			
Project No.	: 340864-01	Eligible Project Cost:	$	1,530,125
FY08 Rank	: 98			
County	: CAPE MAY	Total State Amount :	$	1,530,125

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00181
BDA Points	0
Transit Villages	0
TOTAL POINTS	465.00181

Project Name, Number

AVALON BOROUGH
340864-01
I/I CORRECTION

Priority List Rank

98

County

CAPE MAY

Existing Population

1,810

Service Area

Avalon Borough

Need for Project

Infiltration/Inflow (I/I) studies conducted have revealed that the Borough Sanitary Sewer System is possibly subject to excessive I/I. Sanitary sewer lines are in excess of 80 years old. The leaking joints have caused sinkhole problems, accelerated street deterioration and excessive infiltration/inflow. Additional work is needed on the stormwater sewer system as well.

Project Description

The Borough proposes to replace the existing deteriorated sanitary sewer lines, service laterals and storm sewer lines including: refurbishing approximately 500 sanitary sewer manholes, relining the influent sewer line at the 23rd Street Pump Station, replacing sanitary lines on Heron Drive, Pelican Drive and the Business District, replacing storm lines in the Business District and replace/relocate 11th Street Pump Station and stormwater outfall.

Anticipated Recipient	: CRANFORD TOWNSHIP			
Project No.	: 340858-01	Eligible Project Cost:	$	629,918
FY08 Rank	: 99			
County	: UNION	Total State Amount :	$	629,918

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02408
BDA Points	0
Transit Villages	10
TOTAL POINTS	460.02408

Project Name, Number

CRANFORD TOWNSHIP
340858-01
I/I CORRECTION

Priority List Rank

99

County

UNION

Existing Population

24,080

Service Area

Township of Cranford

Need for Project

To eliminate excessive infiltration in approximately 4,950' of 8" gravity sanitary sewer serving the Township. The Township's system is serviced by the Rahway Valley Regional Sewerage Authority.

Project Description

The project will consist of I/I correction for 4,950' of gravity sanitary sewer (cleaning, lining joint repair).

Anticipated Recipient	: PLEASANTVILLE CITY			
Project No.	: 340752-01	Eligible Project Cost:	$	220,365
FY08 Rank	: 100			
County	: ATLANTIC	Total State Amount :	$	220,365

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01437
BDA Points	0
Transit Villages	10
TOTAL POINTS	460.01437

Project Name, Number

PLEASANTVILLE CITY
340752-01
I/I CORRECTION

Priority List Rank

100

County

ATLANTIC

Existing Population

14,370

Service Area

The service area includes the City of Pleasantville. This is a bayfront community located approximately ten miles west of the Atlantic County coastal wastewater treatment plant.

Need for Project

The wastewater collection system of Pleasantville was originally constructed in 1945, with new extensions added periodically. It consists of 294,684 linear feet of terra cotta, vitrified clay and cast iron pipe. The SSES investigation determined that the system was experiencing an average of 339,120 gpd of infiltration from a total of 37,585 linear feet of pipe.

Project Description

This project entails I/I correction of the sewer system of Pleasantville City.

Anticipated Recipient	: MATAWAN BOROUGH			
Project No.	: 340967-01	Eligible Project Cost:	$	708,917
FY08 Rank	: 101			
County	: MONMOUTH	Total State Amount :	$	708,917

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00927
BDA Points	0
Transit Villages	10
TOTAL POINTS	460.00927

Project Name, Number

MATAWAN BOROUGH
340967-01
I/I CORRECTION

Priority List Rank

101

County

MONMOUTH

Existing Population

9,270

Service Area

Matawan

Need for Project

To reduce elevated levels of bacteria in stormwater discharges to coastal waters.

Project Description

To eliminate cross-connections between sanitary and storm sewers by replacing portions of sewers, sealing manholes, and sealing leaks. To eliminate interconnections due to leaks, flows, or overflows from the sanitary sewer system.

Anticipated Recipient	: SOUTH AMBOY CITY			
Project No.	: 340326-06	Eligible Project Cost:	$	244,515
FY08 Rank	: 102			
County	: MIDDLESEX	Total State Amount :	$	244,515

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00784
BDA Points	0
Transit Villages	10
TOTAL POINTS	460.00784

Project Name, Number

SOUTH AMBOY CITY
340326-06
I/I CORRECTION

Priority List Rank

102

County

MIDDLESEX

Existing Population

7,840

Service Area

City of South Amboy

Need for Project

The sewer systems in the City of South Amboy, constructed prior to the use of secondary treatment methods, did not set strict limits on the volume of infiltration and inflow within sanitary sewers since treatment costs were not greatly affected by these extraneous flows. However, in recent years, the construction costs of conveyance facilities, coupled with rising treatment costs associated with secondary treatment methods, have resulted in efforts to eliminate infiltration and inflow in areas where it is proven to be cost-effective.

Project Description

The proposed project is to provide I/I correction for South Amboy's existing sewer system.

Anticipated Recipient	:	OCEAN COUNTY UA		
Project No.	:	340372-34	Eligible Project Cost:	$ 8,234,403
FY08 Rank	:	103		
County	:	OCEAN	Total State Amount :	$ 8,234,403

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.59999
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.59999

Project Name, Number

OCEAN COUNTY UA
340372-34
INTERCEPTOR REHABILITATION & PS IMPROVEMENTS

Priority List Rank

103

County

OCEAN

Existing Population

599,994

Service Area

Ocean County

Need for Project

Concrete interceptor pipes ranging in size from 24″ to 54″ were constructed in the 1970s and are deteriorating due to hydrogen sulfide attack. The pump station improvement will enhance the Authority’s ability to collect and convey wastewater treatment.

Project Description

The proposed project includes the relining of 1250 feet of 60-inch RCP, and replacement of 50 feet 60-inch RCP, manhole rehabilitation and relining 6,230 feet of 36-inch RCP, and relining 4,200 feet of 8-inch and relining 4,200 feet of 12-inch DIP force main. Rehabilitation at Southern Pump Stations 1,2,3,4,5,6,7,10,12, and 13 includes concrete repairs and coatings, stair and grating replacements, roof replacements, and bubbler system improvements.

Anticipated Recipient	: OCEAN COUNTY UA			
Project No.	: 340372-35	Eligible Project Cost:	$	570,013
FY08 Rank	: 103			
County	: OCEAN	Total State Amount :	$	570,013

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.59999
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.59999

Project Name, Number

OCEAN COUNTY UA
340372-35
SPREAD SPECTRUM RADIO SYSTEM EXPANSION

Priority List Rank

103

County

OCEAN

Existing Population

599,994

Service Area

17 municipalities in central Ocean County

Need for Project

The project involves the replacement of the telephone leased-line system with Spread Spectrum Radio equipment to provide Supervisory Control and Data Acquisition communications between 36 of OCUA’s pump stations and their respective Water Pollution Control Facility.

Project Description

The proposed project includes installation of SSR repeater systems on existing Ocean County communication towers, installation of SSR equipment at the SWPCF and NWPCF, and expansion of the existing SSR equipment at the CWPCF.

Anticipated Recipient :	CAMDEN COUNTY MUA		
Project No. :	340709-02	Eligible Project Cost:	$ 15,673,755
FY08 Rank :	105		
County :	CAMDEN	Total State Amount :	$ 15,673,755

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.50893
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.50893

Project Name, Number

CAMDEN COUNTY MUA
340709-02
I/I CORRECTION

Priority List Rank

105

County

CAMDEN

Existing Population

508,932

Service Area

Entire service area of CCMUA

Need for Project

Several portions of the service area are suspected of being subject to excessive I/I.

Project Description

The proposed project consists of implementing the necessary measures to eliminate excessive I/I, including replacement, grouting and other measures.

Anticipated Recipient	:	MIDDLESEX COUNTY UA		
Project No.	:	340637-04	Eligible Project Cost:	$ 20,043,531
FY08 Rank	:	106		
County	:	MIDDLESEX	Total State Amount :	$ 20,043,531

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.49657
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.49657

Project Name, Number

MIDDLESEX COUNTY UA
340637-04
I/I CORRECTION

Priority List Rank

106

County

MIDDLESEX

Existing Population

496,570

Service Area

Borough of Bound Brook, East Brunswick Sewerage Authority, Township of Edison, Franklin Township Sewerage Authority, Township of Greenbrook, Borough of Highland Park, Borough of Metuchen, Borough of Middlesex, Monroe Township, City of New Brunswick, Borough of Milltown, Township of North Brunswick, Township of Piscataway, Borough of North Plainfield, Borough of Watchung, Township of Scotch Plains, City of Plainfield, Borough of South Bound Brook, Township of South Brunswick, Borough of South Plainfield, Borough of South River, Borough of Spotswood, Borough of Dunellen, Borough of Fanwood

Need for Project

Design capacities of sewer systems constructed prior to the use of secondary treatment methods did not set strict limits on the volume of infiltration and inflow within sanitary sewers since treatment costs were not greatly affected by these extraneous flows. In recent times, however, construction costs of conveyance facilities coupled with rising treatment costs associated with secondary treatment methods have resulted in efforts to eliminate infiltration and inflow in areas where it is proven to be cost-effective.

Project Description

The proposed project is for an Infiltration/Inflow correction program for the MCUA existing sewer systems which currently serve 26 municipalities and 10 direct industries encompassing approximately 350 square miles of densely populated and highly industrialized areas.

Anticipated Recipient	: BERGEN COUNTY UA		
Project No.	: 340768-02	Eligible Project Cost:	$ 15,673,755
FY08 Rank	: 107		
County	: BERGEN	Total State Amount :	$ 15,673,755

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.49114
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.49114

Project Name, Number

BERGEN COUNTY UA
340768-02
I/I CORRECTION

Priority List Rank

107

County

BERGEN

Existing Population

491,140

Service Area

The BCUA currently serves 46 municipalities.

Need for Project

BCUA conducted an Infiltration/Inflow(I/I) analysis and concluded that excessive I/I existed in the sewer system. Additional studies are underway to further define the quantity of excessive I/I and to propose an Infiltration/Inflow correction program to eliminate a portion of the excessive I/I.

Project Description

This proposed project may include the cleaning, grouting and sealing of leaking manholes and sewer lines, and other minor rehabilitation measures.

Anticipated Recipient	:	RAHWAY VALLEY SA		
Project No.	:	340547-03	Eligible Project Cost:	$ 5,938,953
FY08 Rank	:	108		
County	:	UNION	Total State Amount :	$ 5,938,953

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.25000
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.25000

Project Name, Number

RAHWAY VALLEY SA
340547-03
I/I CORRECTION

Priority List Rank

108

County

UNION

Existing Population

250,000

Service Area

Springfield, Mountainside, Westfield, Kenilworth, Winfield, Garwood, Cranford, Roselle Park (part), Scotch Plains, Clark, Woodbridge (part) and Rahway

Need for Project

To eliminate excessive infiltration and inflow and to extend the useful life of the sewer.

Project Description

RVSA operates a 35 mgd secondary sewage treatment facility with a sewer configuration 300 miles in length. The I/I report indicates that the RVSA's sewer system is susceptible to an excessive I/I of 3 mgd which may be cost-effectively removed. This will be verified in the upcoming SSES phase. An Infiltration/Inflow correction program will follow thereafter.

Anticipated Recipient	:	RAHWAY VALLEY SA		
Project No.	:	340547-08	Eligible Project Cost:	$ 1,713,312
FY08 Rank	:	108		
County	:	UNION	Total State Amount :	$ 1,713,312

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.25000
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.25000

Project Name, Number

RAHWAY VALLEY SA
340547-08
SEWER REHABILITATION

Priority List Rank

108

County

UNION

Existing Population

250,000

Service Area

Springfield, Mountainside, Westfield, Kenilworth, Winfield, Garwood, Cranford, Roselle Park (part), Scotch Plains, Clark, Woodbridge (part) and Rahway

Need for Project

The proposed project will restore the structural integrity and hydraulic capacity of approximately 1400 lin. ft. of 60-inch diameter reinforced concrete pipe that has become deteriorated due to the presence of hydrogen sulfide gas.

Project Description

The proposed project includes the cleaning and removal of debris from the pipe, by-pass pumping, installation of a 60-inch diameter cured-in-place liner, TV inspection of the completed project, and restoration of flow through the repaired pipe.

Anticipated Recipient	: GLOUCESTER COUNTY UA		
Project No.	: 340902-04	Eligible Project Cost:	$ 14,642,685
FY08 Rank	: 110		
County	: GLOUCESTER	Total State Amount :	$ 14,642,685

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.20000
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.20000

Project Name, Number

GLOUCESTER COUNTY UA
340902-04
SEWER SYSTEM REHABILITATION

Priority List Rank

110

County

GLOUCESTER

Existing Population

200,000

Service Area

Clayton Borough, Deptford Twp., Glassboro Borough, Mantua Twp., Monroe Twp., National Park Borough, Paulsboro Borough, Washington Twp., Wenonah Borough, W. Deptford Twp., Westville Borough, Woodbury City, and Woodbury Hts Borough

Need for Project

Population growth has increased wastewater flows in GCUA’s system necessitating projects to address near term capacity limitations and to maintain the existing conveyance system.

Project Description

The proposed project includes the rehabilitation and stabilization of the eroded portions of a stream in order to restore the exposed areas of sanitary sewer lines, inspection, rehabilitation and repair of interceptor sewers throughout the system, and upgrade of the Mantua Creek Pump Station to alleviate existing capacity limitations.

Anticipated Recipient	:	ATLANTIC COUNTY UA		
Project No.	:	340809-10	Eligible Project Cost:	$ 4,227,304
FY08 Rank	:	111		
County	:	ATLANTIC	Total State Amount :	$ 4,227,304

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.16367
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.16367

Project Name, Number

ATLANTIC COUNTY UA
340809-10
SEWER REHABILITATION

Priority List Rank

111

County

ATLANTIC

Existing Population

163,667

Service Area

The municipalities of Absecon, Atlantic City, Brigantine, Egg Harbor City, Egg Harbor Township, Galloway, Hamilton, Linwood, Longport, Margate, Northfield, Pleasantville, Somers Point and Ventnor.

Need for Project

The roofs on five of ACUA’s pump stations are in very poor condition and subject to serious leaks and most be replaced or damage will occur to both the structure and the equipment and could severely effect the flow of influent within the system. Also, due to the excessive wear caused by natural sand, emergency repairs were required on some sections of ACUA’s force mains. ACUA intends to investigate its force mains to locate other areas of excessive wear.

Project Description

The proposed project includes the upgrade and repair of five of ACUA’s pump stations. ACUA also proposes to repair/replace approximately 5000 linear feet of the existing 30-inch Ventnor/Margate force main.

Anticipated Recipient	:	NORTH HUDSON SA		
Project No.	:	340952-02	Eligible Project Cost:	$ 6,549,672
FY08 Rank	:	112		
County	:	HUDSON	Total State Amount :	$ 6,549,672

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.14192
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.14192

Project Name, Number

NORTH HUDSON SA
340952-02
SEWER REHABILITATION

Priority List Rank

112

County

HUDSON

Existing Population

141,919

Service Area

Hoboken, Weehawken, West New York

Need for Project

The Authority's combined sewer system and collection system is subject to excessive amounts of inflow and infiltration causing sewage to overflow during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging in the collection and combined systems. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of pipes.

Anticipated Recipient	: LINDEN ROSELLE SA			
Project No.	: 340299-05	Eligible Project Cost:	$	389,787
FY08 Rank	: 113			
County	: UNION	Total State Amount :	$	389,787

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.10070
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.10070

Project Name, Number

LINDEN ROSELLE SA
340299-05
SEWER REHABILITATION

Priority List Rank

113

County

UNION

Existing Population

100,700

Service Area

City of Linden and the Borough of Roselle

Need for Project

The Main Street Pump Station is aging, in need of repair, and undersized to handle current flows.

Project Description

The proposed project is for the repair and upgrade of the Main Street Pump Station.

Anticipated Recipient	:	ROCKAWAY VALLEY REG SA		
Project No.	:	340756-02	Eligible Project Cost:	$ 5,938,953
FY08 Rank	:	114		
County	:	MORRIS	Total State Amount :	$ 5,938,953

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.09218
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.09218

Project Name, Number

ROCKAWAY VALLEY REG SA

340756-02

I/I CORRECTION

Priority List Rank

114

County

MORRIS

Existing Population

92,180

Service Area

Boonton Town, Boonton Township, Dover Town, Randolph Township, Denville Township, Rockaway Township, Rockaway Borough, Victory Gardens Borough, Wharton Borough

Need for Project

Recently, minor sewer rehabilitation work (internal grouting) has been completed for the Rockaway Valley Service Area. Additional studies are underway to further define the excessive I/I and to propose a correction program.

Project Description

This proposed project will consist of an Infiltration/Inflow correction program to further remove a portion of the excessive I/I.

Anticipated Recipient	:	NORTHWEST BERGEN CO UA		
Project No.	:	340700-06	Eligible Project Cost:	$ 7,944,881
FY08 Rank	:	115		
County	:	BERGEN	Total State Amount :	$ 7,944,881

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.09171
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.09171

Project Name, Number

NORTHWEST BERGEN CO UA
340700-06
I/I CORRECTION

Priority List Rank

115

County

BERGEN

Existing Population

91,710

Service Area

This project will serve the residents of the Boroughs of Franklin Lakes, Ramsey, Upper Saddle River, Saddle River, Allendale, Waldwick, Midland Park, and Hohokus, and the Townships of Mahwah and Wyckoff.

Need for Project

An Infiltration/Inflow (I/I) analysis has concluded that excessive I/I exists within the Authority's sewer system. Additional studies will be required to further define the quantity of excessive I/I and to propose an Infiltration/Inflow correction program to eliminate a portion of the excessive I/I.

Project Description

This proposed project will consist of an Infiltration/Inflow correction program to remove a portion of the excessive I/I. This project is presently in the planning stage.

Anticipated Recipient	:	TWO RIVERS WRA		
Project No.	:	340117-03	Eligible Project Cost:	$ 3,866,213
FY08 Rank	:	116		
County	:	MONMOUTH	Total State Amount :	$ 3,866,213

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.07871
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.07871

Project Name, Number

TWO RIVERS WRA
340117-03
PUMP STATION IMPROVEMENTS

Priority List Rank

116

County

MONMOUTH

Existing Population

78,706

Service Area

Eatontown, Fair Haven, Fort Monmouth, Little Silver, Monmouth Beach, Oceanport, Red Bank, Rumson, Sea Bright, Shrewsbury, Shrewsbury Township, a portion of Tinton Falls, West Long Branch

Need for Project

Recent failures have necessitated the upgrade of the Two Rivers Water Reclamation Authority’s main pumping station.

Project Description

The proposed project includes installation of two turbine pumps mounted inside existing manholes, installation of an emergency generator, and installation of all associated electronics and mechanical appurternances associated with the generator and pumps.

Anticipated Recipient	:	EAST ORANGE CITY		
Project No.	:	340843-01	Eligible Project Cost:	$ 2,588,981
FY08 Rank	:	117		
County	:	ESSEX	Total State Amount :	$ 2,588,981

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.07758
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.07758

Project Name, Number

EAST ORANGE CITY
340843-01
I/I CORRECTION

Priority List Rank

117

County

ESSEX

Existing Population

77,580

Service Area

City of East Orange

Need for Project

A sewer system evaluation survey recently performed by Elson T. Killam Associates for the Passaic Valley Sewerage Commissioners' service area found excessive infiltration/inflow (I/I) in this municipality's sewer system. Raw sewage overflows were reported to have occurred on area streets.

Project Description

An I/I correction program, which will consist of grouting, slip lining, and repairing/replacing structurally damaged pipes and manholes, will be undertaken to remove the identified excessive I/I.

Anticipated Recipient	:	CLIFTON CITY		
Project No.	:	340844-01	Eligible Project Cost:	$ 1,428,585
FY08 Rank	:	118		
County	:	PASSAIC	Total State Amount :	$ 1,428,585

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.07652
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.07652

Project Name, Number

CLIFTON CITY
340844-01
I/I CORRECTION

Priority List Rank

118

County

PASSAIC

Existing Population

76,520

Service Area

City of Clifton

Need for Project

A sewer system evaluation survey performed by Elson T. Killam Associates for the Passaic Valley Sewerage Commissioners' service area found excessive infiltration/inflow (I/I) in this municipality's sewer system. Raw sewage overflows were reported to have occurred on area streets.

Project Description

An I/I correction program, which will consist of grouting slip lining, and repairing/replacing structurally damaged pipes and manholes, will be undertaken to remove the identified excessive I/I.

Anticipated Recipient	:	WOODBRIDGE TOWNSHIP		
Project No.	:	340433-04	Eligible Project Cost:	$ 1,132,363
FY08 Rank	:	119		
County	:	MIDDLESEX	Total State Amount :	$ 1,132,363

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06983
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.06983

Project Name, Number

WOODBRIDGE TOWNSHIP
340433-04
I/I CORRECTION

Priority List Rank

119

County

MIDDLESEX

Existing Population

69,830

Service Area

Woodbridge Township, Sewaren and Keasby sections

Need for Project

The sewer systems in the Sewaren and Keasby sections, constructed prior to the use of secondary treatment methods, did not set strict limits on the volume of infiltration and inflow within sanitary sewers since treatment costs were not greatly affected by these extraneous flows. In recent years, however, the construction costs of conveyance facilities, coupled with rising treatment costs associated with secondary treatment methods, have resulted in efforts to eliminate infiltration and inflow in areas where it is proven to be cost-effective.

Project Description

The proposed project is an Infiltration/Inflow Correction program for Woodbridge's existing sewer system within the Sewaren and Keasby sections. The Sewaren sewer system serves Avenel, Port Reading, Sewaren, and Woodbridge proper. Its drainage area encompasses 6,090 acres and contains 89.9 miles of sanitary sewer. The Woodbridge Interceptor (approximately parallel to the Woodbridge River) serves a majority of the system. The Keasby sewerage system serves Fords, Hopelawn, and Keasby. Its drainage area encompasses 2,389 acres and contains 30.2 miles of sanitary sewer.

Anticipated Recipient	:	EWING LAWRENCE SA		
Project No.	:	340391-06	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	120		
County	:	MERCER	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06487
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.06487

Project Name, Number

EWING LAWRENCE SA
340391-06
I/I CORRECTION

Priority List Rank

120

County

MERCER

Existing Population

64,866

Service Area

Mountain View section of Ewing Township

Need for Project

The Township's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system and at the treatment plant site during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system and sewage treatment plant. The project involves an infiltration/inflow correction program including removal of stormwater connections.

Anticipated Recipient	:	EWING LAWRENCE SA		
Project No.	:	340391-08	Eligible Project Cost:	$ 9,782,685
FY08 Rank	:	120		
County	:	MERCER	Total State Amount :	$ 9,782,685

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06487
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.06487

Project Name, Number

EWING LAWRENCE SA
340391-08
FORCE MAIN

Priority List Rank

120

County

MERCER

Existing Population

64,866

Service Area

Mountain View section of Ewing Township

Need for Project

The Mountain View Pump Station needs to be upgraded to eliminate overflows at the Jacobs Creek Diversion Chamber. The overflows adversely impact the Delaware River which is used for potable water and fishing. The Mountain View Relief Force Main must be replaced to handle increased flows. The Fourth Street Force Main must be relined due to corrosion leaks.

Project Description

The proposed project includes the replacement of the 12-inch Mountain View Force Main with an 18-inch force main; and relining of the 24-inch Fourth Street Force Main.

Anticipated Recipient	: GLOUCESTER TOWNSHIP MUA			
Project No.	: 340364-04	Eligible Project Cost:	$	2,718,518
FY08 Rank	: 122			
County	: CAMDEN	Total State Amount :	$	2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06435
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.06435

Project Name, Number

GLOUCESTER TOWNSHIP MUA
340364-04
SEWER SYSTEM REHABILITATION

Priority List Rank

122

County

CAMDEN

Existing Population

64,350

Service Area

Gloucester Township

Need for Project

Most of the sanitary sewers in Gloucester Township were installed between 1962 and 1978 and are now in need of repair and rehabilitation to maintain integrity of the system and to protect the public health.

Project Description

The proposed project includes repair and replacement of the most deteriorated portions of Gloucester Township MUA’s sewer system.

Anticipated Recipient	:	OLD BRIDGE MUA		
Project No.	:	340945-05	Eligible Project Cost:	$ 2,183,362
FY08 Rank	:	123		
County	:	MIDDLESEX	Total State Amount :	$ 2,183,362

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06046
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.06046

Project Name, Number

OLD BRIDGE MUA
340945-05
SEWER REHABILITATION

Priority List Rank

123

County

MIDDLESEX

Existing Population

60,456

Service Area

Old Bridge

Need for Project

The Authority has an on-going program to eliminate sources of excessive I/I in their sewer system. The project is needed due to the deterioration of the structural integrity of the sewers. In addition, the Rams Field and Farrington Pump Stations are old and need to rehabilitated and upgraded to ensure proper operation, to facilitate routine maintenance, and to control odors.

Project Description

The project includes the relining of problem sewer mains throughout the Township and the rehabilitation of two pump stations, including the installation of comminutors with submersible motors and carbon filters for odor controls. A new bypass chamber will be installed in one pump station.

Anticipated Recipient	:	PASSAIC CITY		
Project No.	:	340845-01	Eligible Project Cost:	$ 5,331,697
FY08 Rank	:	124		
County	:	PASSAIC	Total State Amount :	$ 5,331,697

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.05396
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.05396

Project Name, Number

PASSAIC CITY
340845-01
I/I CORRECTION

Priority List Rank

124

County

PASSAIC

Existing Population

53,960

Service Area

City of Passaic

Need for Project

A sewer system evaluation survey recently performed by Elson T. Killam Associates for the Passaic Valley Sewerage Commissioners' service area found excessive Infiltration/Inflow (I/I) in this municipality's sewer system. Raw sewage overflows were reported to have occurred on area streets.

Project Description

An Infiltration/Inflow (I/I) correction program, which will consist of grouting, slip lining, and repairing/replacing structurally damaged pipes and manholes, will be undertaken to remove the identified excessive I/I.

Anticipated Recipient	:	GLOUCESTER TOWNSHIP MUA		
Project No.	:	340364-01	Eligible Project Cost:	$ 1,540,661
FY08 Rank	:	125		
County	:	CAMDEN	Total State Amount :	$ 1,540,661

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.05380
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.05380

Project Name, Number

GLOUCESTER TOWNSHIP MUA
340364-01
PUMP STATION, FORCE MAIN

Priority List Rank

125

County

CAMDEN

Existing Population

53,800

Service Area

The area north of the N.J. State Highway Route 42 in Gloucester Township

Need for Project

The existing pump station and force main are operating near its capacity and require frequent maintenance. The pump station's present locations does not allow for expansion due to environmental constraints and limitations of existing property. The project will allow for future development within the service area and provide emergency backup power. Other improvements to the existing service will also be provided.

Project Description

The project consists of construction of a pump station and associated force main. The proposed pump station will include three (3) submersible pumps within a concrete wetwell. An emergency generator will provide backup power to run the station during periods of electrical outages. A bar screen, odor control and possibly chemical injection to reduce Hydrogen Sulfide generation will be included in the improvements. A building with associated heating, ventilation and electrical work will house the bar screen, generator and controls. All necessary site work and access will also be included. Once the proposed pump station is completed, the existing pump station will have to be dismantled and abandoned. Since the existing pump station site does not have sufficient space, the authority will need to acquire the property located across the N.J. State Highway 168 (Black Horse Pike).

Anticipated Recipient	:	WAYNE TOWNSHIP		
Project No.	:	340393-07	Eligible Project Cost:	$ 2,049,114
FY08 Rank	:	126		
County	:	PASSAIC	Total State Amount :	$ 2,049,114

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04955
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.04955

Project Name, Number

WAYNE TOWNSHIP
340393-07
I/I CORRECTION

Priority List Rank

126

County

PASSAIC

Existing Population

49,550

Service Area

Township of Wayne

Need for Project

This project is for the minor rehabilitation of the Township's existing sewer system. A sewer system evaluation survey concluded that approximately 1.5 million gallons per day (MGD) of excessive Infiltration/Inflow could be removed from the system cost-effectively. This project would ensure the removal of the 1.5 MGD by the accomplishment of this rehabilitation work.

Project Description

The proposed Phase I project (C340393-06) is to rehabilitate portions of the existing sewer system in the area of Pines Lake and Packanack Lake. The work for Phase I includes inversion lining of 3,160 linear feet (LF) of sewer pipe, replacement of approximately 5,130 LF of sewer pipe, grouting and air testing, and rehabilitation of 11 manholes. Phase II investigations (C340393-07) will be required to eliminate all excessive infiltration/inflow for other portions of the existing sewer system.

Anticipated Recipient	: WASHINGTON TOWNSHIP MUA			
Project No.	: 340930-03	Eligible Project Cost:	$	962,250
FY08 Rank	: 127			
County	: GLOUCESTER	Total State Amount :	$	962,250

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.04711
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.04711

Project Name, Number

WASHINGTON TOWNSHIP MUA
340930-03
SEWER REHABILITATION

Priority List Rank

127

County

GLOUCESTER

Existing Population

47,114

Service Area

Washington Township

Need for Project

The Township’s sewer mains are old and have been experiencing blockages due to deterioration, dips, and misalignments causing sewage to surcharge and overflow.

Project Description

The proposed project includes the replacement of the existing sewer main with a new PVC main. One pump station is proposed to be removed and sewer mains will be rerouted to allow for gravity flow in certain areas of the Township.

Anticipated Recipient	: BERKELEY TOWNSHIP			
Project No.	: 340969-01	Eligible Project Cost:	$	2,718,518
FY08 Rank	: 128			
County	: OCEAN	Total State Amount :	$	2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03999
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03999

Project Name, Number

BERKELEY TOWNSHIP
340969-01
I/I CORRECTION

Priority List Rank

128

County

OCEAN

Existing Population

39,991

Service Area

Berkeley Township

Need for Project

To reduce elevated levels of bacteria in stormwater discharges to coastal waters.

Project Description

To eliminate cross-connections between sanitary and storm sewers by replacing portions of sewers, sealing manholes, and sealing leaks. To eliminate interconnections due to leaks, flows, or overflows from the sanitary sewer system.

Anticipated Recipient	:	NEPTUNE TWP SA		
Project No.	:	340410-04	Eligible Project Cost:	$ 4,481,756
FY08 Rank	:	129		
County	:	MONMOUTH	Total State Amount :	$ 4,481,756

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03473
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03473

Project Name, Number

NEPTUNE TWP SA
340410-04
I/I CORRECTION

Priority List Rank

129

County

MONMOUTH

Existing Population

34,727

Service Area

Neptune Township, Avon-By-The-Sea Borough, Bradley Beach Borough, Ocean Grove Camp Meeting Association

Need for Project

The infiltration/inflow analysis has found that the system is subject to excessive infiltration/inflow (I/I).

Project Description

The project will consist of an I/I correction program that is found to be cost-effective during the Sewer System Evaluation Survey. Common methods of rehabilitation are 1) grouting of joints and cracked pipes; 2) slip-lining of select reaches of sewer; and 3) total replacement of select reaches of sewer. The proposed I/I correction project will not have an appreciable effect on the treatment plant's ability to meet the established effluent limitations.

Anticipated Recipient	:	WINSLOW TWP (SICKLERSVILLE)		
Project No.	:	340895-01	Eligible Project Cost:	$ 2,013,118
FY08 Rank	:	130		
County	:	CAMDEN	Total State Amount :	$ 2,013,118

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03461
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03461

Project Name, Number

WINSLOW TWP (SICKLERSVILLE)
340895-01
I/I CORRECTION

Priority List Rank

130

County

CAMDEN

Existing Population

34,611

Service Area

Winslow Township (Sicklersville)

Need for Project

The existing collection system in the Township of Winslow is possibly subject to excessive Infiltration/Inflow (I/I).

Project Description

The project consists of the rehabilitation of the sewer system.

Anticipated Recipient	: FORT LEE BOROUGH			
Project No.	: 340853-01	Eligible Project Cost:	$	682,636
FY08 Rank	: 131			
County	: BERGEN	Total State Amount :	$	682,636

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03262
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03262

Project Name, Number

FORT LEE BOROUGH
340853-01
I/I CORRECTION

Priority List Rank

131

County

BERGEN

Existing Population

32,620

Service Area

Borough of Fort Lee

Need for Project

The Bergen County Utilities Authority Infiltration/Inflow (I/I) Analysis and Sewer System Evaluation survey identified excessive I/I in this municipality's sewer system.

Project Description

The excessive I/I will be removed by grouting, slip lining, and other minor rehabilitation methods.

Anticipated Recipient	: ORANGE CITY			
Project No.	: 340859-01	Eligible Project Cost:	$	964,562
FY08 Rank	: 132			
County	: ESSEX	Total State Amount :	$	964,562

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03173
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03173

Project Name, Number

ORANGE CITY
340859-01
I/I CORRECTION

Priority List Rank

132

County

ESSEX

Existing Population

31,730

Service Area

City of Orange

Need for Project

A sewer system evaluation survey recently performed by Killam Associates for the City of Orange recommended that the combined sanitary/storm sewer systems should be eliminated by internally sealing the overflow weirs in the combination sanitary/storm sewer manholes. In conjunction with sealing the overflows, a program of sewer pipe rehabilitation should be undertaken to reduce infiltration and sewer surcharging conditions.

Project Description

A phased program of sewer system rehabilitation to eliminate sanitary sewer overflows to the Wigwam Brook is being undertaken by the City. The first phase of this program will include sealing the overflow weirs in 21 combination sanitary/storm sewer manholes, replacement of approximately 250 linear feet of 15" and 18" sewer pipe, and sealing underdrain access openings in 20 manholes. The second phase includes replacing approximately 245 linear feet of sewer pipe and slip lining approximately 830 linear feet of pipe. The third phase includes eliminating a bend in the interceptor sewer by constructing a new manhole.

Anticipated Recipient	: EGG HARBOR TOWNSHIP MUA			
Project No.	: 340353-02	Eligible Project Cost:	$	916,350
FY08 Rank	: 133			
County	: ATLANTIC	Total State Amount :	$	916,350

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03073
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03073

Project Name, Number

EGG HARBOR TOWNSHIP MUA
340353-02
SEWER REHABILITATION

Priority List Rank

133

County

ATLANTIC

Existing Population

30,726

Service Area

Township of Egg Harbor

Need for Project

The existing thirty-five-year old asbestos cement sewer lines in West Atlantic City have deteriorated and need to be replaced.

Project Description

The project consists of replacing of 9,100 feet of sewer lines and appurtenances.fourteen inch asbestos cement sanitary sewer force main.

Anticipated Recipient	: EGG HARBOR TOWNSHIP MUA			
Project No.	: 340753-03	Eligible Project Cost:	$	916,350
FY08 Rank	: 133			
County	: ATLANTIC	Total State Amount :	$	916,350

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03073
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.03073

Project Name, Number

EGG HARBOR TOWNSHIP MUA
340753-03
SEWER REHABILITATION

Priority List Rank

133

County

ATLANTIC

Existing Population

30,726

Service Area

West Atlantic City

Need for Project

The sanitary sewer lines are over 35 years old and greatly deteriorated due to the use of asbestos cement pipe, the selected alignment of section of the system and the aggressive nature of the soil.

Project Description

The proposed project involves replacement of 9100 feet of sewer mains, manholes, and sewer laterals.

Anticipated Recipient	:	MONROE MUA		
Project No.	:	340423-03	Eligible Project Cost:	$ 2,249,480
FY08 Rank	:	135		
County	:	GLOUCESTER	Total State Amount :	$ 2,249,480

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02897
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02897

Project Name, Number

MONROE MUA
340423-03
SEWER REHABILITATION

Priority List Rank

135

County

GLOUCESTER

Existing Population

28,967

Service Area

Township of Monroe

Need for Project

The MUAs sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system. The project involves replacement of existing pipes with PVC piping.

Anticipated Recipient	:	PEQUANNOCK RIVER BASIN RSA		
Project No.	:	340459-05	Eligible Project Cost:	$ 604,874
FY08 Rank	:	136		
County	:	MORRIS	Total State Amount :	$ 604,874

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02689
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02689

Project Name, Number

PEQUANNOCK RIVER BASIN RSA
340459-05
SEWER REHABILITATION

Priority List Rank

136

County

MORRIS

Existing Population

26,893

Service Area

Borough of Butler, Borough of Bloomington, Borough of Kinnelon, and Borough of Riverdale

Need for Project

The Boonton Avenue Interceptor is aging is subject to blockages and inflow and infiltration.

Project Description

The proposed project includes replacement/rehabilitation of sections of the interceptor.

Anticipated Recipient	:	BERGEN COUNTY UA (TRIBORO)		
Project No.	:	340769-02	Eligible Project Cost:	$ 1,584,586
FY08 Rank	:	137		
County	:	BERGEN	Total State Amount :	$ 1,584,586

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02509
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02509

Project Name, Number

BERGEN COUNTY UA (TRIBORO)
340769-02
I/I CORRECTION

Priority List Rank

137

County

BERGEN

Existing Population

25,090

Service Area

Borough of Carlstadt and portions of Rutherford and East Rutherford

Need for Project

The Bergen County Utilities Authority conducted an Infiltration/Inflow (I/I) analysis and sewer system evaluation survey which concluded that excessive I/I existed in the sewer system. The correction of this I/I will be cost-effective and result in the improved operation of a 13.8 MGD pump station used for the conveyance of sewage from the Joint Meeting STP to the Bergen County Utilities Authority system. Water Quality violations are currently experienced for dissolved oxygen, fecal coliform, and toxics standards due to the raw discharges of the existing Triboro Joint Meeting Treatment plant into the Hacken-sack River (SE-2).

Project Description

The project will consist of rehabilitation work to remove a portion of the excessive I/I. The rehabilitation project may include repair and/or grouting of sewers and joints, sealing manholes, repair/replacement of defective manhole covers and other standard rehabilitation measures. This project will also eliminate sewerage system overflows.

Anticipated Recipient	:	RIDGEWOOD VILLAGE		
Project No.	:	340639-07	Eligible Project Cost:	$ 6,046,088
FY08 Rank	:	138		
County	:	BERGEN	Total State Amount :	$ 6,046,088

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.02486
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.02486

Project Name, Number

RIDGEWOOD VILLAGE
340639-07
I/I CORRECTION

Priority List Rank

138

County

BERGEN

Existing Population

24,860

Service Area

Village of Ridgewood

Need for Project

An Infiltration/Inflow (I/I) analysis has concluded that excessive I/I exists within the village's sewer system. Additional studies are underway to further define the quantity of excessive I/I and to propose an I/I correction program to eliminate a portion of the excessive I/I.

Project Description

This proposed project will be for the replacement of sections of sanitary sewer pipe, grouting of sewer lines, grouting and sealing leaking manholes, and repair or adjustments of defective manholes.

Anticipated Recipient	:	MADISON-CHATHAM JOINT MEETING		
Project No.	:	340715-03	Eligible Project Cost:	$ 782,388
FY08 Rank	:	139		
County	:	MORRIS	Total State Amount :	$ 782,388

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.02377
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.02377

Project Name, Number

MADISON-CHATHAM JOINT MEETING

340715-03

I/I CORRECTION

Priority List Rank

139

County

MORRIS

Existing Population

23,770

Service Area

Borough of Chatham, Borough of Madison

Need for Project

An Infiltration/Inflow (I/I) analysis has been completed which documents the existence of excessive I/I within the service area. Additional studies are under way to further define the quantity of excessive I/I and to propose an I/I correction program to mitigate hydraulic overloading of the plant during severe storms.

Project Description

This proposed project will consist of an I/I correction program to remove a portion of the excessive I/I. This will include replacement of sections of sanitary sewer pipe, grouting of sewer lines, grouting and sealing leaking manholes and repair of and adjustments to defective manholes.

Anticipated Recipient	: SOUTH BRUNSWICK TOWNSHIP			
Project No.	: 340866-01	Eligible Project Cost:	$	374,327
FY08 Rank	: 140			
County	: MIDDLESEX	Total State Amount :	$	374,327

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02236
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02236

Project Name, Number

SOUTH BRUNSWICK TOWNSHIP
340866-01
I/I CORRECTION

Priority List Rank

140

County

MIDDLESEX

Existing Population

22,360

Service Area

South Brunswick Township (Kendall Park)

Need for Project

The Township has had an ongoing I/I program since 1990. Sewer lines have been televised and problem areas recorded. Small problems have been corrected, but, certain areas reqire lining or replacement of existing lines.

Project Description

The project involves the lining or replacement of existing sewer lines on an "as needed" basis to reduce I/I in the system.

Anticipated Recipient	:	LONG HILL TOWNSHIP		
Project No.	:	340404-06	Eligible Project Cost:	$ 2,317,315
FY08 Rank	:	141		
County	:	MORRIS	Total State Amount :	$ 2,317,315

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02180
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02180

Project Name, Number

LONG HILL TOWNSHIP
340404-06
SEWER REHABILITATION

Priority List Rank

141

County

MORRIS

Existing Population

21,796

Service Area

Township of Long Hill

Need for Project

The Township’s sanitary sewer system is subject inflow and infiltration causing sewage to overflow in the collection system and at the treatment plant increasing loadings to the Passaic River during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system and sewage treatment plant. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the sewer system. The Township also proposes to install phosphorous removal equipment at the treatment plant.

Anticipated Recipient	: HAZLET TOWNSHIP			
Project No.	: 340968-01	Eligible Project Cost:	$	916,350
FY08 Rank	: 142			
County	: MONMOUTH	Total State Amount :	$	916,350

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02138
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02138

Project Name, Number

HAZLET TOWNSHIP
340968-01
I/I CORRECTION

Priority List Rank

142

County

MONMOUTH

Existing Population

21,378

Service Area

Hazlet Township

Need for Project

The Township’s sanitary sewer system is subject to inflow and infiltration causing sewage to back up in the collection system. A 30 year old pump station must be replaced.

Project Description

The proposed project includes an infiltration/inflow correction program and replacement of a pump station.

Anticipated Recipient	: EDGEWATER BOROUGH			
Project No.	: 340443-05	Eligible Project Cost:	$	3,091,877
FY08 Rank	: 142			
County	: BERGEN	Total State Amount :	$	3,091,877

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02138
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02138

Project Name, Number

EDGEWATER BOROUGH
340443-05
I/I CORRECTION

Priority List Rank

142

County

BERGEN

Existing Population

21,380

Service Area

Edgewater, Cliffside Park (portion), Fort Lee (portion)

Need for Project

To eliminate the excessive infiltration and inflow to extend the useful life of the sewer.

Project Description

There are approximately 25 miles of existing sewers in the Borough. The Edgewater STP presently has an influent rate of 3.3 mgd, of which 0.37 mgd has been identified as possibly being excessive. The sewer system evaluation survey program is currently in the process of identifying and verifying those areas which are susceptible to the excessive I/I. I/I correction as determined to be cost effective will follow.

Anticipated Recipient	:	HILLSIDE TOWNSHIP		
Project No.	:	340906-03	Eligible Project Cost:	$ 1,110,388
FY08 Rank	:	144		
County	:	UNION	Total State Amount :	$ 1,110,388

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02137
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02137

Project Name, Number

HILLSIDE TOWNSHIP
340906-03
I/I CORRECTION & SEWER PUMP

Priority List Rank

144

County

UNION

Existing Population

21,370

Service Area

Township of Hillside

Need for Project

The existing collection system serving the Township is very old, and is subject to an extreme amount of I/I. Rehabilitation of the entire sanitary sewer system is necessary to remove 650,000 gpd of I/I to prevent overflows from the existing collection system and back-ups into residential and industrial establishments.

Project Description

This proposed project will be for an I/I correction program to eliminate the portion of I/I that is excessive and detrimental to the existing collection system. In some cases minor replacement may be necessary. Also proposed is the major rehabilitation of an existing sewage pumping station.

Anticipated Recipient	:	ROSELLE BOROUGH		
Project No.	:	340314-01	Eligible Project Cost:	$ 1,592,589
FY08 Rank	:	145		
County	:	UNION	Total State Amount :	$ 1,592,589

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02127
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02127

Project Name, Number

ROSELLE BOROUGH
340314-01
I/I CORRECTION

Priority List Rank

145

County

UNION

Existing Population

21,274

Service Area

Borough of Roselle

Need for Project

The Infiltration/Inflow (I/I) analysis of the collection system indicates that the city sewerage system has excessive I/I.

Project Description

The proposed project will be for an Infiltration/Inflow correction program to eliminate excessive I/I from the sewerage system.

Anticipated Recipient	:	MOUNT HOLLY MUA		
Project No.	:	340817-04	Eligible Project Cost:	$ 1,915,067
FY08 Rank	:	146		
County	:	BURLINGTON	Total State Amount :	$ 1,915,067

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02119
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02119

Project Name, Number

MOUNT HOLLY MUA
340817-04
PUMP STATION UPGRADE

Priority List Rank

146

County

BURLINGTON

Existing Population

21,189

Service Area

Lumberton Township

Need for Project

An existing pump station in Lumberton must be upgraded to operate during 100 year flood conditions, to meet future demands, and to improve operation and ease maintenance.

Project Description

The project includes construction of a 1,870 gpm submersible pumping station at the site of the existing pumping station in Lumberton Township and construction of an emergency pump system located north of the existing pumping station to provide service during power outages and flood conditions.

Anticipated Recipient	:	CARTERET BOROUGH		
Project No.	:	340939-01	Eligible Project Cost:	$ 7,234,505
FY08 Rank	:	147		
County	:	MIDDLESEX	Total State Amount :	$ 7,234,505

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02071
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.02071

Project Name, Number

CARTERET BOROUGH
340939-01
I/I CORRECTION

Priority List Rank

147

County

MIDDLESEX

Existing Population

20,709

Service Area

Borough of Carteret

Need for Project

Having an old sewer system, the rate of infiltration/inflow during storm events in Carteret is very high. Carteret’s main pumping station receives flow far greater than its pumping capacity at such times. The structural integrity of the five pumping stations, sewer lines, and manholes is in question and will need to be replaced, upgraded, and/or rehabilitated.

Project Description

The proposed project includes an I/I correction program consisting of grouting, lining, and repairing/replacing structurally damaged pipes and manholes. In addition, five pumping stations will be upgraded and interceptor may be increased in size.

Anticipated Recipient	: MOORESTOWN TOWNSHIP			
Project No.	: 340912-02	Eligible Project Cost:	$	862,491
FY08 Rank	: 148			
County	: BURLINGTON	Total State Amount :	$	862,491

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01902
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01902

Project Name, Number

MOORESTOWN TOWNSHIP
340912-02
SEWER REHABILITATION

Priority List Rank

148

County

BURLINGTON

Existing Population

19,017

Service Area

Township of Moorestown

Need for Project

The Township’s sewer main is corroded and discharges sewage to the stormwater sytem.

Project Description

The proposed project includes replacement of the asbestos cement pipe with PVC pipe.

Anticipated Recipient	:	ELMWOOD PARK BOROUGH		
Project No.	:	340863-01	Eligible Project Cost:	$ 1,091,170
FY08 Rank	:	149		
County	:	BERGEN	Total State Amount :	$ 1,091,170

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01893
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01893

Project Name, Number

ELMWOOD PARK BOROUGH
340863-01
I/I CORRECTION

Priority List Rank

149

County

BERGEN

Existing Population

18,925

Service Area

Borough of Elmwood Park

Need for Project

A sewer system evaluation survey recently performed by Elson T. Killam Associates for the Passaic Valley Sewerage Commissioners' service area found excessive infiltration/inflow (I/I) in this municipality's sewer system.

Project Description

An I/I correction program, which will consist of grouting, slip lining, and repairing/replacing structurally damaged pipes and manholes will be undertaken to remove the identified excessive I/I.

Anticipated Recipient	:	BRIDGETON CITY		
Project No.	:	340829-01	Eligible Project Cost:	$ 1,362,805
FY08 Rank	:	150		
County	:	CUMBERLAND	Total State Amount :	$ 1,362,805

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01876
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01876

Project Name, Number

BRIDGETON CITY
340829-01
I/I CORRECTION

Priority List Rank

150

County

CUMBERLAND

Existing Population

18,760

Service Area

City of Bridgeton

Need for Project

The majority of the sanitary sewers in the City of Bridgeton were installed between 1880 and 1954 and are now in need of repair and rehabilitation to maintain the integrity of the system as well as protect the public health.

Project Description

The proposed project includes the inspection and repair of the existing sanitary sewer system by flushing, inspecting, sealing or replacing leaking or broken pipes, valves and pumps.

Anticipated Recipient	:	DUMONT BOROUGH		
Project No.	:	340922-01	Eligible Project Cost:	$ 3,625,787
FY08 Rank	:	151		
County	:	BERGEN	Total State Amount :	$ 3,625,787

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01771
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01771

Project Name, Number

DUMONT BOROUGH
340922-01
SEWER REHABILITATION

Priority List Rank

151

County

BERGEN

Existing Population

17,710

Service Area

Dumont

Need for Project

The existing Sanitary Sewer System serves the Borough of Dumont and is approximately 65 years old. Treatment of the wastewater collected is provided by the Bergen County Utilities Authority at the Little Ferry Treatment Plant. Field investigations and existing records available at the Department of Public Works of the Borough of Dumont reveal that the condition of the sanitary sewer system is substandard. There are many sections of this mostly clay pipe system that have been troublesome, resulting in frequent blockages and requiring significant efforts and time by the Department of Public Works to clear the lines. These blockages and problems are caused mainly by undersized piping, cracking of pipes, root intrusion, offset joints and inadequate slopes.

The purpose of the program to rehabilitate the Sanitary Sewer System is to correct these problem areas and also to decrease the amount of infiltration into the system.

Project Description

The areas of the system requiring rehabilitation were selected based on the problems incurred as recorded in the Department of Public Works files and past field investigations.

The proposed scope of work will be carried out in four (4) phases over a 4-year period. The first phase will cover the southwest quadrant of the Borough where the system connects up with Bergen County Utilities Authority's System; the second phase will cover the northwest quandrant; the third phase, the southwest quadrant; and the fourth and final phase, the northeast quadrant.

Anticipated Recipient	: STONY BROOK REGIONAL SA			
Project No.	: 340400-03	Eligible Project Cost:	$	560,281
FY08 Rank	: 152			
County	: MERCER	Total State Amount :	$	560,281

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01712
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01712

Project Name, Number

STONY BROOK REGIONAL SA
340400-03
I/I CORRECTION

Priority List Rank

152

County

MERCER

Existing Population

17,120

Service Area

Township of South Brunswick

Need for Project

The collection system has been studied to identify extraneous infiltration and inflow sources. These sources raise the flow to the Stony Brook STP, but cause no operational or transmission problems other than those associated with a weak influent.

Project Description

This project would provide cost-effective removal of I/I in the South Brunswick collection system. Sections would be repaired, replaced or relined. Also, manholes are to be grouted and manhole covers replaced with gasket covers.

Anticipated Recipient	: PALISADES PARK BOROUGH			
Project No.	: 340313-01	Eligible Project Cost:	$	430,399
FY08 Rank	: 153			
County	: BERGEN	Total State Amount :	$	430,399

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01707
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01707

Project Name, Number

PALISADES PARK BOROUGH
340313-01
SEWER REHABILITATION

Priority List Rank

153

County

BERGEN

Existing Population

17,073

Service Area

Borough of Washington

Need for Project

The Borough's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the sewer system.

Anticipated Recipient	: READINGTON TOWNSHIP			
Project No.	: 340577-07	Eligible Project Cost:	$	226,059
FY08 Rank	: 154			
County	: HUNTERDON	Total State Amount :	$	226,059

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01580
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01580

Project Name, Number

READINGTON TOWNSHIP
340577-07
I/I CORRECTION

Priority List Rank

154

County

HUNTERDON

Existing Population

15,803

Service Area

Township of Readington

Need for Project

The Township's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system and at the treatment plant during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system and sewage treatment plant. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the sewer system.

Anticipated Recipient	: OCEAN CITY			
Project No.	: 340730-01	Eligible Project Cost:	$	57,540
FY08 Rank	: 155			
County	: CAPE MAY	Total State Amount :	$	57,540

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01549
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01549

Project Name, Number

OCEAN CITY
340730-01
I/I CORRECTION

Priority List Rank

155

County

CAPE MAY

Existing Population

15,490

Service Area

Ocean City

Need for Project

The infiltration/inflow analysis has found that the system is subject to possible excessive infiltration/inflow (I/I).

Project Description

The rehabilitation of Ocean City's sanitary sewer system includes the sealing, repair, or replacement of defective pipes, manholes and lateral connections.

Anticipated Recipient	:	WARREN CO LOPAT SA		
Project No.	:	340580-04	Eligible Project Cost:	$ 2,463,225
FY08 Rank	:	156		
County	:	WARREN	Total State Amount :	$ 2,463,225

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01542
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01542

Project Name, Number

WARREN CO LOPAT SA
340580-04
I/I CORRECTION

Priority List Rank

156

County

WARREN

Existing Population

15,420

Service Area

The Warren County-Lopatcong Creek Sewerage Authority is retaining a spot on the Priority List for rehabilitation of the local collection systems within their 201 Facilities Planning Area. The planning area lies in the Delaware Watershed and includes Alpha Borough and Lopatcong, Pohatcong, Harmony and Greenwich Townships.

Need for Project

Sanitary collection systems currently serve Alpha, Lopatcong, and Pohatcong. The existing Phillipsburg plant (NJ0024716) presently treats domestic and industrial waste from the above municipalities. Constructed in 1950 - 1951 with a design capacity of 3.5 MGD, the plant provides secondary treatment by means of an activated sludge process. Present flows average slightly over 2.1 MGD, but peak conditions can result in flows over 6.0 MGD which lead to a by-pass of the plant and direct discharge of untreated effluent into the Lopatcong Creek, FW2-TM (tributary to Delaware River). There also are known cross connection between the storm and sanitary sewerage systems. These raw discharges result in frequent violations of fecal coliform standards, and marginal degradation from nutrient and toxic impacts. An I/I analysis included in the facilities plan concluded infiltration to be non-excessive, but recommended a Sewer System Evaluation Survey (SSES @ $26,000) to study the removal of excessive inflow and the elimination of the system by-passes.

Project Description

The proposed SSES will refine the conclusions of the I/I analysis and make recommendations for I/I correction. The project will allow for the construction and implementation of the cost effective rehabilitation measures. This will result in the abatement of the raw sewage by-pass problem presently experienced both in the collection systems and at the plant.

Anticipated Recipient	: BERNARDS TOWNSHIP SA			
Project No.	: 340382-03	Eligible Project Cost:	$	482,182
FY08 Rank	: 157			
County	: SOMERSET	Total State Amount :	$	482,182

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01530
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01530

Project Name, Number

BERNARDS TOWNSHIP SA
340382-03
I/I CORRECTION

Priority List Rank

157

County

SOMERSET

Existing Population

15,300

Service Area

Bernards Township

Need for Project

There is excessive infiltration/inflow in the existing collection system which can be cost-effectively removed by I/I correction. However, the operation of the treatment plant will not be affected by the excessive I/I.

Project Description

The proposed project involves I/I correction of the existing sewer system through a cleaning, TVing, air testing, and grouting program. To correct the inflow problems, the project will also include manhole cover replacement and will address illegal connections.

Anticipated Recipient	:	HADDON TOWNSHIP		
Project No.	:	340115-01	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	158		
County	:	CAMDEN	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01465
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01465

Project Name, Number

HADDON TOWNSHIP
340115-01
INFILTRATION/INFLOW CORRECTION

Priority List Rank

158

County

CAMDEN

Existing Population

14,651

Service Area

Haddon Township

Need for Project

Excessive inflow of roof drain leader discharge and basement sump pump connections to sanitary sewer mains cause sanitary manholes to surcharge during significant rainfall events and cause sewer effluent splills into streets, creeks and lakes.

Project Description

The proposed project includes rehabilitation of select sanitary sewer mains throughout the Bettlewood section of the Township by sliplining existing terracotta pipe, repairing defects in the piping and repairing/replacing manholes. The project will also address removal of excessive inflow by removing roof leader connections and basement sump pump connections that are connected to the sanitary sewer systems by constructing separate sump discharge collection piping.

Anticipated Recipient	:	VERONA BOROUGH		
Project No.	:	340533-04	Eligible Project Cost:	$ 1,465,130
FY08 Rank	:	159		
County	:	ESSEX	Total State Amount :	$ 1,465,130

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01415
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01415

Project Name, Number

VERONA BOROUGH
340533-04
I/I CORRECTION

Priority List Rank

159

County

ESSEX

Existing Population

14,150

Service Area

Borough of Verona

Need for Project

An Infiltration/Inflow (I/I) analysis has concluded that the Borough's sewer system exhibits excessive I/I. Additional studies are underway to further define the quantity of excessive I/I and to propose a sewer rehabilitation program to mitigate hydraulic overloading of the plant during severe storm events which affects the performance of the treatment plant.

Project Description

This proposed project will consist of I/I correction to remove a portion of the excessive I/I. Construction of an equalization basin for storage of inflow may be necessary depending upon the conclusions of the additional on-going studies.

Anticipated Recipient	:	SPRINGFIELD TOWNSHIP		
Project No.	:	340855-01	Eligible Project Cost:	$ 1,465,130
FY08 Rank	:	160		
County	:	UNION	Total State Amount :	$ 1,465,130

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01409
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01409

Project Name, Number

SPRINGFIELD TOWNSHIP
340855-01
I/I CORRECTION

Priority List Rank

160

County

UNION

Existing Population

14,090

Service Area

Township of Springfield

Need for Project

Recent studies have indicated the presence of excessive Infiltration/Inflow (I/I) within the Township's sewer collection system.

Project Description

Recommended is an I/I correction program consisting of minor rehabilitation measures to remove the excessive Infiltration/Inflow.

Anticipated Recipient	:	HIGHLAND PARK BOROUGH		
Project No.	:	340938-01	Eligible Project Cost:	$ 4,315,232
FY08 Rank	:	161		
County	:	MIDDLESEX	Total State Amount :	$ 4,315,232

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01328
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01328

Project Name, Number

HIGHLAND PARK BOROUGH
340938-01
I/I CORRECTION

Priority List Rank

161

County

MIDDLESEX

Existing Population

13,279

Service Area

Highland Park

Need for Project

The Borough of Highland Park’s gravity sewers suffer from infiltration/inflow due, in part, to faulty joints, cracked or collapsed pipes and leaky manholes. In addition, some of the Borough’s sanitary sewers are located in high groundwater areas, further increasing infiltration.

Project Description

The proposed project includes evaluation of the existing sanitary sewer mains through TV inspection. Pipes found to be in good condition shall be cleaned and have the joints grouted. Pipes with minor cracks will be grouted. Deteriorated manholes will be rehabilitated and have watertight covers installed.

Anticipated Recipient	:	CLINTON TOWNSHIP SA		
Project No.	:	340873-03	Eligible Project Cost:	$ 1,396,910
FY08 Rank	:	162		
County	:	HUNTERDON	Total State Amount :	$ 1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01296
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01296

Project Name, Number

CLINTON TOWNSHIP SA
340873-03
PUMP STATION REHABILITATION

Priority List Rank

162

County

HUNTERDON

Existing Population

12,957

Service Area

Clinton Town

Need for Project

The age of the Beaver Brook Pumping Stations #1 & #2 necessitate that the Authority plan for their rehabilitation to bring the stations into compliance with current regulations and to ensure proper operation and reliabilty. Rehabilitation of existing conveyance and pumping facilities is proposed to correct the periodic sewage overflow problem.

Project Description

The proposed project includes installation of new submersible pumps and controls; construction of new valve chambers; installation of new gate valves, check valves and force main piping; replacment of roofs; installation of new generators and controls; and installation of comminutors.

Anticipated Recipient	: CEDAR GROVE TOWNSHIP			
Project No.	: 340717-05	Eligible Project Cost:	$	374,327
FY08 Rank	: 163			
County	: ESSEX	Total State Amount :	$	374,327

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01262
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01262

Project Name, Number

CEDAR GROVE TOWNSHIP
340717-05
I/I CORRECTION

Priority List Rank

163

County

ESSEX

Existing Population

12,620

Service Area

Township of Cedar Grove

Need for Project

An Infiltration/Inflow (I/I) analysis has concluded that the Township's sewer system exhibits excessive I/I. Additional studies are underway to further define this excessive I/I and to propose a sewer rehabilitation program.

Project Description

This proposed project will consist of minor rehabilitation work to remove a portion of the excessive I/I. Construction of an equalization basin for storage of inflow may be recommended depending upon the conclusion of the additional on-going studies.

Anticipated Recipient	: PARSIPPANY-TROY HILLS TWP			
Project No.	: 340766-02	Eligible Project Cost:	$	51,639
FY08 Rank	: 164			
County	: MORRIS	Total State Amount :	$	51,639

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01260
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01260

Project Name, Number

PARSIPPANY-TROY HILLS TWP
340766-02
I/I CORRECTION

Priority List Rank

164

County

MORRIS

Existing Population

12,600

Service Area

Parsippany-Troy Hills-Study zones C & D

Need for Project

An infiltration/inflow (I/I) analysis has concluded that excessive I/I exists in the sewer system. Additional studies will define this excess quantity and propose an I/I correction program to eliminate a portion of the excessive I/I.

Project Description

This project is for the I/I correction of the Township's sewer system. The project involves grouting of manholes, raising and resetting manhole frames and covers, internal pressure grouting of sewer joints, excavation and removal of 2 storm sewer connections, repair of one service connection, and elimination of sump pumps, roof leaders and yard drains. This I/I correction project does not affect the treatment system.

Anticipated Recipient	: ROXBURY TWP			
Project No.	: 340381-05	Eligible Project Cost:	$	1,344,941
FY08 Rank	: 165			
County	: MORRIS	Total State Amount :	$	1,344,941

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01210
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01210

Project Name, Number

ROXBURY TWP
340381-05
I/I CORRECTION

Priority List Rank

165

County

MORRIS

Existing Population

12,100

Service Area

Roxbury Township and portions of Mine Hill, Mount Arlington and Randolph

Need for Project

To eliminate excessive inflow into the sewer system.

Project Description

The Ajax Terrace sewage treatment plant has a sewer configuration 50 miles in length with a dry weather flow of 0.94 mgd. The infiltration has been determined to be nonexcessive. However, excessive inflow does exist since the plant flow records indicated that the wet weather flows were as much as 4 times greater than the dry weather flows. Inflow investigation is presently underway to identify the locations, magnitudes, and causes of this inflow problem. It is expected that a sewer system evaluation survey and I/I correction program will follow.

Anticipated Recipient	: HASBROUCK HEIGHTS BOROUGH		
Project No.	: 340329-01	Eligible Project Cost:	$ 14,226,449
FY08 Rank	: 166		
County	: BERGEN	Total State Amount :	$ 14,226,449

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01166
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01166

Project Name, Number

HASBROUCK HEIGHTS BOROUGH
340329-01
SEWER REHABILITATION

Priority List Rank

166

County

BERGEN

Existing Population

11,662

Service Area

Borough of Hasbrouck Heights

Need for Project

The existing sanitary sewer system is aging and has deteriorated in some areas and collapsed in other areas. A new siphon line is needed to stop sanitary overflows during rain storms.

Project Description

The proposed project includes consists of the repair, replacement, or relining of several sections of the Borough's sewer system. The Borough also proposes to install a new siphon line and chamber.

Anticipated Recipient	: SOMERS POINT CITY			
Project No.	: 340618-01	Eligible Project Cost:	$	113,605
FY08 Rank	: 167			
County	: ATLANTIC	Total State Amount :	$	113,605

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01122
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01122

Project Name, Number

SOMERS POINT CITY
340618-01
I/I CORRECTION

Priority List Rank

167

County

ATLANTIC

Existing Population

11,220

Service Area

Somers Point City

Need for Project

Based upon existing studies, the sewer system of Somers Point City is subject to excessive infiltration/inflow (I/I).

Project Description

This project includes rehabilitation of the sewer system of Somers Point City to correct I/I problems.

Anticipated Recipient	:	FLORHAM PARK SA		
Project No.	:	340703-05	Eligible Project Cost:	$ 1,396,910
FY08 Rank	:	168		
County	:	MORRIS	Total State Amount :	$ 1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01117
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01117

Project Name, Number

FLORHAM PARK SA
340703-05
I/I CORRECTION

Priority List Rank

168

County

MORRIS

Existing Population

11,172

Service Area

Florham Park SA WMP Areas

Need for Project

The FPSA owns and operates a collection system, ranging from 1 to 33 years old and interceptor sewers dating back to 1964. During periods of high groundwater or wet weather, the FPSA STP experiences high flows. Peak flows have exceeded 5 MGD.

Project Description

The proposed project consists of a flow monitoring program leading to an I/I reduction program consisting of repair and/or replacement to eliminate excessive quantities of I/I.

Anticipated Recipient	: WESTWOOD BOROUGH			
Project No.	: 340862-01	Eligible Project Cost:	$	971,701
FY08 Rank	: 169			
County	: BERGEN	Total State Amount :	$	971,701

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01092
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01092

Project Name, Number

WESTWOOD BOROUGH
340862-01
I/I CORRECTION

Priority List Rank

169

County

BERGEN

Existing Population

10,920

Service Area

Borough of Westwood

Need for Project

The Bergen County Utilities Authority Infiltration Inflow (I/I) Analysis and Sewer System Evaluation Survey identified excessive I/I in this municipality's sewer system.

Project Description

The excessive I/I will be removed by grouting, slip lining, and other minor rehabilitation methods.

Anticipated Recipient	:	LITTLE FALLS MUA		
Project No.	:	340716-04	Eligible Project Cost:	$ 2,183,362
FY08 Rank	:	170		
County	:	PASSAIC	Total State Amount :	$ 2,183,362

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01086
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01086

Project Name, Number

LITTLE FALLS MUA
340716-04
I/I CORRECTION

Priority List Rank

170

County

PASSAIC

Existing Population

10,855

Service Area

Township of Little Falls

Need for Project

The Little Falls Collection System consists of approximately 120,000 linear feet of pipe in size from six to eighteen inches diameter. Eighty-nine percent of pipe is clay tile, ten percent is asbestos cement, and one percent is cast iron pipe. Interviews with the plant operator indicate that sewers in the western section of Little Falls surcharge and overflow during periods of heavy rain and high Passaic River levels. Overflows also occur at the Hopson Street Pumping Station, which receives sewage flow from the easterly section of Little Falls.

Project Description

This proposed project consists of a sewer system evaluation study utilizing manhole inspection, rainfall simulation, and T.V. inspection and the minor rehabilitation of the Township's existing sewer system to eliminate the portion of the I/I that is excessive.

Anticipated Recipient	: RIVER EDGE BOROUGH			
Project No.	: 340841-01	Eligible Project Cost:	$	458,425
FY08 Rank	: 171			
County	: BERGEN	Total State Amount :	$	458,425

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01064
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01064

Project Name, Number

RIVER EDGE BOROUGH
340841-01
I/I CORRECTION

Priority List Rank

171

County

BERGEN

Existing Population

10,640

Service Area

Borough of River Edge

Need for Project

The Bergen County Utilities Authority Infiltration/Inflow (I/I) Analysis and Sewer System Evaluation Survey identified excessive I/I in this municipality's sewer system.

Project Description

The excessive I/I will be removed by grouting, slip lining, and other minor rehabilitation methods.

Anticipated Recipient	:	WANAQUE VALLEY RSA/WANAQUE BOROUGH		
Project No.	:	340780-02	Eligible Project Cost:	$ 1,567,310
FY08 Rank	:	172		
County	:	PASSAIC	Total State Amount :	$ 1,567,310

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01058
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.01058

Project Name, Number

WANAQUE VALLEY RSA/WANAQUE BOROUGH
340780-02
I/I CORRECTION

Priority List Rank

172

County

PASSAIC

Existing Population

10,580

Service Area

Wanaque Borough

Need for Project

An Infiltration/Inflow (I/I) analysis and Sewer System Evaluation Survey (SSES) have been completed which document the existence of excessive I/I within the service area (Haskell and Whistler Place).

Project Description

This proposed project will consist of I/I correction work to remove the excessive I/I in the Haskell and Whistler Place service areas in Wanaque Borough. This work includes replacement or repair of 4000 linear feet of sewers and approximately 150 service laterals.

Anticipated Recipient	: SAYREVILLE BOROUGH			
Project No.	: 340326-04	Eligible Project Cost:	$	244,515
FY08 Rank	: 173			
County	: MIDDLESEX	Total State Amount :	$	244,515

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01050
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01050

Project Name, Number

SAYREVILLE BOROUGH
340326-04
I/I CORRECTION

Priority List Rank

173

County

MIDDLESEX

Existing Population

10,500

Service Area

Borough of Sayreville (Morgan and Melrose Sections)

Need for Project

The sewer systems in the Morgan and Melrose sections of Sayreville Borough constructed prior to the use of secondary treatment methods did not set strict limits on the volume of infiltration and inflow within sanitary sewers since treatment costs were not greatly affected by these extraneous flows. However, in recent years, the construction costs of conveyance facilities, coupled with rising treatment costs associated with secondary treatment methods, have resulted in efforts to eliminate infiltration and inflow in areas where it is proven to be cost-effective.

Project Description

The proposed project is to provide I/I correction for Sayreville's existing system.

Anticipated Recipient	: FAIRVIEW BOROUGH			
Project No.	: 340517-01	Eligible Project Cost:	$	1,431,112
FY08 Rank	: 174			
County	: BERGEN	Total State Amount :	$	1,431,112

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01034
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.01034

Project Name, Number

FAIRVIEW BOROUGH
340517-01
I/I CORRECTION

Priority List Rank

174

County

BERGEN

Existing Population

10,340

Service Area

Borough of Fairview

Need for Project

BCUA has completed an Infiltration/Inflow (I/I) analysis and Sewer System Evaluation Survey which has identified excessive I/I within the Borough's sewer system and proposed an I/I correction program to eliminate a portion of these extraneous I/I flows.

Project Description

This proposed project may include the grouting and sealing of leaking manholes and sewer lines, repair or adjustments of defective manhole covers, and other minor rehabilitation measures.

Anticipated Recipient	:	LITTLE FERRY BOROUGH		
Project No.	:	340425-01	Eligible Project Cost:	$ 4,915,537
FY08 Rank	:	175		
County	:	BERGEN	Total State Amount :	$ 4,915,537

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00970
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00970

Project Name, Number

LITTLE FERRY BOROUGH
340425-01
SEWER REHABILITATION

Priority List Rank

175

County

BERGEN

Existing Population

9,700

Service Area

Borough of Little Ferry

Need for Project

The existing sanitary sewer collection system serving the Borough of Little Ferry is very old and is subject to an extreme amount of infiltration/inflow (I/I). Rehabilitation of portions of the sanitary sewer system is necessary to remove the excessive I/I. Also, rehabilitation of the Main Street pumping station is required.

Project Description

The proposed project includes rehabilitation of the existing Main Street pumping station and replacement of portions of the existing sanitary sewer collection system which are the source of the extraneous flow.

Anticipated Recipient	: AUDUBON BOROUGH			
Project No.	: 340309-01	Eligible Project Cost:	$	1,094,976
FY08 Rank	: 176			
County	: CAMDEN	Total State Amount :	$	1,094,976

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00921
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00921

Project Name, Number

AUDUBON BOROUGH
340309-01
INFILTRATION/INFLOW

Priority List Rank

176

County

CAMDEN

Existing Population

9,205

Service Area

Audubon Borough

Need for Project

This project is necessary to eliminate excessive infiltration/ inflow (I/I) within the service area.

Project Description

The proposed project will replace sanitary sewer mains and manholes that have lost their structural integrity and/or contain severe sags. Other mains will be sliplined to reduce infiltration/inflow.

Anticipated Recipient	:	HARRISON TOWNSHIP		
Project No.	:	340362-04	Eligible Project Cost:	$ 2,054,490
FY08 Rank	:	177		
County	:	GLOUCESTER	Total State Amount :	$ 2,054,490

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00879
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00879

Project Name, Number

HARRISON TOWNSHIP
340362-04
SEWER REHABILITATION

Priority List Rank

177

County

GLOUCESTER

Existing Population

8,788

Service Area

Harrison Township

Need for Project

Sewers in Harrison Township are deteriorating and in need of replacement. A larger interceptor is needed to handle flows.

Project Description

The proposed project includes replacement of sewer mains and related repairs. A 14-inch interceptor will be replaced with an 18-inch one and approximately 8 manholes and 16 laterals will be replaced.

Anticipated Recipient	:	RUNNEMEDE BOROUGH		
Project No.	:	340363-04	Eligible Project Cost:	$ 1,645,877
FY08 Rank	:	178		
County	:	CAMDEN	Total State Amount :	$ 1,645,877

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00853
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00853

Project Name, Number

RUNNEMEDE BOROUGH
340363-04
PUMP STATION REPLACEMENTS

Priority List Rank

178

County

CAMDEN

Existing Population

8,533

Service Area

Borough of Runnemede

Need for Project

The Runnemede Sewerage Authority’s Pumping Stations C & D are overloaded and need rebuilding and enlarging. Pump station overflows discharge directly into adjacent streams.

Project Description

The proposed project includes replacement of pump stations and installation of larger pumps, onsite standby generators, and automatic monitoring equipment.

Anticipated Recipient	:	HADDON HEIGHTS BOROUGH		
Project No.	:	340877-01	Eligible Project Cost:	$ 1,364,098
FY08 Rank	:	179		
County	:	CAMDEN	Total State Amount :	$ 1,364,098

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00820
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00820

Project Name, Number

HADDON HEIGHTS BOROUGH
340877-01
I/I CORRECTION

Priority List Rank

179

County

CAMDEN

Existing Population

8,200

Service Area

Haddon Heights Borough

Need for Project

The existing collection system in the Borough of Haddon Heights is antiquated and subject to possible excessive infiltration/inflow (I/I).

Project Description

The project consists of the rehabilitation of the sewer system.

Anticipated Recipient	: BOGOTA BOROUGH			
Project No.	: 340914-01	Eligible Project Cost:	$	194,773
FY08 Rank	: 180			
County	: BERGEN	Total State Amount :	$	194,773

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00802
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00802

Project Name, Number

BOGOTA BOROUGH
340914-01
SEWER REHABILITATION

Priority List Rank

180

County

BERGEN

Existing Population

8,020

Service Area

Borough of Bogota

Need for Project

A 1981 report prepared by the Bergen County Utilities Authority identified sources of excessive infiltration and inflow which account for 27% of the total average flow and 78% of peak flow. The sewer system improvements will reduce the infiltration/inflow and increase the efficiency of the treatment plant.

Project Description

The proposed project includes the cleaning, televising, and grouting of approximately 17,000 LF of sanitary sewer pipe, the installation of 10 new manholes, and the rehabilitation of an existing pump station.

Anticipated Recipient	: GLEN RIDGE BOROUGH			
Project No.	: 340861-01	Eligible Project Cost:	$	337,786
FY08 Rank	: 181			
County	: ESSEX	Total State Amount :	$	337,786

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00787
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00787

Project Name, Number

GLEN RIDGE BOROUGH
340861-01
I/I CORRECTION

Priority List Rank

181

County

ESSEX

Existing Population

7,870

Service Area

Borough of Glen Ridge

Need for Project

A sewer system evaluation survey recently performed by Elson T. Killam Associates for the Passaic Valley Sewerage Commissioners' service area found excessive infiltration/inflow (I/I) in this municipality's sewer system.

Project Description

An I/I correction program consisting of grouting slip lining, and minor rehabilitation of structurally damaged pipes and manholes will be undertaken to remove the identified excessive I/I.

Anticipated Recipient	: MONTVALE BOROUGH			
Project No.	: 340846-01	Eligible Project Cost:	$	104,753
FY08 Rank	: 182			
County	: BERGEN	Total State Amount :	$	104,753

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00753
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00753

Project Name, Number

MONTVALE BOROUGH
340846-01
I/I CORRECTION

Priority List Rank

182

County

BERGEN

Existing Population

7,530

Service Area

Borough of Montvale

Need for Project

The Bergen County Utilities Authority Infiltration/Inflow (I/I) Analysis and Sewer System Evaluation Survey identified excessive I/I in this municipality's sewer system.

Project Description

The excessive I/I will be removed by grouting, slip lining, and other minor rehabilitation methods.

Anticipated Recipient	:	MEDFORD TOWNSHIP		
Project No.	:	340346-01	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	183		
County	:	BURLINGTON	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00700
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00700

Project Name, Number

MEDFORD TOWNSHIP
340346-01
SEWER REHABILITATION

Priority List Rank

183

County

BURLINGTON

Existing Population

7,000

Service Area

Portions of the following sewer subsystems in the Township: Village South, Birchwood South and Birchwood North

Need for Project

An Infiltration/Inflow Analysis was performed in 1990 which indicated the major areas of I/I problems. These areas have excessive I/I which reduces the capacity of the Sewage Treatment Plant. The line in the Village South area is a major trunk line in a low lying area that is often flooded and has major infiltration problems. Sewage Treatment Plant improvements need to be carried out to improve plant operations and plant efficiency.

Project Description

The proposed project includes the replacement of approximately 30000 LF of 8", 10", 12" and 18" sanitary sewer, manholes, laterals and related appurtenances. The project will be segmented and the first segment will involve rehabilitation of Himmelein Road sewer and Christopher Mill Road force main. Also, proposed in this segment is the STP improvements which involve installation of grit removal system and sludge thickener cover.

Anticipated Recipient	:	DUNELLEN BOROUGH		
Project No.	:	340916-01	Eligible Project Cost:	$ 1,396,910
FY08 Rank	:	184		
County	:	MIDDLESEX	Total State Amount :	$ 1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00652
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00652

Project Name, Number

DUNELLEN BOROUGH
340916-01
SEWER REHABILITATION

Priority List Rank

184

County

MIDDLESEX

Existing Population

6,520

Service Area

Borough of Dunellen

Need for Project

The majority of the sanitary sewer system of Dunellen was installed around 1915. The system consists of vitrified clay pipe, which has been cracking and failing. Over the past four years, the Borough has had to replace or reline several thousand feet of trunk line at a cost of almost $1 million.

Project Description

The proposed project consists of relining or replacing all the trunk lines in the Borough, upgrading and repair of Borough's pump station, upgrading and sealing manholes, and televising and clean remaining system.

Anticipated Recipient	:	UNION BEACH BOROUGH		
Project No.	:	340278-01	Eligible Project Cost:	$ 2,317,315
FY08 Rank	:	185		
County	:	MONMOUTH	Total State Amount :	$ 2,317,315

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00600
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00600

Project Name, Number

UNION BEACH BOROUGH
340278-01
SEWER REHABILITATION

Priority List Rank

185

County

MONMOUTH

Existing Population

6,000

Service Area

Borough of Union Beach

Need for Project

The Borough’s sanitary sewer system is constantly inundated by groundwater and surface flooding due to its proximity to the shore. The Borough’s sanitary sewer study indicates that many sections of sewer pipe and manholes must be rehabilitated to reduce extraneous flows, which are costly to treat.

Project Description

The proposed project involves rehabilitation by grouting, lining, repair and/or replacement of troubled sewer lines which are identified in the Borough’s I/I study.

Anticipated Recipient	:	LOPATCONG TOWNSHIP		
Project No.	:	340264-02	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	186		
County	:	WARREN	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00577
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00577

Project Name, Number

LOPATCONG TOWNSHIP
340264-02
SEWER REHABILITATION

Priority List Rank

186

County

WARREN

Existing Population

5,765

Service Area

Lopatcong Township

Need for Project

The southern portion of the Township’s sewage system drains to two pump stations. The sewage is then pumped to the Township of Phillipsburg sewage system for treatment. These two pump stations are over 20 years old and require extensive maintenance to keep them operable. The Township is planning to either upgrade these facilities or possibly construct an interceptor sewer to replace them. Also several sanitary sewers throughout the Township are in need of replacement. This project will address these known problem areas and provide the Township with a reliable system.

Project Description

The proposed project includes the construction of gravity sewers and a force main in conjunction with the upgrade or replacement of the Baltimore Street Pump Station. The likely plan is to eliminate the Baltimore Street PS and intercept its flow with a gravity sewer that will lead to the Morris Heights PS. The Morris Heights PS will either be expanded or eliminated and replaced by an interceptor that will connect to the Phillipsburg system. Additionally, several pipes in the collection system will be replaced to improve problem areas.

Anticipated Recipient	:	N ARLINGTON - LYNDHURST JT MTG (NARL)		
Project No.	:	340426-06	Eligible Project Cost:	$ 218,940
FY08 Rank	:	187		
County	:	BERGEN	Total State Amount :	$ 218,940

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00559
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00559

Project Name, Number

N ARLINGTON - LYNDHURST JT MTG (NARL)
340426-06
SEWER REHABILITATION

Priority List Rank

187

County

BERGEN

Existing Population

5,590

Service Area

Portions of the Borough of North Arlington

Need for Project

The Joint Meeting has conducted an Infiltration/Inflow (I/I) analysis and concluded that excessive I/I exists in the sewer system. A sewer system evaluation survey has evaluated flow conditions and identified the sewer segments which are cost-effective to rehabilitate. Further sewer system evaluation work will propose an I/I correction program to reduce the excessive I/I flows.

Project Description

This proposed project will consist of an I/I correction program to remove a portion of the excessive I/I flows. This may include grouting of sewer joints, sealing manholes, repairs or replacement of defective manhole covers, and other major rehabilitation measures such as removal and replacement of defective sewer pipes and relining of sewer pipes.

Anticipated Recipient	:	N ARLINGTON-LYNDHURST JT MTG (LYND)		
Project No.	:	340426-05	Eligible Project Cost:	$ 4,688,749
FY08 Rank	:	187		
County	:	BERGEN	Total State Amount :	$ 4,688,749

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00559
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00559

Project Name, Number

N ARLINGTON-LYNDHURST JT MTG (LYND)
340426-05
I/I CORRECTION

Priority List Rank

187

County

BERGEN

Existing Population

5,590

Service Area

Borough of Lyndhurst

Need for Project

The Joint Meeting has conducted an Infiltration/Inflow (I/I) analysis and concluded that excessive I/I exists in the sewer system. A sewer system evaluation survey has evaluated flow conditions and identified the sewer segments which are cost-effective to rehabilitate. Further sewer system evaluation work will propose an I/I correction program to reduce the excessive I/I flows.

Project Description

This proposed project will consist of an I/I correction program to remove a portion of the excessive I/I flows. This may include grouting of sewer joints, sealing manholes, repairs or replacement of defective manhole covers, and other minor rehabilitation measures.

Anticipated Recipient	:	ROCHELLE PARK TOWNSHIP		
Project No.	:	340310-01	Eligible Project Cost:	$ 2,255,626
FY08 Rank	:	187		
County	:	BERGEN	Total State Amount :	$ 2,255,626

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00559
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00559

Project Name, Number

ROCHELLE PARK TOWNSHIP
340310-01
SEWER REHABILITATION

Priority List Rank

187

County

BERGEN

Existing Population

5,587

Service Area

Rochelle Park Township

Need for Project

The sewer main connecting the Township system to the Bergen County UA interceptor is forty years old and has been experiencing blockages due to deterioration. Two pump stations need to be upgraded to allow them to operate as originally intended.

Project Description

The proposed project includes the installation of a new trunk sewer main from the Township’s main pump station to a Bergen County UA interceptor. The existing line will be abandoned in place. The Township’s main pump station will have a second comminutor unit, a backup sanitary sewer pump, and a new pump control system installed. The Sprout Brook Pump Station will be upgraded by replacing the existing pumps, motors and control system with new ones.

Anticipated Recipient	: SPRING LAKES HEIGHTS, BOROUGH OF			
Project No.	: 340840-01	Eligible Project Cost:	$	163,328
FY08 Rank	: 190			
County	: MONMOUTH	Total State Amount :	$	163,328

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00537
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00537

Project Name, Number

SPRING LAKES HEIGHTS, BOROUGH OF
340840-01
I/I CORRECTION

Priority List Rank

190

County

MONMOUTH

Existing Population

5,370

Service Area

Borough of Spring Lake Heights

Need for Project

Excessive infiltration/inflow has been discovered in the Borough's sewer system and is causing unnecessarily high processing charges for sewage treatment. Further studies will be performed to further define the sources of the excessive I/I.

Project Description

The scope of future work is unknown at the present time but may entail the repair of leaking joints and catch basins.

Anticipated Recipient	:	MORRIS PLAINS BOROUGH		
Project No.	:	340330-01	Eligible Project Cost:	$ 479,390
FY08 Rank	:	191		
County	:	MORRIS	Total State Amount :	$ 479,390

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00524
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00524

Project Name, Number

MORRIS PLAINS BOROUGH
340330-01
SEWER REHABLITATION

Priority List Rank

191

County

MORRIS

Existing Population

5,236

Service Area

Borough of Morris Plains

Need for Project

The Borough’s pump station is 27 years old and in need of an upgrade to reduce the possibility of a malfunction and a stream discharge.

Project Description

The proposed project includes the replacement of the Boroughs pump station.

Anticipated Recipient	: NEPTUNE CITY BOROUGH			
Project No.	: 340106-02	Eligible Project Cost:	$	430,399
FY08 Rank	: 192			
County	: MONMOUTH	Total State Amount :	$	430,399

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00522
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00522

Project Name, Number

NEPTUNE CITY BOROUGH
340106-02
SEWER REHABILITATION

Priority List Rank

192

County

MONMOUTH

Existing Population

5,218

Service Area

Borough of Neptune City

Need for Project

The existing pump station is aging, in need of repair, and undersized to handle current flows.

Project Description

The proposed project is for the replacement the existing pump station.

Anticipated Recipient	: HIGHLANDS BOROUGH			
Project No.	: 340901-01	Eligible Project Cost:	$	877,696
FY08 Rank	: 193			
County	: MONMOUTH	Total State Amount :	$	877,696

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00519
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00519

Project Name, Number

HIGHLANDS BOROUGH
340901-01
I/I CORRECTION

Priority List Rank

193

County

MONMOUTH

Existing Population

5,190

Service Area

Highlands Borough

Need for Project

Sewer rehabilitation is necessary to correct excessive I/I. The current flow is equal to the amount designated for the year 2000. The completion of the work in the I/I report will reduce the infiltration and the additional charges for pumping and treatment.

Project Description

I/I correction utilizing standard sewer rehabilitation methods. A minor portion of the work in the I/I report is complete, and thus is ineligible for federal participation.

Anticipated Recipient	:	FRANKLIN BOROUGH		
Project No.	:	340129-01	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	194		
County	:	SUSSEX	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00516
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00516

Project Name, Number

FRANKLIN BOROUGH
340129-01
PUMP STATION IMPROVEMENTS

Priority List Rank

194

County

SUSSEX

Existing Population

5,160

Service Area

Borough of Franklin

Need for Project

An existing pump station in Franklin must be upgraded to operate during 100 year flood conditions, to meet future demands, and to improve operation and ease maintenance.

Project Description

The project includes improvements to the Route 23 pump station.

Anticipated Recipient	: PENNS GROVE SA			
Project No.	: 340502-05	Eligible Project Cost:	$	556,107
FY08 Rank	: 195			
County	: SALEM	Total State Amount :	$	556,107

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00489
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00489

Project Name, Number

PENNS GROVE SA
340502-05
SEWER REHABILITATION

Priority List Rank

195

County

SALEM

Existing Population

4,886

Service Area

Penns Grove Borough

Need for Project

This project is necessary to eliminate blocked sewer lines and excessive infiltration/ inflow (I/I) within the service area.

Project Description

The proposed project will replace sanitary sewer mains and manholes that have lost their structural integrity and/or contain severe sags. Other mains will be sliplined or replaced.

Anticipated Recipient	: HIGHLANDS BOROUGH			
Project No.	: 340901-02	Eligible Project Cost:	$	147,540
FY08 Rank	: 196			
County	: MONMOUTH	Total State Amount :	$	147,540

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00485
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00485

Project Name, Number

HIGHLANDS BOROUGH
340901-02
I/I CORRECTION

Priority List Rank

196

County

MONMOUTH

Existing Population

4,850

Service Area

Borough of Highlands

Need for Project

To reduce elevated levels of bacteria in stormwater discharges to coastal waters.

Project Description

To eliminate cross-connections between sanitary and storm sewers by replacing portions of sewers, sealing manholes, and sealing leaks. To eliminate interconnections due to leaks, flows, or overflows from the sanitary sewer system.

Anticipated Recipient	: ROSELAND BOROUGH			
Project No.	: 340361-01	Eligible Project Cost:	$	123,712
FY08 Rank	: 196			
County	: ESSEX	Total State Amount :	$	123,712

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00485
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00485

Project Name, Number

ROSELAND BOROUGH
340361-01
I/I CORRECTION

Priority List Rank

196

County

ESSEX

Existing Population

4,850

Service Area

Borough of Roseland

Need for Project

The excessive inflow and infiltration condition results in surcharging of the collection system. In addition, the excess flow is being directed to the Caldwell STP and these additional volumes result in higher treatment costs to the Borough of Roseland.

Project Description

The Borough has conducted preliminary field investigations and determined that several residential neighborhoods are experiencing significant inflow/infiltration problems. These impacted areas represent approximately twenty (20) percent of the utility users. The Borough will embark upon final studies to determine the exact location and magnitude of the problems. The rehabilitation work will include air testing and chemical grouting of approximately 8,000 linear feet of sanitary sewer.

Anticipated Recipient	: HARRISON TOWNSHIP			
Project No.	: 340362-01	Eligible Project Cost:	$	3,125,171
FY08 Rank	: 198			
County	: GLOUCESTER	Total State Amount :	$	3,125,171

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00472
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00472

Project Name, Number

HARRISON TOWNSHIP
340362-01
SYSTEM REHABILITATION

Priority List Rank

198

County

GLOUCESTER

Existing Population

4,720

Service Area

Harrison Township

Need for Project

The sanitary sewer system is approximately 25 to 30 years old and was constructed of terra cotta pipe. A majority of these sewer mains are located in low lying areas adjacent to wetlands or streams. In addition, the 11 pump stations are also 25 to 30 years old and are in need of rehabilitation to bring them up to current operational standards. Several of the pump stations do not have back-up emergency generators or other alternate power source.

Project Description

The Township will repair and/or replace those sections of the sewer system which experience problems. Also included is the necessary work to upgrade the existing pump stations to current standards.

Anticipated Recipient	:	SAYREVILLE BOROUGH		
Project No.	:	340326-07	Eligible Project Cost:	$ 4,688,749
FY08 Rank	:	199		
County	:	MIDDLESEX	Total State Amount :	$ 4,688,749

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00443
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00443

Project Name, Number

SAYREVILLE BOROUGH
340326-07
I/I CORRECTION

Priority List Rank

199

County

MIDDLESEX

Existing Population

4,430

Service Area

Sayreville Borough

Need for Project

The southern and western portions of the Morgan Section of the Borough of Sayreville are presently served by a series of six municipal pump stations and one privately owned pump station which convey the wastewater flow to the Middlesex County Utilities Authority's secondary treatment facility. The gravity collection system downstream of the discharge of a major basin pumping station is subject to surcharge to the point of overflow during dry weather, peak flow periods. Anticipated growth in the area will additionally stress the already overloaded conveyance facilities.

Project Description

The proposed project calls for the construction of a gravity interceptor, regional pump station and force main, and the upgrading of four existing sub-regional pump stations. The wastewater flow will ultimately discharge directly to the Middlesex County Utilities Authority gravity sewer which runs parallel to the New York and Long Branch railroad.

Anticipated Recipient	: FLEMINGTON BOROUGH			
Project No.	: 340440-04	Eligible Project Cost:	$	1,645,877
FY08 Rank	: 200			
County	: HUNTERDON	Total State Amount :	$	1,645,877

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00420
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00420

Project Name, Number

FLEMINGTON BOROUGH
340440-04
I/I CORRECTION

Priority List Rank

200

County

HUNTERDON

Existing Population

4,200

Service Area

Borough of Flemington

Need for Project

The Borough’s sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system and at the treatment plant site during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system and sewage treatment plant. The project involves an infiltration/inflow correction program including relining of pipes and removal of stormwater connections.

Anticipated Recipient	:	MEDFORD LAKES BOROUGH		
Project No.	:	340319-01	Eligible Project Cost:	$ 289,789
FY08 Rank	:	201		
County	:	BURLINGTON	Total State Amount :	$ 289,789

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00417
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00417

Project Name, Number

MEDFORD LAKES BOROUGH
340319-01
SEWER REHABILITATION

Priority List Rank

201

County

BURLINGTON

Existing Population

4,173

Service Area

Borough of Medford Lakes

Need for Project

The Borough's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the sewer system.

Anticipated Recipient	: DELAWARE TOWNSHIP MUA			
Project No.	: 340917-02	Eligible Project Cost:	$	430,399
FY08 Rank	: 202			
County	: HUNTERDON	Total State Amount :	$	430,399

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00398
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00398

Project Name, Number

DELAWARE TOWNSHIP MUA
340917-02
I/I CORRECTION

Priority List Rank

202

County

HUNTERDON

Existing Population

3,980

Service Area

Sergeantsville Light District

Need for Project

The Sergeantsville Light district is experiencing excessive infiltration. The collection system must be inspected to identify and correct the cause(s) of infiltration.

Project Description

The proposed project will include smoke testing and video camera inspection of approximately 10,000 linear feet of sewer line. In addition, cracks will be grouted and any collapsed or obstructed lines repaired.

Anticipated Recipient	: HIGH BRIDGE BOROUGH			
Project No.	: 340842-01	Eligible Project Cost:	$	243,967
FY08 Rank	: 203			
County	: HUNTERDON	Total State Amount :	$	243,967

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00377
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00377

Project Name, Number

HIGH BRIDGE BOROUGH
340842-01
I/I CORRECTION

Priority List Rank

203

County

HUNTERDON

Existing Population

3,770

Service Area

Borough of High Bridge

Need for Project

The Borough of High Bridge suspects excessive Infiltration/Inflow quantities to be present in their municipal sewerage system.

Project Description

Pending study by the Borough, the excessive I/I is proposed to be removed by grouting, manhole replacement and other minor rehabilitation methods.

Anticipated Recipient	: STANHOPE BOROUGH			
Project No.	: 340504-02	Eligible Project Cost:	$	415,019
FY08 Rank	: 204			
County	: SUSSEX	Total State Amount :	$	415,019

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00370
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00370

Project Name, Number

STANHOPE BOROUGH
340504-02
I/I CORRECTION

Priority List Rank

204

County

SUSSEX

Existing Population

3,700

Service Area

Stanhope Borough

Need for Project

A study was performed on the existing sanitary sewer system and it was determined that the possibility of excess infiltration/inflow does exist.

Project Description

A continuation of this study has been submitted to NJDEP and will be evaluated shortly. If the study confirms that infiltration/inflow does exist, then I/I correction of the system will be implemented.

Anticipated Recipient	: POHATCONG TOWNSHIP			
Project No.	: 340109-01	Eligible Project Cost:	$	706,450
FY08 Rank	: 205			
County	: WARREN	Total State Amount :	$	706,450

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00342
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00342

Project Name, Number

POHATCONG TOWNSHIP
340109-01
I/I CORRECTION

Priority List Rank

205

County

WARREN

Existing Population

3,416

Service Area

Pohatcong Township

Need for Project

The Township’s sanitary sewer system is subject to inflow and infiltration causing sewage to back up in the collection system.

Project Description

The proposed project includes cleaning and lining of approximately 10,400 L.F. of existing pipe, removing and replacing approximately 600 L.F. of exiting pipe, grouting and sealing 40 manholes and cleanouts, and replacing or repairing 20 leaking sevice connections.

Anticipated Recipient	: DELANCO TOWNSHIP SA			
Project No.	: 340956-02	Eligible Project Cost:	$	1,854,849
FY08 Rank	: 206			
County	: BURLINGTON	Total State Amount :	$	1,854,849

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00324
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00324

Project Name, Number

DELANCO TOWNSHIP SA
340956-02
SEWER REHABILITATION

Priority List Rank

206

County

BURLINGTON

Existing Population

3,237

Service Area

Delanco Township

Need for Project

The Borough's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system and at the treatment plant site during wet weather periods. The Hickory Street Pump Station and the existing trunk sewer are not adequate to handle peak flows causing back-ups and overflows.

Project Description

The project includes replacement or relining of 8000 feet sewer lines, construction of 10 new manholes, sealing 110 existing manholes, and inspection of another 5100 feet 0of sewer line. The Hickory Street Pump Station will be rehabilitated and upgraded, and a new force main constructed to by-pass the existing trunk sewer.

Anticipated Recipient	:	WOODBURY HEIGHTS BOROUGH		
Project No.	:	340257-02	Eligible Project Cost:	$ 1,841,186
FY08 Rank	:	207		
County	:	GLOUCESTER	Total State Amount :	$ 1,841,186

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00299
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00299

Project Name, Number

WOODBURY HEIGHTS BOROUGH
340257-02
SEWER REHABILITATION

Priority List Rank

207

County

GLOUCESTER

Existing Population

2,988

Service Area

Borough of Woodbury Heights

Need for Project

The Borough's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system during wet weather periods.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the sewer system.

Anticipated Recipient	: SEA ISLE CITY			
Project No.	: 340659-01	Eligible Project Cost:	$	667,397
FY08 Rank	: 208			
County	: CAPE MAY	Total State Amount :	$	667,397

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00295
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00295

Project Name, Number

SEA ISLE CITY
340659-01
I/I CORRECTION

Priority List Rank

208

County

CAPE MAY

Existing Population

2,950

Service Area

Sea Isle City

Need for Project

The Sea Isle City collection system is subject to possible excessive amounts of infiltration/inflow (I/I) as documented in a sewer system evaluation survey.

Project Description

The proposed rehabilitation tasks include: cleaning and inspection, repair and/or replacement of damaged or deteriorated sewer pipes and manholes.

Anticipated Recipient	: MOONACHIE BOROUGH			
Project No.	: 340970-02	Eligible Project Cost:	$	332,158
FY08 Rank	: 209			
County	: BERGEN	Total State Amount :	$	332,158

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00279
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00279

Project Name, Number

MOONACHIE BOROUGH
340970-02
I/I CORRECTION

Priority List Rank

209

County

BERGEN

Existing Population

2,790

Service Area

Borough of Moonachie

Need for Project

An Infiltration/Inflow study conducted by the Bergen County Utilities Authority identified Meter Area 146 (Moonachie Avenue Pumping Station) as requiring sewer rehabilitation.

Project Description

The proposed project includes the televised inspection and repair of sewers which are the source of extraneous flow.

Anticipated Recipient	:	WOODLYNNE BOROUGH		
Project No.	:	340849-01	Eligible Project Cost:	$ 4,264,056
FY08 Rank	:	210		
County	:	CAMDEN	Total State Amount :	$ 4,264,056

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00258
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00258

Project Name, Number

WOODLYNNE BOROUGH
340849-01
I/I CORRECTION

Priority List Rank

210

County

CAMDEN

Existing Population

2,580

Service Area

Woodlynne Borough

Need for Project

The existing collection system is deteriorated with cracked pipes and open joints. Consequently, the infiltration/inflow (I/I) levels in the sewer system is possibly excessive.

Project Description

The proposed project consists of rehabilitation of the sewer system through the replacement of existing cracked pipes with PVC lines.

Anticipated Recipient	: ALPHA BOROUGH			
Project No.	: 340324-01	Eligible Project Cost:	$	639,645
FY08 Rank	: 211			
County	: WARREN	Total State Amount :	$	639,645

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00248
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00248

Project Name, Number

ALPHA BOROUGH
340324-01
SEWER REHABILITATION

Priority List Rank

211

County

WARREN

Existing Population

2,482

Service Area

Borough of Alpha

Need for Project

The Borough has been experiencing pipe collapses plus other problems due to undersized, tuberculated pipes. The Borough's pump station needs to be rehabilitated and upgraded to handle increased flows.

Project Description

The proposed project includes the replacement of gravity sewers and installation of new flow monitoring equipment. Pump station improvements include wet well rehabilitation, new pumps and controllers, chemical feed equipment, and emergency generator.

Anticipated Recipient	:	GIBBSBORO BOROUGH		
Project No.	:	340871-03	Eligible Project Cost:	$ 1,518,344
FY08 Rank	:	212		
County	:	CAMDEN	Total State Amount :	$ 1,518,344

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00244
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00244

Project Name, Number

GIBBSBORO BOROUGH
340871-03
SEWER REHABILITATION

Priority List Rank

212

County

CAMDEN

Existing Population

2,435

Service Area

Borough of Gibbsboro

Need for Project

Many of the sanitary sewer mains and service laterals in the Development Section of the Borough are in very poor, deteriorated condition and have outlived their expected service life of forty years.

Project Description

The proposed project includes replacement of approximately six sanitary sewer manholes, 2,226 linear feet of 8” diameter pipe main, 228 linear feet of 10” diameter pipe, 65 service laterals and clean outs. Approximately 1,00 linear feet of slip lining is also proposed. Some stormwater work is also proposed including construction of a precast concrete headwall within the existing drainage ditch and stabilization of the slopes with erosion control matting. Replacement of 50 feet of 15” diameter storm main is also proposed.

Anticipated Recipient	: AVON-BY-THE-SEA BOROUGH			
Project No.	: 340335-01	Eligible Project Cost:	$	3,973,856
FY08 Rank	: 213			
County	: MONMOUTH	Total State Amount :	$	3,973,856

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00235
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00235

Project Name, Number

AVON-BY-THE-SEA BOROUGH
340335-01
SEWER REHABILITATION

Priority List Rank

213

County

MONMOUTH

Existing Population

2,350

Service Area

Avon-By-The-Sea

Need for Project

An economic study of flow level with sewer improvements versus Township of Neptune Sewerage Authority current charges for flow, indicates that flow levels may be in excess of contractual amounts. The excessive flow results in dilute flow into the treatment plant. This contributes to unwarranted costs and possible penalties for excessive flow. The original sewer system was constructed prior to 1920.

Project Description

The proposed project would reduce infiltration of groundwater into the existing sewer system and includes sleeving/lining of the sanitary sewers, grouting all connections to the trunk sewers, repairing and replacing manholes and the replacement of the deteriorated sewer on Lincoln Lane.

Anticipated Recipient	:	LAVALETTE BOROUGH		
Project No.	:	340966-03	Eligible Project Cost:	$ 2,526,305
FY08 Rank	:	214		
County	:	OCEAN	Total State Amount :	$ 2,526,305

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00230
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00230

Project Name, Number

LAVALETTE BOROUGH
340966-03
SEWER REHABILITATION

Priority List Rank

214

County

OCEAN

Existing Population

2,300

Service Area

Borough of Lavallette

Need for Project

The project is needed to effectively limit infiltration/inflow into the sanitary sewer system. This will alleviate adverse downstream impacts on infrastructure and will reduce wastewater treatment costs.

Project Description

The proposed project involves the Phase III Sanitary Sewer Rehabilitation activities which includes cleaning, videoing and lining sewers, the replacement of deteriorated sections of sewer, lateral testing and sealing, rehabilitation of manhole structures, etc.

Anticipated Recipient	: LAVALETTE BOROUGH			
Project No.	: 340966-02	Eligible Project Cost:	$	430,399
FY08 Rank	: 215			
County	: OCEAN	Total State Amount :	$	430,399

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00229
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00229

Project Name, Number

LAVALETTE BOROUGH
340966-02
I/I CORRECTION

Priority List Rank

215

County

OCEAN

Existing Population

2,290

Service Area

Borough of Lavallette

Need for Project

The investigate the presence of any cross connections and repair same to eliminate contamination of bay waters from leaking or improperly installed sanitary sewage systems.

Project Description

Hydraulically clean storm sewer pipes and inspect to locate and determine all cross connections. Once cross connections have been located, affect repairs of same to eliminate contamination and install pinch type check valves.

Anticipated Recipient	: WEYMOUTH TOWNSHIP MUA			
Project No.	: 340713-02	Eligible Project Cost:	$	570,013
FY08 Rank	: 216			
County	: ATLANTIC	Total State Amount :	$	570,013

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00226
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00226

Project Name, Number

WEYMOUTH TOWNSHIP MUA
340713-02
SEWER REHABILITATION

Priority List Rank

216

County

ATLANTIC

Existing Population

2,257

Service Area

Weymouth Township

Need for Project

The Township’s sanitary sewer system is inundated by infiltration and tidal flooding causing discharges at the pump station and through manholes.

Project Description

The proposed project involves replacement and upgrade of the pump station, replacement of all sewer laterals, and replacement of manhole covers.

Anticipated Recipient	: PEAPACK & GLADSTONE BOROUGH			
Project No.	: 340822-01	Eligible Project Cost:	$	125,409
FY08 Rank	: 217			
County	: SOMERSET	Total State Amount :	$	125,409

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00212
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00212

Project Name, Number

PEAPACK & GLADSTONE BOROUGH
340822-01
I/I CORRECTION

Priority List Rank

217

County

SOMERSET

Existing Population

2,120

Service Area

Entire Borough of Peapack-Gladstone

Need for Project

The existing sewer system has excessive I/I. Rehabilitation is necessary to remove excessive I/I, and to extend the useful life of the sewer system.

Project Description

The Borough has completed a TV & grouting program to reduce infil- tration. The scope of the SSES will be reviewed after these measures are evaluated. The survey should consider inflow problems identified in subsystems 3, 4 and 5, which are defined in the original analysis (201 facilities plan).

Anticipated Recipient	: WYCKOFF TOWNSHIP		
Project No.	: 340738-03	Eligible Project Cost:	$ 14,494,384
FY08 Rank	: 218		
County	: BERGEN	Total State Amount :	$ 14,494,384

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	25
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	100
Nutrients	0	25	50	0
Toxics	0	25	50	50
			Subtotal	150
			State Planning Commission	0.00000
			Population	0.00190
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00190

Project Name, Number

WYCKOFF TOWNSHIP
340738-03
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

218

County

BERGEN

Existing Population

1,900

Service Area

Township of Wyckoff

Need for Project

The area is served by on-site septic systems. The majority of these systems do not function satisfactorily, primarily due to poor soil conditions and the age of the individual systems. Health records along with on-site inspections and surveys indicate failing septics are contributing to the degradation of HoHoKus Brook (FW2-NT), consequently impacting fishable non-trout and industrial uses. Water quality in the area does not meet standards for fecal coliform and toxics.

Project Description

Project is currently in the design stage and will involve construction of 71,600 linear feet of lateral sewer and interceptors to replace septic systems. This project, along with C340739-02 (collection system, P.S.) and C340482-02 (pump station, force main, and interceptor) provides an integrated collection system for the Township. Flows will be conveyed to the Northeast Bergen County Utilities Authority interceptor sewer.

Anticipated Recipient	: ALLENTOWN BOROUGH			
Project No.	: 340567-04	Eligible Project Cost:	$	570,013
FY08 Rank	: 219			
County	: MONMOUTH	Total State Amount :	$	570,013

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00188
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00188

Project Name, Number

ALLENTOWN BOROUGH
340567-04
I/I CORRECTION

Priority List Rank

219

County

MONMOUTH

Existing Population

1,882

Service Area

Borough of Allentown

Need for Project

The Borough's sanitary sewer system is subject to excessive amounts of inflow and infiltration causing sewage to overflow in the collection system and at the treatment plant site during wet weather periods. Allentown’s wastewater treatment plant needs upgrades and replacement of deteriorated, outdated equipment to improve removal efficancy and reduce the chance of surcharge or overflow.

Project Description

The purpose of the project is to reduce rainfall-induced surcharging of the collection system and sewage treatment plant. The project involves an infiltration/inflow correction program in conjunction with the replacement/rehabilitation of sections of the sewer system. Upgrade of the treatment plant would include electrical and control system replacement, installation of a comminutor, replacement of trickling filter media, chemical feed systems modifications, RBC reconstruction, and other miscellaneous improvements.

Anticipated Recipient	:	DEAL BOROUGH		
Project No.	:	340412-08	Eligible Project Cost:	$ 1,259,960
FY08 Rank	:	220		
County	:	MONMOUTH	Total State Amount :	$ 1,259,960

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00185
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00185

Project Name, Number

DEAL BOROUGH
340412-08
I/I CORRECTION

Priority List Rank

220

County

MONMOUTH

Existing Population

1,850

Service Area

Borough of Deal

Need for Project

The Infiltration/Inflow (I/I) analysis of the collection system indicates that the city sewerage system has excessive I/I which can be removed cost-effectively.

Project Description

The proposed project will be for an Infiltration/Inflow correction program to eliminate excessive I/I from the sewerage system.

Anticipated Recipient	: SHIP BOTTOM BOROUGH			
Project No.	: 340311-02	Eligible Project Cost:	$	805,887
FY08 Rank	: 221			
County	: OCEAN	Total State Amount :	$	805,887

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00138
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00138

Project Name, Number

SHIP BOTTOM BOROUGH
340311-02
SEWER REHABILITATION

Priority List Rank

221

County

OCEAN

Existing Population

1,384

Service Area

Borough of Ship Bottom

Need for Project

The Borough of Ship Bottom inspected and televised the conditions of their 79,000 LF sanitary sewer system between 1997 and 1998. Based on the deterioration found in the existing asbestos cement sewer system and the potential for collapse of critical sections, the Borough determined that a sewer system rehabilitation project is required.

Project Description

This proposed project will consist sewer repair/replacement project. This will include replacement of sections of sanitary sewer pipe, grouting of sewer lines, grouting and sealing leaking manholes and repair of and adjustments to defective manholes.

Anticipated Recipient	:	BAY HEAD BOROUGH		
Project No.	:	340590-02	Eligible Project Cost:	$ 2,230,279
FY08 Rank	:	222		
County	:	OCEAN	Total State Amount :	$ 2,230,279

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00134
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	450.00134

Project Name, Number

BAY HEAD BOROUGH
340590-02
I/I CORRECTION

Priority List Rank

222

County

OCEAN

Existing Population

1,340

Service Area

Bay Head Borough

Need for Project

The Borough of Bay Head has an old sewerage collection system consisting of clay pipes and lead joints. Cracked pipes and weak joints lead to excessive infiltration/inflow to the existing sanitary sewers. During wet weather, the infiltration/inflow to the system peaks at 0.8 mgd. It is cost effective to perform I/I correction as compared to transporting and treating these extraneous flows at the Ocean County Utilities Authority Wastewater Treatment Facility.

Project Description

At present the project is in Phase II of SSES. This consists of preparatory cleaning and internal TV inspection of 15,281 linear feet and smoke testing of 29,005 linear feet of sewer line. Dye water flooding and dye tracing will be done at the conclusion of smoke testing. In addition, a pilot grouting program of the worst 10 lines will also be undertaken during this phase and the results so obtained will be used in the subsequent work in Phase 3, which will consist of the I/I correction of the remaining lines with excessive infiltration/inflow, grouting of 17 leaking manholes and utilizing manhole inserts to eliminate inflow in 47 manholes. The I/I correction program will remove extraneous flow from this sewer system.

Anticipated Recipient	: MANSFIELD TOWNSHIP			
Project No.	: 340935-02	Eligible Project Cost:	$	147,540
FY08 Rank	: 223			
County	: WARREN	Total State Amount :	$	147,540

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00100
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00100

Project Name, Number

MANSFIELD TOWNSHIP
340935-02
I/I CORRECTION

Priority List Rank

223

County

WARREN

Existing Population

1,000

Service Area

Diamond Hill Development

Need for Project

The treatment plant is inundated during heavy rainfall.

Project Description

Work under this project will include, but not necessarily be limited to, minor cleaning and TV inspection of sewer lines, joint pressure testing to determine if sealing is required to eliminate infiltration, manhole sealing if required, and root removal.

Anticipated Recipient	:	ROOSEVELT BOROUGH		
Project No.	:	340761-02	Eligible Project Cost:	$ 1,522,661
FY08 Rank	:	224		
County	:	MONMOUTH	Total State Amount :	$ 1,522,661

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	450
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	450

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00085
BDA Points	0
Transit Villages	0
TOTAL POINTS	450.00085

Project Name, Number

ROOSEVELT BOROUGH
340761-02
I/I CORRECTION

Priority List Rank

224

County

MONMOUTH

Existing Population

850

Service Area

Borough of Roosevelt

Need for Project

The existing collection system serving the Borough of Roosevelt is very old, and is subject to an extreme amount of I/I. Replacement of the existing sewers will eliminate a portion of excessive I/I in approximately 22,000 LF of collection system serving the Borough.

Project Description

The proposed project will consist of removal and replacement of the existing VTP sanitary lines with new PVC lines to provide for watertight joints and eliminate dips. Aged manholes and portions of house connections will be replaced. Certain manholes will be treated with a bonding agent to seal the internal walls.

Anticipated Recipient	: PASSAIC VALLEY SC		
Project No.	: 340683-05	Eligible Project Cost:	$ 132,505,940
FY08 Rank	: 225		
County	: ESSEX	Total State Amount :	$ 132,505,940

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	1.35000
BDA Points	0
Transit Villages	0
TOTAL POINTS	401.35000

Project Name, Number

PASSAIC VALLEY SC
340683-05
SLUDGE TREATMENT & DISPOSAL

Priority List Rank

225

County

ESSEX

Existing Population

1,350,000

Service Area

Various communities in Bergen, Essex, Hudson, and Passaic counties

Need for Project

PVSC operates a 230 mgd secondary sewage treatment plant which produces 945,000 dry pounds/day of sludge which is currently dewatered and shipped to Texas. This interim sludge disposal alternative was implemented by the PVSC in order to enable the PVSC to cease the ocean dumping of sewage sludge as mandated by federal and state legislation. However, this practice is costly and its future availability is uncertain.

Project Description

The proposed project would provide a long-term method for the disposal of sewage sludge. A Step 1 grant was awarded in January 1977 for a land-based sludge management study which recommended the implementation of a sludge disposal scheme consisting of a belt filter press for dewatering and incineration. The Sludge Management Plan dated June 1989 recommended a fluidized bed incinerator be constructed as a long-term plan. The PVSC will be required to appropriately update the Sludge Management Plan to ensure that adequate consideration of beneficial reuse alternatives has been included, as required by the Department's White Paper on Beneficial Use of Sewage Sludge, issued in November 1990.

Anticipated Recipient	: PASSAIC VALLEY SEWERAGE COMMISSIONERS		
Project No.	: 340689-06	Eligible Project Cost:	$ 63,223,700
FY08 Rank	: 225		
County	: ESSEX	Total State Amount :	$ 63,223,700

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	1.35000
BDA Points	0
Transit Villages	0
TOTAL POINTS	401.35000

Project Name, Number

PASSAIC VALLEY SEWERAGE COMMISSIONERS

340689-06

SLUDGE MANAGEMENT

Priority List Rank

225

County

ESSEX

Existing Population

1,350,000

Service Area

Parts of Bergen, Essex, Hudson and Passaic Counties

Need for Project

The Passaic Valley Sewerage Commissioners are investigating improvements to their STP, NJPDES No. NJ0021016. The high strength Zimpro sidestream is returned to the activated sludge treatment plant which leads to instability in the activated sludge process. Other improvements are needed to the the sludge processing equipment.

Project Description

The proposed project includes an anaerobic treatment system for the high strength Zimpro sidestream, methane gas recovery and electrical generation facility and various improvements to the sludge processing equipment.

Anticipated Recipient	: CAMDEN CITY			
Project No.	: 340366-02	Eligible Project Cost:	$	667,397
FY08 Rank	: 227			
County	: CAMDEN	Total State Amount :	$	667,397

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.08700
BDA Points	0
Transit Villages	0
TOTAL POINTS	400.08700

Project Name, Number

CAMDEN CITY
340366-02
SLUDGE MANAGEMENT

Priority List Rank

227

County

CAMDEN

Existing Population

87,000

Service Area

City of Camden

Need for Project

The City has identified a need to increase capacity of the Morris-Delair potable water treatment plant’s residuals handling system.

Project Description

The proposed project consists of the purchase and installation of a plate drying bed system.

Anticipated Recipient	: ASBURY PARK CITY			
Project No.	: 340883-01	Eligible Project Cost:	$	746,386
FY08 Rank	: 228			
County	: MONMOUTH	Total State Amount :	$	746,386

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01625
BDA Points	0
Transit Villages	0
TOTAL POINTS	400.01625

Project Name, Number

ASBURY PARK CITY
340883-01
SLUDGE MANAGEMENT

Priority List Rank

228

County

MONMOUTH

Existing Population

16,250

Service Area

Asbury Park City

Need for Project

The sludge generated at the City's wastewater treatment facilities is trucked to a landfill; this is not a viable long term method for sludge disposal. Additional sludge is generated due to the secondary treatment facilities being completed.

Project Description

This project consists of land application of sludge.

Anticipated Recipient	:	LONG BRANCH SA		
Project No.	:	340820-03	Eligible Project Cost:	$ 3,766,422
FY08 Rank	:	229		
County	:	MONMOUTH	Total State Amount :	$ 3,766,422

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.03006
BDA Points	0
Transit Villages	0
TOTAL POINTS	375.03006

Project Name, Number

LONG BRANCH SA
340820-03
SLUDGE TREATMENT & DISPOSAL

Priority List Rank

229

County

MONMOUTH

Existing Population

30,060

Service Area

City of Long Branch, West Long Branch (portion)

Need for Project

Long Branch Sewerage Authority is presently disposing of sludge by incineration, however, this is on a short term basis only. This project is necessary to identify a long term disposal alternative for disposal of the 1235 lbs. of sludge (dry weight basis) produced at the plant each day.

Project Description

The project report for this project is essentially complete and has recommended a long term sludge management plan which calls for in-vessel composting with distribution. After resolution of several minor issues, the project report may be approved.

Anticipated Recipient	: HIGHTSTOWN BOROUGH			
Project No.	: 340915-02	Eligible Project Cost:	$	804,506
FY08 Rank	: 230			
County	: MERCER	Total State Amount :	$	804,506

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00513
BDA Points	0
Transit Villages	0
TOTAL POINTS	365.00513

Project Name, Number

HIGHTSTOWN BOROUGH
340915-02
SLUDGE MANAGEMENT

Priority List Rank

230

County

MERCER

Existing Population

5,130

Service Area

Borough of Hightstown

Need for Project

The need for the project is to provide improved biosolids handling and reduce costs.

Project Description

The purpose of the project is to purchase a Belt Filter Press for handling biosolids in a liquid or cake form, which ever is more cost effective. A building will be required for the press and dumpster during freezing weather.

Major project components include:

A) Building Site Work
B) Yard piping to convey biosolids to press
C) Building accessories, lighting, dumpster, rollup monorail, door, eyewash, shower, etc.
D) Utilities, plumbing, heating, floor drainage, ventilation
E) Piping modification, valves, pipes, supports
F) Equipment, belt press filter new, polymer feed system, progressive cavity pump, equipment installation, spiral conveyer, air compressor

Anticipated Recipient :	CAMDEN COUNTY MUA		
Project No. :	340640-06	Eligible Project Cost:	$ 16,713,680
FY08 Rank :	231		
County :	CAMDEN	Total State Amount :	$ 16,713,680

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.50893
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	350.50893

Project Name, Number

CAMDEN COUNTY MUA
340640-06
SLUDGE MANAGEMENT

Priority List Rank

231

County

CAMDEN

Existing Population

508,932

Service Area

Most of Camden County

Need for Project

Installation of a new sludge drying facilty will reduce odors, reduce operating costs and improve water quality.

Project Description

The proposed project includes installation of a new sludge drying facilty at the treatment plant to treat all of CCMUA’s dewatered sludge cake.

Anticipated Recipient :	BERGEN COUNTY UA		
Project No. :	340687-05	Eligible Project Cost:	$ 37,834,533
FY08 Rank :	232		
County :	BERGEN	Total State Amount :	$ 37,834,533

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.49114
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.49114

Project Name, Number

BERGEN COUNTY UA
340687-05
SLUDGE MANAGEMENT

Priority List Rank

232

County

BERGEN

Existing Population

491,140

Service Area

The service area consists of 46 municipalities in Bergen County

Need for Project

BCUA operates a 94 mgd secondary sewage treatment plant which produces 35 dry tons/day of anaerobically digested liquid sludge which is currently dewatered by Spectroserv, Inc. in the Town of Kearny and shipped to Pennslyvania to be landfilled. This interim sludge disposal alternative was implemented by the BCUA in order to enable the Authority to cease the ocean dumping of sewage sludge as mandated by federal and state legislation. However, this practice is costly and its future availability is uncertain.

Project Description

The BCUA has modified its Sludge Management Plan to include beneficial reuse of the sludge.

The modified plan calls for the chemical stabilization of the sludge and use of the product as final cover of the landfills in the Meadowlands area.

As required by the Judicial Consent Decree, the BCUA is required to pursue its original plan of incineration until such time as the beneficial use plan is approved.

Anticipated Recipient :	ESSEX-UNION JOINT MEETING		
Project No. :	340686-03	Eligible Project Cost:	$ 19,257,315
FY08 Rank :	233		
County :	UNION	Total State Amount :	$ 19,257,315

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.47800
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.47800

Project Name, Number

ESSEX-UNION JOINT MEETING
340686-03
SLUDGE TREATMENT & DISPOSAL

Priority List Rank

233

County

UNION

Existing Population

478,000

Service Area

16 communities in Essex and Union Counties

Need for Project

JMEUC operates a 75 mgd secondary sewage treatment plant which produces 35 dry tons per day of anaerobically digested sludge which is currently dewatered and shipped to Pennsylvania to be landfilled. This interim sludge disposal alternative was implemented by the JMEUC in order to enable the Authority to cease the ocean dumping of sewage sludge as mandated by federal and state legislation. However, this practice is costly and its future availability is uncertain.

Project Description

The proposed project would provide a long-term method for the disposal of sewage sludge. A Step 1 grant was awarded in 1977 for a land-based sludge management study. The "Land-Based Sludge Management Facilities Plan Update" dated March 1989 recommended construction of a multiple hearth incinerator with a hot water generator, Venturi scrubber, impingement plate after cooler, wet electrostatic precipitator, induced draft fan, regenerative after burner and a pneumatic dry ash system as the most cost-effective alternative. The JMEUC present plans are to abandon the original idea of sludge incineration and to pursue a beneficial reuse alternative utilizing a sludge drying process.

Anticipated Recipient :	BURLINGTON COUNTY BOARD OF FREEHOLDERS		
Project No. :	340818-04	Eligible Project Cost:	$ 10,144,771
FY08 Rank :	234		
County :	BURLINGTON	Total State Amount :	$ 10,144,771

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.38246
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.38246

Project Name, Number

BURLINGTON COUNTY BOARD OF FREEHOLDERS
340818-04
SLUDGE MANAGEMENT

Priority List Rank

234

County

BURLINGTON

Existing Population

382,460

Service Area

Burlington County

Need for Project

The Leachate Treatment Plant (LTP) expansion and upgrade is necessary to provide treatment and capacity for the wastewater to be generated through operation of the county co-composting facility. The existing LTP currently treats leachate and sanitary wastewater from the county landfill and associated support facilities at the county Resource Recovery Facilities Complex. In accordance with NJPDES Permit No. NJ0055395 issued October 23, 1991 which provides the discharge requirements for the LTP, expansion of the hydraulic design capacity of the plant from 50,000 gpd to 130,000 gpd average daily flow (ADF) on a monthly basis will allow for the treatment of wastewater to be generated from the previously funded co-composting facility operations (approximately 56,000 gpd - monthly ADF, Project No. S340818-03). Permitted capacity was increased from 28,000 gpd to 130,000 gpd (monthly ADF) under NJPDES No. NJ0055395.

Project Description

Expansion of the facility may include physical-chemical treatment units, biological and physiochemical treatment units, rapid sand filtration, ultraviolet disinfection and a wastewater heating system.

Anticipated Recipient :	HUDSON COUNTY UA		
Project No. :	340399-15	Eligible Project Cost:	$ 20,024,455
FY08 Rank :	235		
County :	HUDSON	Total State Amount :	$ 20,024,455

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.22135
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.22135

Project Name, Number

HUDSON COUNTY UA
340399-15
SLUDGE TREATMENT & DISPOSAL

Priority List Rank

235

County

HUDSON

Existing Population

221,350

Service Area

Guttenberg, Hoboken, North Bergen Township, Secaucus, Union City, Weehawken, West New York

Need for Project

Landfilling of sludge in Pennsylvania is the primary means of sludge disposal for the Hudson County treatment plants. However, this is a short term solution only.

Project Description

This project is the third segment of the Hudson County Utilities Authority's segmented sludge management plan. The proposed project is the construction of a fluidized bed incinerator that is to accept municipal sludge generated within the county.

Anticipated Recipient	:	HUDSON COUNTY UA (AREA I)		
Project No.	:	340900-01	Eligible Project Cost:	$ 26,962,839
FY08 Rank	:	236		
County	:	HUDSON	Total State Amount :	$ 26,962,839

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	50.00000
			Population	0.21858
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	350.21858

Project Name, Number

HUDSON COUNTY UA (AREA I)
340900-01
COLLECTION SYSTEM

Priority List Rank

236

County

HUDSON

Existing Population

218,580

Service Area

City of Jersey City

Need for Project

The construction of sewers are necessary to replace failing and malfunctioning septic systems in the unsewered areas of the City of Jersey City. These systems are old, inadequate, and are known to cause a public nuisance.

Project Description

This project proposes the construction of a new collection system to service that portion of the City of Jersey City that is unsewered. It will convey the wastewater of this unsewered area of the City to PVSC for wastewater treatment.

Anticipated Recipient :	ATLANTIC COUNTY UA		
Project No. :	340405-04	Eligible Project Cost:	$ 19,607,239
FY08 Rank :	237		
County :	ATLANTIC	Total State Amount :	$ 19,607,239

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.16367
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	350.16367

Project Name, Number

ATLANTIC COUNTY UA
340405-04
SLUDGE MANAGEMENT

Priority List Rank

237

County

ATLANTIC

Existing Population

163,667

Service Area

Several Municipalities in Atlantic County and Mercer County

Need for Project

The Authority has several goals for this project. First, to diversify the Authority's method (by providing a back-up for the existing sludge incinerators) and increase capacity for the disposal of municipal wastewater sludge. The second goal relates to the Interdistrict Agreement by which the ACUA is required to accept up to 19,000 tons per year of compostable material from Mercer County. Finally, to meet the Authority's recycling goals, large source separated generations of food waste within the county will be directed to the proposed facility.

Project Description

The Authority is planning to construct an Enclosed Composting Facility at the Environmental Park Site in Egg Harbor Township. The facility will process the following selective waste streams: food waste, municipal wastewater sludge, vegetative waste and clean wood waste. These selective waste streams will produce a compost which can be used as a soil amendment. The proposed facility has an array of unique features to avoid the pitfalls of other composting facilities which have been forced to close due to mechanical and odor control problems. An integrated building ventilation system, including a biofilter for odor control will be constructed. The facility will be totally enclosed and designed to handle 159 wet tons per day.

Anticipated Recipient	:	PARSIPPANY-TROY HILLS TWP		
Project No.	:	340886-01	Eligible Project Cost:	$ 1,398,180
FY08 Rank	:	238		
County	:	MORRIS	Total State Amount :	$ 1,398,180

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06310
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.06310

Project Name, Number

PARSIPPANY-TROY HILLS TWP
340886-01
SLUDGE HANDLING FACILITIES

Priority List Rank

238

County

MORRIS

Existing Population

63,100

Service Area

Parsippany Troy Hills, Mountain Lakes Borough, East Hanover Township

Need for Project

This project is required to provide an additional sludge blending tank and grit removal equipment including belt filter press for dewatering with associated piping and pumping equipment. It should be noted that the present facilities for handling sludge waste generated from other sewage treatment plants are inadequate. The project is necessary to insure that additional sludge facilities for existing and future development is in conformance with approved facilities plan.

Project Description

Parsippany-Troy Hills has completed an NJDEP approved facilities plan which recommends construction of facilities that include an additional sludge blending tank, grit removal equipment and belt filter press for dewatering with associated piping and pumping equipment.

Anticipated Recipient :	CAPE MAY COUNTY MUA		
Project No. :	340661-06	Eligible Project Cost:	$ 12,302,395
FY08 Rank :	239		
County :	CAPE MAY	Total State Amount :	$ 12,302,395

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.05014
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.05014

Project Name, Number

CAPE MAY COUNTY MUA
340661-06
SLUDGE MANAGEMENT

Priority List Rank

239

County

CAPE MAY

Existing Population

50,140

Service Area

Cape May County MUA - Wildwood/Lower Region and CMCMUA - Seven Mile/Middle Region

Need for Project

The project is required to provide sludge/septage treatment and disposal for the Cape May County MUA - Wildwood/Lower Regional and Seven Mile/Middle Regional Wastewater Systems.

Project Description

The project is the second phase of the Cape May County MUA - County-wide enclosed vessel mechanical composting system. This component is planned to service combined primary and secondary belt filter press dewatered sludge from the 14.18 mgd Wildwood/Lower Regional WWTF and the 7.67 mgd Seven Mile/Middle Region WWTF. The septage treatment facilities will be incorporated into the CMCMUA Seven Mile/Middle Regional WWTF.

Anticipated Recipient	: WANAQUE VALLEY REG SA		
Project No.	: 340390-05	Eligible Project Cost:	$ 25,607,620
FY08 Rank	: 240		
County	: PASSAIC	Total State Amount :	$ 25,607,620

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04776
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.04776

Project Name, Number

WANAQUE VALLEY REG SA
340390-05
SLUDGE/SEPTAGE TREATMENT/DISPOSAL

Priority List Rank

240

County

PASSAIC

Existing Population

47,760

Service Area

The Wanaque Valley Regional Sewerage Authority's (WVRSA) Water Pollution Control Facility includes the service areas of Wanaque, Ringwood, and West Milford.

Need for Project

Growth, for this region, is expected to outpace other areas of New Jersey due to the long-awaited extension of Route 287, linking several major arteries of the metropolitan area. For this reason, land acquisition for an approximate 2.0 MGD expansion of the facility was initiated in 1988.

Infiltration and inflow have had negative effects on the existing facility's past performance. Rehabilitation of the I/I is crucial in optimizing the facility's performance.

The sludge produced by the WVRSA's Water Pollution Control Facility is being transported off-site to the TBRSA's incinerator. The incinerator authority charges disposal fees by the gallon, resulting in excessive sludge disposal costs.

There are no facilities within WVRSA's service area accepting septage wastes at this time. The TBRSA's facility is currently identified as disposal site for septage generated in the WVRSA's service. As with sludge, continued treatment capacity for the area's septage wastes is not assured at the TBRSA facility, and disposal costs are high.

The WVRSA is required by the regulations promulgated under PL 92-500 and by the USEPA to develop a long term sludge management plan that is the most cost-effective, environmentally sound and implementable solution to the disposal problem.

Project Description

The WVRSA can reduce the excessive sludge disposal costs with the addition of a sludge thickening system. Although incineration of dewatered or thickened sludge is the most cost-effective and promising alternative at this time as plant capacity increases, in-vessel composting becomes most cost effective and is preferred.

In addition, acceptance of septage at the local treatment plants rather than directly at the incinerator facility will reduce homeowner's disposal costs. The selected plan, soon to be completed, will provide a long term sludge management system that will accommodate the quantity of sludge generated within the WVRSA and PRBRSA regions.

Anticipated Recipient	:	MOUNT HOLLY SA		
Project No.	:	340819-02	Eligible Project Cost:	$ 5,203,507
FY08 Rank	:	241		
County	:	BURLINGTON	Total State Amount :	$ 5,203,507

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02659
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.02659

Project Name, Number

MOUNT HOLLY SA
340819-02
SLUDGE MANAGEMENT

Priority List Rank

241

County

BURLINGTON

Existing Population

26,590

Service Area

Mount Holly, Eastampton, Lumberton, Hainesport, part of Westampton

Need for Project

This is a sludge management project. The Mount Holly Sewerage Authority Wastewater Treatment Plant has been expanded and upgraded from 2.0 mgd to 5.0 mgd flow under USEPA/State project no. C340251 grant. The (201) Facilities Plan recommended that ultimate sludge disposal would be to a licensed landfill.

Subsequent to the completion of this original facilities plan and the initiation of construction of the plant expansion, the State of New Jersey enacted new laws relative to the treatment and disposal of sludge. Accordingly, the Mount Holly Sewerage Authority was required to prepare a sludge management plan in accordance with the current state guidelines for the preparation of sludge management plans.

Project Description

The project consists of construction of sludge management facilities at the existing Mount Holly SA Sewage Treatment Plant site. This is a short term solution only.

The ultimate sludge disposal will be incorporated into the on-going county-wide sludge and septage management plan recommendations. Mt. Holly will subsequently become a contingency back-up facility for sludge/septage treatment.

Anticipated Recipient	:	MILFORD BOROUGH		
Project No.	:	340805-02	Eligible Project Cost:	$ 4,076,260
FY08 Rank	:	242		
County	:	HUNTERDON	Total State Amount :	$ 4,076,260

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	350
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	350

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00610
BDA Points	0
Transit Villages	0
TOTAL POINTS	350.00610

Project Name, Number

MILFORD BOROUGH
340805-02
I/I CORRECTION; SLUDGE/SEPTAGE

Priority List Rank

242

County

HUNTERDON

Existing Population

6,100

Service Area

Milford Borough, Holland Township

Need for Project

There is serious I/I existing in the sanitary sewer lines in Holland Township, which is causing noncompliance with the suspended solids limitations of the NJPDES permit during periods of excessive rain. In addition, the Milford Borough Sewer Utility, which is classified as a Category D facility, does not have the capability of handling septage and must plan for accepting the septage generated in its service area. Furthermore, alternatives to the treatment plant's current method of disposing of liquid sludge at a Pennsylvania landfill must be evaluated since it is on a short term basis.

Project Description

This project will be classified as a complete wastewater treatment system which includes Holland Township and Milford Borough. The Facilities Plan will develop alternatives for sludge disposal, and evaluate a septic management district. Also, an I/I and cost effectiveness analysis will be performed to determine the extent of excessive I/I in the system.

Anticipated Recipient	:	ALLOWAY TOWNSHIP/QUINTON TOWNSHIP		
Project No.	:	340965-01	Eligible Project Cost:	$ 9,963,124
FY08 Rank	:	243		
County	:	SALEM	Total State Amount :	$ 9,963,124

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	25
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	25
Industrial Water Use	25	25
	Subtotal	75

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00310
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	325.00310

Project Name, Number

ALLOWAY TOWNSHIP/QUINTON TOWNSHIP
340965-01
COLLECTION SYSTEM

Priority List Rank

243

County

SALEM

Existing Population

3,100

Service Area

Sections of both Alloway and Quinton Townships

Need for Project

The on-site septic systems in the proposed service area are malfunctioning and causing groundwater degradation. The area borders Elkington Lake and Laurel Lake as well as Alloway Lake and Alloway Creek. The existing systems are impacting fishable (non-trout), recreational, industrial and agricultural uses of these waterbodies.

Project Description

The proposed project consists of the construction of force mains, gravity sewers and pumping stations. The collected wastewater either will be conveyed to the Salem treatment plant or to a newly erected treatment plant within the service area which will be a part of this project.

Anticipated Recipient	:	STAFFORD TOWNSHIP		
Project No.	:	340946-02	Eligible Project Cost:	$ 7,975,913
FY08 Rank	:	244		
County	:	OCEAN	Total State Amount :	$ 7,975,913

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00190
BDA Points	0
Transit Villages	0
TOTAL POINTS	325.00190

Project Name, Number

STAFFORD TOWNSHIP
340946-02
COLLECTION SYSTEM

Priority List Rank

244

County

OCEAN

Existing Population

1,900

Service Area

Ocean Acres Area of Stafford Township

Need for Project

The area residents are using individual on-site septic systems for wastewater disposal which pose a pollution threat to the groundwater and to public health. The area is in a Regional Growth Area of the Pinelands Commission and is identified as an area to be sewered in the Pinelands Infrastructure Master Plan with an allowable development of approximately 1,800 residential lots.

Project Description

The project is for the construction of approximately 20 miles of gravity sewers and force mains, 4 pump stations, and the associated manholes and house laterals which will collect and convey about 0.5 mgd projected ultimate wasteflow via the existing Manahawkin Interceptor to the Ocean County Utilities Authority's Southern Water Pollution Control Facilities located in West Creek.

Anticipated Recipient	:	BRIDGEWATER TOWNSHIP		
Project No.	:	340638-03	Eligible Project Cost:	$ 2,273,143
FY08 Rank	:	245		
County	:	SOMERSET	Total State Amount :	$ 2,273,143

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00133
BDA Points	0
Transit Villages	0
TOTAL POINTS	325.00133

Project Name, Number

BRIDGEWATER TOWNSHIP
340638-03
COLLECTION SYSTEM

Priority List Rank

245

County

SOMERSET

Existing Population

1,330

Service Area

Bridgewater Township (various portions)

Need for Project

Poor soil conditions and shallow depth to bedrock are causing a significant number of septic systems in the service area to malfunction and cause a public nuisance.

Project Description

This project involves construction of collector and interceptor sewers in eight sections of Bridgewater Township. These collectors will tie into existing trunk sewers which lead to the Somerset-Raritan Valley Sewerage Authority treatment plant.

Anticipated Recipient	: WEST WILDWOOD BOROUGH			
Project No.	: 340626-04	Eligible Project Cost:	$	55,180
FY08 Rank	: 246			
County	: CAPE MAY	Total State Amount :	$	55,180

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00045
BDA Points	0
Transit Villages	0
TOTAL POINTS	325.00045

Project Name, Number

WEST WILDWOOD BOROUGH
340626-04
COLLECTION SYSTEM

Priority List Rank

246

County

CAPE MAY

Existing Population

453

Service Area

West Wildwood Borough

Need for Project

The sanitary sewer extension in West Wildwood will allow for the elimination of existing on-site wastewater disposal systems, which are located within 100 feet of tidal water, in an area with depth to groundwater of less than three feet and subject to periodic tidal flooding.

Project Description

The proposed project includes the purchase and installation of pumps and controls to complete the Twenty Sixth Street Sanitary Sewer Extension in West Wildwood.

Anticipated Recipient	: RARITAN BOROUGH			
Project No.	: 340781-03	Eligible Project Cost:	$	551,932
FY08 Rank	: 247			
County	: SOMERSET	Total State Amount :	$	551,932

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00010
BDA Points	0
Transit Villages	0
TOTAL POINTS	325.00010

Project Name, Number

RARITAN BOROUGH
340781-03
COLLECTION SYSTEM

Priority List Rank

247

County

SOMERSET

Existing Population

100

Service Area

Vones Lane Section of Raritan Borough

Need for Project

The Vones Lane Section of Raritan Borough is experiencing a high degree of septic tank failures (70%) overflows due to poor soil and high groundwater. This has resulted in septage flowing onto yards and streets.

Project Description

The proposed project will eliminate the septic systems through the construction of a collection system and conveyance facilities.

Anticipated Recipient	: WANAQUE BOROUGH			
Project No.	: 340434-02	Eligible Project Cost:	$	306,771
FY08 Rank	: 248			
County	: PASSAIC	Total State Amount :	$	306,771

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01058
BDA Points	0
Transit Villages	0
TOTAL POINTS	315.01058

Project Name, Number

WANAQUE BOROUGH
340434-02
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

248

County

PASSAIC

Existing Population

10,580

Service Area

Wanaque Borough

Need for Project

This project is necessary for the construction of a sewer extension. This is the second phase of the Borough's collection system project. The first phase (75,130 l.f.) has already been constructed. In several instances, septic systems have been malfunctioning, creating potential health hazard situations and a public nuisance.

Project Description

This project involves the construction of 4251 linear feet of collector and interceptor sewer and a pump station, which will convey wastewater to the proposed Wanaque Valley Regional Sewerage Authority treatment plant (0.68 MGD capacity). The planning work for the collection system needs to be addressed.

Anticipated Recipient	:	HAMMONTON TOWN		
Project No.	:	340927-03	Eligible Project Cost:	$ 4,983,647
FY08 Rank	:	249		
County	:	ATLANTIC	Total State Amount :	$ 4,983,647

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.01260
BDA Points	0
Transit Villages	0
TOTAL POINTS	310.01260

Project Name, Number

HAMMONTON TOWN
340927-03
COLLECTION SYSTEM

Priority List Rank

249

County

ATLANTIC

Existing Population

12,604

Service Area

Southwest/Southeast portions of Hammonton

Need for Project

Residents in the area have expressed problems with failing septic systems and individual potable water supply well contamination. This project will also assist residents who have lost the use of their land due to the septic nitrate regulations of the Pinelands Commission. The increased amount of customers will assist the sewer user base and help to reduce the overall user cost for everyone on line.

Project Description

The project consists of replacement of existing sewer interceptors and the construction of new interceptors, pump station, force mains and sewer collection mains. Although the projects are not contiguous, the type of work and benefits derived will be similar.

The Southeast Hammonton area will consist of the placement of a 12" sanitary sewer trunk line within the rights-of-way of Thirteenth Street, Egg Harbor Road and Fourteenth Street. Eight (8) inch collector sewer lines will be installed within the remaining roadways of this project area.

The Southeast Hammonton area will consist of the placement of a 12 inch sanitary sewer trunk line within Park Avenue, easement areas, Grand Street and through a portion of the Fox Chase Development. A 10" line will be installed along Ninth Street and a portion of Tenth Street. The remaining streets in this area will be serviced with an 8 inch sanitary sewer. It is also anticipated that an upgrade of the existing pump station located on Park Avenue will have to be completed or a new station installed on Grand Street at the low point to service this area.

Anticipated Recipient	: HOPE TOWNSHIP			
Project No.	: 340872-01	Eligible Project Cost:	$	508,696
FY08 Rank	: 250			
County	: WARREN	Total State Amount :	$	508,696

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.00166
BDA Points	0
Transit Villages	0
TOTAL POINTS	310.00166

Project Name, Number

HOPE TOWNSHIP
340872-01
INTERCEPTOR SEWERS

Priority List Rank

250

County

WARREN

Existing Population

1,660

Service Area

The study area for this project consists of Hope Township within the Pequest Basin.

Need for Project

The majority of the township is currently using cesspools as a means of on-site wastewater disposal. Failures of these systems have created potential health hazards. In the Silver Lake area, the water table is high and wells are shallow. Cesspools and septic systems have been a public nuisance through surface failures and groundwater pollution. The septic malfunctions have been threatening the health and welfare of the local residents. Because of the existing small lot size, soil limitations and lack of adequate planning for runoff management, there is significant potential for future environmental and health problems within the community as well as problems of the degradation of water quality in Silver Lake.

Project Description

This project is still in early stage of planning and proposes small diameter gravity system connected to a community-based leaching field as an alternative solution to malfunctioning septic systems. Also included is a sub-surface drainage system to be installed to collect and divert high, seasonal groundwater and run-off to protect the disposal bed from flooding.

Anticipated Recipient	:	ATLANTIC COUNTY UA		
Project No.	:	340809-14	Eligible Project Cost:	$ 4,679,566
FY08 Rank	:	251		
County	:	ATLANTIC	Total State Amount :	$ 4,679,566

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	300
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	300

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.16763
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.16763

Project Name, Number

ATLANTIC COUNTY UA
340809-14
WATER RECLAMATION-SMITHVILLE

Priority List Rank

251

County

ATLANTIC

Existing Population

167,633

Service Area

The municipalities of Absecon, Brigantine, Egg Harbor City, Egg Harbor Township, Galloway, Hamilton, Linwood, Longport, Margate, Northfield, Pleasantville, Somers Point Ventnor, Port Republic, and Weymouth.

Need for Project

Reclamation of wastewater for beneficial reuse will protect aquifers, assist potable water conservation in Atlantic County, and reduce treated wastewater discharges into the Atlantic Ocean.

Project Description

The proposed project includes the construction of treatment facilities, pumping and conveyance facilities to provide landscape irrigation for six residential communities. The project consists of a new 0.36 MGD membrane bioreactor treatment system, a 300,000 gallon storage tank as well as pumping facilities, 8500 LF of force main, piping and other related appurtenances.

Anticipated Recipient	:	ATLANTIC COUNTY UA		
Project No.	:	340809-11	Eligible Project Cost:	$ 7,602,671
FY08 Rank	:	252		
County	:	ATLANTIC	Total State Amount :	$ 7,602,671

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	300
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	300

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.16367
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.16367

Project Name, Number

ATLANTIC COUNTY UA
340809-11
WATER RECLAMATION

Priority List Rank

252

County

ATLANTIC

Existing Population

163,667

Service Area

The municipalities of Absecon, Brigantine, Egg Harbor City, Egg Harbor Township, Galloway, Hamilton, Linwood, Longport, Margate, Northfield, Pleasantville, Somers Point Ventnor, Port Republic and Weymouth Township.

Need for Project

Reclamation of wastewater for beneficial reuse will protect aquifers, assist potable water conservation in Atlantic County, and reduce treated wastewater discharges into the Atlantic Ocean.

Project Description

The proposed project includes the construction of treatment facilities, pumping and conveyance facilities to provide local customers with treated wastewater from the reclaimed water for beneficial reuse program. The proposed project will divert primary treated influent wastewater to a new membrane bioreactor treatment system and ultraviolet disinfection system. A pumping station, force main and distribution facility will be constructed to convey the reclaimed water to customers for use as irrigation water and cooling tower make-up water.

Anticipated Recipient :	OLD BRIDGE MUA		
Project No. :	340945-04	Eligible Project Cost:	$ 33,032,119
FY08 Rank :	253		
County :	MIDDLESEX	Total State Amount :	$ 33,032,119

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.06046
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.06046

Project Name, Number

OLD BRIDGE MUA
340945-04
COLLECTION SYSTEM

Priority List Rank

253

County

MIDDLESEX

Existing Population

60,456

Service Area

Old Bridge Township, S. Old Bridge Brook Drainage Basin and Runyon Drainage Basin

Need for Project

South Old Bridge area is presently serviced by on-site systems. Many of these systems are malfunctioning.

Project Description

The proposed project consists of 2 pumping stations, trunk sewer, force main and collection systems.

Anticipated Recipient	:	WAYNE TOWNSHIP		
Project No.	:	340929-01	Eligible Project Cost:	$ 1,861,346
FY08 Rank	:	254		
County	:	PASSAIC	Total State Amount :	$ 1,861,346

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04555
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.04555

Project Name, Number

WAYNE TOWNSHIP
340929-01
COLLECTION SYSTEM

Priority List Rank

254

County

PASSAIC

Existing Population

45,550

Service Area

This project will serve various areas throughout the Township such as Ludlum Road, Arbor Road, Riverlawn Drive, Riverdale Drive, and Hoffman Grove area.

Need for Project

Many areas of the Township presently served by on-site systems have exhibited problems and/or malfunctions as evidenced by foul odors and numerous homeowner complaints, thus causing a public nuisance. As determined by the soil conservation service, these areas correspond to soils with severe limitations for on-site disposal.

Project Description

This project is for the construction of a sanitary sewer collection system within problem areas of the Township. All of the areas will tie into existing transmission lines for ultimate disposal at the Mountain View treatment plant.

Anticipated Recipient	: NEW BRUNSWICK CITY			
Project No.	: 340437-03	Eligible Project Cost:	$	950,799
FY08 Rank	: 255			
County	: MIDDLESEX	Total State Amount :	$	950,799

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.04171
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.04171

Project Name, Number

NEW BRUNSWICK CITY
340437-03
I/I CORRECTION

Priority List Rank

255

County

MIDDLESEX

Existing Population

41,710

Service Area

City of New Brunswick

Need for Project

The existing sewer system in the City of New Brunswick is suspected of containing excessive I/I, partially due to the combined nature of its sewer system.

Project Description

The proposed project consists of the construction of improvement to the City's sewer system, including grouting, slip lining and other corrective measures.

Anticipated Recipient	:	WINSLOW TWP		
Project No.	:	340895-02	Eligible Project Cost:	$ 2,722,377
FY08 Rank	:	256		
County	:	CAMDEN	Total State Amount :	$ 2,722,377

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03009
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.03009

Project Name, Number

WINSLOW TWP
340895-02
COLLECTION SYSTEM, PUMPING STATION, FORCE

Priority List Rank

256

County

CAMDEN

Existing Population

30,090

Service Area

Winslow Township

Need for Project

A portion of Winslow Township is presently served by on-site systems. Many of these systems are malfunctioning; consequently, there is potential for groundwater contamination.

Project Description

The project consists of the construction of gravity sewer lines, pumping stations and force mains. The areas to be served are a portion a residential area, a church and two schools in Winslow Township. The collection system will be proposed to convey 73,000 gallons of wastewater per day initially. The proposed system will discharge to the Route 73 corridor project which is under construction and it will ultimately be conveyed to the CCMUA Delaware No. 1 Water Pollution Control Facility (WPCF) at Camden.

Anticipated Recipient	: VOORHEES TOWNSHIP			
Project No.	: 340875-01	Eligible Project Cost:	$	5,630,570
FY08 Rank	: 257			
County	: CAMDEN	Total State Amount :	$	5,630,570

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02813
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.02813

Project Name, Number

VOORHEES TOWNSHIP
340875-01
COLLECTION SYSTEM, FORCE MAIN & PUMP STATION

Priority List Rank

257

County

CAMDEN

Existing Population

28,126

Service Area

Voorhees Township

Need for Project

The proposed project is needed to improve the pumping/conveyance system within the Township.

Project Description

The proposed project includes the construction of a pumping station at Dutchtown Road, the construction of a new force main from the Dutchtown Road pumping station to an existing interceptor, the construction of a sanitary sewer interceptor from the Cooper Road pumping station to the Dutchtown Road pumping station, the demolition of the Cooper Road pumping station, and the construction of a sanitary sewer interceptor from the Sturbridge Lakes pumping station to Route 73 and the demolition of the Sturbridge Lakes pumping station.

Anticipated Recipient	: FREEHOLD TOWNSHIP			
Project No.	: 340304-01	Eligible Project Cost:	$	4,886,714
FY08 Rank	: 258			
County	: MONMOUTH	Total State Amount :	$	4,886,714

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02471
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.02471

Project Name, Number

FREEHOLD TOWNSHIP
340304-01
COLLECTION SYSTEM

Priority List Rank

258

County

MONMOUTH

Existing Population

24,710

Service Area

Unsewered areas within the Township of Freehold

Need for Project

The construction of sanitary sewers will eliminate the use of existing, failing on-site septic systems in developed portions of the Township.

Project Description

The proposed project consists of construction of approximateley 24,300 LF of gravity sewers, two pump stations and related force mains and a low pressure sewer system to serve approximately 365 existing homes.

Anticipated Recipient	:	GLOUCESTER CO UA (MONROE)		
Project No.	:	340526-03	Eligible Project Cost:	$ 2,911,180
FY08 Rank	:	259		
County	:	GLOUCESTER	Total State Amount :	$ 2,911,180

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.02314
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.02314

Project Name, Number

GLOUCESTER CO UA (MONROE)
340526-03
COLLECTION SYSTEM, SLUDGE MANAGEMENT

Priority List Rank

259

County

GLOUCESTER

Existing Population

23,140

Service Area

Monroe Township

Need for Project

Failure of on-site sewage disposal systems within the township, surrounding Victory, Timber and Sunset Lakes have created a public nuisance, and have contributed to water quality degradation in the area.

Project Description

The facilities plan recommends the construction of a collection system, interceptor, pump stations and force mains. Sewage will flow to GCUA for treatment and disposal.

Anticipated Recipient	: SOUTH BRUNSWICK TOWNSHIP			
Project No.	: 340897-01	Eligible Project Cost:	$	1,254,485
FY08 Rank	: 260			
County	: MIDDLESEX	Total State Amount :	$	1,254,485

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02236
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.02236

Project Name, Number

SOUTH BRUNSWICK TOWNSHIP
340897-01
COLLECTION SYSTEM

Priority List Rank

260

County

MIDDLESEX

Existing Population

22,360

Service Area

This project will serve existing and new development along the Major Road area of the Township.

Need for Project

Approximately 36 homes are served by on-site systems, a significant portion of which have exhibited problems and/or malfunctions, thus causing a public nuisance. The Soil Conservation Service has determined that the Major Road area corresponds to soils with severe limitations for on-site disposal systems. South Brunswick Township will apply under the Public Health Hazard Bypass provisions of the priority system.

Project Description

The proposed project is for the construction of approximately 4,500 feet of ten inch sewer line and 1,450 feet of eight inch sewer line. The project also calls for the reconstruction of approximately 834 feet of the existing "Town Center Sewer". Approximately 31 of the existing properties could make gravity connection to the sewer line and the other 5 homes would have to utilize small grinder pumps to tie into the proposed project.

Anticipated Recipient :	ROCKAWAY TOWNSHIP		
Project No. :	340478-05	Eligible Project Cost:	$ 17,510,632
FY08 Rank :	261		
County :	MORRIS	Total State Amount :	$ 17,510,632

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01956
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.01956

Project Name, Number

ROCKAWAY TOWNSHIP
340478-05
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

261

County

MORRIS

Existing Population

19,560

Service Area

Rockaway Township

Need for Project

Certain areas of the Township have malfunctioning septic systems which have been creating a potential health hazard situation and public nuisance.

Project Description

It is anticipated that this project will be for a collection system or other alternative system in White Meadow Lake and remaining unsewered areas of the Township. This project will alleviate the potential health hazard caused by malfunctioning septic systems.

Anticipated Recipient :	MONTVILLE TOWNSHIP MUA		
Project No. :	340931-02	Eligible Project Cost:	$ 16,484,390
FY08 Rank :	262		
County :	MORRIS	Total State Amount :	$ 16,484,390

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01620
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.01620

Project Name, Number

MONTVILLE TOWNSHIP MUA
340931-02
COLLECTION SYSTEM

Priority List Rank

262

County

MORRIS

Existing Population

16,200

Service Area

Montville Township

Need for Project

An expansion of the collection system is needed to replace inadequate on-site systems which are malfunctioning and pose a potential health hazard to local residents by adversely impacting well waters.

Project Description

The proposed project involves the construction of lateral sewers and a pumping station to relieve malfunctioning septic systems. This project will provide a collection system for the remaining areas of the Township. These areas include areas 7, 8, 9, 14 and 15-5 as identified in the amendment to the 1981 facilities plan (dated June 1, 1990). Wastewater will be conveyed to the Parsippany-Troy Hills STP for treatment.

Anticipated Recipient	: MANCHESTER TWP			
Project No.	: 340650-03	Eligible Project Cost:	$	8,972,628
FY08 Rank	: 263			
County	: OCEAN	Total State Amount :	$	8,972,628

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01540
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.01540

Project Name, Number

MANCHESTER TWP
340650-03
COLLECTION SYSTEM

Priority List Rank

263

County

OCEAN

Existing Population

15,400

Service Area

Parts of Manchester Township

Need for Project

The tremendous rate of growth in the planning area, coupled with an increasing number of septic tanks, has placed a severe strain on the very permeable sandy soils to adequately treat the domestic wastes. Because of a generally high groundwater table and the high percentage of septic system failures, pollution of the groundwater is suspected. The pollution to surface water in the planning area has already been documented in the Ocean County Areawide Water Quality Management Plan. The continuation of current septic tank problems poses a potential threat to the groundwater in the region. Therefore, a proper sewage disposal system is necessary.

Project Description

Based upon economic, environmental and engineering aspects, the construction of the following collection system has been recommended: Summit Park, 13,282 feet of gravity sewers; Savannah Acres, Low pressure/grinder pump system with 17,085 feet of 2" PVC low-pressure piping; Cedar Glen Homes, 16,000 feet of gravity sewers; Richard and Whitney Estates, 1½" and 2" low-pressure sewers; Cedar Glen West, 3,900 feet of 8" and 15" gravity sewers; a pumping station; and 8,700 feet of 6" force main. The flow from the area will be conveyed to the Ocean County Utilities Authority's Central Plant for treatment and disposal.

Anticipated Recipient	: BERNARDS TOWNSHIP SA			
Project No.	: 340382-02	Eligible Project Cost:	$	542,184
FY08 Rank	: 264			
County	: SOMERSET	Total State Amount :	$	542,184

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01530
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.01530

Project Name, Number

BERNARDS TOWNSHIP SA
340382-02
COLLECTION SYSTEM

Priority List Rank

264

County

SOMERSET

Existing Population

15,300

Service Area

Bernards Township

Need for Project

Some of the septic systems of the Township are malfunctioning and thus causing potential environmental or health hazard situations and creating a public nuisance.

Project Description

This project involves construction of a new sewerage system to serve twenty-two (22) homes in the Rocky Lane/Columbia Road area of Basking Ridge. The system will consist of all gravity sewers with the exception of two properties which will require pumping to a pressure sewer. The wastewater will be conveyed to the 1.2 MGD capacity treatment plant.

Anticipated Recipient	:	GLOUCESTER COUNTY UA (FRANKLIN TWP)		
Project No.	:	340461-04	Eligible Project Cost:	$ 7,211,095
FY08 Rank	:	265		
County	:	GLOUCESTER	Total State Amount :	$ 7,211,095

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01448
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.01448

Project Name, Number

GLOUCESTER COUNTY UA (FRANKLIN TWP)
340461-04
INTERCEPTOR, PUMP STATION, FORCE MAIN,

Priority List Rank

265

County

GLOUCESTER

Existing Population

14,480

Service Area

Franklin Township

Need for Project

The project area in Franklin Township consists of Franklinville, Malaga, and Newfield, which are existing developments served by individual on-lot systems. There is public nuisance associated with these on-site disposal systems in the area.

Project Description

The selected plan of the GCUA Facilities Plan calls for the complete regionalization of the proposed sewer collection systems for Franklin Township and the Borough of Newfield with an interceptor system to convey wastewater to the Landis Sewerage Authority Plant for treatment and ultimate disposal. The selected plan basically involves the construction of three pump stations, interceptors, and force mains to convey the wastewater to the Landis SA plant.

Anticipated Recipient	: OAKLAND BOROUGH		
Project No.	: 340418-05	Eligible Project Cost:	$ 40,854,622
FY08 Rank	: 266		
County	: BERGEN	Total State Amount :	$ 40,854,622

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01300
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.01300

Project Name, Number

OAKLAND BOROUGH
340418-05
COLLECTION SYSTEM

Priority List Rank

266

County

BERGEN

Existing Population

13,000

Service Area

Borough of Oakland

Need for Project

The area is currently served by septic systems and some small package treatment plants. Existing disposal facilities result in a public nuisance as a result of high groundwater and impervious soils.

Project Description

The facilities plan recommends the design and construction of a gravity collection system for the majority of the developed areas of the Borough and interceptor sewers. This project involves the collection and interceptor sewers.

Anticipated Recipient	: VERNON TWP			
Project No.	: 340745-02	Eligible Project Cost:	$	6,677,126
FY08 Rank	: 267			
County	: SUSSEX	Total State Amount :	$	6,677,126

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01108
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.01108

Project Name, Number

VERNON TWP
340745-02
ALTERNATIVE WASTEWATER SYSTEM

Priority List Rank

267

County

SUSSEX

Existing Population

11,080

Service Area

The service area consists of the portion (62%) of Vernon Township which lies in the Pochuck Basin.

Need for Project

Vernon Township is comprised of clusters of lakeside communities (including Barry Lakes) that have developed from seasonal vacation homes to year-round dwellings. This fact, coupled with the restrictions of small, undersized lots located on soils with severe limitations for on-site systems, has resulted in an overburdening of the soil stratum. This has led to an increasing number of septic system failures which previously had functioned satisfactorily. In addition, a number of existing systems are known to be inadequate through design and/or installation deficiencies. This situation poses public health as well as nuisance problems to the Township. The needs of Vernon Township as identified under the Sussex County Step I Study (C340503-01) are to be resolved on a local level through this project.

Project Description

This project would implement the wastewater management recommendations of the Sussex County-Pochuck Facilities Plan on a local level. Collection, low pressure, and/or cluster systems may be involved in this project. On-site rehabilitation in conjunction with the establishment of a septic management district(s) may also be a viable alternative. The construction of this project should satisfy the wastewater needs of Vernon Township, as well as maintaining water quality and safeguarding the public health.

Anticipated Recipient	: MAHWAH TOWNSHIP			
Project No.	: 340592-03	Eligible Project Cost:	$	9,194,418
FY08 Rank	: 268			
County	: BERGEN	Total State Amount :	$	9,194,418

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01048
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.01048

Project Name, Number

MAHWAH TOWNSHIP
340592-03
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

268

County

BERGEN

Existing Population

10,480

Service Area

Township of Mahwah (Portion)

Need for Project

The area is currently served by septic systems; failures appear to be contributing to the pollution of groundwater, a potable water source. This could result in health problems in the community. The project would also convey wastewater from package plants in the Township. The water quality in the area marginally meets standards for fecal coliform and nutrients.

Project Description

The project involves construction of a collection system and interceptor to serve the Fardale Section of Mahwah Township. The wastewater will be conveyed through the Northwest Bergen County Utilities Authority interceptors and then to the treatment plant in Waldwick. The project report has not been submitted by the Township.

Anticipated Recipient	: WANTAGE TWP			
Project No.	: 340760-03	Eligible Project Cost:	$	572,805
FY08 Rank	: 269			
County	: SUSSEX	Total State Amount :	$	572,805

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00949
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00949

Project Name, Number

WANTAGE TWP
340760-03
ALTERNATIVE WASTEWATER SYSTEMS

Priority List Rank

269

County

SUSSEX

Existing Population

9,490

Service Area

Wantage Township

Need for Project

The entire Township of Wantage is currently using on-site wastewater disposal. However, in several areas there are failing systems which qualify as a public nuisance.

Project Description

The Sussex County Municipal Utilities Authority is developing a complete wastewater treatment system which includes upgrading of the Sussex Borough STP. The Sussex Borough STP may be available to serve new systems within Wantage Township. This project includes the design and construction of a local collection system and possible upgrading of existing on-site systems for the Wantage Township area, pending submittal and approval of the Sussex County Municipal Utilities Authority-Lower Wallkill 201 Facilities Plan (No. C340573-01).

Anticipated Recipient	: CHATHAM TOWNSHIP			
Project No.	: 340403-05	Eligible Project Cost:	$	708,917
FY08 Rank	: 270			
County	: MORRIS	Total State Amount :	$	708,917

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00936
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00936

Project Name, Number

CHATHAM TOWNSHIP
340403-05
SEPTAGE TREATMENT/DISPOSAL

Priority List Rank

270

County

MORRIS

Existing Population

9,361

Service Area

Portions of Green Village Road and Britten Road in Chatham Township

Need for Project

The Green Village service area is the last major area in Chatham Township that remains unsewered. The existing water table is high and most of the service area is adjacent to the Great Swamp National Wildlife Refuge. Several existing septic systems have failed and several more are projected to fail within the next 2 years.

Project Description

The proposed project includes installation of community and individual mound type treatment systems for those portions of Green Village Road that have failing or failed septic systems.

Anticipated Recipient	:	BLOOMINGDALE BOROUGH		
Project No.	:	340634-03	Eligible Project Cost:	$ 3,790,064
FY08 Rank	:	271		
County	:	PASSAIC	Total State Amount :	$ 3,790,064

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00806
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00806

Project Name, Number

BLOOMINGDALE BOROUGH
340634-03
COLLECTION SYSTEM

Priority List Rank

271

County

PASSAIC

Existing Population

8,060

Service Area

Bloomingdale

Need for Project

Some of the septic systems in the township are malfunctioning and causing potential environmental or health hazard situations and creating a public nuisance.

Project Description

This project involves construction of new sewerage system facilities including interceptors, pump stations, force mains, and collection systems and/or other alternatives for wastewater disposal problems in the areas of Morse Lake, Union Avenue, Hillside Drive and Vreeland Avenue. The wastewater would be conveyed to the Butler Bloomingdale Sewage treatment plant, which is to be upgraded and expanded to 2.5 MGD. The facilities plan work for the collection system project is currently under review.

Anticipated Recipient	:	UPPER SADDLE RIVER, BOROUGH OF		
Project No.	:	340909-01	Eligible Project Cost:	$ 1,384,609
FY08 Rank	:	272		
County	:	BERGEN	Total State Amount :	$ 1,384,609

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00784
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00784

Project Name, Number

UPPER SADDLE RIVER, BOROUGH OF
340909-01
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

272

County

BERGEN

Existing Population

7,840

Service Area

Southwest portion of Upper Saddle River

Need for Project

Sanitary sewers from the commercial buildings in the southwest portion of Upper Saddle River drain into the Ramsey Brook Interceptor. The Ramsey Brook Interceptor was not originally designed to handle flow from the southwest portion of Upper Saddle River. As a result, the line runs near capacity with some surcharging. Continuing commercial development in this area necessitates an alternate drainage source. Construction of a sanitary sewer collection system, which would drain into the northwest Bergen Interceptor, to serve both the expanding commercial and residential (currently served by septic system) communities in the southwest portion of Upper Saddle River has been proposed.

Project Description

Construction of a sanitary sewer collection system and interceptor. The sewer system would contain 9800 linear feet of 8-inch and 1000 linear feet of 10-inch diameter sanitary sewers.

Anticipated Recipient	: LONG HILL TWP		
Project No.	: 340404-05	Eligible Project Cost:	$ 14,495,600
FY08 Rank	: 273		
County	: MORRIS	Total State Amount :	$ 14,495,600

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00766
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00766

Project Name, Number

LONG HILL TWP
340404-05
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

273

County

MORRIS

Existing Population

7,660

Service Area

Passaic Township

Need for Project

Certain areas of Passaic Township have malfunctioning septic systems which have been creating potential health hazard situations and a public nuisance.

Project Description

It is anticipated that this project will be for a collection system including interceptors, or other alternative system to alleviate the existing septic system problems. The project report plan work has not been initiated.

Anticipated Recipient :	MANCHESTER TOWNSHIP		
Project No. :	340650-05	Eligible Project Cost:	$ 13,791,502
FY08 Rank :	274		
County :	OCEAN	Total State Amount :	$ 13,791,502

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00646
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00646

Project Name, Number

MANCHESTER TOWNSHIP
340650-05
PUMP STATION, FORCE MAIN

Priority List Rank

274

County

OCEAN

Existing Population

6,460

Service Area

Pine Lake Park area of Manchester Township

Need for Project

The tremendous rate of growth in the area, coupled with an increasing number of septic tanks, has placed a severe strain on the very permeable sandy soils to adequately treat the domestic wastewater. Because of a generally high groundwater table and the high percentage of septic system failures, pollution of the groundwater and surface water is suspected. Also, the current septic tank problems pose a potential threat to the health of local residents. Therefore, a proper sewage disposal system is necessary.

Project Description

The project is for the construction of three pump stations and approximately 35 miles of force mains and gravity sewers with diameters ranging from 8 inches to 24 inches. The wastewater will be conveyed to the existing 42-inch diameter Union Branch Interceptor owned and operated by the Ocean County Utilities Authority (OCUA). The wastewater will be treated at the OCUA's Central Plant located in Bayville for secondary treatment with effluent disposal to the Atlantic Ocean.

Anticipated Recipient	:	FAIRFIELD TOWNSHIP		
Project No.	:	340957-01	Eligible Project Cost:	$ 7,336,023
FY08 Rank	:	275		
County	:	CUMBERLAND	Total State Amount :	$ 7,336,023

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00628
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00628

Project Name, Number

FAIRFIELD TOWNSHIP
340957-01
COLLECTION SYSTEM

Priority List Rank

275

County

CUMBERLAND

Existing Population

6,283

Service Area

Township of Fairfield

Need for Project

The Gould town center area to be serviced relies on the discharge to groundwater through individual onsite septic systems that are close to 30 years old. As a result of aging and failing septic systems the project will provide a sanitary sewer extension to address groundwater quality standards.

Project Description

The proposed project includes the installation of 18,000 linear feet of gravity sewer ranging in size from 8 to 12 inches and the upgrade or replacement of an existing pump station to eliminate the onsite systems.

Anticipated Recipient	:	CARLSTADT SA		
Project No.	:	340705-03	Eligible Project Cost:	$ 5,342,181
FY08 Rank	:	276		
County	:	BERGEN	Total State Amount :	$ 5,342,181

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00612
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00612

Project Name, Number

CARLSTADT SA
340705-03
NEW INTERCEPTOR SEWERS/COLLECTION SYSTEM

Priority List Rank

276

County

BERGEN

Existing Population

6,120

Service Area

Borough of Carlstadt

Need for Project

There are malfunctioning and inadequate on-site systems which cause a public nuisance in unsewered areas of Carlstadt. Additionally, a portion of Carlstadt's sewered flows are currently conveyed to the Rutherford/Carlstadt's Joint Meeting STP for treatment prior to dis- charge to Berry's Creek (FW2-NT/SE-2). This plant has been under a court order on consent to be abandoned in favor of regional treatment by the Bergen County Utilities Authority (BCUA). Existing water quality violates standards for dissolved oxygen, fecal coliform, and toxics.

Project Description

The facilities plan has evaluated alternative methods for the diversion of all or part of the flow from the Joint Meeting plant to the BCUA regional treatment facilities. The plan also identifies additional sanitary facilities needed to collect sewage in developed and developing areas of Carlstadt.

Anticipated Recipient	: PLUMSTED TWP		
Project No.	: 340607-03	Eligible Project Cost:	$ 53,312,773
FY08 Rank	: 277		
County	: OCEAN	Total State Amount :	$ 53,312,773

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00601
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00601

Project Name, Number

PLUMSTED TWP
340607-03
COLLECTION SYSTEM, STP

Priority List Rank

277

County

OCEAN

Existing Population

6,010

Service Area

Plumsted Township (includes New Egypt, Archers Corner, Archertown, Brindletown and Colliers Mill areas)

Need for Project

A study performed for the service area has determined that overflowing and malfunctioning septic systems, poor soils and high density housing conditions exist in the planning area. A septic system survey found 81 percent of the residents in Plumsted Township are affected by malfunctioning on-site systems. The existing school sewage plant also needs improvement to meet treatment criteria and a new school is proposed which will need a larger capacity treatment facility.

Project Description

The proposed project includes the construction of a municipal collection system and a 210,000 GPD treatment plant to be located on Bight Road and discharge to Crosswicks Creek. The New Egypt School treatment plant will be eliminated. The collection system will include the downtown area of New Egypt and will include pumping stations, force mains, gravity sewers and related appurtenances as necessary. The sludge disposal method will be incorporated into the Ocean County sludge management plan.

Anticipated Recipient	: MAHWAH TOWNSHIP			
Project No.	: 340737-01	Eligible Project Cost:	$	230,325
FY08 Rank	: 278			
County	: BERGEN	Total State Amount :	$	230,325

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00600
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00600

Project Name, Number

MAHWAH TOWNSHIP
340737-01
ALTERNATE WASTEWATER SYSTEM

Priority List Rank

278

County

BERGEN

Existing Population

6,000

Service Area

Mahwah Township (unsewered portion)

Need for Project

Facilities planning in Mahwah Township has identified areas of low density development which will remain unsewered for the planning period. However, areas of soils with limitations to on-site disposal exist, and on-site systems continue to fail in these areas. These malfunctions are considered to be public nuisances and must be addressed. It is, therefore, necessary to create a management program to address the correction of malfunctioning systems in unsewered areas.

Project Description

This project is still in the planning stages and the specifics of the septic management program to be adopted by the Township have not yet been determined. However, at a minimum, the program must provide for inspections of systems every three years.

Anticipated Recipient	:	SUSSEX CO. MUA-BRANCHVILLE/FRANKFORD		
Project No.	:	340759-02	Eligible Project Cost:	$ 7,234,628
FY08 Rank	:	279		
County	:	SUSSEX	Total State Amount :	$ 7,234,628

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00596
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00596

Project Name, Number

SUSSEX CO. MUA-BRANCHVILLE/FRANKFORD
340759-02
COLLECTION SYSTEM

Priority List Rank

279

County

SUSSEX

Existing Population

5,960

Service Area

Branchville Borough and sections of Frankford Township.

Need for Project

The service area is a clustered community which currently relies on on-site septic disposal systems for the treatment of wastewater. Many of these systems appear inadequate and are a public nuisance to the community. An on-going planning study was conducted under the Sussex County-Paulinskill planning grant (C340449-01), to determine the nature, severity, and extent of the wastewater disposal problems for the impacted areas.

Project Description

The proposed project includes the construction of a pump station and force main to convey flow to the wastewater treatment plant site, construction of a treatment plant with the ability to treat effluent to Class II A grounwater standards, with subsurface disposal of the treated effluent.

Anticipated Recipient	: WHARTON BOROUGH			
Project No.	: 340489-03	Eligible Project Cost:	$	599,302
FY08 Rank	: 280			
County	: MORRIS	Total State Amount :	$	599,302

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00557
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00557

Project Name, Number

WHARTON BOROUGH
340489-03
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

280

County

MORRIS

Existing Population

5,570

Service Area

Borough of Wharton

Need for Project

The construction of sewers may be necessary for a small portion of the Township which is presently served by septic systems. Some of these septic systems have been malfunctioning, creating a public nuisance.

Project Description

This project involves the construction of a collection and interceptor system in a small portion of the Borough which would convey the waste- water to the Rockaway Valley Regional Sewerage Authority treatment plant. The facilities planning work is yet to be initiated.

Anticipated Recipient	: BERLIN TOWNSHIP			
Project No.	: 340790-02	Eligible Project Cost:	$	847,274
FY08 Rank	: 281			
County	: CAMDEN	Total State Amount :	$	847,274

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00555
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00555

Project Name, Number

BERLIN TOWNSHIP
340790-02
COLLECTION SYSTEM

Priority List Rank

281

County

CAMDEN

Existing Population

5,550

Service Area

Berlin Township

Need for Project

At present there is no sewer service to the residents of Berlin Township. Well-drained, sandy soils and a shallow groundwater table increase the possibility of contamination to ground waters by individual septic tank disposal systems. In addition, contamination of the head waters of the Great Egg Harbor River (PL and FW2-NT) and nitrogen contamination of wells has been attributed to septic tank sources in Berlin Township. The systems are also creating a public nuisance.

Project Description

The proposed project consists of the construction of a new collection system of approximately 138,774 linear feet and four pumping stations. The collection system will connect to the regional CCMUA pumping station.

Anticipated Recipient	:	FRANKFORD TWP		
Project No.	:	340742-02	Eligible Project Cost:	$ 2,727,380
FY08 Rank	:	282		
County	:	SUSSEX	Total State Amount :	$ 2,727,380

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00511
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00511

Project Name, Number

FRANKFORD TWP
340742-02
COLLECTION SYSTEM

Priority List Rank

282

County

SUSSEX

Existing Population

5,110

Service Area

Frankford Township

Need for Project

The Frankford Township area is currently relying on on-site septic disposal systems for the treatment of wastewater. Many of these existing systems appear inadequate. This is creating a public nuisance.

Project Description

This project is part of a wastewater treatment system to be developed by the Sussex County Municipal Utilities Authority, and consists of a proposed regional sewage treatment plant which will serve Frankford Township along with Branchville Borough. It includes the construction of a collection and interceptor system for the Frankford Township area.

Anticipated Recipient	: BLAIRSTOWN TWP			
Project No.	: 340568-02	Eligible Project Cost:	$	1,512,694
FY08 Rank	: 283			
County	: WARREN	Total State Amount :	$	1,512,694

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00489
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00489

Project Name, Number

BLAIRSTOWN TWP
340568-02
COLLECTION SYSTEM

Priority List Rank

283

County

WARREN

Existing Population

4,890

Service Area

Blairstown

Need for Project

Presently Blairstown Township has failing on-site wastewater disposal systems. There are documented failures in parts of the Township that may eventually pose health problems in the future. There are no public wastewater collection and treatment facilities in the study area but there are currently two privately owned and operated wastewater treatment plants: Blair Academy and N. Warren Regional High School

Project Description

This project (C340568-02) includes the construction of a collection system for the Village of Blairstown area. The sewage will be conveyed to and treated at the propoised regional STP.

Anticipated Recipient	: RIVERDALE BOROUGH			
Project No.	: 340729-01	Eligible Project Cost:	$	1,744,301
FY08 Rank	: 284			
County	: MORRIS	Total State Amount :	$	1,744,301

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00242
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00242

Project Name, Number

RIVERDALE BOROUGH
340729-01
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

284

County

MORRIS

Existing Population

2,420

Service Area

The service area consists of the Borough of Riverdale.

Need for Project

The area is served entirely by individual septic systems discharging to the ground water table. Failures appear to be contributing to surface and subsurface pollution of the ground and groundwater, posing a potential health problem and public nuisance.

Project Description

The project consists of a collection system and interceptor for the major portion of the Borough. This will significantly reduce the potential for water pollution from malfunctioning septic systems and reduce the public health hazard. The project report has not yet been submitted.

Anticipated Recipient	: RIVERDALE BOROUGH			
Project No.	: 340473-01	Eligible Project Cost:	$	4,345,404
FY08 Rank	: 285			
County	: MORRIS	Total State Amount :	$	4,345,404

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00241
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00241

Project Name, Number

RIVERDALE BOROUGH
340473-01
INTERCEPTOR

Priority List Rank

285

County

MORRIS

Existing Population

2,410

Service Area

The service area consists of the Borough of Riverdale.

Need for Project

The area is served entirely by individual septic systems discharging to the groundwater table. Failures appear to be contributing to surface and subsurface pollution of the ground and groundwater, posing a potential health problem and public nuisance.

Project Description

The project consists of construction of an interceptor sewer to provide a complete collection system for the major part of the Borough. This will significantly reduce the potential for water pollution from malfunctioning septic systems and reduce the public health hazard. The project report work has not yet been initiated.

Anticipated Recipient	: MAHWAH TOWNSHIP			
Project No.	: 340592-06	Eligible Project Cost:	$	5,532,128
FY08 Rank	: 286			
County	: BERGEN	Total State Amount :	$	5,532,128

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00235
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00235

Project Name, Number

MAHWAH TOWNSHIP
340592-06
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

286

County

BERGEN

Existing Population

2,350

Service Area

Portion of the Township of Mahwah

Need for Project

The area is currently served by septic systems; failures appear to be contributing to the pollution of groundwater, a potable water source, however this has yet to be documented. This could result in health problems in the community. The project would also convey wastewater from package plants in the Township.

Project Description

The project involves construction of collection system to serve Craigmere and Oak Hills sections of Mahwah Township. The wastewater will be conveyed through the Northwest Bergen County Sewer Authority interceptors and then to the treatment plant in Waldwick. The facilities plan work has not been submitted by the Township.

Anticipated Recipient	:	NORTH BERGEN MUA		
Project No.	:	340652-06	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	287		
County	:	HUDSON	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.00233
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00233

Project Name, Number

NORTH BERGEN MUA
340652-06
STP EXPANSION

Priority List Rank

287

County

HUDSON

Existing Population

2,330

Service Area

North Bergen Township and Guttenberg Town

Need for Project

The Authority is in the process of designing new sanitary sewers to serve the River Road portion of the Township. This area is currently served by on-site systems many of which are failing, or through direct, illegal, discharges to the Hudson River. This project will be necessary to ensure continued permit compliance once the River Road system is completed.

Sewage Treatment Plant (STP) Name (NJPDES #)	Flow (mgd)		Effluent			
			Reported BOD		Reported SS	
	Design	Present	%	mg/l	%	mg/l
Woodcliff (Secondary) (NJ0029084)	2.65	2.67	89	16	89	8

Project Description

Expansion of the existing Woodcliff Wastewater Treatment Plant to accommodate additional flows from the River Road service area in the Township of North Bergen.

Anticipated Recipient	: OXFORD TOWNSHIP			
Project No.	: 340445-02	Eligible Project Cost:	$	183,343
FY08 Rank	: 288			
County	: WARREN	Total State Amount :	$	183,343

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00231
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00231

Project Name, Number

OXFORD TOWNSHIP
340445-02
COLLECTION SYSTEM

Priority List Rank

288

County

WARREN

Existing Population

2,307

Service Area

Township of Oxford

Need for Project

The lots in the project area are very small and most have cess pools. A ground-water problem is causing many of the on-site systems to fail.

Project Description

The proposed project includes the construction of approximately 550 feet of eight-inch sanitary sewer line with manholes and service connections to 12 properties.

Anticipated Recipient	:	EVESHAM MUA		
Project No.	:	340838-01	Eligible Project Cost:	$ 3,665,234
FY08 Rank	:	289		
County	:	BURLINGTON	Total State Amount :	$ 3,665,234

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00210
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00210

Project Name, Number

EVESHAM MUA
340838-01
ALTERNATIVE WASTEWATER SYSTEM

Priority List Rank

289

County

BURLINGTON

Existing Population

2,100

Service Area

Highly dispersed areas of Evesham Township including the Marlton Lakes area.

Need for Project

The Marlton Lakes area of Evesham Township has experienced on-site disposal problems for the past seven years. Monitoring of potable water wells has shown high nitrate readings and the lake has shown indications of eutrophication from elevated nitrate levels. Approximately 850 developed properties exist in the southern two thirds of the Township, with about 40% concentrated in the Marlton Lakes area. A review of the more concentrated areas of development shows that on-site systems are located on Lakewood and Evesboro soils that have severe limitations for septic systems due to high permeability. Many homes in the highly dispersed areas of the Township have also experienced on-site disposal problems. In the northern portions of the Township, outside of the existing sewer service areas, many homes experiencing problems are located on Kresson and Marlton soils, having severe limitation for on-site disposal due to poor permeability.

Project Description

The recommended plan for wastewater management for southern Evesham Township has been divided into two regions based primarily on the need for wastewater management and population density:

- Marlton Lakes Community: Small Diameter/STEP sewer system with centralized wastewater treatment utilizing the Carrousel process followed by effluent disposal in a series of Rapid Infiltration basins.

- Remainder of Southern Evesham Township: Privately owned publicly managed septic system management district entailing periodic septic tank pump-out and septic system inspection. Pump-out and maintenance/repair costs would be the responsibility of the owner.

Anticipated Recipient	: KINNELON BOROUGH			
Project No.	: 340487-02	Eligible Project Cost:	$	9,964,412
FY08 Rank	: 290			
County	: MORRIS	Total State Amount :	$	9,964,412

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00170
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00170

Project Name, Number

KINNELON BOROUGH
340487-02
COLLECTION SYSTEM

Priority List Rank

290

County

MORRIS

Existing Population

1,700

Service Area

A portion of the Borough of Kinnelon

Need for Project

The Borough has proposed the construction of a collection system for a small area of the Borough where on-site disposal systems have been experiencing problems and have malfunctioned. Water quality standards are currently marginally meeting fecal coliform and nutrients.

Project Description

It is anticipated that this project will be for the construction of one pump station, force main, and approximately 48,000 L.F. of gravity sewer. The Borough of Kinnelon has become a member of the Pequannock River Basin Regional Sewerage Authority (PRBRSA) (January 1, 1991). The project would connect to a PRBRSA interceptor at the Butler/Kinnelon boundary and all wastewater would be discharged to the Pequannock-Lincoln Park-Fairfield Sewerage Authority for treatment.

Anticipated Recipient	:	PEQUANNOCK TOWNSHIP		
Project No.	:	340480-06	Eligible Project Cost:	$ 9,333,821
FY08 Rank	:	291		
County	:	MORRIS	Total State Amount :	$ 9,333,821

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00134
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00134

Project Name, Number

PEQUANNOCK TOWNSHIP
340480-06
COLLECTION SYSTEM

Priority List Rank

291

County

MORRIS

Existing Population

1,340

Service Area

Pequannock Township

Need for Project

The project is needed to improve existing wastewater treatment practices through the elimination of approximately 490 on-site disposal systems in a residential/commercial area and replacing them with a sanitary sewer system. The soils in this service area are classified by the Soil Conservation Service as severely limiting for on-site disposal. The average housing stock in this area is in excess of 35 years and health surveys have indicated an incidence of septic system malfunctions and shallow aquifer contamination. The proposed sewer system will provide the transmission facilities to convey the wastewater to the Pequannock, Lincoln Park and Fairfield Park Sewerage Authority (TBSA) facilities for ultimate treatment.

Project Description

This Phase IV project will be an extension of the Phase III sanitary sewer system and will include the residential area known as the "Village" and the commercial areas on Route 23.

Anticipated Recipient	:	WASHINGTON TOWNSHIP		
Project No.	:	340930-01	Eligible Project Cost:	$ 3,335,192
FY08 Rank	:	292		
County	:	GLOUCESTER	Total State Amount :	$ 3,335,192

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00131
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00131

Project Name, Number

WASHINGTON TOWNSHIP
340930-01
COLLECTION SYSTEM

Priority List Rank

292

County

GLOUCESTER

Existing Population

1,310

Service Area

Washington Township

Need for Project

Failure of on-site sewage disposal systems within the Gardendale and Grenlock areas of Washington Township have created a public nuisance. Project is necessary to eliminate failing septic systems and to construct a sanitary sewer collection system to service several of the older developments within Washington Township.

Project Description

Construction of extensions to the existing sanitary sewer collection system. The extension to the Grenloch area collection system will consist of approximately 9,895 linear feet (L.F.) of gravity main, 1,750 LF of 4" force main, 1 pump station and all appurtenances along Park Avenue, Lake Avenue, Central Avenue, Edgewater Avenue, Milburn Avenue, Arbutus Avenue and Woodbury-Turnersville Road.

The extension to the East Gardendale area collection system will consist of approximately 10,940 LF of 8" gravity main and all other appurtenances. The extension will include McKinley Avenue, Garfield Avenue, Myrtle Avenue, Spruce Street, Chestnut Street, Lucust Street, Pine Street, Copper Street, Hilbert Drive and Forrest Street.

The extension to the Wilson Road area collection system will consist of approximately 2,890 LF of 8" gravity main and all appurtenances. The Wilson Road area extension will include West End Avenue, Salem Avenue, Glen Avenue, Wilson Road and Woodbury-Turnersville Road.

All new flows are to be conveyed to and treated at the Gloucester County Utilities Treatment Plant.

Anticipated Recipient	:	MANCHESTER TOWNSHIP		
Project No.	:	340650-06	Eligible Project Cost:	$ 3,340,073
FY08 Rank	:	293		
County	:	OCEAN	Total State Amount :	$ 3,340,073

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00128
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00128

Project Name, Number

MANCHESTER TOWNSHIP
340650-06
PUMP STATION, FORCE MAIN

Priority List Rank

293

County

OCEAN

Existing Population

1,280

Service Area

Holly Oaks/Knollwoods area of the Manchester Township

Need for Project

The tremendous rate of growth in the area, coupled with an increasing number of septic tanks, has placed a severe strain on the very permeable sandy soils to adequately treat the domestic wastewater. Because of a generally high groundwater table and the high percentage of septic system failures, pollution of the groundwater and surface water is suspected. Also, the current septic tank problems pose a potential threat to the health oflocal residents. Therefore, a proper sewage disposal system is necessary.

Project Description

The project is for the construction of two pump stations and approximately 8 miles of force mains and gravity sewers with diameters ranging from 6 inches to 12 inches. The wastewater will be conveyed to the existing 42-inch diameter Union Branch Interceptor owned and operated by the Ocean County Utilities Authority (OCUA). The wastewater will be treated at the OCUA's Central Plant located in Bayville for secondary treatment with effluent disposal to the Atlantic Ocean.

Anticipated Recipient	:	RARITAN TOWNSHIP MUA		
Project No.	:	340485-04	Eligible Project Cost:	$ 8,583,061
FY08 Rank	:	294		
County	:	HUNTERDON	Total State Amount :	$ 8,583,061

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00114
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00114

Project Name, Number

RARITAN TOWNSHIP MUA
340485-04
ALTERNATIVE COLLECTION/SYSTEMS

Priority List Rank

294

County

HUNTERDON

Existing Population

1,140

Service Area

Raritan Township

Need for Project

This project is proposed for the elimination of malfunctioning septic systems. Existing water quality in the area does not meet standards for dissolved oxygen and fecal coliform and marginally meets standards for nutrient and toxics.

Project Description

According to the 201 Facilities Plan for the Middle South Branch of the Raritan River, collection systems were proposed for Sand Hill Road, Sunny Hills Estates, Old Craton Road, Raritan Gardens, Broad Acres and Ridge Road areas, individual & mound systems for the Deerpath Village and Southridge areas, and a STEP system for Bridgeview Estates. The septic tank effluent from the effluent collectors and STEP System will be treated at the Raritan Township MUA.

Anticipated Recipient	:	UPPER TWP (STRATHMERE)		
Project No.	:	340619-03	Eligible Project Cost:	$ 2,326,681
FY08 Rank	:	295		
County	:	CAPE MAY	Total State Amount :	$ 2,326,681

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00091
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00091

Project Name, Number

UPPER TWP (STRATHMERE)
340619-03
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

295

County

CAPE MAY

Existing Population

910

Service Area

Strathmere Section of Upper Township

Need for Project

This project is proposed for the elimination of public nuisance associated with ground and surface water pollution possibly resulting from malfunctioning individual on-site wastewater treatment systems. The Strathmere section of Upper Township is a recreational island community characterized by high summer population densities and high groundwater levels.

Project Description

Upper Township proposes the planning, design and construction of a new sanitary sewage collection and interceptor system for the elimination of the existing improperly operating on-site systems. Wastes collected in this system will be pumped into the Avalon system for transmission to the proposed 7.67 mgd Seven Mile/Middle regional treatment facility. The collection and treatment of wastes generated by the Strathmere section of Upper Township were included in the Seven Mile/Middle regional plans.

Anticipated Recipient	: PEQUANNOCK TOWNSHIP			
Project No.	: 340480-05	Eligible Project Cost:	$	6,403,679
FY08 Rank	: 296			
County	: MORRIS	Total State Amount :	$	6,403,679

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00086
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00086

Project Name, Number

PEQUANNOCK TOWNSHIP
340480-05
COLLECTION SYSTEM

Priority List Rank

296

County

MORRIS

Existing Population

860

Service Area

Pequannock Township

Need for Project

The project is needed to improve existing wastewater treatment practices through the elimination of on-site disposal systems in a residential/commercial area and replacing them with a sanitary sewer system as well as for future growth. The soils in this service area are classified by the Soil Conservation Service as severely limiting for on-site disposal. The average housing stock in this area is in excess of 35 years and health surveys have indicated an incidence of septic system malfunctions and shallow aquifer contamination.

Project Description

This Phase III project will be an extension of the Phase I sanitary sewer system and will include the residential area between Greenwood Avenue and Pequannock Avenue and the commercial properties along the southern portion of Route 23. The proposed sewer system will provide the transmission facilities to convey the wastewater to the Pequannock, Lincoln Park and Fairfield Park Sewerage Authority (TBSA) facilities for ultimate treatment.

Anticipated Recipient	: BRANCHVILLE BOROUGH			
Project No.	: 340740-02	Eligible Project Cost:	$	2,584,971
FY08 Rank	: 297			
County	: SUSSEX	Total State Amount :	$	2,584,971

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00085
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00085

Project Name, Number

BRANCHVILLE BOROUGH
340740-02
COLLECTION SYSTEM

Priority List Rank

297

County

SUSSEX

Existing Population

850

Service Area

Branchville

Need for Project

The Branchville area is currently relying on on-site septic disposal systems for the treatment of wastewater. Many of these existing systems appear inadequate and are becoming a public nuisance.

Project Description

This project is part of a wastewater treatment system to be developed by the Sussex County Municipal Utilities Authority and consists of a proposed regional sewage treatment plant which will serve Frankford Township along with Branchville Borough. It includes the construction of a collection and interceptor system for the Branchville Borough area.

Anticipated Recipient	:	SOUTHAMPTON TOWNSHIP		
Project No.	:	340961-01	Eligible Project Cost:	$ 2,459,208
FY08 Rank	:	298		
County	:	BURLINGTON	Total State Amount :	$ 2,459,208

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00081
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00081

Project Name, Number

SOUTHAMPTON TOWNSHIP
340961-01
SEWER SYSTEM, FORCE MAIN

Priority List Rank

298

County

BURLINGTON

Existing Population

810

Service Area

Village of Vincentown

Need for Project

The Village of Vincentown is primarily a residential area currently using individual on-site wastewater treatment disposal systems. A survey report was made by the Burlington County Health Department, which showed that many of the systems are having serious problems.

Project Description

The topography of the area to be served (Village of Vincentown) is not steep sloped, but with gently sloping grades. The major obstacles are three small streams, which will be crossed by hanging insulated pipes on the existing bridges. 11,200 L.F. 8 inch san. sewer pipe and 3800 L.F. force main will be installed. The project also entails 230 laterals, 44 manholes, and pavement restoration.

Anticipated Recipient	: GALLOWAY TOWNSHIP			
Project No.	: 340892-02	Eligible Project Cost:	$	5,700,971
FY08 Rank	: 299			
County	: ATLANTIC	Total State Amount :	$	5,700,971

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00080
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00080

Project Name, Number

GALLOWAY TOWNSHIP
340892-02
COLLECTION SYSTEM

Priority List Rank

299

County

ATLANTIC

Existing Population

800

Service Area

South Egg Harbor City

Need for Project

The present disposal system for the area is a septic system, which is failing and may pose a threat to health and may also contaminate surface and groundwaters.

The Pinelands Commission has recently adopted a new ordinance that affects this area. The zoning of the South Egg Harbor City Section of the Township reflects this change and conforms to the Pinelands comprehensive management plan.

Project Description

The proposed sanitary sewer extension project consists of approximately 60,000 linear feet of 8-inch, 10-inch, or 12-inch diameter gravity sanitary sewer lines to service the existing population of the area. The system is designed to consist of 231 unsewered dwelling units (@ 3.5 persons per dwelling unit).

Two pumping stations will also be necessary. One is planned to be located along Pittsburg Avenue, the other along Bella Donna Street.

The wastewater flow from this area will be conveyed via the ACUA Pomona Pump Station to the ACUA Coastal Plant for secondary treatment, with effluent discharge to the Atlantic Ocean.

Anticipated Recipient	: NORTH ARLINGTON BOROUGH			
Project No.	: 340959-02	Eligible Project Cost:	$	708,917
FY08 Rank	: 300			
County	: BERGEN	Total State Amount :	$	708,917

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00066
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00066

Project Name, Number

NORTH ARLINGTON BOROUGH
340959-02
COLLECTION SYSTEM

Priority List Rank

300

County

BERGEN

Existing Population

660

Service Area

North Arlington Borough

Need for Project

Elimination of malfunctioning on-site septic systems and holding tanks, by providing new collection system and transportation of wastewater flows to the Passaic Valley Sewerage Commissioners STP for treatment and disposal.

Project Description

Construction of 3,600 feet of collection sewers, to serve the Porete Avenues section of North Arlington. The wastewater will be conveyed through the North Arlington-Lyndhurst Joint Meeting's sewer system to the Passaic Valley Sewerage Commissioners STP.

Anticipated Recipient	:	SHAMONG TWP		
Project No.	:	340831-01	Eligible Project Cost:	$ 2,702,506
FY08 Rank	:	301		
County	:	BURLINGTON	Total State Amount :	$ 2,702,506

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00062
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00062

Project Name, Number

SHAMONG TWP
340831-01
ALTERNATIVE WASTEWATER SYSTEM

Priority List Rank

301

County

BURLINGTON

Existing Population

620

Service Area

Barton's Lake and Fawn Lake Villages in Shamong Township

Need for Project

The Fawn Lake and Barton's Lake areas of Shamong Township have been experiencing on-site disposal problems for the past ten years. Barton's Lake Village is a development of 77 homes adjacent to Indian Mills Lake. This development is experiencing failures due to high groundwater and soil constraints.

The Fawn Lake Village is a mobile home park with approximately 114 units, served by combined septic systems. Problems experienced in the development appear to be associated with undersized systems and soil constraints. The Fawn Lake Village is adjacent to Springers Brook, a tributary of the Mullica River.

Project Description

The facilities plan indicates that two septic tank effluent collection systems, which will convey partially treated wastewater to two community leachfields, will be the most cost-effective solutions for the two problem areas.

Anticipated Recipient	:	MILLSTONE BOROUGH		
Project No.	:	340271-01	Eligible Project Cost:	$ 3,340,073
FY08 Rank	:	302		
County	:	SOMERSET	Total State Amount :	$ 3,340,073

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00055
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00055

Project Name, Number

MILLSTONE BOROUGH
340271-01
COLLECTION SYSTEM

Priority List Rank

302

County

SOMERSET

Existing Population

550

Service Area

Millstone Borough

Need for Project

The existing homes are served by cesspools and septic systems. Many of the systems are failing and are located on small lots with no place to replace them. Some homes are over 100 years old. High groundwater and clay soils prevent replacement of septic systems.

Project Description

The proposed project includes the installation of a sewage collection system, one pump station, 2 ejection stations, and associated PVC pipe. The sewage will be conveyed via a force main to Franklin Township.

Anticipated Recipient	: PLAINSBORO TOWNSHIP			
Project No.	: 340836-01	Eligible Project Cost:	$	2,089,419
FY08 Rank	: 303			
County	: MIDDLESEX	Total State Amount :	$	2,089,419

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00045
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00045

Project Name, Number

PLAINSBORO TOWNSHIP
340836-01
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

303

County

MIDDLESEX

Existing Population

450

Service Area

Township of Plainsboro

Need for Project

A portion of Plainsboro Township is presently served by on-site systems. Many of these systems are malfunctioning and result in the surfacing of sewage and sewage back-ups into homes. This problem is a potential health threat and public nuisance to the residents in that area.

Project Description

The preliminary solution to the malfunctioning septic systems is to install a gravity collection system and interceptor for treatment at the Lin Pro Utility Company STP and discharge into Cranbury Brook, a tributary to the Millstone River.

Anticipated Recipient	:	CLAYTON BOROUGH(SILVER LAKE)		
Project No.	:	340918-01	Eligible Project Cost:	$ 1,162,637
FY08 Rank	:	304		
County	:	GLOUCESTER	Total State Amount :	$ 1,162,637

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00041
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00041

Project Name, Number

CLAYTON BOROUGH(SILVER LAKE)
340918-01
COLLECTION SYSTEM

Priority List Rank

304

County

GLOUCESTER

Existing Population

410

Service Area

Silver Lake Area of Clayton

Need for Project

There are 105 homes within the proposed service area (Silver Lake) which have experienced problems and/or failures with their individual disposal systems. This situation has created a public nuisance.

Project Description

The proposed project is for the construction of collector sewers for the Silver Lake service area to the existing 8" gravity system on Bernard Street. The wastewater will be conveyed via an existing Gloucester County Utilities Authority interceptor to the regional plant in Paulsboro for treatment.

Anticipated Recipient	:	PENNSVILLE SA		
Project No.	:	340870-01	Eligible Project Cost:	$ 2,157,878
FY08 Rank	:	305		
County	:	SALEM	Total State Amount :	$ 2,157,878

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00040
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00040

Project Name, Number

PENNSVILLE SA
340870-01
COLLECTION SYSTEM

Priority List Rank

305

County

SALEM

Existing Population

400

Service Area

A portion of the Township of Pennsville

Need for Project

The Hook Road and Sapawna Lane areas of the Township of Pennsville contain a large percentage of septic overflow problems, resulting in the existence of a public health nuisance.

Project Description

This project will consist of the installation of a low pressure collection system for the Hook Road and Sapawna Lane sections of the Township.

Anticipated Recipient	: BUENA BOROUGH MUA			
Project No.	: 340833-01	Eligible Project Cost:	$	721,335
FY08 Rank	: 306			
County	: ATLANTIC	Total State Amount :	$	721,335

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00035
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00035

Project Name, Number

BUENA BOROUGH MUA
340833-01
COLLECTION SYSTEM, STP

Priority List Rank

306

County

ATLANTIC

Existing Population

350

Service Area

Borough of Buena

Need for Project

A high water table and poor soil conditions contribute to the failure of the existing on-site systems. Continued reliance on inadequate systems may degrade groundwater quality in the area. In addition, the potential for ponding septage and other problems associated with system failure may create a public health problem.

Project Description

The project report will evaluate all feasible collection and on-site treatment alternatives in order to determine the most cost-effective and environmentally acceptable alternative to treat wastewater in those areas of Buena which are presently unsewered.

Anticipated Recipient	:	PEQUANNOCK TOWNSHIP		
Project No.	:	340480-03	Eligible Project Cost:	$ 1,645,877
FY08 Rank	:	307		
County	:	MORRIS	Total State Amount :	$ 1,645,877

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00018
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	300.00018

Project Name, Number

PEQUANNOCK TOWNSHIP
340480-03
COLLECTION SYSTEM

Priority List Rank

307

County

MORRIS

Existing Population

180

Service Area

Pequannock Township - Pequannock Avenue from Newark-Pompton Turnpike to Route 23 and a portion of Madison Street

Need for Project

The project is needed to improve existing wastewater treatment practices through the elimination of on-site disposal systems which serve a residential area of 61 units and replacing them with a sanitary sewer system. The soils in this service area are classified by the Soil Conservation Service as severely limiting for on-site disposal. The average housing stock in this area is in excess of 50 years and health surveys have indicated an incidence of septic system malfunctions and shallow aquifer contamination.

Project Description

The proposed project includes the construction of approximately 320 linear feet of 8-inch diameter PVC sewer main and 2,825 linear feet of 10-inch diameter sewer main and all necessary appurtenances to serve 61 properties. Also included in the project is a culvert crossing and the crossing of the City of Newark's twin water supply aqueducts. The proposed sewer system will provide the transmission facilities to convey the wastewater to the Pequannock, Lincoln Park and Fairfield Park Sewerage Authority (TBSA) facilities for treatment.

Anticipated Recipient	:	LINCOLN PARK BOROUGH		
Project No.	:	340594-02	Eligible Project Cost:	$ 4,245,681
FY08 Rank	:	308		
County	:	MORRIS	Total State Amount :	$ 4,245,681

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00014
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00014

Project Name, Number

LINCOLN PARK BOROUGH
340594-02
COLLECTION SYSTEM

Priority List Rank

308

County

MORRIS

Existing Population

140

Service Area

Borough of Lincoln Park (portion)

Need for Project

There are approximately 67 homes within the proposed service area (Jacksonville Road) which have experienced problems and/or failures with their individual disposal systems. This has created a public nuisance.

Project Description

This project is for the construction of a pump station, force main, interceptor and collector sewers for this service area. These facilities will convey the Borough's wastewater to an existing interceptor of the Pequannock, Fairfield and Lincoln Park Sewerage Authority (TBSA) for ultimate disposal at the existing TBSA's treatment plant. This project is presently in the facilities planning stage.

Anticipated Recipient	: WOODBRIDGE TOWNSHIP			
Project No.	: 340433-08	Eligible Project Cost:	$	36,885
FY08 Rank	: 309			
County	: MIDDLESEX	Total State Amount :	$	36,885

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	50
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	50

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00002
BDA Points	0
Transit Villages	0
TOTAL POINTS	300.00002

Project Name, Number

WOODBRIDGE TOWNSHIP
340433-08
COLLECTION SYSTEM

Priority List Rank

309

County

MIDDLESEX

Existing Population

20

Service Area

A portion of the Township of Woodbridge

Need for Project

Septic systems on Florida Grove Road have been experiencing problems and/or failures and causing a public nuisance.

Project Description

The proposed project is for the construction of a sewer system to serve homes on Florida Grove Road.

Anticipated Recipient	:	BAYONNE LRA		
Project No.	:	340051-04	Eligible Project Cost:	$ 4,850,022
FY08 Rank	:	310		
County	:	HUDSON	Total State Amount :	$ 4,850,022

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.06184
BDA Points	10
Transit Villages	0
TOTAL POINTS	285.06184

Project Name, Number

BAYONNE LRA
340051-04
STORMWATER MANAGEMENT

Priority List Rank

310

County

HUDSON

Existing Population

61,842

Service Area

Penninsula at Bayonne Harbor

Need for Project

Existing stormwater management infrastructure for the facility does not meet current water quality regulations, and allows stormwater to flow over contaminated soils before being discharged to surface waters. The proposed project includes construction of a stormwater management system that meets current regulations.The design calls for collection of all stormwater falling on impervious surfaces, treatment of the stormwater for 80% TSS removal, and discharge to the base of Port Jersey Channel.

Project Description

The proposed project includes construction of a stormwater management system for the access road and truck parking areas of the maritime district located on a portion of the former Military Ocean Terminal - Bayonne (MOTBY) site. Construction will include stormwater inlets, pipes, water quality treatment devices, and a stormwater basin.

Anticipated Recipient	:	JERSEY CITY RA		
Project No.	:	340119-01	Eligible Project Cost:	$ 3,000,793
FY08 Rank	:	311		
County	:	HUDSON	Total State Amount :	$ 3,000,793

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.24006
BDA Points	0
Transit Villages	0
TOTAL POINTS	275.24006

Project Name, Number

JERSEY CITY RA
340119-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

311

County

HUDSON

Existing Population

240,055

Service Area

Jersey City

Need for Project

The proposed project significantly reduces the amount of storm water flowing into the already burdened combined sewer system. Installation of low-flow water fixtures will help reduce the impact to the cities sewer system by 20%.

Project Description

The proposed project includes installation of green roofs, rainwater harveting technology, a sub-surface detention system, photovoltaic arrays, and low-flow water fixtures.

Anticipated Recipient	:	ELIZABETH CITY		
Project No.	:	340942-09	Eligible Project Cost:	$ 4,653,327
FY08 Rank	:	312		
County	:	UNION	Total State Amount :	$ 4,653,327

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.12057
BDA Points	0
Transit Villages	0
TOTAL POINTS	275.12057

Project Name, Number

ELIZABETH CITY
340942-09
STORMWATER MANAGEMENT

Priority List Rank

312

County

UNION

Existing Population

120,568

Service Area

City of Elizabeth

Need for Project

Elizabeth proposes to install a new storm sewer system to serve the 53.11-acre drainage area for the Verona and Gebhardt sections of the City to separate the stormwater runoff from the City’s combined sewer system.

Project Description

The proposed project includes installation of approximately 4,300 LF of 15 to 60-inch diameter storm sewers to collect storm water and convey it to a new discharge point near the Elizabeth River.

Anticipated Recipient	: HOBOKEN CITY			
Project No.	: 340635-03	Eligible Project Cost:	$	73,770
FY08 Rank	: 313			
County	: HUDSON	Total State Amount :	$	73,770

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.03858
BDA Points	0
Transit Villages	0
TOTAL POINTS	275.03858

Project Name, Number

HOBOKEN CITY
340635-03
STORMWATER MANAGEMENT

Priority List Rank

313

County

HUDSON

Existing Population

38,577

Service Area

City of Hoboken

Need for Project

Hoboken plans to install a detention system and storm sewer to serve a section of the City, and will connect to an existing storm sewer.

Project Description

The proposed project includes a series of 21 inch diameter storage pipes with outfalls connected to the storm drainage system in Jackson Street.

Anticipated Recipient	:	SECAUCUS TOWN		
Project No.	:	340029-03	Eligible Project Cost:	$ 2,250,375
FY08 Rank	:	314		
County	:	HUDSON	Total State Amount :	$ 2,250,375

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01593
BDA Points	0
Transit Villages	0
TOTAL POINTS	275.01593

Project Name, Number

SECAUCUS TOWN
340029-03
STORM SEWER EXTENSION

Priority List Rank

314

County

HUDSON

Existing Population

15,931

Service Area

Town of Secaucus

Need for Project

The proposed project is needed to address the impacts of nonpoint source pollution by reducing flooding in the Upper Sack Creek watershed.

Project Description

The proposed project includes the replacement of a 5.5 foot by 2.7 foot culvert with a 60 inch diameter 48 inch diameter storm sewer pipes to convey additional flows to the upgraded Golden Avenue storm water pump station.

Anticipated Recipient	: TOTOWA BOROUGH			
Project No.	: 340778-04	Eligible Project Cost:	$	420,000
FY08 Rank	: 315			
County	: PASSAIC	Total State Amount :	$	420,000

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.01119
BDA Points	0
Transit Villages	0
TOTAL POINTS	265.01119

Project Name, Number

TOTOWA BOROUGH
340778-04
FORCE MAIN

Priority List Rank

315

County

PASSAIC

Existing Population

11,190

Service Area

Borough of Totowa

Need for Project

The proposed project will coonect 214 homes to the Borough’s wastewater system.

Project Description

The proposed project consists of the construction of approximately 3,200 linear feet of sanitary sewer force main to connect a collection system for 214 homes to the Borough’s main conveyance system.

Anticipated Recipient	: BERNARDSVILLE BOROUGH			
Project No.	: 340816-04	Eligible Project Cost:	$	646,588
FY08 Rank	: 316			
County	: SOMERSET	Total State Amount :	$	646,588

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00668
BDA Points	0
Transit Villages	0
TOTAL POINTS	265.00668

Project Name, Number

BERNARDSVILLE BOROUGH
340816-04
SEWER REHABILITATION

Priority List Rank

316

County

SOMERSET

Existing Population

6,680

Service Area

Borough of Bernardsville

Need for Project

An existing six-inch asbestos cement pipe force main continuously breaks causing the release of untreated sewage onto Borough streets.

Project Description

The proposed project includes the replacement of approximately 3,500 feet of existing six inch asbestos cement force main with new six-inch high-density polyethylene pipe.

Anticipated Recipient	: CAPE MAY CITY			
Project No.	: 340258-01	Eligible Project Cost:	$	360,245
FY08 Rank	: 317			
County	: CAPE MAY	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00650
BDA Points	0
Transit Villages	0
TOTAL POINTS	265.00650

Project Name, Number

CAPE MAY CITY
340258-01
DESALINATION CONCENTRATE DISPOSAL

Priority List Rank

317

County

CAPE MAY

Existing Population

6,500

Service Area

City of Cape May, Borough of West Cape May, Borough of Cape May Point, portion of Lower Township and Coast Guard Base

Need for Project

The Cohansey Aquifer from which the Cape May Water Utility draws its potable water is experiencing salt water intrusion. To prolong the life of the Cohansey Aquifer and to meet summer water needs, the City is proposing to derive 1.4 MGD of brackish water from the Atlantic City 800-feet deep sand aquifer and build a desalination facility employing a reverse osmosis process.

Project Description

The desalination facility will generate 1.0 MGD of potable water, 0.4 MGD of concentrate and 1,000 gpd of sanitary wastewater. The conveyance facilities is included in this project and involves the construction of two force mains. One force main will be 2-inch diameter, 2,300 feet long and will carry sanitary waste, membrane wash water and water from floor drains to the West Cape May Borough’s sewer system where it will flow to the Cape May County MUA’s STP for treatment and disposal in the Atlantic Ocean. The second force main will be 6-inch diameter, 2,700 feet long and will be designed to carry 0.4 MGD of desalination concentrate to the Cape Island Creek.

Anticipated Recipient :	BEDMINSTER TOWNSHIP		
Project No. :	340830-01	Eligible Project Cost:	$ 44,376,955
FY08 Rank :	318		
County :	SOMERSET	Total State Amount :	$ 44,376,955

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.00830
BDA Points	0
Transit Villages	0
TOTAL POINTS	260.00830

Project Name, Number

BEDMINSTER TOWNSHIP
340830-01
STP PURCHASE

Priority List Rank

318

County

SOMERSET

Existing Population

8,302

Service Area

Sections of Bernards, Far Hills, Peapack-Gladstone, Bedminster

Need for Project

The purchase of the EDC wastewater system will ensure continuing, efficient service to the existing customers at reasonable rates. The existing system includes a 2.10 MGD wastewater treatment plant that discharges to the North Branch of the Raritan River. The purchase is intended to maintain water quality through an efficient municipal operation and controlled growth in the service area.

Project Description

The proposed project includes the purchase of the entire EDC wastewater collection system within the utilities franchise area in Bernards and Bedminster along with the company’s 2.1 MGD central wastewater treatment plant located in Bedminster.

Anticipated Recipient	:	CRANBURY TOWNSHIP		
Project No.	:	340506-02	Eligible Project Cost:	$ 3,603,428
FY08 Rank	:	319		
County	:	MIDDLESEX	Total State Amount :	$ 3,603,428

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.00250
BDA Points	0
Transit Villages	0
TOTAL POINTS	260.00250

Project Name, Number

CRANBURY TOWNSHIP
340506-02
COLLECTION SYSTEM

Priority List Rank

319

County

MIDDLESEX

Existing Population

2,500

Service Area

Portions of Cranbury Township

Need for Project

Cranbury Township Planning Board recently changed their zoning on the east of Route 130 to permit 100% warehouse development. This has caused a dramatic increase in growth on the east side of Route 130 during the past year. The installation of the proposed sanitary system would benefit future development in the area east of 130. By diverting all flows presently directed to the Village Area Pump Station from the east side of Route 130, the Village Area Pump Station and force mains will have sufficient capacity for all projected flows west 130.

Project Description

The proposed project includes installation two new pump stations, one at 1.75 MGD with 1700 LF of 12” force main, the second at 3.75 MGD with 4000 LF of 16” force main.

Anticipated Recipient	:	MIDDLESEX COUNTY UA		
Project No.	:	340680-05	Eligible Project Cost:	$ 1,419,732
FY08 Rank	:	320		
County	:	MIDDLESEX	Total State Amount :	$ 1,419,732

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	1.78184
BDA Points	0
Transit Villages	0
TOTAL POINTS	251.78184

Project Name, Number

MIDDLESEX COUNTY UA
340680-05
SEPTAGE RECEIVING FACILITIES

Priority List Rank

320

County

MIDDLESEX

Existing Population

1,781,840

Service Area

Bound Brook Borough, Carteret Borough, Chatham Township (C), Clark Township (C), Cranford Township (C), Dunellen Borough, East Brunswick Township, Edison Township, Elizabeth City (C), Fanwood Borough, Franklin Township, Garwood Borough (C), Helmetta Borough, Highland Park Borough, Hillside Township (C), Irvington (C), Jamesburg Borough, Kenilworth Borough, Linden (C), Maplewood Township (C), Middlesex Borough, Millburn Township (C), Milltown Borough, Monmouth County (C), Monroe Township, Mountainside Township, New Brunswick, New Providence (C), North Plainfield, Old Bridge Township, Perth Amboy, Piscataway Township, Plainfield, Plainsboro Township, Rahway (C), Roselle (C), Roselle Park (C), Sayreville, Scotch Plains Township, South Bound Brook Borough, South Brunswick Township, South Orange Village, South Plainfield Borough, South River Borough, Spotswood Borough, Springfield Township (C), Summit (C), Watchung, Westfield (C), Winfield Township (C), West Orange (C), Woodbridge

(C) - Contracted for Septage Disposal

Need for Project

This project will provide the necessary septage receiving facilities to ensure the proper treatment and disposal of septage from MCUA's designated septage service area. The project will provide clean-up facilities for any spills during unloading and will enable all septage haulers to utilize the disposal site. Operations at the plant will be greatly improved and the waiting period which haulers are frequently subject to will be eliminated. This will reduce the illegal disposal of septage.

Project Description

The new receiving facilities will consist of a paved receiving area for septage trucks, a piping and walkway structure, a quality control and receiving station, and new septage pumps installed in the existing grit chamber control building basement. The receiving station will be designed to adequately handle up to 120,000 gallons of septage per day.

Anticipated Recipient	:	BERGEN COUNTY UA		
Project No.	:	340386-06	Eligible Project Cost:	$ 31,783,125
FY08 Rank	:	321		
County	:	BERGEN	Total State Amount :	$ 31,783,125

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.49214
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	250.49214

Project Name, Number

BERGEN COUNTY UA
340386-06
ACQUISITION OF EDGEWATER MUA STP

Priority List Rank

321

County

BERGEN

Existing Population

492,140

Service Area

The BCUA currently serves 51 municipalities.

Need for Project

The Edgewater MUA operates a secondary sewage treatment plant in the Borough of Edgewater. The Borough has determined that the consolidation of services provided by the Bergen County UA and EMUA would produce savings to the member municipalities of both BCUA and EMUA by reducing the overall costs of the combined operations.

Project Description

The proposed project includes the acquisition of Edgewater MUA’s STP by Bergen County UA.

Anticipated Recipient	:	MOUNT HOLLY SA		
Project No.	:	340817-02	Eligible Project Cost:	$ 1,525,150
FY08 Rank	:	322		
County	:	BURLINGTON	Total State Amount :	$ 1,525,150

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.35829
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.35829

Project Name, Number

MOUNT HOLLY SA
340817-02
SEPTAGE TREATMENT & DISPOSAL

Priority List Rank

322

County

BURLINGTON

Existing Population

358,290

Service Area

Several Municipalities in New Jersey

Need for Project

The State of New Jersey has mandated that all septic tank wastes (septage) be banned from disposal in unlined landfills as of March 15, 1985. Subsequently, as there are no adequate landfills in the County, an agreement has been reached between Burlington County and the Mount Holly Sewerage Authority in which the latter would act as the lead agency to dispose of the County's septage on an interim basis. However, the Authority's facility is not designed to accept septage and the septage management plan concluded that treatment plant modifications are necessary.

Since there are no adequate means of septage disposal in the County, initial investigations indicate that septage is being dumped illegally and, in all likelihood, is resulting in localized surface and ground water degradation.

Project Description

The proposed project will treat and dispose of all the septage generated in the County on a short term basis at relatively minor costs. The county-wide sludge/septage study (C340818-01) will plan for septage disposal on a long-term basis. The latter study may conclude that the Authority should dispose of septage also for the long-term. The plans and specifications recently submitted will provide for the following:

1. Screening and Grit Removal Equipment
2. Comminutor
3. Aerated Holding Tanks
4. Chlorination Equipment
5. Pumps
6. Odor Control
7. Prefabricated Structure

Anticipated Recipient	:	GLOUCESTER COUNTY UA		
Project No.	:	340902-01	Eligible Project Cost:	$ 4,945,666
FY08 Rank	:	323		
County	:	GLOUCESTER	Total State Amount :	$ 4,945,666

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.15977
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.15977

Project Name, Number

GLOUCESTER COUNTY UA
340902-01
SLUDGE MANAGEMENT

Priority List Rank

323

County

GLOUCESTER

Existing Population

159,770

Service Area

Clayton Borough, Deptford Twp., Glassboro Borough, Mantua Twp., Monroe Twp., National Park Borough, Paulsboro Borough, Washington Twp., Wenonah Borough, W. Deptford Twp., Westville Borough, Woodbury City, and Woodbury Hts Borough

Need for Project

The Gloucester County Utilities Authority (GCUA) is presently disposing of sludge by incineration. The design capacity of the GCUA incinerator is inadequate to handle the 15 tons of sludge (dry weight basis) produced at the GCUA Regional Plant. As a result, the Authority proposes to add another fluidized bed to the existing incinerator in order to increase its design capacity.

The approved (201) Facilities Plan for the GCUA consolidated region calls for static pile composing as a long term sludge management alternative. Therefore, the Authority may be required to amend the facilities plan, should they intend to employ incineration as the most cost effective, environmentally sound and implementable long term sludge management alternative.

Project Description

The project will consist of the addition of a fluidized bed to the existing incinerator of the GCUA Regional Plant for disposal of all the sludges produced in the GCUA-consolidated region.

Anticipated Recipient	:	SOMERSET-RARITAN VALLEY SA		
Project No.	:	340801-03	Eligible Project Cost:	$ 1,465,130
FY08 Rank	:	324		
County	:	SOMERSET	Total State Amount :	$ 1,465,130

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.10070
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.10070

Project Name, Number

SOMERSET-RARITAN VALLEY SA
340801-03
SEPTAGE TREATMENT/DISPOSAL

Priority List Rank

324

County

SOMERSET

Existing Population

100,700

Service Area

Bedminster Township, Bernards Township, Bernardsville Borough, Branchburg Township, Bridgewater Township, Far Hills Borough, Hillsborough Township, Manville Borough, Millstone Borough, Montgomery Township, Peapack Gladstone Borough, Raritan Borough, Rocky Hill Borough, Somerville Borough, Warren Township

Need for Project

Disposing of septage in unlined landfills was banned on March 15, 1985 pursuant to amendments of the Solid Waste Management Act to prevent the danger of groundwater contamination. An alternative disposal method is the utilization of existing treatment facilities. Therefore, the municipalities indicated above have been assigned to the Somerset-Raritan Valley SA treatment plant as designated in Appendix A of the Statewide Septage Management Plan. The present facilities at SRVSA for handling septage wastes are inadequate to handle the quantity and quality of wastes proposed to be accepted. This project is necessary to ensure that septage disposal for existing and future development is in conformance with said plan.

Project Description

This project is for the construction of septage facilities at the SRVSA plant so that it may dispose of the septage generated in Somerset County. The septage management plan recommends that the design capacity of the septage receiving station at the SRVSA plant be 28,000 gallons per day. In addition, the plan is addressing management and implementation considerations. The septage plan will provide SRVSA with a septage treatment and disposal method that will enable the Authority to accept all the wastes from its designated areas while also meeting its discharge requirements.

Anticipated Recipient	:	SALEM COUNTY BD OF CHOSEN FREEHOLDERS		
Project No.	:	340804-03	Eligible Project Cost:	$ 6,816,427
FY08 Rank	:	325		
County	:	SALEM	Total State Amount :	$ 6,816,427

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.05688
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.05688

Project Name, Number | Priority List Rank

SALEM COUNTY BD OF CHOSEN FREEHOLDERS | 325
340804-03
SEPTAGE TREATMENT/DISPOSAL

County

SALEM

Existing Population

56,880

Service Area

Allowlay Township, Carney's Point Township, Elmer Borough, Elsinboro Township, Lower Alloways Creek Township, Mannington Township, Oldmans Township, Pennsville Township, Pilesgrove Township, Pittsgrove Township, Quinton Township, Salem City, Upper Pittsgrove Township

Need for Project

Approximately 30 percent of County residents employ on-lot individual septic systems to treat their wastewater. Currently, numerous problems exist with these systems as a result of their installation in inappropriate soils and due to inadequate design. This situation leads to nuisance conditions, possibility of public health problems, and localized groundwater quality degradation.

The problems in Salem County are further aggravated by the lack of adequate facilities to accept and properly dispose of septage pumpouts. The State of New Jersey mandated that septage be banned from all but lined landfills with leachate control effective March 15, 1985. There are no such facilities in the planning area. It is presumed that a good deal of illegal septage dumping is occurring in the County and that surface and groundwater quality degradation may result.

Project Description

The planning for this project is to provide two basic responses to the problem outlined above. The first response is to plan for the adequate treatment and disposal for all the septage generated within the County. The second is to develop an overall management system of the County where on-lot systems currently exist. These solutions would involve the application and innovation of advanced technologies to resolve these problems. The facilities plan will consist of the following components:

1. County-wide Septage Disposal Plan
2. On-lot Septic Tank Management Plan
3. Environmental Analysis
4. Full-scale Public Participation Program.

Implementation of the selected plan will resolve the problem indicated above in a cost-effective, environmentally sound manner.

Anticipated Recipient	: PARSIPPANY-TROY HILLS TWP			
Project No.	: 340806-03	Eligible Project Cost:	$	354,638
FY08 Rank	: 326			
County	: MORRIS	Total State Amount :	$	354,638

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.05065
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.05065

Project Name, Number

PARSIPPANY-TROY HILLS TWP
340806-03
SEPTAGE TREATMENT/DISPOSAL

Priority List Rank

326

County

MORRIS

Existing Population

50,649

Service Area

Denville Township, East Hanover Township, Montville Township, Mountain Lakes Borough, Parsippany-Troy Hills Township

Need for Project

Disposal of septage in unlined landfills was prohibited effective March 15, 1985 to prevent the danger of groundwater contamination. An alternative disposal method is to use existing treatment facilities. Therefore, the municipalities indicated above have been assigned to the Parsippany-Troy Hills treatment plant as designated in Appendix A of the Statewide Septage Management Plan. The project is necessary to insure that septage disposal for existing and future development is in conformance with said plan.

The Township of Parsippany-Troy Hills is in the last stages of completing the construction of a 16 mgd advanced wastewater treatment facility. The present septage handling facilities were adequate to handle the flows from just the immediate service area but they are not adequate to handle the quantity and quality of wastes directed to this facility by the Department.

It is the intent of this project to develop and implement a comprehensive plan to evaluate the capability of the treatment facility to accept additional septage wastes and to recommend necessary modifications be constructed.

Project Description

Parsippany-Troy Hills Wastewater Treatment Plant will have responsibility of treating an estimated 54,000 GPD of septage. In order to handle these wastes, Parsippany-Troy Hills has completed an NJDEP approved septage management plan which recommends construction of facilities that include the truck receiving area, gravel trap, coarse bar screens, holding tank, and associated appurtenances.

Anticipated Recipient	:	NORTHWEST BERGEN CO UA		
Project No.	:	340700-05	Eligible Project Cost:	$ 2,294,564
FY08 Rank	:	327		
County	:	BERGEN	Total State Amount :	$ 2,294,564

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.05055
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	250.05055

Project Name, Number

NORTHWEST BERGEN CO UA
340700-05
SEPTAGE DISPOSAL FACILITY

Priority List Rank

327

County

BERGEN

Existing Population

50,550

Service Area

Allendale Borough, Franklin Lakes Borough, HoHoKus Borough, Mahwah Township, Midland Park Borough, Ramsey Borough, Saddle River Borough, Upper Saddle River Borough, Waldwick Borough, Wyckoff Township

Need for Project

Although the unsewered areas are included in the Planning Area for Northwest Bergen County Utilities Authority, there is presently no formal provision to treat septage from these areas. Septage from NWBCUA is presently being taken by informal agreement to Bergen County Utilities Authority treatment plant. The distance to this facility creates a climate for illegal dumping. The lack of a long term formal arrangement with Bergen County is unacceptable, and the lack of quality assurance is unacceptable.

Project Description

This project will provide for the construction of septage handling facilities to receive all septage generated within the planning area for treatment at the Northwest Bergen treatment plant. The septage facilities will provide for quality assurance to prevent treatment plant upset, and will provide odor control. The construction of septage facilities in conjunction with the initiation of a voucher system for tracking septage from "cradle to grave" will assure control, collection, disposal, and treatment of septage wastes from approximately 50,000 people in the planning area, thereby eliminating present unacceptable trucking and disposal of septage.

Anticipated Recipient	: BRIDGEWATER TOWNSHIP			
Project No.	: 340638-05	Eligible Project Cost:	$	788,517
FY08 Rank	: 328			
County	: SOMERSET	Total State Amount :	$	788,517

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.04294
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.04294

Project Name, Number

BRIDGEWATER TOWNSHIP
340638-05
STORMWATER MANAGEMENT

Priority List Rank

328

County

SOMERSET

Existing Population

42,940

Service Area

Township of Bridgewater

Need for Project

Construction of a detention basin will enable runoff to be held for an extended period of time allowing water to recharge back to the basin and settling silt prior to release into the storm system.

Project Description

The proposed project includes construction of a detention basin at the new municipal complex. The new basin will control and reduce runoff.

Anticipated Recipient	: WEST ORANGE TOWNSHIP		
Project No.	: 340865-01	Eligible Project Cost:	$ 12,117,146
FY08 Rank	: 329		
County	: ESSEX	Total State Amount :	$ 12,117,146

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.03911
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	250.03911

Project Name, Number

WEST ORANGE TOWNSHIP
340865-01
INTERCEPTOR SEWERS

Priority List Rank

329

County

ESSEX

Existing Population

39,110

Service Area

West Orange Township

Need for Project

The existing sewerage system in West Orange has inadequate capacity to allow for future growth potential. New interceptors and appurtenances are required to provide the needed reserve capacity for both planned and proposed sewer connections. The Township of West Orange is included within the sewer service area of the Essex/Union Joint Meeting. Since this project will have no direct impact upon existing water quality, only discharge category points for new systems can be justified.

Project Description

Proposed is the construction of new interceptors consisting of both gravity sewers and pump station/force main and appurtenances to provide additional capacity for the First and Second Mountain areas of West Orange and Livingston. An old interceptor line (PS/FM and Gravity) is also proposed for replacement as part of a major sewer system rehabilitation effort.

Anticipated Recipient	:	MANASQUAN RIVER REG SA		
Project No.	:	340832-02	Eligible Project Cost:	$ 4,610,126
FY08 Rank	:	330		
County	:	MONMOUTH	Total State Amount :	$ 4,610,126

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03900
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03900

Project Name, Number

MANASQUAN RIVER REG SA
340832-02
NEW INTERCEPTOR SYSTEM

Priority List Rank

330

County

MONMOUTH

Existing Population

39,000

Service Area

Howell Township, Farmingdale, Freehold Borough, Freehold Township and Wall Township

Need for Project

The project will eliminate point sources of pollution in the below mentioned areas (Project Description). Along the southern Route 9 corridor, the need for onsite septage systems will be eliminated. Project is needed to serve Wall Township growth and eliminate onsite disposal systems adjacent to Route 34.

Project Description

The project involves construction of an extension of interceptor sewers in the Lone Pine Landfill (Freehold Township), Brisbane Hospital (Wall Township) and Southern Route 9 Corridor (Howell Township).

Anticipated Recipient	: HOPEWELL TOWNSHIP		
Project No.	: 340282-01	Eligible Project Cost:	$ 23,940,222
FY08 Rank	: 331		
County	: MERCER	Total State Amount :	$ 23,940,222

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03846
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03846

Project Name, Number

HOPEWELL TOWNSHIP
340282-01
INTERCEPTOR SEWERS

Priority List Rank

331

County

MERCER

Existing Population

38,460

Service Area

The service area is bounded by Lawrenceville-Pennington Road and Washington Crossing Road to the north, the Township boundary to the south, Brandon Farms development to the east and the rear of the lots which front on Jacobs Creek Road. Also included is the municipal facility and the Indian Village development.

Need for Project

The project is needed to provide public sewer service to small residential lots currently served by individual on-site disposal systems underlain by rock and shallow seasonal high groundwater tables.

Project Description

The proposed project involves the construction of gravity collection sewers, trunk mains, force mains and pump stations to service the southeast sector of Hopewell Township. The sewage will be conveyed to the Ewing-Lawrence SA’s treatment facility.

Anticipated Recipient	:	HILLSBOROUGH TOWNSHIP		
Project No.	:	340099-01	Eligible Project Cost:	$ 5,570,096
FY08 Rank	:	332		
County	:	SOMERSET	Total State Amount :	$ 5,570,096

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03663
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03663

Project Name, Number

HILLSBOROUGH TOWNSHIP
340099-01
SEWER EXTENSION

Priority List Rank

332

County

SOMERSET

Existing Population

36,634

Service Area

Hillsborough Township

Need for Project

Hillsborough is proposing to provide sewer service for 238 existing homes, many with failing septic systems.

Project Description

The proposed project includes construction of approximately of 24,000 linear feet of 8-inch sewer pipe, one pumping station and approximately 14,000 linear feet of force main to connect the homes in the Claremont area to the Hillsborough Township MUA system.

Anticipated Recipient	:	CHERRY HILL TOWNSHIP		
Project No.	:	340954-01	Eligible Project Cost:	$ 1,276,427
FY08 Rank	:	333		
County	:	CAMDEN	Total State Amount :	$ 1,276,427

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03647
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03647

Project Name, Number

CHERRY HILL TOWNSHIP
340954-01
COLLECTION SYSTEM, REHABILITATION

Priority List Rank

333

County

CAMDEN

Existing Population

36,470

Service Area

Cherry Hill Township

Need for Project

To remove aging septic systems and replace them with sanitary sewer extensions and to rehabilitate aging pump stations.

Project Description

The Township of Cherry Hill plans to extend their sanitary sewers to reach several remaining unsewered sections of the Township. The various extensions are spread throughout the Township. The project will consist of gravity sewer mains, several force mains, house connections, all restorations and appurtenances. Also, the Peppermill Pump Station and Batesville Pump Station will be rehabilitated. The project may include the elimination of the School Lane Pump Station and connection by gravity sewer to an existing Camden County MUA interceptor. The Peppermill Pump Station has an existing peak flow rate of 0.13 mgd, and the Batesville Pump Station has an existing flow rate of 0.52 mgd. Each pump station will have their wetwells and pumps replaced along with related electrical services.

Anticipated Recipient	: PEMBERTON TOWNSHIP MUA		
Project No.	: 340649-02	Eligible Project Cost:	$ 13,800,360
FY08 Rank	: 334		
County	: BURLINGTON	Total State Amount :	$ 13,800,360

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03134
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03134

Project Name, Number

PEMBERTON TOWNSHIP MUA
340649-02
STP IMPROVEMENT, COLLECTION SYSTEM

Priority List Rank

334

County

BURLINGTON

Existing Population

31,340

Service Area

Portions of Pemberton Township including areas designated as regional growth within the Pinelands

Need for Project

The implementation of the upgrading of the Pemberton Township Municipal Utilities Authority Wastewater Treatment System will serve to enhance the groundwater quality in those area which are presently serviced by on-site septic systems. The properly planned expansion of the system will protect the environment from improper discharges to the groundwater and surface water. The upgrading of the existing facilities at the Authority's STP will be necessary to maintain the high level of treatment required for discharge into the North Branch of the Rancocas Creek in accordance with NJPDES permit No. NJ0024821. The existing plant is over twenty (20) years old is in need of rehabilitation and replacement of equipment. In the event that the collection system is enlarged the treatment plant capacity will have to expand to meet the demand.

Project Description

The proposed project includes the construction of a regional collection system and repair/replacement of various treatment units to improve treatment capabilities at the Pemberton Township MUA's STP.

Anticipated Recipient	:	WINSLOW TOWNSHIP (CEDAR BROOK)		
Project No.	:	340895-04	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	335		
County	:	CAMDEN	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03009
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03009

Project Name, Number

WINSLOW TOWNSHIP (CEDAR BROOK)
340895-04
COLLECTION SYSTEM

Priority List Rank

335

County

CAMDEN

Existing Population

30,090

Service Area

Winslow Township

Need for Project

A portion of Winslow Township is presently served by on-site systems. Many of these systems are malfunctioning; consequently, there is potential for groundwater contamination.

Project Description

The project consists of the construction of a sanitary sewer extension and pump stations necessary to service the schools and local residents.

Anticipated Recipient	:	WINSLOW TOWNSHIP (W. ATCO)		
Project No.	:	340895-05	Eligible Project Cost:	$ 4,852,482
FY08 Rank	:	335		
County	:	CAMDEN	Total State Amount :	$ 4,852,482

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03009
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.03009

Project Name, Number

WINSLOW TOWNSHIP (W. ATCO)
340895-05
COLLECTION SYSTEM

Priority List Rank

335

County

CAMDEN

Existing Population

30,090

Service Area

Winslow Township

Need for Project

The West Atco area is comprised of approximately 182 acres and is contained within the Pinelands Regional Growth Area and is designated as a sewer service area in the cuurent CCMUA Wastewater Management Plan. Existing development within this area consists of approximately 200 single family homes on small lots with wells that rely upon individual septic systems. There have been a number of failing septic systems within the West Atco area

Project Description

The proposed project includes construction of a sanitary sewer collection system, a pumping station and a force main.

Anticipated Recipient	:	DEPTFORD TOWNSHIP MUA		
Project No.	:	340066-01	Eligible Project Cost:	$ 1,677,717
FY08 Rank	:	337		
County	:	GLOUCESTER	Total State Amount :	$ 1,677,717

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02676
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.02676

Project Name, Number

DEPTFORD TOWNSHIP MUA
340066-01
PUMP STATION

Priority List Rank

337

County

GLOUCESTER

Existing Population

26,763

Service Area

Deptford Township

Need for Project

The RCA sewer-pumping station is a 35-year-old “Can” station. Failure of the station may cause contamination of the Alomonesson Creek and the Delaware River. The station conveys wastewater from the busiest section of the Township to a Gloucester County UA pump station and ultimately to GCUA for treatment. Upgrades and expansion will assure proper operation.

Project Description

The proposed project includes construction of a new, larger wet well with 3 submersible variable speed pumps. The controls for the new facility will be above ground in a secure building to do away with the “Can” station. New instrumentation, pumps, alarm system and a natural gas generator for emergency supply will be installed. Upon completion of the project the existing pump station shall be abandoned, the property graded and a new fence installed to secure the area.

Anticipated Recipient	:	RANDOLPH TOWNSHIP		
Project No.	:	340632-07	Eligible Project Cost:	$ 8,842,391
FY08 Rank	:	338		
County	:	MORRIS	Total State Amount :	$ 8,842,391

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01997
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01997

Project Name, Number

RANDOLPH TOWNSHIP
340632-07
INTERCEPTOR, REHABILITATION

Priority List Rank

338

County

MORRIS

Existing Population

19,974

Service Area

Township of Randolph

Need for Project

Several areas of the Township are currently served by on-site septic systems. These systems are old and in need of replacement due to soil conditions and development.

Project Description

The proposed project involves construction of the Mount Freedom Collection System with pump station and force main, as well as the upgrade of the Butterworth Interceptor.

Anticipated Recipient	: EDGEWATER BOROUGH			
Project No.	: 340446-06	Eligible Project Cost:	$	2,207,442
FY08 Rank	: 339			
County	: BERGEN	Total State Amount :	$	2,207,442

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01850
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01850

Project Name, Number

EDGEWATER BOROUGH
340446-06
COLLECTION SYSTEM

Priority List Rank

339

County

BERGEN

Existing Population

18,500

Service Area

A 26 acre tract, containing 113 residences, at the north end of the Borough of Edgewater, east of River Road.

Need for Project

Failures of on-site septic systems have lead to warnings from State and local health officials.

Project Description

The proposed project involves the construction of a new collection system to service the currently unsewered portion of the Borough of Edgewater known as “Edgewater Colony.”

Anticipated Recipient	: ABERDEEN TOWNSHIP			
Project No.	: 340869-02	Eligible Project Cost:	$	2,871,253
FY08 Rank	: 340			
County	: MONMOUTH	Total State Amount :	$	2,871,253

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01745
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01745

Project Name, Number

ABERDEEN TOWNSHIP
340869-02
COLLECTION SYSTEM

Priority List Rank

340

County

MONMOUTH

Existing Population

17,454

Service Area

Freneau section of Aberdeen Township

Need for Project

The Freneau section of Aberdeen Township is serviced by individual subsurface sewage disposal systems. Due to the soil characteristics and high-groundwater table, many of the systems are failing and discharging into Birch Swamp Brook and Matawan Creek.

Project Description

The proposed project includes construction of a wastewater collection system along with a pump station and force main to connect to an existing interceptor.

Anticipated Recipient	: WEST WINDSOR TOWNSHIP			
Project No.	: 340491-02	Eligible Project Cost:	$	570,013
FY08 Rank	: 341			
County	: MERCER	Total State Amount :	$	570,013

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01602
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01602

Project Name, Number

WEST WINDSOR TOWNSHIP
340491-02
COLLECTION SYSTEM

Priority List Rank

341

County

MERCER

Existing Population

16,021

Service Area

West Windsor Township

Need for Project

Failure of on-site sewage disposal systems within the township are causing potential environmental or health hazards and creating a public nuisance.

Project Description

The proposed project includes the construction of a collection system and force main to connect to an existing pump station that will convey flows to the Township’s treatment facility.

Anticipated Recipient	:	GLASSBORO BOROUGH		
Project No.	:	340545-04	Eligible Project Cost:	$ 3,968,099
FY08 Rank	:	342		
County	:	GLOUCESTER	Total State Amount :	$ 3,968,099

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01561
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01561

Project Name, Number

GLASSBORO BOROUGH
340545-04
COLLECTION SYSTEM

Priority List Rank

342

County

GLOUCESTER

Existing Population

15,614

Service Area

Borough of Glassboro

Need for Project

The project is needed to extend sanitary sewer into the last portion of the Borough that is not currently serviced. The sixty-plus homes not serviced have antiquated disposal systems several decades old. Residents are experiencing problems due to insufficient soils and high ground water.

Project Description

The proposed project involves extension of the 15” interceptor along with construction of a gravity collection system.

Anticipated Recipient	:	FRANKLIN TOWNSHIP (GLOUCESTER CO.)		
Project No.	:	340839-03	Eligible Project Cost:	$ 1,645,877
FY08 Rank	:	343		
County	:	GLOUCESTER	Total State Amount :	$ 1,645,877

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01547
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	250.01547

Project Name, Number

FRANKLIN TOWNSHIP (GLOUCESTER CO.)
340839-03
COLLECTION SYSTEM

Priority List Rank

343

County

GLOUCESTER

Existing Population

15,466

Service Area

Township of Franklin

Need for Project

The proposed project will replace existing on-site sewage disposal systems, some of which reportedly are failing, or do not meet current standards.

Project Description

The proposed project includes installation of a new collection system.

Anticipated Recipient	:	SPARTA TOWNSHIP		
Project No.	:	340495-04	Eligible Project Cost:	$ 2,821,542
FY08 Rank	:	344		
County	:	SUSSEX	Total State Amount :	$ 2,821,542

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01516
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01516

Project Name, Number

SPARTA TOWNSHIP
340495-04
COLLECTION SYSTEM

Priority List Rank

344

County

SUSSEX

Existing Population

15,157

Service Area

Township of Sparta

Need for Project

The Township has identified the need for sewer collection system in the designated Town Center.

Project Description

The proposed project includes the construction of a collection and conveyance system consisting of 13,300 l.f. of gravity line plus appurtenances and two pumping stations.

Anticipated Recipient	: HACKETTSTOWN MUA			
Project No.	: 340803-03	Eligible Project Cost:	$	641,034
FY08 Rank	: 345			
County	: WARREN	Total State Amount :	$	641,034

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01199
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01199

Project Name, Number

HACKETTSTOWN MUA
340803-03
SEWAGE TREATMENT & DISPOSAL

Priority List Rank

345

County

WARREN

Existing Population

11,990

Service Area

Hackettstown Town, Independence Township

Need for Project

Disposing of septage in unlined landfills was prohibited as of March 15, 1985 to prevent degradation of groundwater quality. An alterna- tive disposal method is the utilization of existing treatment facili- ties. Therefore, the municipalities indicated above have been assigned to the Hackettstown Municipal Utilities Authority treatment plant as designated in Appendix A of the Statewide Septage Management Plan. This project is necessary to ensure that septage disposal for existing and future development is in conformance with said plan.

It should also be noted that the present facilities for handling septage wastes generated within the above service area are inadequate to handle the quantity and quality of wastes proposed to be accepted.

Project Description

A septage management plan has already been approved by the NJDEP. The facility plan recommends the construction of additional septage handling facilities at the HMUA wastewater treatment plant. The proposed facilities consist of a receiving station, receiving chamber, holding tank, pumping station, piping, valves and miscellaneous equipment to provide the capability of diverting septage at a controlled rate to the primary digester or the division box upstream of the primary clarifier.

Anticipated Recipient	: HOLMDEL TOWNSHIP		
Project No.	: 340919-02	Eligible Project Cost:	$ 40,665,789
FY08 Rank	: 346		
County	: MONMOUTH	Total State Amount :	$ 40,665,789

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01153
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01153

Project Name, Number

HOLMDEL TOWNSHIP
340919-02
COLLECTION SYSTEM, INTERCEPTOR

Priority List Rank

346

County

MONMOUTH

Existing Population

11,532

Service Area

Holmdel Township

Need for Project

The Township has identified several unsewered areas which are in need of a sanitary sewer system.

Project Description

The proposed project involves the construction of a collection and conveyance system to serve Wychwood, Heather Hills, Blue Hills, Sweetbriar, Wild Hedge, Grandview, Deercrest, Stillwell Drive, Country Farms, and a portion of Country Woods on VanSchiock. Also included is the Route 520 Trunkline System and associated road restoration activities.

Anticipated Recipient	: WEST PATERSON BOROUGH			
Project No.	: 340778-05	Eligible Project Cost:	$	733,721
FY08 Rank	: 347			
County	: PASSAIC	Total State Amount :	$	733,721

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01099
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01099

Project Name, Number

WEST PATERSON BOROUGH
340778-05
SEWER REHABILITATION

Priority List Rank

347

County

PASSAIC

Existing Population

10,987

Service Area

Borough of West Paterson

Need for Project

The proposed gravity sewer will serve an area of the Borough characterized by small lots, shallow depth to bedrock and old individual sewage disposal systems. The Borough has committed to providing sewer service to the area due to polluted wells and septic system failures.

Project Description

This project includes construction of 2,940 linear feet of 8” inch gravity sewer that will extend north and south from Hillside Terrace and connect to existing sewer lines.

Anticipated Recipient	:	WATERFORD TOWNSHIP MUA		
Project No.	:	340163-01	Eligible Project Cost:	$ 3,309,186
FY08 Rank	:	348		
County	:	CAMDEN	Total State Amount :	$ 3,309,186

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01094
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.01094

Project Name, Number

WATERFORD TOWNSHIP MUA
340163-01
COLLECTION SYSTEM

Priority List Rank

348

County

CAMDEN

Existing Population

10,940

Service Area

Waterford Township

Need for Project

The proposed service area is currently using on-site systems. The area is in the Pinelands regional growth area; the Pinelands management plan promotes sewers in the growth area due to higher densities and water quality issues.

Project Description

The proposed project includes installation of sewer mains, force main and one pump station. The proposed force main will connect to an existing sewer main which then pumps into the CCMUA regional system.

Anticipated Recipient	:	HAMILTON TOWNSHIP MUA		
Project No.	:	340903-02	Eligible Project Cost:	$ 2,774,147
FY08 Rank	:	349		
County	:	ATLANTIC	Total State Amount :	$ 2,774,147

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00770
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00770

Project Name, Number

HAMILTON TOWNSHIP MUA
340903-02
COLLECTION SYSTEM

Priority List Rank

349

County

ATLANTIC

Existing Population

7,700

Service Area

The service area is bounded by the Atlantic City Expressway to the North, the Egg Harbor Township boundary to the East, West Jersey Avenue to the South and the Hamilton Mall area to the West.

Need for Project

The project is necessary to provide sewer service to the areas of the Township which are not presently sewered in order to prevent future contamination of the ground water quality.

Project Description

The proposed project consists of the construction of a collection system within Hamilton Township. The flow will be conveyed through two pump stations and gravity sewers of PVC design ranging from 8-inch to 24-inch. The estimated design flow is 1.2 MGD. The wastewater will be treated at the Atlantic County Utilities Authority (ACUA) City Island Treatment Plant.

Anticipated Recipient	:	HOPEWELL TOWNSHIP		
Project No.	:	340282-02	Eligible Project Cost:	$ 3,475,917
FY08 Rank	:	350		
County	:	MERCER	Total State Amount :	$ 3,475,917

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00615
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00615

Project Name, Number

HOPEWELL TOWNSHIP
340282-02
COLLECTION SYSTEM

Priority List Rank

350

County

MERCER

Existing Population

6,150

Service Area

The service area includes from Route 31 north of Woodsville Road to Dublin Road and east to an existing railroad right-of-way.

Need for Project

The Route 31 service area is severely constrained for individual subsurface disposal systems because of high groundwater tables and rock. The Pennytown site currently discharges all of its waste to a holding tank due to septic system failure.

Project Description

The proposed project includes the construction of gravity collection sewers, force mains and pump stations. The sewage will be conveyed to the Stony Brook Regional Sewerage Authority for treatment.

Anticipated Recipient	: EAST GREENWICH TOWNSHIP			
Project No.	: 340368-01	Eligible Project Cost:	$	660,187
FY08 Rank	: 351			
County	: GLOUCESTER	Total State Amount :	$	660,187

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00526
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00526

Project Name, Number

EAST GREENWICH TOWNSHIP
340368-01
COLLECTION SYSTEM

Priority List Rank

351

County

GLOUCESTER

Existing Population

5,260

Service Area

Kings Highway, Cohawkin Road, County House Road

Need for Project

The purpose of the project is to eliminate individual on-site septic systems.

Project Description

The proposed project involves the construction of a sanitary sewer collection system along various streets covering approximately 6,050 linear feet with 8-inch diameter PVC sewer main.

Anticipated Recipient	:	WILDWOOD CITY		
Project No.	:	340664-02	Eligible Project Cost:	$ 2,492,677
FY08 Rank	:	352		
County	:	CAPE MAY	Total State Amount :	$ 2,492,677

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00448
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00448

Project Name, Number

WILDWOOD CITY
340664-02
STORM SEWER REHABILITATION

Priority List Rank

352

County

CAPE MAY

Existing Population

4,480

Service Area

Cresse Avenue to 26th Street Beaches, City of Wildwood

Need for Project

The sand on the Wildwood beach has accreted approximately 1,700 feet since 1950, creating a beach front that is over a quarter mile from the Boardwalk to the water's edge. The existing outfall lines no longer extend far enough out into the ocean. Storm drain runoff, containing animal and bird excrement, washes back onto our bathing beaches. High fecal coliform counts, detected in the weekly sampling conducted by the Cape May County Health Department each summer, has confirmed unsafe condition and has resulted in beach closing. Ponding of this contaminated water occurs at the terminus of the outfall lines after each rain and the area must be plowed and leveled. The health and safety of the beach bathers have been imperiled and the beach closings produce a tremendous negative impact on tourism for many weeks thereafter.

Project Description

The ten (10) outfall lines will be retrenched, and pilings and cross-beams will be installed to support and contain the lines with 1,400 foot extensions. Trenches for the extensions will be dug during the low tide and the entire line will be re-covered with the accumulated sand.

Anticipated Recipient	:	DELANCO TOWNSHIP SA		
Project No.	:	340956-03	Eligible Project Cost:	$ 1,915,067
FY08 Rank	:	353		
County	:	BURLINGTON	Total State Amount :	$ 1,915,067

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00324
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00324

Project Name, Number

DELANCO TOWNSHIP SA
340956-03
COLLECTION SYSTEM

Priority List Rank

353

County

BURLINGTON

Existing Population

3,237

Service Area

Delanco Township

Need for Project

The proposed project will replace existing on-site sewage disposal systems, some of which reportedly are failing, do not meet current standards,or do not meet the needs of the homeowners.

Project Description

The proposed project construction of a sewer collection system and a pump station.

Anticipated Recipient	: WOODBINE MUA		
Project No.	: 340370-01	Eligible Project Cost:	$ 12,630,925
FY08 Rank	: 354		
County	: CAPE MAY	Total State Amount :	$ 12,630,925

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00300
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00300

Project Name, Number

WOODBINE MUA
340370-01
STP UPGRADE, EXPANSION

Priority List Rank

354

County

CAPE MAY

Existing Population

3,000

Service Area

Woodbine Borough

Need for Project

The existing residences are served by individual on-site septic systems which are suspected to contribute to groundwater pollution. The State Department of Human Services owns and operates the only treatment facility in the Borough and it is located at and serves only the Woodbine Development Center.

Project Description

The proposed project involves the acquisition of the Woodbine Development Center's STP and the upgrade and expansion of the treatment facility from 0.16 MGD to 0.5 MGD. The upgrade will employ the sequential batch reactor process and denitrification. In addition, the project includes pump stations, force mains and approximately 60,000 linear feet of gravity sewers to collect and transport wastewater to the upgraded STP.

Anticipated Recipient	: WEYMOUTH TOWNSHIP MUA			
Project No.	: 340078-01	Eligible Project Cost:	$	236,752
FY08 Rank	: 355			
County	: ATLANTIC	Total State Amount :	$	236,752

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00226
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00226

Project Name, Number

WEYMOUTH TOWNSHIP MUA
340078-01
PUMP STATION

Priority List Rank

355

County

ATLANTIC

Existing Population

2,257

Service Area

Weymouth Township

Need for Project

Equipment at the Township’s pump station has exceeded its useful life and must be reconstructed and upgraded to handle peak flows. The inability of the pumps to adequately handle the sewage causes severe odor problems throughout the collection system and poses the potential for overflows.

Project Description

The proposed project includes the replacement of equipment at the Township’s pump station.

Anticipated Recipient	: GREENWICH TOWNSHIP		
Project No.	: 340359-01	Eligible Project Cost:	$ 11,199,679
FY08 Rank	: 356		
County	: WARREN	Total State Amount :	$ 11,199,679

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00190
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00190

Project Name, Number

GREENWICH TOWNSHIP
340359-01
STP, COLLECTION SYSTEM

Priority List Rank

356

County

WARREN

Existing Population

1,900

Service Area

Southerly Sewer Service Area in Greenwich Township

Need for Project

This project will provide a necessary economic base for Greenwich Township and Warren County. The State of New Jersey will also benefit from the commercial development which will be created in the Industrial Zone of the Southerly Sewer District. It will specifically service the existing KOH-I-NOOR RAPIDOGRAPH, INC. facilities which presently have septic disposal only and the Cross Jersey Executive Park which will be constructed when the wastewater treatment plant becomes operational.

Project Description

The proposed project includes the construction of a wastewater treatment plant and collection system to serve the areas.

Anticipated Recipient	:	CHESTER BOROUGH		
Project No.	:	340876-02	Eligible Project Cost:	$ 1,191,434
FY08 Rank	:	357		
County	:	MORRIS	Total State Amount :	$ 1,191,434

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00151
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00151

Project Name, Number

CHESTER BOROUGH
340876-02
STP, COLLECTION SYSTEM

Priority List Rank

357

County

MORRIS

Existing Population

1,510

Service Area

Borough of Chester

Need for Project

The only means of wastewater treatment/disposal in Borough is via septic systems. These systems are old and experiencing significant rate of failure resulting in pollution problems for the Borough and adjacent municipalities. Funding is necessary to provide treatment to eliminate these conditions.

Project Description

The Borough proposed the construction of a wastewater treatment facility (WWTF) to service the Borough. The project includes the required collection and conveyance system components to eliminate the failing septic-systems.

Anticipated Recipient	:	COMMERCIAL TOWNSHIP		
Project No.	:	340955-01	Eligible Project Cost:	$ 9,207,328
FY08 Rank	:	358		
County	:	CUMBERLAND	Total State Amount :	$ 9,207,328

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00150
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00150

Project Name, Number

COMMERCIAL TOWNSHIP
340955-01
COLLECTION SYSTEM, STP

Priority List Rank

358

County

CUMBERLAND

Existing Population

1,500

Service Area

Port Norris

Need for Project

The commercial industries and marinas along the Maurice River are under consent order to improve their wastewater discharges into the River.

Project Description

A new collection system will be built to replace the current individual treatment systems. The collection system will be composed of approximately 4,800 L.F. of gravity main, 11,900 L.F. force main, and all appurtenances. A new wastewater treatment facility will be constructed.

Anticipated Recipient	: PEMBERTON TOWNSHIP MUA			
Project No.	: 340649-04	Eligible Project Cost:	$	1,232,571
FY08 Rank	: 359			
County	: BURLINGTON	Total State Amount :	$	1,232,571

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	250
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	250

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00121
BDA Points	0
Transit Villages	0
TOTAL POINTS	250.00121

Project Name, Number

PEMBERTON TOWNSHIP MUA
340649-04
SEPTIC MANAGEMENT DISTRICT

Priority List Rank

359

County

BURLINGTON

Existing Population

1,210

Service Area

Pemberton Township

Need for Project

Pemberton is developing a program to correct failing septic systems to improve the community’s groundwater and surface water quality and protect residents from exposure to septage.

Project Description

The proposed project includes the creation of a septic management district.

Anticipated Recipient	: PALMYRA BOROUGH			
Project No.	: 340030-02	Eligible Project Cost:	$	343,408
FY08 Rank	: 360			
County	: BURLINGTON	Total State Amount :	$	343,408

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00709
BDA Points	0
Transit Villages	0
TOTAL POINTS	240.00709

Project Name, Number

PALMYRA BOROUGH
340030-02
NPS CONTROLS

Priority List Rank

360

County

BURLINGTON

Existing Population

7,091

Service Area

Palmyra Borough

Need for Project

The existing riverwall has deteriorated due to age resulting in erosion from wave action along the shore, which allows top soil, debris, and other non-point source pollution to enter the Delaware River.

Project Description

The proposed project includes repair/replacement of riverwall to halt the introduction of pollutants into the Delaware River.

Anticipated Recipient	: MATAWAN BOROUGH			
Project No.	: 340967-02	Eligible Project Cost:	$	4,404,418
FY08 Rank	: 361			
County	: MONMOUTH	Total State Amount :	$	4,404,418

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00891
BDA Points	0
Transit Villages	10
TOTAL POINTS	235.00891

Project Name, Number

MATAWAN BOROUGH
340967-02
STORMWATER MANAGEMENT

Priority List Rank

361

County

MONMOUTH

Existing Population

8,910

Service Area

Borough of Matawan

Need for Project

The Borough’s Lake Lefferts has accumulated sediment, its banks are significantly eroded and its storage capacity has decreased. The spillway of the Dam is inoperable and inadequate in keeping solids/floatables out of the lake.

Project Description

The proposed project includes several measures to reduce erosion and control solids/floatables. Also included are measures to restore the Lake to its original storage capacity.

Anticipated Recipient	: MATAWAN BOROUGH			
Project No.	: 340967-03	Eligible Project Cost:	$	289,789
FY08 Rank	: 361			
County	: MONMOUTH	Total State Amount :	$	289,789

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00891
BDA Points	0
Transit Villages	10
TOTAL POINTS	235.00891

Project Name, Number

MATAWAN BOROUGH
340967-03
STORMWATER / NPS MANAGEMENT

Priority List Rank

361

County

MONMOUTH

Existing Population

8,910

Service Area

Borough of Matawan

Need for Project

The Borough of Matawan is located in a relatvely low lying area surrounding Lake Lefferts and Matawan Lake. Periodically, the Borough’s storm sewers collect debris and contaminants which eventually pass through the storm sewer system and into the lakes and surrounding waterways. The Borough is concerned with the non-point source pollution problem and believes this problem can be reduced through better maitenance which will be enhanced by the use of “Jet Vac” equipment and certain specific improvements to the existing stormwater facilities.

Project Description

The proposed project involves the purchase of a Jet-Vac Truck to clean debris from the storm sewers and minimze adverse impacts on Lake Lefferts.

Anticipated Recipient	: BYRAM TOWNSHIP			
Project No.	: 340569-03	Eligible Project Cost:	$	218,940
FY08 Rank	: 363			
County	: SUSSEX	Total State Amount :	$	218,940

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.00870
BDA Points	0
Transit Villages	0
TOTAL POINTS	235.00870

Project Name, Number

BYRAM TOWNSHIP
340569-03
EQUIPMENT (WEED HARVESTER)

Priority List Rank

363

County

SUSSEX

Existing Population

8,700

Service Area

Township of Byram

Need for Project

Several of Byram Township’s settled lakes are regularly subjected to herbicide treatments to control nuisance weeds. Extensive herbicide use is likely to be affecting wells in the “Cranberry” neighborhood, especially along the shoreline.

Project Description

The proposed project is for the purchase of a weed harvester to mechanically harvest nuisance weeds in the shallower areas of the lakes, thereby reducing the need for the use of herbicides.

Anticipated Recipient	: MENDHAM BOROUGH			
Project No.	: 340159-01	Eligible Project Cost:	$	318,067
FY08 Rank	: 364			
County	: MORRIS	Total State Amount :	$	318,067

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.00489
BDA Points	0
Transit Villages	0
TOTAL POINTS	235.00489

Project Name, Number

MENDHAM BOROUGH
340159-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

364

County

MORRIS

Existing Population

4,890

Service Area

Mendham Borough

Need for Project

Mendham Borough is in need of a street sweeper. The purchase of this equipment will help the Township reduce the amount of debris that accumulates in the sewer system and, in turn, reduce solids/floatables from entering the waters of the upper Passaic and upper Raritan watersheds.

Project Description

The proposed project involves the purchase of one street sweeper.

Anticipated Recipient	: MENDHAM BOROUGH			
Project No.	: 340159-02	Eligible Project Cost:	$	193,346
FY08 Rank	: 364			
County	: MORRIS	Total State Amount :	$	193,346

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	10.00000
Population	0.00489
BDA Points	0
Transit Villages	0
TOTAL POINTS	235.00489

Project Name, Number

MENDHAM BOROUGH
340159-02
STORMWATER/NPS MANAGEMENT

Priority List Rank

364

County

MORRIS

Existing Population

4,890

Service Area

Mendham Borough

Need for Project

Erosion problems in Mendham Borough are contributing to sedimentation of streams in the headwaters of the Passaic River

Project Description

The proposed project includes erosion protections and stream bank stabilization measures.

Anticipated Recipient	:	MONMOUTH COUNTY BOARD OF FREEHOLDERS		
Project No.	:	340788-05	Eligible Project Cost:	$ 923,244
FY08 Rank	:	366		
County	:	MONMOUTH	Total State Amount :	$ 923,244

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.55312
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.55312

Project Name, Number

MONMOUTH COUNTY BOARD OF FREEHOLDERS
340788-05
STORMWATER/NPS MANAGEMENT

Priority List Rank

366

County

MONMOUTH

Existing Population

553,124

Service Area

Monmouth County

Need for Project

Sediment build up in many of the lakes and ponds in the County has lead to poor water quality, algae growth, mosquito breeding, odors and low oxygen levels. Many beach closings are attributable to stormwater runoff from coastal lakes. Deepening the lakes will improve habitat and increase assimilative capacity for nutrients and other pollutants.

Project Description

The proposed project includes establishment of a silt removal program including purchase of dredging equipment and implementation of other measures to restore lakes and ponds to their original storage capacity.

Anticipated Recipient	:	CAMDEN COUNTY BOARD OF FREEHOLDERS		
Project No.	:	340525-01	Eligible Project Cost:	$ 792,068
FY08 Rank	:	367		
County	:	CAMDEN	Total State Amount :	$ 792,068

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.50282
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.50282

Project Name, Number

CAMDEN COUNTY BOARD OF FREEHOLDERS
340525-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

367

County

CAMDEN

Existing Population

502,824

Service Area

Hero’s Island in Pennsuaken/Cherry Hill

Need for Project

Veteran’s Island in the Cooper River is suffering serious erosion with its banks being washed away at a rapid rate causing silt build-up elsewhere in the river and effecting the overall quality of the river. The Island also acts as a natural barrier to erosion along a sensitive area of Cooper River Park. The Island’s banks need to be restored and stabilized to stem erosion and reduce solids transportation.

Project Description

The proposed project includes a bank restoration and stabilization through the use of crib walls and vegetative plantings to provide for safe embankments and prevent further soil erosion.

Anticipated Recipient	:	CAMDEN COUNTY DEPARTMENT OF PARKS		
Project No.	:	340525-02	Eligible Project Cost:	$ 1,693,221
FY08 Rank	:	367		
County	:	CAMDEN	Total State Amount :	$ 1,693,221

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.50282
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	225.50282

Project Name, Number

CAMDEN COUNTY DEPARTMENT OF PARKS
340525-02
STORMWATER/NPS MANAGEMENT

Priority List Rank

367

County

CAMDEN

Existing Population

502,824

Service Area

Camden County

Need for Project

Existing water quality of Haddon Lake has been degraded by undetained stormwater runoff from urbanized upstream drainage and runoff of nonpoint organic pollutants from the shoreline. Bank stabilization will create an in-line sedimentation basin for filtration of stormwater runoff and banks planted with wetland vegetation will filter nonpoint pollutant sources around the lake perimeter.

Project Description

The proposed project includes dredging of sediment from the lakebed coupled with rip rap stabilization of existing stormpipe outfalls and stabilization of eroded banks using a combination of bioengineering and structural improvements.

Anticipated Recipient	:	CAMDEN COUNTY DEPARTMENT OF PARKS		
Project No.	:	340525-03	Eligible Project Cost:	$ 781,693
FY08 Rank	:	367		
County	:	CAMDEN	Total State Amount :	$ 781,693

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.50282
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.50282

Project Name, Number

CAMDEN COUNTY DEPARTMENT OF PARKS
340525-03
STORMWATER/NPS MANAGEMENT

Priority List Rank

367

County

CAMDEN

Existing Population

502,824

Service Area

Camden County

Need for Project

Existing water quality of Newton Lake has been degraded by undetained stormwater runoff from urbanized upstream drainage and runoff of nonpoint organic pollutants from the shoreline. Bank stabilization will create an in-line sedimentation basin for filtration of stormwater runoff and banks planted with wetland vegetation will filter nonpoint pollutant sources around the lake perimeter.

Project Description

The proposed project includes dredging of sediment from the lakebed coupled with rip rap stabilization of existing stormpipe outfalls and stabilization of eroded banks using a combination of bioengineering and structural improvements.

Anticipated Recipient	:	UNION COUNTY		
Project No.	:	340280-01	Eligible Project Cost:	$ 5,015,073
FY08 Rank	:	370		
County	:	UNION	Total State Amount :	$ 5,015,073

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.49631
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.49631

Project Name, Number

UNION COUNTY
340280-01
STORMWATER MANAGEMENT

Priority List Rank

370

County

UNION

Existing Population

496,310

Service Area

Trotters Lane Branch Drainage Area

Need for Project

The project is needed to relieve flooding in Morris Avenue and in the Kean College Dormatory area and to screen out debris from the stormwater prior to discharge in the Trotters Lane Branch of the Elizabeth River. The existing brick storm drain from the west side of Morris Avenue to the Elizabeth River is too small and needs to be replaced.

Project Description

The proposed project involves the replacement of the storm drain with an adequately sized concrete box culvert. The upstream end of the culvert will be equipped with a screen to collect debris.

Anticipated Recipient	:	MIDDLETOWN TOWNSHIP		
Project No.	:	340097-01	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	371		
County	:	MONMOUTH	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06633
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.06633

Project Name, Number

MIDDLETOWN TOWNSHIP
340097-01
SHADOW LAKE RESTORATION

Priority List Rank

371

County

MONMOUTH

Existing Population

66,327

Service Area

Middletown Township

Need for Project

Shadow Lake is a significant natural and recreational resource and is designated for trout production and maintenance. Middletown Township is dredging Shadow Lake to improve water quality, reopen areas to light watercraft, remove excessive aquatic plant growth, and reestablish fish populations. Since Shadow Lake discharges into the upper reaches of the Navesink River, dredging the lake will inherently improve water quality in the Navesink River. Dredging will also reduce or eliminate the need to use chemical herbicides to curb excessive aquatic plant growth.

Project Description

The proposed project includes the dredging to remove approximately 300,000 cubic yards of sediment from the upper portion of Shadow Lake. This will restore the lake to its original depth, eliminate the swamp like conditions, and lower the phosphorous concentration.

Anticipated Recipient	: GLOUCESTER TOWNSHIP MUA			
Project No.	: 340364-05	Eligible Project Cost:	$	1,328,511
FY08 Rank	: 372			
County	: CAMDEN	Total State Amount :	$	1,328,511

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06435
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.06435

Project Name, Number

GLOUCESTER TOWNSHIP MUA
340364-05
COMPOSTING REHABILITATION

Priority List Rank

372

County

CAMDEN

Existing Population

64,350

Service Area

Gloucester Township

Need for Project

The GTMUA operates a regional grass and leaf composting facility that accepts waste from all of Gloucester Township and over 15 other municipalities. The composting facility pile turning and screening equipment are old and are failing. The equipment being replaced is critical to successful and compliant operation of the composting facility.

Project Description

The proposed project includes replacement of equipment at GTMUA’s composting facility.

Anticipated Recipient	: BERKELEY TOWNSHIP		
Project No.	: 340969-06	Eligible Project Cost:	$ 10,723,443
FY08 Rank	: 373		
County	: OCEAN	Total State Amount :	$ 10,723,443

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03999
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.03999

Project Name, Number

BERKELEY TOWNSHIP
340969-06
STORMWATER MANAGEMENT

Priority List Rank

373

County

OCEAN

Existing Population

39,991

Service Area

Berkeley Township

Need for Project

Stormwater runoff is the most common way that nonpoint source pollution reaches local rivers, creeks and lakes. Rainwater carries chemicals, nutrients, sediments and other forms of nonpoint source pollution into local streams if the water is not absorbed by soil and vegetation. The Township’s goal with its stormwater management plan is to increase absorption of rainwater by soil and vegetation using mechanisms that reduce the velocity of flow and retain the water in natural areas. This will reduce the amount of pollutants being carried off to nearby watercourses and reduce flooding.

Project Description

The proposed project includes replacement of existing compacted gravel roads that currently have no stormwater management controls with pavement and specific stormwater controls, both structural and nonstructural , to properly control stormwater runoff and reduce nonpoint source pollution. Nonstructural management will include practices such as allowing stormwater to runoff roadways into vegetated areas as sheet flow where feasible, directing runoff into vegetated swales where feasible, and allowing stormwater that must be collected to bubble up through outlets and spread out as sheet flow runoff through vegetated filter strips and forested riparian buffers. Where it is not practical to utilize those nonstrucural practices, stormwater will be collected and directed into an underground stormwater recharge system.
Berkeley also intends to purchase two street sweepers to enhance the Township’s stormwater management plan.

Anticipated Recipient	: EWING TOWNSHIP			
Project No.	: 340397-01	Eligible Project Cost:	$	465,419
FY08 Rank	: 374			
County	: MERCER	Total State Amount :	$	465,419

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03419
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.03419

Project Name, Number

EWING TOWNSHIP
340397-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

374

County

MERCER

Existing Population

34,185

Service Area

Township of Ewing

Need for Project

The Township of Ewing is in need of both a street sweeper and a flush truck. The purchase of this equipment will help the Township reduce the amount of debris that accumulates in the sewer system and, in turn, reduce solids/floatables from entering Shabakunk Creek.

Project Description

The proposed project involves the purchase of one street sweeper and one flush truck.

Anticipated Recipient	: EWING TOWNSHIP			
Project No.	: 340397-03	Eligible Project Cost:	$	185,346
FY08 Rank	: 374			
County	: MERCER	Total State Amount :	$	185,346

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03419
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.03419

Project Name, Number

EWING TOWNSHIP
340397-03
STORMWATER MANAGEMENT

Priority List Rank

374

County

MERCER

Existing Population

34,185

Service Area

Ewing Township

Need for Project

The Township needs to reduce flooding and reduce solids transportation. The project would reduce the sediment load to prevent creation of sediment islands and minimize the scour effect on stream banks.

Project Description

The proposed project will address the degradation of the water quality in a tributary to the Gold Run by stabilizing its banks and restoring the bed to its original configuration. The stream has many areas of severe erosion that are causing significant property damage. The stabilization is approximately 1300 feet in length and will restore the conveyance area to reduce erosive velocities.

Anticipated Recipient	: MONROE TOWNSHIP			
Project No.	: 340423-04	Eligible Project Cost:	$	318,067
FY08 Rank	: 376			
County	: MIDDLESEX	Total State Amount :	$	318,067

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02800
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02800

Project Name, Number

MONROE TOWNSHIP
340423-04
STORMWATER/NPS MANAGEMENT

Priority List Rank

376

County

MIDDLESEX

Existing Population

27,999

Service Area

Monroe Township

Need for Project

Monroe Township is in need of a street sweeper and vacuum truck. The purchase of this equipment will help the Township reduce the amount of debris that accumulates in the sewer system and, in turn, reduce solids/floatables from entering the waters of the local watershed.

Project Description

The proposed project involves the purchase of one street sweeper and vacuum truck.

Anticipated Recipient	: MARLBORO TOWNSHIP			
Project No.	: 340268-01	Eligible Project Cost:	$	169,048
FY08 Rank	: 377			
County	: MONMOUTH	Total State Amount :	$	169,048

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02797
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02797

Project Name, Number

MARLBORO TOWNSHIP
340268-01
STORMWATER/NPS MAINTENANCE EQUIPMENT

Priority List Rank

377

County

MONMOUTH

Existing Population

27,974

Service Area

Marlboro Township

Need for Project

The equipment is needed to maintain the stormwater system and detention basins to remove debris.

Project Description

The proposed project includes the purchase of special tractors to cut grass on slopes of detention basins and self-contained vacuum leaf machines.

Anticipated Recipient	:	OCEAN TOWNSHIP		
Project No.	:	340750-04	Eligible Project Cost:	$ 1,198,294
FY08 Rank	:	378		
County	:	MONMOUTH	Total State Amount :	$ 1,198,294

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02506
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02506

Project Name, Number

OCEAN TOWNSHIP
340750-04
STORMWATER MANAGEMENT

Priority List Rank

378

County

MONMOUTH

Existing Population

25,058

Service Area

Township of Ocean

Need for Project

The project is needed to reduce the amount of floatables and other debris from entering the storm sewers and to reduce soil erosion and sedimentation in Harvey Brook which discharges to Deal Lake.

Project Description

The proposed project includes the purchase of a four-wheel street sweeper and streambank stabilization along Harvey Brook.

Anticipated Recipient	:	MAPLEWOOD TOWNSHIP		
Project No.	:	340283-02	Eligible Project Cost:	$ 5,479,091
FY08 Rank	:	379		
County	:	ESSEX	Total State Amount :	$ 5,479,091

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02387
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02387

Project Name, Number

MAPLEWOOD TOWNSHIP
340283-02
STORMWATER MANAGEMENT

Priority List Rank

379

County

ESSEX

Existing Population

23,868

Service Area

Maplewood Township

Need for Project

The Township needs to reduce flooding and reduce solids transportation. The project would reduce the sediment load to prevent creation of sediment islands and minimize the scour effect on stream banks.

Project Description

The proposed project will address the degradation of the water quality in East Branch of the Rahway River by stabilizing its banks and restoring the bed to its original configuration.

Anticipated Recipient	:	GALLOWAY TOWNSHIP		
Project No.	:	340892-03	Eligible Project Cost:	$ 9,008,725
FY08 Rank	:	380		
County	:	ATLANTIC	Total State Amount :	$ 9,008,725

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02333
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02333

Project Name, Number

GALLOWAY TOWNSHIP
340892-03
STORMWATER

Priority List Rank

380

County

ATLANTIC

Existing Population

23,330

Service Area

The Pinehurst section of Galloway

Need for Project

A storm drainage system is necessary to alleviate problems caused by flooding during storm events. A collection system is needed to service existing problem areas.

Project Description

The proposed project includes construction of a storm drainage system consisting of interconnected inlets with perforated pipe discharges into strategically placed detention basins. An 8″ PVC gravity collection system will be constructed to connect to existing lines.

Anticipated Recipient	:	SCOTCH PLAINS TOWNSHIP		
Project No.	:	340113-01	Eligible Project Cost:	$ 1,847,907
FY08 Rank	:	381		
County	:	UNION	Total State Amount :	$ 1,847,907

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02273
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02273

Project Name, Number

SCOTCH PLAINS TOWNSHIP
340113-01
STORMWATER MANAGEMENT

Priority List Rank

381

County

UNION

Existing Population

22,732

Service Area

Scotch Plains Township

Need for Project

The Shackamaxon Lake has not been dredged since 1997. Since the sediment has accumulated in amny areas to the point where it is above the surface elevation of the Lake. The Lake is no longer able to serve the purpose of sedimentation of pollutants prior to flowing downstream. Cleaning the Lake and restoring its storage capacity will increase the quality of the water flowing into the Middlesex Water Company Reservoir that is less than one mile downstream of the dam and will limit rainfall induced floooding downstream. Removing and replacing the inadequately sized bridges with properly engineered bridges will eliminate bank erosion around the bridges and will reduce the amount of silt accumulation in the storage volume from these areas.

Project Description

The proposed project includes dredging accumulated sediment that comes from upstream roads, lawns, and stream banks; stabilization of eroded bank areas; and removal and replacement of inadequately sized RCP pipe vehicand pedestrian bridges.

Anticipated Recipient	:	MEDFORD TOWNSHIP		
Project No.	:	340346-02	Eligible Project Cost:	$ 4,784,482
FY08 Rank	:	382		
County	:	BURLINGTON	Total State Amount :	$ 4,784,482

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.02225
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	225.02225

Project Name, Number

MEDFORD TOWNSHIP
340346-02
STORMWATER MANAGEMENT

Priority List Rank

382

County

BURLINGTON

Existing Population

22,253

Service Area

Medford Township

Need for Project

The Birchwood Lakes and Blue Lake are essential to Medford’s storm drainage system and flood control. Sediment needs to be removed to restore proper storm drainage. The bulkhead reduces the amount of sediment that builds up in the lakes and without it sediment and debris is flowing into the lakes and downstream.

Project Description

The proposed project includes removal of sediment and debris from the lakes and replacement/repair of bulkheads to reduce erosion and control solids/floatables.

Anticipated Recipient	: HAZLET TOWNSHIP			
Project No.	: 340968-02	Eligible Project Cost:	$	416,419
FY08 Rank	: 383			
County	: MONMOUTH	Total State Amount :	$	416,419

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02138
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02138

Project Name, Number

HAZLET TOWNSHIP
340968-02
STORMWATER/NPS MANAGEMENT

Priority List Rank

383

County

MONMOUTH

Existing Population

21,378

Service Area

Hazlet Township

Need for Project

The Township lacks a stormwater drainage system, which results in frequent flooding and other concerns.

Project Description

The proposed project includes the installation and replacement of inlets and storm pipes in problem areas of the Township. Also included is the construction of a salt dome for stormwater/nps management.

Anticipated Recipient	: HAZLET TOWNSHIP			
Project No.	: 340968-03	Eligible Project Cost:	$	140,163
FY08 Rank	: 383			
County	: MONMOUTH	Total State Amount :	$	140,163

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02138
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02138

Project Name, Number

HAZLET TOWNSHIP
340968-03
STORMWATER MANAGEMENT

Priority List Rank

383

County

MONMOUTH

Existing Population

21,378

Service Area

Hazlet Township

Need for Project

The Township needs a jet-vac so that clogged storm sewers can be cleared to prevent standing stormwater that can contribute to non-point source pollution of the Township waterways.

Project Description

The proposed project is for the purchase of a jet-vac for cleaning storm sewers.

Anticipated Recipient	:	MOUNT OLIVE TOWNSHIP		
Project No.	:	340537-05	Eligible Project Cost:	$ 1,266,579
FY08 Rank	:	385		
County	:	MORRIS	Total State Amount :	$ 1,266,579

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02128
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.02128

Project Name, Number

MOUNT OLIVE TOWNSHIP
340537-05
STORMWATER MANAGEMENT

Priority List Rank

385

County

MORRIS

Existing Population

21,282

Service Area

Township of Mount Olive

Need for Project

The stormwater runoff from the Country Club Estates development is conveyed to the floodplain of the South Branch of the Raritan River and Budd Lake via overland flow. No drainage system currently exists.

Project Description

The proposed project involves the construction of a storm drainage system, including storm pipes, inlets and headwalls.

Anticipated Recipient	: HOLMDEL TOWNSHIP			
Project No.	: 340919-03	Eligible Project Cost:	$	316,480
FY08 Rank	: 386			
County	: MONMOUTH	Total State Amount :	$	316,480

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01578
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.01578

Project Name, Number

HOLMDEL TOWNSHIP
340919-03
EQUIPMENT PURCHASE

Priority List Rank

386

County

MONMOUTH

Existing Population

15,781

Service Area

Holmdel Township

Need for Project

Thw Township plans to purchase a sewer Jet Vac to maintain existing sewers.

Project Description

The proposed project includes purchase of a sewer Jet Vac.

Anticipated Recipient	: BERKELEY HEIGHTS TOWNSHIP			
Project No.	: 340385-03	Eligible Project Cost:	$	500,308
FY08 Rank	: 387			
County	: UNION	Total State Amount :	$	500,308

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01341
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.01341

Project Name, Number

BERKELEY HEIGHTS TOWNSHIP
340385-03
STORMWATER MANAGEMENT

Priority List Rank

387

County

UNION

Existing Population

13,407

Service Area

Township of Berkeley Heights

Need for Project

The existing storm sewer system in the Township has deteriorated pipes, inadequately sized pipes, and an inadequate number of catch basins resulting in flooding. Flooding also results in more grease/oil, pesticides, fertilizers, etc. being introduced into the storm system and discharging into local waters.

Project Description

The proposed project includes improvements to existing detention and retention facilities, improvements to existing stormwater drainage piping systems, and construction of new stormwater drainage piping systems.

Anticipated Recipient	: HIGHLAND PARK BOROUGH			
Project No.	: 340938-02	Eligible Project Cost:	$	479,390
FY08 Rank	: 388			
County	: MIDDLESEX	Total State Amount :	$	479,390

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01328
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.01328

Project Name, Number

HIGHLAND PARK BOROUGH
340938-02
STORMWATER MANAGEMENT

Priority List Rank

388

County

MIDDLESEX

Existing Population

13,279

Service Area

Highland Park

Need for Project

The Borough plans to inspect and map the storm sewer system to identify sensitive areas affected by the discharge of storm sewer flows and to locate any existing cross connections. This will enable the Borough to respond better to potential future hazardous material spills. In addition, storm sewer system cleaning and rehabilitation will improve water quality and reduce localized flooding.

Project Description

This project proposes to clean, TV inspect, and map the existing storm sewer system. Deteriorated catch basins and manholes will be rehabilitated, broken pipes replaced or repaired and any cross connections eliminated.

Anticipated Recipient	: HAMMONTON TOWN			
Project No.	: 340927-04	Eligible Project Cost:	$	247,348
FY08 Rank	: 389			
County	: ATLANTIC	Total State Amount :	$	247,348

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01260
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	225.01260

Project Name, Number

HAMMONTON TOWN
340927-04
EQUIPMENT PURCHASE

Priority List Rank

389

County

ATLANTIC

Existing Population

12,604

Service Area

Hammonton Town

Need for Project

In accordance with the NJPDES Municipal Stormwater Regulation Program, Hammonton is implementing a street-sweeping program to reduce solids and floatables from entering the storm sewer system.

Project Description

The proposed project involves the purchase of two street sweepers.

Anticipated Recipient	: NEW PROVIDENCE BOROUGH			
Project No.	: 340474-01	Eligible Project Cost:	$	180,000
FY08 Rank	: 390			
County	: UNION	Total State Amount :	$	180,000

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01191
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.01191

Project Name, Number

NEW PROVIDENCE BOROUGH
340474-01
EQUIPMENT PURCHASE

Priority List Rank

390

County

UNION

Existing Population

11,907

Service Area

Borough of New Providence

Need for Project

The Borough needs a hydraulic storm drain cleaner device so that storm sewer inlets can be cleaned more frequently to help prevent contamination of local waterways.

Project Description

The proposed project is for the purchase of a hydraulic storm drain cleaner device.

Anticipated Recipient	:	HASBROUCK HEIGHTS BOROUGH		
Project No.	:	340329-02	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	391		
County	:	BERGEN	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01166
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.01166

Project Name, Number

HASBROUCK HEIGHTS BOROUGH
340329-02
STORMWATER MANAGEMENT

Priority List Rank

391

County

BERGEN

Existing Population

11,662

Service Area

Borough of Hasbrouck Heights

Need for Project

The storm sewer system in the Borough does not function properly because of problems with the riser ditch resulting in flooding. Flooding also results in more grease/oil, pesticides, fertilizers, etc. being introduced into the storm system and discharging into local waters.

Project Description

The proposed project includes improvements to existing detention and retention facilities, improvements to existing stormwater drainage piping systems, and construction of new stormwater pump station.

Anticipated Recipient	: BRIGANTINE CITY			
Project No.	: 340827-03	Eligible Project Cost:	$	267,182
FY08 Rank	: 392			
County	: ATLANTIC	Total State Amount :	$	267,182

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01135
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.01135

Project Name, Number

BRIGANTINE CITY
340827-03
EQUIPMENT PURCHASE

Priority List Rank

392

County

ATLANTIC

Existing Population

11,354

Service Area

City of Brigantine

Need for Project

The City of Brigantine is in need of a street sweeper. The purchase of this equipment will help the City reduce the amount of debris that accumulates in the sewer and stormwater systems and, in turn, reduce solids/floatables from entering the waters of bay and ocean.

Project Description

The proposed project involves the purchase of a street sweeper.

Anticipated Recipient	: MILLSTONE TOWNSHIP			
Project No.	: 340126-01	Eligible Project Cost:	$	360,245
FY08 Rank	: 393			
County	: MONMOUTH	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00897
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00897

Project Name, Number

MILLSTONE TOWNSHIP
340126-01
TRUCK WASHING FACILITY

Priority List Rank

393

County

MONMOUTH

Existing Population

8,970

Service Area

Millstone Township

Need for Project

To comply with the good housekeeping section of the Millstone Township Stormwater Pollution Prevention Plan and to eliminate nonpoint source pollution Millstone proposes to build a truck washing facility designed to allow 100% recycling of water runoff. This process will eliminate truck detergents that conain phosphates from discharging into the local watershed.

Project Description

The proposed project includes construction of a truck washing facility for the Department of Public Works.

Anticipated Recipient	: LEONIA BOROUGH			
Project No.	: 340073-02	Eligible Project Cost:	$	451,426
FY08 Rank	: 394			
County	: BERGEN	Total State Amount :	$	451,426

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00891
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00891

Project Name, Number

LEONIA BOROUGH
340073-02
SALT DOME

Priority List Rank

394

County

BERGEN

Existing Population

8,914

Service Area

Borough of Leonia

Need for Project

The existing salt storage has created problems due to runoff discharges to local waterways. The Borough is currently under orders to eliminate such runoff.

Project Description

The proposed project includes construction of a 50-foot diameter, dome shaped, salt storage shed with a 6-foot high concrete perimeter walls.

Anticipated Recipient	:	RUNNEMEDE BOROUGH		
Project No.	:	340363-05	Eligible Project Cost:	$ 1,460,102
FY08 Rank	:	395		
County	:	CAMDEN	Total State Amount :	$ 1,460,102

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00853
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	225.00853

Project Name, Number

RUNNEMEDE BOROUGH
340363-05
STORMWATER MANAGEMENT & EQUIPMENT PURCHASE

Priority List Rank

395

County

CAMDEN

Existing Population

8,533

Service Area

Borough of Runnemede

Need for Project

The existing stormwater system is inadequate the Borough wants to improve the system to meet new regulations. The Borough will update the system with new environmentally friendly drainage inlets to remove solids, install erosion controls, and add new piping to eliminate ponding.

Project Description

The proposed project includes installation of stormwater drainage improvements including new inlets, piping, concrete curbs and gutters.

Anticipated Recipient	:	EDGEWATER PARK TOWNSHIP		
Project No.	:	340166-01	Eligible Project Cost:	$ 2,049,114
FY08 Rank	:	396		
County	:	BURLINGTON	Total State Amount :	$ 2,049,114

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00839
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00839

Project Name, Number

EDGEWATER PARK TOWNSHIP
340166-01
STORMWATER MANAGEMENT

Priority List Rank

396

County

BURLINGTON

Existing Population

8,388

Service Area

Edgewater Park Township

Need for Project

The existing storm sewer system in the Township has deteriorated pipes, inadequately sized pipes, and an inadequate number of catch basins resulting in flooding. Flooding also results in more grease/oil, pesticides, fertilizers, etc. being introduced into the storm system and discharging into local waters.

Project Description

The proposed project includes improvements to existing detention and retention facilities, improvements to existing stormwater drainage piping systems, and construction of new stormwater drainage piping systems.

Anticipated Recipient	: BOONTON TOWN			
Project No.	: 340265-01	Eligible Project Cost:	$	360,245
FY08 Rank	: 397			
County	: MORRIS	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00835
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00835

Project Name, Number

BOONTON TOWN
340265-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

397

County

MORRIS

Existing Population

8,347

Service Area

Town of Boonton

Need for Project

The Town’s existing storm sewer system is undersized resulting in flooding and the discharge of debris to the Rockaway River.

Project Description

The proposed project is to improve stormwater collection on Wotton, Oak, and Hillside streets. Stormwater from these areas would then be piped to the existing system on Hillside. Improvements would include inlets, subdrains, stormwater piping, curbing, and roadway reconstruction.

Anticipated Recipient	: EDGEWATER MUA			
Project No.	: 340446-10	Eligible Project Cost:	$	2,639,511
FY08 Rank	: 398			
County	: BERGEN	Total State Amount :	$	2,639,511

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00768
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00768

Project Name, Number

EDGEWATER MUA
340446-10
STORMWATER MANAGEMENT

Priority List Rank

398

County

BERGEN

Existing Population

7,677

Service Area

Edgewater Borough

Need for Project

The proposed project will provide filtration to stormwater to remove suspended solids and debris; the project will add a series of level spreaders to dissipate the stormwater discharge to minimize soil erosion in the Hudson River.

Project Description

The proposed project includes installation of a filtration system for stormwater and installation of a series of level spreaders to dissipate the discharge over a wide area.

Anticipated Recipient	: KEYPORT BOROUGH			
Project No.	: 340267-01	Eligible Project Cost:	$	360,245
FY08 Rank	: 399			
County	: MONMOUTH	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00759
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00759

Project Name, Number

KEYPORT BOROUGH
340267-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

399

County

MONMOUTH

Existing Population

7,586

Service Area

Borough of Keyport

Need for Project

The Borough needs to remediate certain areas which experience flooding and properly maintain its stormwater sewers. The existing facilities adversely impact water quality in the Raritan Bay.

Project Description

The proposed project involves the construction of approximately 200 feet of reinforced concrete pipe (RCP) and two doghouse drainage structures to create a bypass system to divert stormwater runoff to a separate outfall on Broad Street. Also included in the project is the construction of approximately 800 feet of RCP to replace an existing storm system on Second Street, Waverly Street and Third Street and the purchase of a “Scavenge-Vac” to properly maintain the system.

Anticipated Recipient	: CRESSKILL BOROUGH			
Project No.	: 340374-01	Eligible Project Cost:	$	444,422
FY08 Rank	: 400			
County	: BERGEN	Total State Amount :	$	444,422

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00756
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00756

Project Name, Number

CRESSKILL BOROUGH
340374-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

400

County

BERGEN

Existing Population

7,560

Service Area

Borough of Cresskill (Magnolia Avenue Area)

Need for Project

The Magnolia Avenue area does not drain properly during wet weather events.

Project Description

The proposed project includes the installation of a new drainage system, including the removal and replacement of existing pavement, curbs and other amenities.

Anticipated Recipient	: WESTAMPTON TOWNSHIP			
Project No.	: 340105-01	Eligible Project Cost:	$	289,789
FY08 Rank	: 401			
County	: BURLINGTON	Total State Amount :	$	289,789

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00722
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00722

Project Name, Number

WESTAMPTON TOWNSHIP
340105-01
EQUIPMENT PURCHASE

Priority List Rank

401

County

BURLINGTON

Existing Population

7,217

Service Area

Township of Westampton

Need for Project

Runoff from streets carries debris and contaminants which eventually pass through the storm sewer system and into the surrounding waterways. The Township is concerned with the non-point source pollution problem and believes this problem can be reduced through increased streetsweeping.

Project Description

The proposed project involves the purchase of a street sweeper to clean debris and contaminates from roadways to minimze adverse impacts on local waterways.

Anticipated Recipient	: PAULSBORO BOROUGH			
Project No.	: 340164-01	Eligible Project Cost:	$	967,451
FY08 Rank	: 402			
County	: GLOUCESTER	Total State Amount :	$	967,451

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00658
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00658

Project Name, Number

PAULSBORO BOROUGH
340164-01
STORMWATER MANAGEMENT

Priority List Rank

402

County

GLOUCESTER

Existing Population

6,577

Service Area

Paulsboro Borough

Need for Project

The existing substandard stormwater systems are subject to failure during storm events causing flooding. The stormwater and sanitary flows co-mingle during flooding and are discharged to Mantua Creek.

Project Description

The proposed project includes construction of a new storm sewer system with uniform slopes between manholes and inlets to maintain an unobstructed flow, mininmize trapping of debris, eliminate flooding, and improve water quality. This will include construction of new inlets to replace existing undersized inlets for more efficient flow and improved ease of maintence.

Anticipated Recipient	: OCEAN TOWNSHIP			
Project No.	: 340112-01	Eligible Project Cost:	$	708,917
FY08 Rank	: 403			
County	: OCEAN	Total State Amount :	$	708,917

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00645
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00645

Project Name, Number

OCEAN TOWNSHIP
340112-01
EQUIPMENT PURCHASE

Priority List Rank

403

County

OCEAN

Existing Population

6,450

Service Area

Ocean Township

Need for Project

Ocean Township plans to purchase a jet vactor truck and two dump trucks for to support municipal stormwater maintenance. The Township will reduce the amount of debris that accumulates in the sewer system and, in turn, reduce solids/floatables from entering local waters.

Project Description

The proposed project involves the purchase of jet vactor truck and two dump trucks.

Anticipated Recipient	: BERLIN BOROUGH			
Project No.	: 340308-01	Eligible Project Cost:	$	708,917
FY08 Rank	: 404			
County	: CAMDEN	Total State Amount :	$	708,917

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00567
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00567

Project Name, Number

BERLIN BOROUGH
340308-01
STORMWATER MANAGEMENT

Priority List Rank

404

County

CAMDEN

Existing Population

5,672

Service Area

Borough of Berlin

Need for Project

The Borough needs equipment to reduce the amount of debris entering its stormwater management system. The Borough also hopes to reduce non-point source pollution from run off from salt facilities and a deteriorated stream bank.

Project Description

The proposed project includes the purchase of a street sweeper and construction of a salt storage bin. The project also includes construction of a water quality basin, installation of a stormwater pipe and restoration of a stream bank.

Anticipated Recipient	: BERLIN TOWNSHIP			
Project No.	: 340790-03	Eligible Project Cost:	$	1,317,721
FY08 Rank	: 405			
County	: CAMDEN	Total State Amount :	$	1,317,721

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00547
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00547

Project Name, Number

BERLIN TOWNSHIP
340790-03
STORMWATER MANAGEMENT

Priority List Rank

405

County

CAMDEN

Existing Population

5,466

Service Area

Township of Berlin

Need for Project

Inadequate facilities to convey and manage stormwater have caused problems such as ponding in certain areas of the Township during storm events. The Township also stores its road maintenance salt and sand in an open uncovered area with the potential for runoff to convey salt and sand to the nearby wetland.

Project Description

The proposed project involves construction of storm drainage systems including storm pipes inlets and basins to address the areas impacted adversely by stormwater build up. The proposed project also includes construction of a salt dome.

Anticipated Recipient	: SOMERDALE BOROUGH			
Project No.	: 340338-03	Eligible Project Cost:	$	1,331,729
FY08 Rank	: 406			
County	: CAMDEN	Total State Amount :	$	1,331,729

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00544
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00544

Project Name, Number

SOMERDALE BOROUGH
340338-03
STORMWATER/NPS MANAGEMENT

Priority List Rank

406

County

CAMDEN

Existing Population

5,440

Service Area

Borough of Somerdale

Need for Project

Extreme stormwater runoff in the Borough cannot be handled by existing ditches resulting in soil erosion and loss of trees. Soil erosion contributes to silt deposits in Otter Brook and degrades local wetlands and streams.

Project Description

The proposed project involves creating a stormwater detention basin by modifying an existing culvert to restrict flow. Improvements to existing ditches will also be made.

Anticipated Recipient	: EDGEWATER BOROUGH			
Project No.	: 340446-07	Eligible Project Cost:	$	2,718,518
FY08 Rank	: 407			
County	: BERGEN	Total State Amount :	$	2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00500
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00500

Project Name, Number

EDGEWATER BOROUGH
340446-07
STORMWATER MANAGEMENT

Priority List Rank

407

County

BERGEN

Existing Population

5,001

Service Area

Edgewater Borough

Need for Project

The Borough needs to reduce flooding and reduce solids transportation. The project would reduce the sediment load to prevent creation of sediment islands and minimize the scour effect on stream banks.

Project Description

The proposed project includes bank stabilization and water quality improvements. The project consists of deepening the stream and stabilizing sections of the stream bank to prevent further soil erosion.

Anticipated Recipient	: HIGHLANDS BOROUGH			
Project No.	: 340901-04	Eligible Project Cost:	$	781,697
FY08 Rank	: 408			
County	: MONMOUTH	Total State Amount :	$	781,697

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00486
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00486

Project Name, Number

HIGHLANDS BOROUGH
340901-04
STORMWATER MANAGEMENT

Priority List Rank

408

County

MONMOUTH

Existing Population

4,855

Service Area

Highlands Borough

Need for Project

The Borough has a known nonpoint source pollution problem which needs to be corrected. The downtown area of the Borough frequently floods during periods of rain or high tides and Jones Creek cuts through the middle of this area. The floods damage property and collect debris and contaminants which are passed through the system to Raritan Bay.

Project Description

The proposed project involves the installation of a stormwater pump station.

Anticipated Recipient	: ROSELAND BOROUGH			
Project No.	: 340361-02	Eligible Project Cost:	$	1,396,910
FY08 Rank	: 409			
County	: ESSEX	Total State Amount :	$	1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00485
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00485

Project Name, Number

ROSELAND BOROUGH
340361-02
STORMWATER MANAGEMENT

Priority List Rank

409

County

ESSEX

Existing Population

4,850

Service Area

Borough of Roseland

Need for Project

The Borough has determined that stormwater management improvements are necessary to correct drainage problems in the area of Birch Drive and Martha Drive.

Project Description

The Borough is currently studying options to correct the stormwater management concerns in the Birch Drive and Martha Drive areas of the municipality. The proposed project would involve the implementation of the measures needed to correct the drainage and runoff problems.

Anticipated Recipient	:	HIGHLANDS BOROUGH		
Project No.	:	340901-03	Eligible Project Cost:	$ 1,205,942
FY08 Rank	:	409		
County	:	MONMOUTH	Total State Amount :	$ 1,205,942

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00485
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00485

Project Name, Number

HIGHLANDS BOROUGH
340901-03
STORMWATER/NPS MANAGEMENT

Priority List Rank

409

County

MONMOUTH

Existing Population

4,849

Service Area

Highlands Borough

Need for Project

The Borough has a known nonpoint source pollution problem which needs to be corrected. Several times a year beach closures occur which are primarily due to the debris and contaminants which collect in the storm sewer system. In addition, the North Street sanitary and storm sewer system contributes high levels of fecal coliform to Sandy Hook Bay.

Project Description

The proposed project involves (1) the rehabilitation of the North Street storm sewer and replacement of the old sanitary sewer system, as well as roadway repair, (2) the elimination of flooding in problem areas 3, 4, and 16 by installing properly sized storm sewers and check valves at the outfalls and (3) the purchase of a vacuum sweeper, leaf collector and Jet-Vac.

Anticipated Recipient	: MOUNT ARLINGTON BOROUGH			
Project No.	: 340541-04	Eligible Project Cost:	$	134,261
FY08 Rank	: 411			
County	: MORRIS	Total State Amount :	$	134,261

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00466
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00466

Project Name, Number

MOUNT ARLINGTON BOROUGH
340541-04
STORMWATER MANAGEMENT

Priority List Rank

411

County

MORRIS

Existing Population

4,663

Service Area

Borough of Mount Arlington

Need for Project

The Borough needs to collect and pre-treat nonpoint source pollution from road runoff that drains into Lake Hopatcong.

Project Description

The proposed project involves the construction of a storm drainage system, including storm pipes, inlets and headwalls.

Anticipated Recipient	:	EGG HARBOR TOWNSHIP		
Project No.	:	340856-01	Eligible Project Cost:	$ 2,643,901
FY08 Rank	:	412		
County	:	ATLANTIC	Total State Amount :	$ 2,643,901

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00455
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	225.00455

Project Name, Number

EGG HARBOR TOWNSHIP
340856-01
STORMWATER MANAGEMENT

Priority List Rank

412

County

ATLANTIC

Existing Population

4,545

Service Area

West Atlantic City section of Egg Harbor Township

Need for Project

The existing stormwater collection system in West Atlantic City is physically deteriorating and is inadequate to collect and discharge runoff to Lakes Bay. Under normal conditions, tidal flooding often surcharges the system and discharges tidal water back through stormwater inlets due to a lack of back flow prevention devices. This increased flooding increases the amount of sediment and other pollutants that enter the collection system and are discharged to Lakes Bay. A new stormwater system will reduce the amount and frequency of flooding, which will decrease the concentration of solids, nutrients, and fecal coliform in the Bay.

Project Description

The proposed project includes construction of a stormwater management system that will handle runoff from a 100-year storm event. This will include replacing all existing inlets and piping, eliminating numerous bay discharge points, and installing new outfalls.

Anticipated Recipient	: MAGNOLIA BOROUGH			
Project No.	: 340285-03	Eligible Project Cost:	$	455,626
FY08 Rank	: 413			
County	: CAMDEN	Total State Amount :	$	455,626

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00440
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00440

Project Name, Number

MAGNOLIA BOROUGH
340285-03
EQUIPMENT PURCHASE

Priority List Rank

413

County

CAMDEN

Existing Population

4,404

Service Area

Borough of Magnolia

Need for Project

The Borough of Magnolia plans to purchase a combination jetter/cleaner to help meet stormwater rules requiring yearly cleaning of stormwater inlets. The Borough also plans to purchase a Muffin Monster grinder pump to prevent overflows at the Evesham Avenue pump station caused by clogs.

Project Description

The proposed project includes purchase of a combination jetter/cleaner and a Muffin Monster grinder pump.

Anticipated Recipient	: MAGNOLIA BOROUGH			
Project No.	: 340285-04	Eligible Project Cost:	$	159,031
FY08 Rank	: 414			
County	: CAMDEN	Total State Amount :	$	159,031

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00439
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	225.00439

Project Name, Number

MAGNOLIA BOROUGH
340285-04
SALT DOME

Priority List Rank

414

County

CAMDEN

Existing Population

4,394

Service Area

Borough of Magnolia

Need for Project

The existing salt storage has created problems due to runoff discharges to local waterways. The Borough is currently under orders to eliminate such runoff.

Project Description

The proposed project includes construction of a salt storage facility.

Anticipated Recipient	: MEDFORD LAKES BOROUGH			
Project No.	: 340319-02	Eligible Project Cost:	$	360,245
FY08 Rank	: 415			
County	: BURLINGTON	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00417
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00417

Project Name, Number

MEDFORD LAKES BOROUGH
340319-02
STORMWATER MANAGEMENT

Priority List Rank

415

County

BURLINGTON

Existing Population

4,173

Service Area

Borough of Medford Lakes

Need for Project

The Medford Lake are essential to the Borough’s storm drainage system and flood control. The bulkhead reduces the amount of sediment that builds up in the lake and without it sediment and debris is flowing into the lake and downstream.

Project Description

The proposed project includes replacement/repair of the bulkhead to reduce erosion and control solids/floatables.

Anticipated Recipient	: HIGH BRIDGE BOROUGH			
Project No.	: 340842-02	Eligible Project Cost:	$	162,326
FY08 Rank	: 416			
County	: HUNTERDON	Total State Amount :	$	162,326

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00378
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00378

Project Name, Number

HIGH BRIDGE BOROUGH
340842-02
STORMWATER/NPS MANAGEMENT

Priority List Rank

416

County

HUNTERDON

Existing Population

3,776

Service Area

Borough of High Bridge

Need for Project

The Borough of High Bridge proposes to build a salt barn to replace two deteriorated buildings where runoff threatens a tributary of the South Branch of the Raritan River. Covered-inside storage will elimnate the possibility of contaminating the stream, wells, and ground water with salt run-off.

Project Description

The proposed project includes construction of a salt barn with 631 tons capacity.

Anticipated Recipient	:	HIGH BRIDGE BOROUGH		
Project No.	:	340842-03	Eligible Project Cost:	$ 6,863,603
FY08 Rank	:	416		
County	:	HUNTERDON	Total State Amount :	$ 6,863,603

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00378
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00378

Project Name, Number

HIGH BRIDGE BOROUGH
340842-03
DAM REMOVAL

Priority List Rank

416

County

HUNTERDON

Existing Population

3,776

Service Area

Borough of High Bridge

Need for Project

The Borough of High Bridge proposes to drain Lake Solitude and remove a high hazard. Removal of the dam will reduce the risk to the Borough and downstream communities and allow for improvements to the spillway.

Project Description

The proposed project includes removal of a high hazard dam and reconfiguration of the spillway. The project will also include breaching, lakebed/stream stabilization and silt removal.

Anticipated Recipient	: LAWNSIDE BOROUGH			
Project No.	: 340263-01	Eligible Project Cost:	$	193,346
FY08 Rank	: 418			
County	: CAMDEN	Total State Amount :	$	193,346

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00284
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00284

Project Name, Number

LAWNSIDE BOROUGH
340263-01
STORMWATER MANAGEMENT

Priority List Rank

418

County

CAMDEN

Existing Population

2,841

Service Area

Borough of Lawnside

Need for Project

The project is needed to rehabilitate an existing stormwater channel southeast of JFK Boulevard.

Project Description

The proposed project involves the rehabilitation of the stormwater channel to minimize erosion.

Anticipated Recipient	: LAVALETTE BOROUGH			
Project No.	: 340966-04	Eligible Project Cost:	$	405,216
FY08 Rank	: 419			
County	: OCEAN	Total State Amount :	$	405,216

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00267
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00267

Project Name, Number

LAVALETTE BOROUGH
340966-04
STORMWATER MANAGEMENT

Priority List Rank

419

County

OCEAN

Existing Population

2,665

Service Area

Borough of Lavalette

Need for Project

The existing storm sewer system is undersized in areas of the Borough resulting in localized street flooding and the discharge of debris and sediment into local waters. Other sections of the stormwater system have leaking joints and other problems and need to be repaired.

Project Description

The proposed project includes cleaning, TV inspection and grouting of stormpipe connections and installation of a new stormwater drainage pipe

Anticipated Recipient	: RIVERDALE BOROUGH			
Project No.	: 340729-02	Eligible Project Cost:	$	289,789
FY08 Rank	: 420			
County	: MORRIS	Total State Amount :	$	289,789

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00250
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00250

Project Name, Number

RIVERDALE BOROUGH
340729-02
EQUIPMENT PURCHASE

Priority List Rank

420

County

MORRIS

Existing Population

2,498

Service Area

Borough of Riverdale

Need for Project

Periodically, the Borough’s storm sewers collect debris and contaminants which eventually pass through the storm sewer system and into the lakes and surrounding waterways. The Borough is concerned with the non-point source pollution problem and believes this problem can be reduced through better maitenance which will be enhanced by the use of “Jet Vac” equipment and certain specific improvements to the existing stormwater facilities.

Project Description

The proposed project involves the purchase of a Jet-Vac Truck to clean debris from the storm sewers and minimze adverse impacts on local waterways.

Anticipated Recipient	: LIBERTY TOWNSHIP			
Project No.	: 340165-01	Eligible Project Cost:	$	148,979
FY08 Rank	: 421			
County	: WARREN	Total State Amount :	$	148,979

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00249
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00249

Project Name, Number

LIBERTY TOWNSHIP
340165-01
STORMWATER/NPS MANAGEMENT

Priority List Rank

421

County

WARREN

Existing Population

2,493

Service Area

Liberty Township

Need for Project

Liberty Township is in need of a street sweeper. The purchase of this equipment will help the Township reduce the amount of debris that accumulates in the sewer system and, in turn, reduce solids/floatables from entering the waters of the Pequest Watershed.

Project Description

The proposed project involves the purchase of one street sweeper.

Anticipated Recipient	: AVON BY THE SEA BOROUGH			
Project No.	: 340335-02	Eligible Project Cost:	$	360,245
FY08 Rank	: 422			
County	: MONMOUTH	Total State Amount :	$	360,245

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00235
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00235

Project Name, Number

AVON BY THE SEA BOROUGH
340335-02
STORMWATER MANAGEMENT

Priority List Rank

422

County

MONMOUTH

Existing Population

2,350

Service Area

Avon-By-The-Sea

Need for Project

The purpose of the project is eliminate pollutants from entering tidal waters and Sylvan Lake through the stormwater system.

Project Description

The proposed project includes the construction of a catch basin system to reduce the pollutant load into the surface waters·

Anticipated Recipient	:	SEA BRIGHT BOROUGH		
Project No.	:	340077-01	Eligible Project Cost:	$ 3,419,139
FY08 Rank	:	423		
County	:	MONMOUTH	Total State Amount :	$ 3,419,139

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00182
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00182

Project Name, Number

SEA BRIGHT BOROUGH
340077-01
STORMWATER PUMP STATION

Priority List Rank

423

County

MONMOUTH

Existing Population

1,818

Service Area

Borough of Sea Bright

Need for Project

The Borough has a known nonpoint source pollution problem which needs to be corrected. The downtown area of the Borough frequently floods during periods of rain or high tides. The floods damage property and collect debris and contaminants which are passed through the system to Raritan Bay.

Project Description

The proposed project involves the installation of a stormwater pump station.

Anticipated Recipient	:	TETERBORO BOROUGH		
Project No.	:	340339-01	Eligible Project Cost:	$ 1,219,513
FY08 Rank	:	424		
County	:	BERGEN	Total State Amount :	$ 1,219,513

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	225
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	225

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00002
BDA Points	0
Transit Villages	0
TOTAL POINTS	225.00002

Project Name, Number

TETERBORO BOROUGH
340339-01
STORMWATER MANAGEMENT

Priority List Rank

424

County

BERGEN

Existing Population

18

Service Area

Teterboro Airport and West Riser Ditch Storm Drainage Systems

Need for Project

The existing pump station was built in 1950 to assist two smaller pump houses which date back to 1917. Currently all three pumps are in operation and the system is in need of repair.

Project Description

The proposed project is to extend the two existing 60-inch diameter storm trunk mains to a new pump house constructed with an emergency generator and a variable speed pumping system. Also included is the abandonment and demolition of the two 1917 pump houses and alterations associated with the riser ditch and bulkhead.

Anticipated Recipient	: JERSEY CITY		
Project No.	: 343069-01	Eligible Project Cost:	$ 13,000,360
FY08 Rank	: 425		
County	: HUDSON	Total State Amount :	$ 13,000,360

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.24006
BDA Points	0
Transit Villages	0
TOTAL POINTS	200.24006

Project Name, Number

JERSEY CITY
343069-01
LAND ACQUISITION

Priority List Rank

425

County

HUDSON

Existing Population

240,055

Service Area

Jersey City

Need for Project

The City plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase 6.2 acres along the PRR Harimus Branch Embankment to preserve open space and to protect water quality.

Anticipated Recipient	:	CAMDEN CITY		
Project No.	:	340366-05	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	426		
County	:	CAMDEN	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.07990
BDA Points	0
Transit Villages	0
TOTAL POINTS	200.07990

Project Name, Number

CAMDEN CITY
340366-05
WELL SEALING

Priority List Rank

426

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

The City has identified a need to seal abandoned wells to protect the aquifer by preventing groundwater contamination.

Project Description

The proposed project includes the sealing of approximately 52 improperly abandoned wells in the North Morris Wellfield.

Anticipated Recipient	:	BAYONNE LOCAL REDEVELOPMENT AUTHORITY		
Project No.	:	342009-01	Eligible Project Cost:	$ 3,941,003
FY08 Rank	:	427		
County	:	HUDSON	Total State Amount :	$ 3,941,003

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.06184
BDA Points	0
Transit Villages	0
TOTAL POINTS	200.06184

Project Name, Number

BAYONNE LOCAL REDEVELOPMENT AUTHORITY
342009-01
LANDFILL CLOSURE

Priority List Rank

427

County

HUDSON

Existing Population

61,842

Service Area

City of Bayonne

Need for Project

A 26 acre landfill in Bayonne requires final capping.

Project Description

The project will include the installation of a final cap consisting of 18-inches of fill overlain by a 6-inch topsoil erosion layer along with erosion controls and groundwater monitoring.

Anticipated Recipient	:	PRINCETON TOWNSHIP		
Project No.	:	343008-01	Eligible Project Cost:	$ 4,653,327
FY08 Rank	:	428		
County	:	MERCER	Total State Amount :	$ 4,653,327

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.01320
BDA Points	0
Transit Villages	0
TOTAL POINTS	175.01320

Project Name, Number

PRINCETON TOWNSHIP
343008-01
LAND ACQUISITION

Priority List Rank

428

County

MERCER

Existing Population

13,198

Service Area

Township of Princeton

Need for Project

The Township plans to purchase the R.W. Johnson and Gulick properties for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of the R.W. Johnson and Gulick properties to preserve open space and to protect water quality.

Anticipated Recipient	:	WILDWOOD CREST BOROUGH		
Project No.	:	343041-01	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	429		
County	:	CAPE MAY	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	25.00000
Population	0.00398
BDA Points	0
Transit Villages	0
TOTAL POINTS	175.00398

Project Name, Number

WILDWOOD CREST BOROUGH
343041-01
LAND ACQUISITION

Priority List Rank

429

County

CAPE MAY

Existing Population

3,980

Service Area

Borough of Wildwood Crest

Need for Project

The Borough plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of a 2.5-acre parcel adjacent to the beachfront in the southern portion of the island to prevent ponding of stormwater runoff and to maintain or improve existing drainage patterns.

Anticipated Recipient	:	CAPE MAY CITY		
Project No.	:	343045-01	Eligible Project Cost:	$ 5,308,104
FY08 Rank	:	430		
County	:	CAPE MAY	Total State Amount :	$ 5,308,104

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	15.00000
Population	0.00403
BDA Points	0
Transit Villages	0
TOTAL POINTS	165.00403

Project Name, Number

CAPE MAY CITY
343045-01
LAND ACQUISITION

Priority List Rank

430

County

CAPE MAY

Existing Population

4,034

Service Area

City of Cape May

Need for Project

The City plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. This project is less than 2000 feet from the Atlantic Ocean and 1000 feet from a Green Acres conservation area, which protects the southern shoreline of Cape May Harbor. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of Sewell Point Tract, which consists of approximately 90% palustrine wetlands that are stated to be of “exceptional resource value”. The parcel currently exists as a wildlife sanctuary with the threat of residential development on 10% of the parcel. The proposed project will not only preserve open space and protect water quality, but will also protect several species of threatened and endangered birds that have been identified on the parcel.

Anticipated Recipient	:	MENDHAM TOWNSHIP		
Project No.	:	343031-01	Eligible Project Cost:	$ 5,308,104
FY08 Rank	:	431		
County	:	MORRIS	Total State Amount :	$ 5,308,104

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	10.00000
			Population	0.00454
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	160.00454

Project Name, Number

MENDHAM TOWNSHIP
343031-01
LAND ACQUISITION

Priority List Rank

431

County

MORRIS

Existing Population

4,537

Service Area

Township of Mendham

Need for Project

The Township plans to purchase the Clyde Potts Reservoir and the surrounding drainage basin. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of the Clyde Potts Reservoir and the surrounding drainage basin to preserve open space and to protect water quality.

Anticipated Recipient	:	MERCER COUNTY		
Project No.	:	343004-03	Eligible Project Cost:	$ 1,122,734
FY08 Rank	:	432		
County	:	MERCER	Total State Amount :	$ 1,122,734

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.35076
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.35076

Project Name, Number

MERCER COUNTY
343004-03
LAND ACQUISITION

Priority List Rank

432

County

MERCER

Existing Population

350,761

Service Area

County of Mercer

Need for Project

The County plans to purchase land for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land adjacent to the Delaware and Raritan Canal, within one mile of both Baldpate Mountain preserve and Mercer County Howell Living History Farm, to preserve open space and to protect water quality.

Anticipated Recipient	:	SUSSEX COUNTY MUA		
Project No.	:	342008-01	Eligible Project Cost:	$ 2,451,173
FY08 Rank	:	433		
County	:	SUSSEX	Total State Amount :	$ 2,451,173

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.13094
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.13094

Project Name, Number

SUSSEX COUNTY MUA
342008-01
LANDFILL CLOSURE

Priority List Rank

433

County

SUSSEX

Existing Population

130,943

Service Area

Sussex County

Need for Project

Sussex County needs to cap the remaining uncapped 8.5 acres of the County’s landfill in order to control and manage leachate generation, gas production, and stormwater runoff.

Project Description

The project will include the installation of a final cap consisting of the final grading of the solid waste, a 12 inch sand layer (for methane gas venting), an impermeable membrane, a 12 inch sand drainage layer, a 12 inch final cover, a stormwater diversion and drainage system, and a landfill gas extraction system.

Anticipated Recipient	:	WARREN COUNTY		
Project No.	:	343035-01	Eligible Project Cost:	$ 3,185,630
FY08 Rank	:	434		
County	:	WARREN	Total State Amount :	$ 3,185,630

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.10244
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.10244

Project Name, Number

WARREN COUNTY
343035-01
LAND ACQUISITION

Priority List Rank

434

County

WARREN

Existing Population

102,437

Service Area

Warren County

Need for Project

The County plans to purchase land throughout the county for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land throughout Warren County to preserve open space and to protect water quality.

Anticipated Recipient	: EDISON TOWNSHIP		
Project No.	: 343027-02	Eligible Project Cost:	$ 55,475,227
FY08 Rank	: 435		
County	: MIDDLESEX	Total State Amount :	$ 55,475,227

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.09769
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.09769

Project Name, Number

EDISON TOWNSHIP
343027-02
LAND ACQUISITION

Priority List Rank

435

County

MIDDLESEX

Existing Population

97,687

Service Area

Township of Edison

Need for Project

The Township plans to purchase parcels of land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land including the Raritan River Ravine, Silver Lake, Glendale Avenue/Martin’s Dock and other lands to preserve open space, to protect water quality and to safeguard wildlife habitats.

Anticipated Recipient	: HAMILTON TOWNSHIP			
Project No.	: 343051-02	Eligible Project Cost:	$	1,709,268
FY08 Rank	: 436			
County	: MERCER	Total State Amount :	$	1,709,268

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.08711
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.08711

Project Name, Number

HAMILTON TOWNSHIP
343051-02
LAND ACQUISITION

Priority List Rank

436

County

MERCER

Existing Population

87,109

Service Area

Township of Hamilton

Need for Project

The Township plans to purchase of property to protect water quality by preserving land that encompasses an unnamed tributary of Pond Run located in the Delaware River Watershed. Since water drains from the parcel into Veteran’s Park, preservation of the parcel also prevents nonpoint source pollution from entering Martin’s Lake. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the acquisition of Klockner Woods property to preserve open space and to protect water quality.

Anticipated Recipient	: BRICK TOWNSHIP			
Project No.	: 343010-02	Eligible Project Cost:	$	4,345,207
FY08 Rank	: 437			
County	: OCEAN	Total State Amount :	$	4,345,207

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06647
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.06647

Project Name, Number

BRICK TOWNSHIP
343010-02
LAND ACQUISITION

Priority List Rank

437

County

OCEAN

Existing Population

66,473

Service Area

Township of Brick

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area including the Kettle Creek drainage area, Beaver Dam watershed, and unnamed tributaries of the Metedecank River. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase eight parcels of land to preserve open space and to protect water quality. The purchase of the parcels will expand the Cedar Bridge Branch Greenway, Midstreams Greenway, and Metedecank Greenway.

Anticipated Recipient	:	MIDDLETOWN TOWNSHIP		
Project No.	:	343021-02	Eligible Project Cost:	$ 3,193,018
FY08 Rank	:	438		
County	:	MONMOUTH	Total State Amount :	$ 3,193,018

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.06633
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.06633

Project Name, Number

MIDDLETOWN TOWNSHIP
343021-02
LAND ACQUISITION

Priority List Rank

438

County

MONMOUTH

Existing Population

66,327

Service Area

Township of Middletown

Need for Project

The Township plans to purchase land along McClees Creek and its tributaries for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of a portion of the Tretter property to preserve open space and to protect water quality.

Anticipated Recipient	: GLOUCESTER TOWNSHIP			
Project No.	: 343014-01	Eligible Project Cost:	$	1,328,374
FY08 Rank	: 439			
County	: CAMDEN	Total State Amount :	$	1,328,374

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.05380
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.05380

Project Name, Number

GLOUCESTER TOWNSHIP
343014-01
LAND ACQUISITION

Priority List Rank

439

County

CAMDEN

Existing Population

53,797

Service Area

Township of Gloucester

Need for Project

The Township plans to purchase the Lake Mathilde and Country Oaks land parcels for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land including 81 acres of the Lake Mathilde parcel and the Country Oaks parcel to preserve open space and to protect water quality.

Anticipated Recipient :	NJ WATER SA (MANASQUAN BASIN)		
Project No. :	343055-01	Eligible Project Cost:	$ 13,000,360
FY08 Rank :	440		
County :	MONMOUTH	Total State Amount :	$ 13,000,360

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04890
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.04890

Project Name, Number

NJ WATER SA (MANASQUAN BASIN)
343055-01
LAND ACQUISITION

Priority List Rank

440

County

MONMOUTH

Existing Population

48,903

Service Area

Township of Howell

Need for Project

The Authority and the Township plan to purchase land surrounding the Manasquan Reservoir for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land around Manasquan Reservoir to preserve open space and to protect water quality.

Anticipated Recipient	:	WASHINGTON TOWNSHIP (GLOUCESTER CO.)		
Project No.	:	343044-01	Eligible Project Cost:	$ 1,019,650
FY08 Rank	:	441		
County	:	GLOUCESTER	Total State Amount :	$ 1,019,650

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.04711
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.04711

Project Name, Number

WASHINGTON TOWNSHIP (GLOUCESTER CO.)
343044-01
LAND ACQUISITION

Priority List Rank

441

County

GLOUCESTER

Existing Population

47,114

Service Area

Township of Washington

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of the land is important to help protect and maintain the natural ability of the wetlands to filter nonpoint source contaminants and absorb stormwater runoff in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of the Rio Grande Tract and the Goodwin Tract to preserve open space and to protect water quality.

Anticipated Recipient :	FRANKLIN TOWNSHIP		
Project No. :	343017-01	Eligible Project Cost:	$ 21,625,688
FY08 Rank :	442		
County :	SOMERSET	Total State Amount :	$ 21,625,688

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04278
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.04278

Project Name, Number

FRANKLIN TOWNSHIP
343017-01
LAND ACQUISITION

Priority List Rank

442

County

SOMERSET

Existing Population

42,780

Service Area

Township of Franklin

Need for Project

The Township plans to purchase 12 parcels of land including the Catalpa and Princeton Highlands tracts for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of 591 acres of land including the Catalpa and Princeton Highlands tracts to preserve open space and to protect water quality.

Anticipated Recipient	: EVESHAM TOWNSHIP			
Project No.	: 343023-02	Eligible Project Cost:	$	616,010
FY08 Rank	: 443			
County	: BURLINGTON	Total State Amount :	$	616,010

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04228
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.04228

Project Name, Number

EVESHAM TOWNSHIP
343023-02
LAND ACQUISITION

Priority List Rank

443

County

BURLINGTON

Existing Population

42,275

Service Area

Township of Evesham

Need for Project

The Township plans to purchase several parcels of land to protect stream corridors, watersheds, and wetlands. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of the Hamiliton-Georgetown tract and other available lands to preserve open space and to protect water quality.

Anticipated Recipient	:	HOWELL TOWNSHIP		
Project No.	:	343011-01	Eligible Project Cost:	$ 2,049,114
FY08 Rank	:	444		
County	:	MONMOUTH	Total State Amount :	$ 2,049,114

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03899
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.03899

Project Name, Number

HOWELL TOWNSHIP
343011-01
LAND ACQUISITION

Priority List Rank

444

County

MONMOUTH

Existing Population

38,987

Service Area

Township of Howell

Need for Project

The Township plans to purchase 203 acres on the Schuch and Hascup farms for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of 203 acres on the Schuch and Hascup farms to preserve open space and to protect water quality.

Anticipated Recipient	: HACKENSACK CITY			
Project No.	: 343024-01	Eligible Project Cost:	$	735,292
FY08 Rank	: 445			
County	: BERGEN	Total State Amount :	$	735,292

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03705
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.03705

Project Name, Number

HACKENSACK CITY
343024-01
LAND ACQUISITION

Priority List Rank

445

County

BERGEN

Existing Population

37,049

Service Area

City of Hackensack

Need for Project

The City plans to purchase land along the Hackensack River Waterfront Corridor for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land along the Hackensack River Waterfront Corridor to preserve open space and to protect water quality.

Anticipated Recipient	: LINDEN CITY			
Project No.	: 342005-02	Eligible Project Cost:	$	971,440
FY08 Rank	: 446			
County	: UNION	Total State Amount :	$	971,440

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03670
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.03670

Project Name, Number

LINDEN CITY
342005-02
LANDFILL VENTING

Priority List Rank

446

County

UNION

Existing Population

36,701

Service Area

City of Linden

Need for Project

The City of Linden Sanitary Landfill is currently operating under an ACO. The City has submitted a revised Closure Plan to the Department in accordance with the Amended ACO requirements, which include final landfill capping, a stormwater management system, and methane gas management system. Proper closure of the Linden Landfill will minimize the amount of leachate generated and will also minimize adverse impacts from uncontrolled runoff.

Project Description

The proposed project includes installation of an active flare/venting gas system as part of the Linden Landfill closure.

Anticipated Recipient	:	MARLBORO TOWNSHIP		
Project No.	:	343059-01	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	447		
County	:	MONMOUTH	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03640
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.03640

Project Name, Number

MARLBORO TOWNSHIP
343059-01
LAND ACQUISITION

Priority List Rank

447

County

MONMOUTH

Existing Population

36,398

Service Area

Township of Marlboro

Need for Project

The Township plans to purchase land for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	:	EVESHAM TOWNSHIP		
Project No.	:	342003-01	Eligible Project Cost:	$ 3,055,927
FY08 Rank	:	448		
County	:	BURLINGTON	Total State Amount :	$ 3,055,927

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.03531
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.03531

Project Name, Number

EVESHAM TOWNSHIP
342003-01
LANDFILL CLOSURE

Priority List Rank

448

County

BURLINGTON

Existing Population

35,309

Service Area

Evesham Township

Need for Project

The Township’s former landfill is generating leachate, which is causing surface and groundwater impacts in an area containing the headwaters of two drainage basins. A capping system is needed to reduce infiltration, which will subsequently minimize further leachate generation and migration.

Project Description

The proposed project will include the construction of a capping system consisting of an impervious clay cap, a sand drainage layer, a vegetative layer, a ground/surface water monitoring system, and drainage improvements. The entire landfill will be re-contoured to remove waste around the perimeter and to establish appropriate cross slope grades.

Anticipated Recipient	:	MANALAPAN TOWNSHIP		
Project No.	:	343039-01	Eligible Project Cost:	$ 3,471,822
FY08 Rank	:	449		
County	:	MONMOUTH	Total State Amount :	$ 3,471,822

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03342
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.03342

Project Name, Number

MANALAPAN TOWNSHIP
343039-01
LAND ACQUISITION

Priority List Rank

449

County

MONMOUTH

Existing Population

33,423

Service Area

Township of Manalapan

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	:	MOUNT LAUREL TOWNSHIP		
Project No.	:	343015-01	Eligible Project Cost:	$ 4,174,867
FY08 Rank	:	450		
County	:	BURLINGTON	Total State Amount :	$ 4,174,867

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.03027
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.03027

Project Name, Number

MOUNT LAUREL TOWNSHIP
343015-01
LAND ACQUISITION

Priority List Rank

450

County

BURLINGTON

Existing Population

30,270

Service Area

Township of Mount Laurel

Need for Project

The Township plans to purchase land including the Palumbo parcel, the Neuber Trust, and the McKay Trust for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land including the Palumbo parcel, the 23 acre Neuber Trust, and the 48 acre McKay Trust to preserve open space and to protect water quality.

Anticipated Recipient	: FREEHOLD TOWNSHIP			
Project No.	: 343018-01	Eligible Project Cost:	$	2,718,518
FY08 Rank	: 451			
County	: MONMOUTH	Total State Amount :	$	2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02471
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.02471

Project Name, Number

FREEHOLD TOWNSHIP
343018-01
LAND ACQUISITION

Priority List Rank

451

County

MONMOUTH

Existing Population

24,710

Service Area

Township of Freehold

Need for Project

The Township plans to purchase land adjacent to the headwaters of the Metedeconk and Manasquan Rivers for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land adjacent to the headwaters of the Metedeconk and Manasquan Rivers to preserve open space and to protect water quality.

Anticipated Recipient	:	WEST WINDSOR TOWNSHIP		
Project No.	:	343005-02	Eligible Project Cost:	$ 8,712,041
FY08 Rank	:	452		
County	:	MERCER	Total State Amount :	$ 8,712,041

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.02191
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.02191

Project Name, Number

WEST WINDSOR TOWNSHIP
343005-02
LAND ACQUISITION

Priority List Rank

452

County

MERCER

Existing Population

21,907

Service Area

Township of West Windsor

Need for Project

The Township plans to purchase land in the Duck Pond Run Basin Area for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land in the Duck Pond Run Basin Area and other areas to preserve open space and to protect water quality. The preservation of the parcels in this area should prevent further degradation of Duck Pond Run, which is listed as being ‘severely impaired’ according to the Department’s Office of Monitoring Management.

Anticipated Recipient	: BURLINGTON TOWNSHIP			
Project No.	: 343060-01	Eligible Project Cost:	$	610,884
FY08 Rank	: 453			
County	: BURLINGTON	Total State Amount :	$	610,884

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.02029
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.02029

Project Name, Number

BURLINGTON TOWNSHIP
343060-01
LAND ACQUISITION

Priority List Rank

453

County

BURLINGTON

Existing Population

20,294

Service Area

Burlington Township

Need for Project

The Township plans to purchase land from the Tillinghast property to preserve the water quality of Riggs Mill Creek. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land on the Tillinghast property to preserve open space and to protect water quality.

Anticipated Recipient :	RANDOLPH TOWNSHIP		
Project No. :	343007-01	Eligible Project Cost:	$ 10,903,537
FY08 Rank :	454		
County :	MORRIS	Total State Amount :	$ 10,903,537

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01997
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01997

Project Name, Number

RANDOLPH TOWNSHIP
343007-01
LAND ACQUISITION

Priority List Rank

454

County

MORRIS

Existing Population

19,974

Service Area

Township of Randolph

Need for Project

The Township plans to purchase the Clyde Potts Reservoir and the surrounding drainage basin for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of the Clyde Potts Reservoir and the surrounding drainage basin to preserve open space and to protect water quality.

Anticipated Recipient	:	MORRIS TOWNSHIP		
Project No.	:	343022-01	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	455		
County	:	MORRIS	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01995
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.01995

Project Name, Number

MORRIS TOWNSHIP
343022-01
LAND ACQUISITION

Priority List Rank

455

County

MORRIS

Existing Population

19,952

Service Area

Township of Morris

Need for Project

The Township plans to purchase land within the Jockey Hollow Top Tract and other lands for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land within the Jockey Hollow Top Tract and other lands to preserve open space and to protect water quality.

Anticipated Recipient	: POINT PLEASANT BOROUGH			
Project No.	: 343025-01	Eligible Project Cost:	$	654,846
FY08 Rank	: 456			
County	: OCEAN	Total State Amount :	$	654,846

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01818
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01818

Project Name, Number

POINT PLEASANT BOROUGH
343025-01
LAND ACQUISITION

Priority List Rank

456

County

OCEAN

Existing Population

18,177

Service Area

Borough of Point Pleasant

Need for Project

The Borough plans to purchase land along the Point Pleasant Canal for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land along the Point Pleasant Canal to preserve open space and to protect water quality.

Anticipated Recipient	:	READINGTON TOWNSHIP		
Project No.	:	343034-04	Eligible Project Cost:	$ 14,000,636
FY08 Rank	:	457		
County	:	HUNTERDON	Total State Amount :	$ 14,000,636

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01580
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01580

Project Name, Number

READINGTON TOWNSHIP
343034-04
LAND ACQUISITION

Priority List Rank

457

County

HUNTERDON

Existing Population

15,803

Service Area

Township of Readington

Need for Project

Open lands still remaining in Readington serve as water quality protection for the headwaters of vital tributaries to the North and South Branches to the Raritan River. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land including parcels in the Raritan Basin Management Area to preserve open space and to protect water quality.

Anticipated Recipient	:	NJ WATER SA		
Project No.	:	343054-05	Eligible Project Cost:	$ 2,869,810
FY08 Rank	:	458		
County	:	HUNTERDON	Total State Amount :	$ 2,869,810

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01421
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.01421

Project Name, Number

NJ WATER SA
343054-05
LAND ACQUISITION

Priority List Rank

458

County

HUNTERDON

Existing Population

14,206

Service Area

Townships of Lebanon, Franklin, Mendham,

Need for Project

The NJWSA operates three facilities within the Raritan Basin: Spruce Run Reservoir, Round Valley Reservoir and the Delaware & Raritan Canal. These facilities are managed for the State, providing untreated bulk water to eleven major purveyors for treatment and distribution, providing an estimated 225-mgd supply of drinking water to central New Jersey residents.

The NJWSA (in some cases in partnership with local, county and state governments, as well as other, non-profit organizations) plans to purchase open space within the Raritan Basin for water quality protection. Preservation of land is important in order to help protect and maintain water quality in the project area. In general, the loss of open space contributes to adverse water quality impacts resulting from increases in impervious cover, loss of recharge areas and buffer zones and undesirable changes to historic stormwater drainage patterns.

Project Description

The proposed project is for the acquisition of land within the Raritan River Basin for the purpose of preserving open space and the protection of water quality.

Anticipated Recipient	: CLINTON TOWNSHIP		
Project No.	: 343012-01	Eligible Project Cost:	$ 12,493,116
FY08 Rank	: 459		
County	: HUNTERDON	Total State Amount :	$ 12,493,116

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01296
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01296

Project Name, Number

CLINTON TOWNSHIP
343012-01
LAND ACQUISITION

Priority List Rank

459

County

HUNTERDON

Existing Population

12,957

Service Area

Township of Clinton

Need for Project

The Township plans to purchase land including Exxon and Mortara tracts for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land including the Exxon and Mortara tracts to preserve open space and to protect water quality.

Anticipated Recipient	: HANOVER TOWNSHIP		
Project No.	: 343003-01	Eligible Project Cost:	$ 11,714,265
FY08 Rank	: 460		
County	: MORRIS	Total State Amount :	$ 11,714,265

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01290
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01290

Project Name, Number

HANOVER TOWNSHIP
343003-01
LAND ACQUISITION

Priority List Rank

460

County

MORRIS

Existing Population

12,898

Service Area

Township of Hanover

Need for Project

The Township plans to purchase a parcel to protect the Stoney Brook tributary of the Whippany River and wetlands. Preservation and conservation of land is important to help protect and maintain water quality in the project area.

Project Description

The proposed project includes the purchase of approximately 66 acres in the Whippany River watershed to preserve open space, promote flood control and protect water quality.

Anticipated Recipient	: BRIGANTINE CITY			
Project No.	: 343042-01	Eligible Project Cost:	$	6,614,815
FY08 Rank	: 461			
County	: ATLANTIC	Total State Amount :	$	6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01259
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01259

Project Name, Number

BRIGANTINE CITY
343042-01
LAND ACQUISITION

Priority List Rank

461

County

ATLANTIC

Existing Population

12,594

Service Area

City of Brigantine

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of open space areas of a golf course located in the City and may include other lands to preserve open space and to protect water quality.

Anticipated Recipient	: OAKLAND BOROUGH		
Project No.	: 343070-01	Eligible Project Cost:	$ 15,516,767
FY08 Rank	: 462		
County	: BERGEN	Total State Amount :	$ 15,516,767

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01247
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01247

Project Name, Number

OAKLAND BOROUGH
343070-01
LAND ACQUISITION

Priority List Rank

462

County

BERGEN

Existing Population

12,466

Service Area

Borough of Oakland

Need for Project

The Borough plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land in the Highlands Protection Area to preserve open space and to protect water quality.

Anticipated Recipient :	SOMERVILLE BOROUGH		
Project No. :	342013-01	Eligible Project Cost:	$ 10,684,529
FY08 Rank :	463		
County :	SOMERSET	Total State Amount :	$ 10,684,529

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01242
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.01242

Project Name, Number

SOMERVILLE BOROUGH
342013-01
LANDFILL CLOSURE

Priority List Rank

463

County

SOMERSET

Existing Population

12,423

Service Area

Borough of Somerville

Need for Project

Landfill leachate contains pollutants that can contaminate water sources and make it unsafe. The Borough intends to remediate contamination and close the landfill. The Borough has also proposed a plan to set aside approximately 41 acres for rehabilitation as passive stormwater mitigation and nonpoint source pollution management.

Project Description

The proposed project includes remediation and closure of a municipal landfill and installation of stormwater management measures.

Anticipated Recipient	:	MARLTON/BURLINGTON COUNTY BCF		
Project No.	:	343068-01	Eligible Project Cost:	$ 76,721
FY08 Rank	:	464		
County	:	BURLINGTON	Total State Amount :	$ 76,721

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01026
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.01026

Project Name, Number

MARLTON/BURLINGTON COUNTY BCF
343068-01
LAND ACQUISITION

Priority List Rank

464

County

BURLINGTON

Existing Population

10,260

Service Area

Township of Marlton

Need for Project

The Township plans to purchase land for water quality protection. The propoerty contains riparian woodlands and wetlands. Conservation of this parcel would also provide additional protection for the stream corridor of the southbranch of the Rancocas Creek that bisects the property. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase 9.925 acres to preserve open space and to protect water quality.

Anticipated Recipient	:	MONTGOMERY TOWNSHIP		
Project No.	:	343029-01	Eligible Project Cost:	$ 4,594,151
FY08 Rank	:	465		
County	:	SOMERSET	Total State Amount :	$ 4,594,151

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00961
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.00961

Project Name, Number

MONTGOMERY TOWNSHIP
343029-01
LAND ACQUISITION

Priority List Rank

465

County

SOMERSET

Existing Population

9,612

Service Area

Township of Montgomery

Need for Project

The Township plans to purchase a parcel that borders the Fox Brook. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land bordering Fox Brook to preserve open space and to protect water quality.

Anticipated Recipient	:	RIVER VALE TOWNSHIP		
Project No.	:	343064-01	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	466		
County	:	BERGEN	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00945
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00945

Project Name, Number

RIVER VALE TOWNSHIP
343064-01
LAND ACQUISITION

Priority List Rank

466

County

BERGEN

Existing Population

9,449

Service Area

Township OF River Vale

Need for Project

The Township plans to purchase land to preserve the water quality. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes purchase of a wooded, leased portion of the Bergen Hills Country Club to preserve open space and to protect water quality.

Anticipated Recipient	:	CHATHAM TOWNSHIP		
Project No.	:	343016-01	Eligible Project Cost:	$ 2,718,518
FY08 Rank	:	467		
County	:	MORRIS	Total State Amount :	$ 2,718,518

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00936
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.00936

Project Name, Number

CHATHAM TOWNSHIP
343016-01
LAND ACQUISITION

Priority List Rank

467

County

MORRIS

Existing Population

9,361

Service Area

Township of Chatham

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	:	FLORHAM PARK BOROUGH		
Project No.	:	343001-01	Eligible Project Cost:	$ 9,782,685
FY08 Rank	:	468		
County	:	MORRIS	Total State Amount :	$ 9,782,685

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00852
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00852

Project Name, Number

FLORHAM PARK BOROUGH
343001-01
LAND ACQUISITION

Priority List Rank

468

County

MORRIS

Existing Population

8,521

Service Area

Borough of Florham Park

Need for Project

The Borough plans to purchase a parcel that lies in the Passaic River Flood Control Basin. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of about 50 acres on the Fish family farm to preserve open space and to protect water quality.

Anticipated Recipient :	BORDENTOWN TOWNSHIP		
Project No. :	343036-01	Eligible Project Cost:	$ 13,550,697
FY08 Rank :	469		
County :	BURLINGTON	Total State Amount :	$ 13,550,697

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00838
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00838

Project Name, Number

BORDENTOWN TOWNSHIP
343036-01
LAND ACQUISITION

Priority List Rank

469

County

BURLINGTON

Existing Population

8,380

Service Area

Township of Bordentown

Need for Project

The Township has identified several parcels for purchase. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of several parcels to preserve open space and to protect water quality.

Anticipated Recipient	: BYRAM TOWNSHIP			
Project No.	: 343047-01	Eligible Project Cost:	$	1,915,067
FY08 Rank	: 470			
County	: SUSSEX	Total State Amount :	$	1,915,067

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00825
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00825

Project Name, Number

BYRAM TOWNSHIP
343047-01
LAND ACQUISITION

Priority List Rank

470

County

SUSSEX

Existing Population

8,254

Service Area

Township of Byram

Need for Project

The Township plans to purchase land for water quality protection. Preservation of the Lubbers Run Greenway will preserve and protect the stream corridor, wetlands, and watershed of Lubbers Run, a trout maintenance stream and the largest tributary to the Musconetcong River. Byram is under extreme development pressure and the geological resources conducive to groundwater supplies are limited. Areas of high recharge like Lubbers Run Greenway need to be protected to maintain groundwater supplies in the Township.

Project Description

The proposed project is for the purchase of an easement on land adjacent to Lubbers Run Greenway. Purchase of this land will limit development and sprawl and will preserve open space and protect water quality.

Anticipated Recipient	: EDGEWATER PARK TOWNSHIP			
Project No.	: 343038-01	Eligible Project Cost:	$	147,540
FY08 Rank	: 471			
County	: BURLINGTON	Total State Amount :	$	147,540

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00786
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00786

Project Name, Number

EDGEWATER PARK TOWNSHIP
343038-01
LAND ACQUISITION

Priority List Rank

471

County

BURLINGTON

Existing Population

7,864

Service Area

Township of Edgewater Park

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to maintain existing groundwater recharge capabilities.

Anticipated Recipient	:	MILLTOWN BOROUGH		
Project No.	:	343052-01	Eligible Project Cost:	$ 4,653,327
FY08 Rank	:	472		
County	:	MIDDLESEX	Total State Amount :	$ 4,653,327

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00700
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00700

Project Name, Number

MILLTOWN BOROUGH
343052-01
LAND ACQUISITION

Priority List Rank

472

County

MIDDLESEX

Existing Population

7,000

Service Area

Borough of Milltown

Need for Project

The Borough plans to purchase land surrounding Mill Pond for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of land to Mill Pond to preserve open space and to protect water quality.

Anticipated Recipient	:	ALLENDALE BOROUGH		
Project No.	:	343067-01	Eligible Project Cost:	$ 6,863,603
FY08 Rank	:	473		
County	:	BERGEN	Total State Amount :	$ 6,863,603

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00670
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00670

Project Name, Number

ALLENDALE BOROUGH
343067-01
LAND ACQUISITION

Priority List Rank

473

County

BERGEN

Existing Population

6,699

Service Area

Borough of Allendale

Need for Project

The Borough plans to purchase land on the Orchard Commons property to preserve open space. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land on the Orchard Commons property to preserve open space and to protect water quality.

Anticipated Recipient	:	MANSFIELD TOWNSHIP		
Project No.	:	343040-01	Eligible Project Cost:	$ 1,641,302
FY08 Rank	:	474		
County	:	WARREN	Total State Amount :	$ 1,641,302

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00665
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.00665

Project Name, Number

MANSFIELD TOWNSHIP
343040-01
LAND ACQUISITION

Priority List Rank

474

County

WARREN

Existing Population

6,653

Service Area

Township of Mansfiled

Need for Project

The Township plans to purchase land for the protection of ground water and a stream feeding the Musconetcong River. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of approximately 60 acres to preserve open space and to protect water quality.

Anticipated Recipient	:	PLUMSTED TOWNSHIP		
Project No.	:	343019-01	Eligible Project Cost:	$ 8,879,791
FY08 Rank	:	475		
County	:	OCEAN	Total State Amount :	$ 8,879,791

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00601
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.00601

Project Name, Number

PLUMSTED TOWNSHIP
343019-01
LAND ACQUISITION

Priority List Rank

475

County

OCEAN

Existing Population

6,005

Service Area

Township of Plumsted

Need for Project

The Township plans to purchase land in aquifer recharge areas that are critical to local and regional water quality. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	:	FAIRFIELD TOWNSHIP		
Project No.	:	342004-01	Eligible Project Cost:	$ 1,645,877
FY08 Rank	:	476		
County	:	CUMBERLAND	Total State Amount :	$ 1,645,877

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00570
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.00570

Project Name, Number

FAIRFIELD TOWNSHIP
342004-01
LANDFILL CLOSURE

Priority List Rank

476

County

CUMBERLAND

Existing Population

5,699

Service Area

Township of Fairfield

Need for Project

The municipal landfill in Fairfield is generating leachate, which is impacting surface and ground water. The site adjoins a waterway known as Rattlesnake Gut, which flows directly into the Cohansey River. A capping system is needed to prevent further leachate impacts.

Project Description

The proposed project includes construction of fill and an impervious cap to prevent infiltration. Since the site adjoins an intermittent waterway, it may be necessary to remove some of the landfill adjacent to the stream for wetlands reclamation and buffering.

Anticipated Recipient :	POINT PLEASANT BEACH BOROUGH		
Project No. :	343073-01	Eligible Project Cost:	$ 19,257,315
FY08 Rank :	477		
County :	OCEAN	Total State Amount :	$ 19,257,315

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00531
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00531

Project Name, Number

POINT PLEASANT BEACH BOROUGH
343073-01
LAND ACQUISITION

Priority List Rank

477

County

OCEAN

Existing Population

5,314

Service Area

Borough of Point Pleasant

Need for Project

The Borough plans to purchase land to preserve, protect and maintain the native dune vegetation, saltwater wetlands along the beach front, and certain wildlife habitats. Acquisition of the properties will also assist the Borough in controlling development, which result in the reduction of stormwater runoff that could have adverse impacts on the area. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	: MILLSTONE TOWNSHIP		
Project No.	: 343009-01	Eligible Project Cost:	$ 11,714,265
FY08 Rank	: 478		
County	: MONMOUTH	Total State Amount :	$ 11,714,265

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00507
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00507

Project Name, Number

MILLSTONE TOWNSHIP
343009-01
LAND ACQUISITION

Priority List Rank

478

County

MONMOUTH

Existing Population

5,069

Service Area

Township of Millstone

Need for Project

The Township plans to purchase land including the Chiusano, Palma, Dr. Sie, Smith and Maor tracts for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land including the Chiusano, Palma, Dr. Sie, Smith and Maor tracts to preserve open space and to protect water quality.

Anticipated Recipient	:	EASTAMPTON TOWNSHIP		
Project No.	:	343026-01	Eligible Project Cost:	$ 3,997,392
FY08 Rank	:	479		
County	:	BURLINGTON	Total State Amount :	$ 3,997,392

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00496
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00496

Project Name, Number

EASTAMPTON TOWNSHIP
343026-01
LAND ACQUISITION

Priority List Rank

479

County

BURLINGTON

Existing Population

4,962

Service Area

Township of Eastampton

Need for Project

The Township plans to purchase land for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	: EAST AMWELL TOWNSHIP			
Project No.	: 343062-01	Eligible Project Cost:	$	500,588
FY08 Rank	: 480			
County	: HUNTERDON	Total State Amount :	$	500,588

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00446
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00446

Project Name, Number

EAST AMWELL TOWNSHIP
343062-01
LAND ACQUISITION

Priority List Rank

480

County

HUNTERDON

Existing Population

4,455

Service Area

East Amwell Township

Need for Project

The Township plans to purchase land within the Sourland Mountain District to preserve the water quality. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	:	HIGH BRIDGE BOROUGH		
Project No.	:	343072-02	Eligible Project Cost:	$ 5,570,096
FY08 Rank	:	481		
County	:	HUNTERDON	Total State Amount :	$ 5,570,096

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00378
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00378

Project Name, Number

HIGH BRIDGE BOROUGH
343072-02
LAND ACQUISITION

Priority List Rank

481

County

HUNTERDON

Existing Population

3,776

Service Area

Borough of High Bridge

Need for Project

The Borough plans to purchase land for the preservation of land on the South Branch of the Raritan River. The property contains wetlands, steep slopes and both open and wooded areas. The property also contains Lake Solitude and the Historic Solitude House. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land along the South Branch of the Raritan River to preserve open space and to protect water quality.

Anticipated Recipient	:	MINE HILL TOWNSHIP		
Project No.	:	343053-01	Eligible Project Cost:	$ 1,396,910
FY08 Rank	:	482		
County	:	MORRIS	Total State Amount :	$ 1,396,910

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00368
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00368

Project Name, Number

MINE HILL TOWNSHIP
343053-01
LAND ACQUISITION

Priority List Rank

482

County

MORRIS

Existing Population

3,679

Service Area

Township of Mine Hill

Need for Project

The Township plans to purchase the Dickerson Mine Tract, which is the headwaters of Dicker Mine Brook, Shaw Brook, and Lamington River, for water quality protection. Preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project is for the purchase of the Dickerson Mine Tract and other parcels to preserve open space and to protect water quality.

Anticipated Recipient	:	PEAPACK & GLADSTONE BOROUGH		
Project No.	:	343049-01	Eligible Project Cost:	$ 1,054,062
FY08 Rank	:	483		
County	:	SOMERSET	Total State Amount :	$ 1,054,062

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00243
BDA Points	0
Transit Villages	0
TOTAL POINTS	150.00243

Project Name, Number

PEAPACK & GLADSTONE BOROUGH
343049-01
LAND ACQUISITION

Priority List Rank

483

County

SOMERSET

Existing Population

2,433

Service Area

Borough of Peapack & Gladstone

Need for Project

The Township plans to purchase land for water quality protection. The preservation and conservation of land is important to help protect and maintain water quality in the project area. In general, the loss of open space is known to have adverse water quality impacts that result from increases in impervious cover, loss of recharge areas or buffer zones and undesirable changes in historic stormwater drainage patterns.

Project Description

The proposed project includes the purchase of land to preserve open space and to protect water quality.

Anticipated Recipient	:	ESTELL MANOR CITY		
Project No.	:	342002-01	Eligible Project Cost:	$ 1,572,251
FY08 Rank	:	484		
County	:	ATLANTIC	Total State Amount :	$ 1,572,251

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	150
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	0
	Subtotal	150

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00140
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	150.00140

Project Name, Number

ESTELL MANOR CITY
342002-01
LANDFILL CLOSURE

Priority List Rank

484

County

ATLANTIC

Existing Population

1,404

Service Area

City of Estell Manor

Need for Project

The municipal landfill in Estell Manor is generating leachate which could impact ground water. A capping system is needed to prevent further potential leachate impacts.

Project Description

The proposed project includes construction a geomembrane impervious cap over an 8-acre area to prevent infiltration.

Anticipated Recipient	: TRENTON CITY		
Project No.	: 340416-13	Eligible Project Cost:	$ 10,091,960
FY08 Rank	: 485		
County	: MERCER	Total State Amount :	$ 10,091,960

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.08540
BDA Points	10
Transit Villages	0
TOTAL POINTS	135.08540

Project Name, Number

TRENTON CITY
340416-13
SITE REMEDIATION

Priority List Rank

485

County

MERCER

Existing Population

85,403

Service Area

City of Trenton

Need for Project

Clean-up of the contaminated industrial sites along Assunpink Creek will remove the potential of polluting the Creek and groundwater. The clean-up will allow Trenton to convert the area into a recreational greenway, which will increase the permeable surface within the watershed.

Project Description

The proposed project includes the remediation of soil contamination on several parcels along the Assunpink Creek. These parcels are contaminated with petroleum, heavy metals, and PCBs from previous years of industrial use.

Anticipated Recipient :	CAMDEN REDEVELOPMENT AGENCY		
Project No. :	340044-01	Eligible Project Cost:	$ 172,309,962
FY08 Rank :	486		
County :	CAMDEN	Total State Amount :	$ 172,309,962

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.07990
BDA Points	10
Transit Villages	0
TOTAL POINTS	135.07990

Project Name, Number

CAMDEN REDEVELOPMENT AGENCY
340044-01
SITE REMEDIATION

Priority List Rank

486

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

The Harrison Avenue Landfill is no longer in operation. The landfill has not been properly closed in accordance with applicable regulations. The runoff and leachate from this landfill discharges to surrounding water bodies and groundwater and adversely impacts water quality in the project area.

Project Description

The proposed project includes the remediation the Harrison Avenue Landfill, capping 260 acres to reduce leachate generation, excavation and disposal of contaminated soils, in-situ groundwater treatment, sheet piling of certain sections along the Delaware and Cooper Rivers, and sanitary and storm sewer improvements.

Anticipated Recipient	: BAYONNE LRA		
Project No.	: 340051-03	Eligible Project Cost:	$ 26,849,966
FY08 Rank	: 487		
County	: HUDSON	Total State Amount :	$ 26,849,966

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.06184
BDA Points	10
Transit Villages	0
TOTAL POINTS	135.06184

Project Name, Number

BAYONNE LRA
340051-03
SITE REMEDIATION

Priority List Rank

487

County

HUDSON

Existing Population

61,842

Service Area

Bayonne Bay Redevelopment District

Need for Project

Bayonne Crossing needs remedial action to address historic petroleum contamination and soils impacted by constituents that exceed soil cleanup criteria to reduce/eliminate groundwater contamination.

Project Description

The proposed project includes remedial activities to clean up a Brownfield Development Area within the City of Bayonne.

Anticipated Recipient	: NJ CITY UNIVERSITY/JERSEY CITY MUA		
Project No.	: 340111-02	Eligible Project Cost:	$ 22,174,074
FY08 Rank	: 488		
County	: HUDSON	Total State Amount :	$ 22,174,074

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.24006
BDA Points	0
Transit Villages	0
TOTAL POINTS	125.24006

Project Name, Number

NJ CITY UNIVERSITY/JERSEY CITY MUA
340111-02
REMEDIATION/SANITARY/STORM

Priority List Rank

488

County

HUDSON

Existing Population

240,055

Service Area

New Jersey City University West Campus

Need for Project

PAH, metal, mercury, and PBC concentrations above the DEP applicable remediation standards are present in the soils on-site. The phreatic zone is six feet below the ground surface. As a result, the groundwater is impacted with metals and carbon tetrachloride above the DEP Groundwater Quality Criteria. The soil contamination is present below six existing buildings.

Project Description

The proposed remediation includes a vapor cap for hexavalent chromium and mercury vapor and excavation for PAHs and other metals. The buildings and their foundations overlying the AOCs need to be demolished in order to perform the remediation. Sanitary sewer mains will also be installed.

Anticipated Recipient	: NEWARK CITY		
Project No.	: 340815-12	Eligible Project Cost:	$ 13,000,360
FY08 Rank	: 489		
County	: ESSEX	Total State Amount :	$ 13,000,360

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.27355
BDA Points	10
Transit Villages	0
TOTAL POINTS	110.27355

Project Name, Number

NEWARK CITY
340815-12
SITE REMEDIATION

Priority List Rank

489

County

ESSEX

Existing Population

273,550

Service Area

City of Newark

Need for Project

A former paint factory requires remedial measures to support brownfield development and provide significant environmental benefits. Placement of an impermeable cap along with installation of stormwater controls will ensure that rain water will not mobilize contaminates and pollute groundwater or the adjacent waterways.

Project Description

The proposed project includes demolition of existing buildings, installation of an impermeable cap and cover system, installation of stormwater controls.

Anticipated Recipient	: HARRISON TOWN/RA		
Project No.	: 340098-01	Eligible Project Cost:	$ 46,098,319
FY08 Rank	: 490		
County	: HUDSON	Total State Amount :	$ 46,098,319

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01442
BDA Points	10
Transit Villages	0
TOTAL POINTS	110.01442

Project Name, Number

HARRISON TOWN/RA
340098-01
SITE REMEDIATION, SANITARY & STORMWATER

Priority List Rank

490

County

HUDSON

Existing Population

14,424

Service Area

Town of Harrison

Need for Project

A redevelopment project in Harrison will elimnate contaminated runoff and leachate from discharges to surrounding water bodies and groundwater that could adversely impact water quality in the project area.

Project Description

The proposed project includes the remediation of a site in the Town of Harrison including installation of sanitary and storm sewer systems.

Anticipated Recipient	: NEWARK CITY		
Project No.	: 340815-11	Eligible Project Cost:	$ 25,607,620
FY08 Rank	: 491		
County	: ESSEX	Total State Amount :	$ 25,607,620

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.27355
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.27355

Project Name, Number

NEWARK CITY
340815-11
SITE REMEDIATION

Priority List Rank

491

County

ESSEX

Existing Population

273,550

Service Area

City of Newark

Need for Project

A former chemical site requires remedial measures to support brownfield development and provide significant environmental benefits. Placement of an impermeable cap along with installation of stormwater controls will ensure that rain water will not mobilize contaminates and pollute groundwater or the adjacent waterways.

Project Description

The proposed project includes demolition of existing buildings, installation of an impermeable cap and cover system, installation of stormwater controls.

Anticipated Recipient	:	ELIZABETH CITY		
Project No.	:	340942-06	Eligible Project Cost:	$ 3,340,073
FY08 Rank	:	492		
County	:	UNION	Total State Amount :	$ 3,340,073

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.12057
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.12057

Project Name, Number

ELIZABETH CITY
340942-06
SITE REMEDIATION

Priority List Rank

492

County

UNION

Existing Population

120,568

Service Area

City of Elizabeth

Need for Project

A redevelopment project in Elizabeth will elimnate contaminated runoff and leachate from discharges to surrounding water bodies and groundwater that could adversely impact water quality in the project area.

Project Description

The proposed project includes the remediation a site in the City of Elizabeth to remove contaminated soils.

Anticipated Recipient	: ELIZABETH CITY			
Project No.	: 340942-10	Eligible Project Cost:	$	9,911,578
FY08 Rank	: 492			
County	: UNION	Total State Amount :	$	9,911,578

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.12057
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.12057

Project Name, Number

ELIZABETH CITY
340942-10
SITE REMEDIATION

Priority List Rank

492

County

UNION

Existing Population

120,568

Service Area

City of Elizabeth

Need for Project

The former Borne Chemical Site in Elizabeth needs remedial measures to support brownfield development and provide significant environmental benefits. Placement of an impermeable cap along with installation of stormwater controls and construction of a bulkhead will ensure that rain water will not mobilize contaminates and pollute groundwater or the adjacent Arthur Kill River.

Project Description

The proposed project includes demolition of existing buildings, installation of an impermeable cap and cover system, installation of stormwater controls, and construction of a bulkhead.

Anticipated Recipient	:	TRENTON CITY/MCIA		
Project No.	:	340087-01	Eligible Project Cost:	$ 2,844,687
FY08 Rank	:	494		
County	:	MERCER	Total State Amount :	$ 2,844,687

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.08540
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.08540

Project Name, Number

TRENTON CITY/MCIA
340087-01
SITE REMEDIATION

Priority List Rank

494

County

MERCER

Existing Population

85,403

Service Area

City of Trenton

Need for Project

The City of Trenton proposes to redevelop twenty city lots in the area of Montgomery and East State Street, which will be known as “Trenton Town Center”. Remediation of contaminated soils will be required along with installation of stormwater infrastructure that includes the use of green and wastewater reuse technolgies to reduce stormwater runoff and wastewater generation.

Project Description

The proposed project includes remediation of contaminated soils and installation of stormwater infrastructure that includes the use of green and wastewater reuse technologies.

Anticipated Recipient :	CAMDEN REDEVELOPMENT AGENCY		
Project No. :	340044-02	Eligible Project Cost:	$ 45,383,793
FY08 Rank :	495		
County :	CAMDEN	Total State Amount :	$ 45,383,793

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.07990
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.07990

Project Name, Number

CAMDEN REDEVELOPMENT AGENCY
340044-02
SITE REMEDIATION

Priority List Rank

495

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

A redevelopment project in Camden will elimnate contaminated runoff and leachate from discharges to surrounding water bodies and groundwater that could adversely impact water quality in the project area.

Project Description

The proposed project includes the remediation a site in the City of Camden including installation of sanitary and storm sewer systems.

Anticipated Recipient :	CAMDEN REDEVELOPMENT AGENCY		
Project No. :	340044-03	Eligible Project Cost:	$ 13,000,360
FY08 Rank :	495		
County :	CAMDEN	Total State Amount :	$ 13,000,360

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.07990
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.07990

Project Name, Number

CAMDEN REDEVELOPMENT AGENCY
340044-03
SITE REMEDIATION

Priority List Rank

495

County

CAMDEN

Existing Population

79,904

Service Area

City of Camden

Need for Project

A redevelopment project in Camden will elimnate the potential for the discharge of contaminants to surrounding water bodies and groundwater that could adversely impact water quality in the project area.

Project Description

The proposed project includes remediation of the former RCA Building No. 8 in the City of Camden. This project includes the removal of contaminated debris, and the clean up of PCB's, lead, asbestos, and dioxins.

Anticipated Recipient	: NEW BRUNSWICK			
Project No.	: 340437-12	Eligible Project Cost:	$	3,340,073
FY08 Rank	: 497			
County	: MIDDLESEX	Total State Amount :	$	3,340,073

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.04857
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.04857

Project Name, Number

NEW BRUNSWICK
340437-12
BROWNFIELDS/STORMWATER MANAGEMENT

Priority List Rank

497

County

MIDDLESEX

Existing Population

48,573

Service Area

New Brunswick, Piscataway, Highland Park, East Brunswick, North Brunswick

Need for Project

Clean-up of the contaminated industrial site along Spring Street will remove the potential of polluting the nearby waterways as well as groundwater.

Project Description

The proposed project includes the clean-up of the an industrial site along Spring Street.

Anticipated Recipient	:	HUDSON COUNTY IA		
Project No.	:	340094-01	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	498		
County	:	HUDSON	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.03858
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.03858

Project Name, Number

HUDSON COUNTY IA
340094-01
NONPOINT SOURCE MANGEMENT

Priority List Rank

498

County

HUDSON

Existing Population

38,577

Service Area

City of Hoboken

Need for Project

The project includes rehabilitation of existing structures incorporating water conservation/treatment and recycling that will reduce the volume of discharge and result in a higher quality discharge of both stormwater and black water from the site.

Project Description

The proposed water quality/water conservation project includes low water fixtures, a roof garden, stormwater storage, and geothermal piles.

Anticipated Recipient :	HARRISON TOWN/HUDSON COUNTY IA		
Project No. :	340341-05	Eligible Project Cost:	$ 31,783,125
FY08 Rank :	499		
County :	HUDSON	Total State Amount :	$ 31,783,125

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01442
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.01442

Project Name, Number

HARRISON TOWN/HUDSON COUNTY IA
340341-05
SITE REMEDIATION

Priority List Rank

499

County

HUDSON

Existing Population

14,424

Service Area

Town of Harrison

Need for Project

Clean-up of the former Hartz site that is contaminated with PCBs, chlorinated solvents, base neutrals, and priority pollutant metals. The clean-up will remove the potential of polluting the nearby waterways as well as groundwater.

Project Description

The proposed project includes the clean-up of the redevelopment of the Hartz site.

Anticipated Recipient	: HARRISON TOWN/RA			
Project No.	: 340098-02	Eligible Project Cost:	$	6,189,443
FY08 Rank	: 499			
County	: HUDSON	Total State Amount :	$	6,189,443

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01442
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.01442

Project Name, Number

HARRISON TOWN/RA
340098-02
REDEVELOPMENT INFRASTRUCTURE

Priority List Rank

499

County

HUDSON

Existing Population

14,424

Service Area

Town of Harrison

Need for Project

A redevelopment project in Harrison will elimnate contaminated runoff and leachate from discharges to surrounding water bodies and groundwater that could adversely impact water quality in the project area. New sewer and stormwater infrastructure will elimanate an existing combined system.

Project Description

The proposed project includes construction of stormwater management controls and a sanitary sewer conveyance system.

Anticipated Recipient	: UNION COUNTY IA		
Project No.	: 340124-01	Eligible Project Cost:	$ 23,069,596
FY08 Rank	: 501		
County	: UNION	Total State Amount :	$ 23,069,596

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	50.00000
Population	0.01100
BDA Points	0
Transit Villages	0
TOTAL POINTS	100.01100

Project Name, Number

UNION COUNTY IA
340124-01
SITE REMEDIATION

Priority List Rank

501

County

UNION

Existing Population

11,000

Service Area

City of Elizabeth

Need for Project

The former Celadon Site in Elizabeth needs remedial measures to support brownfield development and provide significant environmental benefits. Placement of an impermeable cap along with installation of stormwater controls will ensure that rain water will not mobilize contaminates and pollute groundwater or the adjacent Newark Bay.

Project Description

The proposed project includes demolition of existing buildings, installation of an impermeable cap and cover system and installation of stormwater controls.

Anticipated Recipient :	MORRIS COUNTY		
Project No. :	340107-01	Eligible Project Cost:	$ 13,000,360
FY08 Rank :	502		
County :	MORRIS	Total State Amount :	$ 13,000,360

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.47021
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	75.47021

Project Name, Number

MORRIS COUNTY
340107-01
BROWNFIELDS

Priority List Rank

502

County

MORRIS

Existing Population

470,212

Service Area

County of Morris

Need for Project

Clean-up of the contaminated site will remove the potential of polluting the adjacent streams and wetlands as well as groundwater.

Project Description

The proposed project includes the clean-up of the contaminated Greystoke Park Psychiatric Hospital site to protect water quality in the area.

Anticipated Recipient	: PERTH AMBOY RA		
Project No.	: 340435-07	Eligible Project Cost:	$ 36,825,064
FY08 Rank	: 503		
County	: MIDDLESEX	Total State Amount :	$ 36,825,064

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04730
BDA Points	0
Transit Villages	0
TOTAL POINTS	75.04730

Project Name, Number

PERTH AMBOY RA
340435-07
SITE RMEDIATION

Priority List Rank

503

County

MIDDLESEX

Existing Population

47,303

Service Area

City of Perth Amboy

Need for Project

A 105.4-acre site in Perth Amboy is contaminated as a result of widespread distribution of slag fill. The contaminants of concern are primarily arsenic, antimony and lead.

Project Description

The proposed project includes soil and groundwater remediation of a 105.4-acre site. Remediation will consist of excavation and removal of select areas of slag materials in direct contact with groundwater, targeted soil remediation for select areas with petroleum-related and PCB contamintants, a reduction in groundwater flow through the site, treatment of groundwater to reduce contaminant loading to Crane’s Creek, and implementation of site-wide engineering controls to minimize stormwater infiltration as well as direct contact with contaminated material.

Anticipated Recipient	: EAST AMWELL			
Project No.	: 340037-01	Eligible Project Cost:	$	639,645
FY08 Rank	: 504			
County	: HUNTERDON	Total State Amount :	$	639,645

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	75
Conduit Projects	50	0
	Subtotal	75

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00446
BDA Points	0
Transit Villages	0
TOTAL POINTS	75.00446

Project Name, Number

EAST AMWELL
340037-01
SITE REMEDIATION

Priority List Rank

504

County

HUNTERDON

Existing Population

4,455

Service Area

East Amwell Township

Need for Project

Clean-up of a contaminated area in the Sourland Mountains will remove the potential of polluting the nearby waterways as well as groundwater.

Project Description

The proposed project includes the clean-up of a contaminated site so that the land can be purchased for preservation.

Anticipated Recipient :	PENNSAUKEN TOWNSHIP		
Project No. :	340349-04	Eligible Project Cost:	$ 55,431,119
FY08 Rank :	505		
County :	CAMDEN	Total State Amount :	$ 55,431,119

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.03574
			BDA Points	10
			Transit Villages	0
			TOTAL POINTS	60.03574

Project Name, Number

PENNSAUKEN TOWNSHIP
340349-04
SITE REMEDIATION

Priority List Rank

505

County

CAMDEN

Existing Population

35,737

Service Area

Township of Pennsauken

Need for Project

Proper clean-up of the contaminated industrial sites will eliminate a source of groundwater and surface water pollution.

Project Description

The proposed project includes the excavation and disposal of contaminated soils, placement of fill to reduce leachate generation, closure of underground storage tanks, in-situ groundwater treatment and fencing to restrict access to tidal and wetland areas, and sanitary and storm sewer improvements.

Anticipated Recipient	:	SOUTH ORANGE VILLAGE TOWNSHIP		
Project No.	:	340103-01	Eligible Project Cost:	$ 2,049,114
FY08 Rank	:	506		
County	:	ESSEX	Total State Amount :	$ 2,049,114

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.01696
			BDA Points	0
			Transit Villages	10
			TOTAL POINTS	60.01696

Project Name, Number

SOUTH ORANGE VILLAGE TOWNSHIP
340103-01
SITE REMEDIATION

Priority List Rank

506

County

ESSEX

Existing Population

16,964

Service Area

Township of South Orange Village

Need for Project

Clean-up of the contaminated new market square redevelopment area will remove the potential of polluting the nearby waterways as well as groundwater.

Project Description

The proposed project includes the clean-up of the new market square redevelopment area.

Anticipated Recipient :	PERTH AMBOY RA		
Project No. :	340435-08	Eligible Project Cost:	$ 19,257,315
FY08 Rank :	507		
County :	MIDDLESEX	Total State Amount :	$ 19,257,315

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04730
BDA Points	0
Transit Villages	0
TOTAL POINTS	50.04730

Project Name, Number

PERTH AMBOY RA
340435-08
SITE REMEDIATION

Priority List Rank

507

County

MIDDLESEX

Existing Population

47,303

Service Area

City of Perth Amboy

Need for Project

Remediation of soil and groundwater impacts and proper closure of a former landfill will minimize direct contact with contaminated fill, properly manage methane gas generated by landfill materials, and ensure future protection of groundwater quality.

Project Description

The proposed project includes soil and groundwater remediation of a former landfill, alternate capping of the landfill, and installation of a methane recovery sytem.

Anticipated Recipient	:	HACKENSACK CITY		
Project No.	:	340923-09	Eligible Project Cost:	$ 9,589,269
FY08 Rank	:	508		
County	:	BERGEN	Total State Amount :	$ 9,589,269

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.04268
BDA Points	0
Transit Villages	0
TOTAL POINTS	50.04268

Project Name, Number

HACKENSACK CITY
340923-09
SITE REMEDIATION, STORMWATER MANAGEMENT

Priority List Rank

508

County

BERGEN

Existing Population

42,677

Service Area

City of Hackensack

Need for Project

Petroleum discharges at the Eval Oil Terminal on the Hackensack River have resulted in saturated soil that is a continuing source of adverse impacts to groundwater including the accumulation of free-phase petroleum product on the shallow water table and that pose an ongoing threat to the surface water and sediment quality of the River.

Project Description

The proposed project includes soil and groundwater remediation of petroleum impacts that threaten the surface and sediment quality of the adjacent Hackensack River; restoration of the bulkhead to stabilize the shoreline and diminish the potential for contamination seepage; and stormwater management improvements to comply with regulations.

Anticipated Recipient :	BELLMAWR BOROUGH		
Project No. :	342011-01	Eligible Project Cost:	$ 36,129,988
FY08 Rank :	509		
County :	CAMDEN	Total State Amount :	$ 36,129,988

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.01126
BDA Points	0
Transit Villages	0
TOTAL POINTS	50.01126

Project Name, Number

BELLMAWR BOROUGH
342011-01
LANDFILL CLOSURE

Priority List Rank

509

County

CAMDEN

Existing Population

11,262

Service Area

Borough of Bellmawr

Need for Project

Proper closure of these three landfills will reduce leachate and stormwater discharges to Big Timber Creek.

Project Description

The proposed project includes closure of three landfills encompassing 110 acres, replacement of two partially failed and deteriorating stormwater pipes, and installation of a sewer collection system. The proposed landfill closure improvements include the installation of an impermeable landfill capping system, which will promote enhanced stormwater runoff as well as prevent stormwater infiltration into the landfill.

Anticipated Recipient	:	MILLTOWN BOROUGH		
Project No.	:	340102-01	Eligible Project Cost:	$ 6,614,815
FY08 Rank	:	510		
County	:	MIDDLESEX	Total State Amount :	$ 6,614,815

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use

	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0
			State Planning Commission	0.00000
			Population	0.00700
			BDA Points	0
			Transit Villages	0
			TOTAL POINTS	50.00700

Project Name, Number

MILLTOWN BOROUGH
340102-01
SITE REMEDIATION

Priority List Rank

510

County

MIDDLESEX

Existing Population

7,000

Service Area

Borough of Milltown, New Brunswick, East Brunswick

Need for Project

Clean-up of the contaminated industrial site will remove the potential of polluting the adjacent Mill Pond and other nearby waterways as well as groundwater.

Project Description

The proposed project includes the clean-up of the former Micheline Tire industrial site to protect water quality in the area.

Anticipated Recipient :	ATLANTIC CITY MUA		
Project No. :	340063-01	Eligible Project Cost:	$ 28,243,275
FY08 Rank :	511		
County :	BURLINGTON	Total State Amount :	$ 28,243,275

I. LOCAL ENVIRONMENTAL ENHANCEMENT PLANNING ACTIVITIES	Possible Points	Points Scored
	0-200	0

II. PROJECT DISCHARGE TYPE	Possible Points	Points Scored
CSO/SSO	600	0
Treatment Plant Improvements	500	0
SS Rehabilitation	450	0
Sludge Disposal/Treatment	350	0
WW Reuse	300	0
Septic Repair	275	0
New Systems	250	0
Stormwater/NPS Management	225	0
Landfill Closure, Land Acq, Well Sealing	150	0
Landfill Constr, Site Remediation	75	0
Conduit Projects	50	50
	Subtotal	50

III. WATER USE/WATER QUALITY POINTS

A. Water Use	Possible Points	Points Scored
Potable Water Supply	200	0
Shellfish	125	0
Recreation(Primary Contact)	125	0
Freshwater Fisheries(Trout/NonTrout)	75/25	0
Public Nuisance(On Site Systems Only)	50	0
Agriculture Water Use	25	0
Industrial Water Use	25	0
	Subtotal	0

B. Existing Water Quality

Parameter	Meets Standards	Marginally Meets Standards	Does Not Meet Standards	Points Scored
Dissolved Oxygen	0	50	100	0
Fecal Coliform	0	50	100	0
Nutrients	0	25	50	0
Toxics	0	25	50	0
			Subtotal	0

State Planning Commission	0.00000
Population	0.00000
BDA Points	0
Transit Villages	0
TOTAL POINTS	50.00000

Project Name, Number

ATLANTIC CITY MUA
340063-01
STORMWATER MANAGEMENT

Priority List Rank

511

County

BURLINGTON

Existing Population

0

Service Area

Burlington County

Need for Project

Eastern Oganic currently operates open air composting facility. Runoff from the piles could contaminate groundwater and local water bodies.

Project Description

The project also includes construction of an anaerobic digester program, which would enclose the operation and eliminate contaminated runoff.